MATLAB®

The Language of Technical Computing

- Computation
- Visualization
- Programming

Function Reference
Volume 3: P - Z

Version 7

How to Contact The MathWorks:

`www.mathworks.com`	Web
`comp.soft-sys.matlab`	Newsgroup

`support@mathworks.com`	Technical support
`suggest@mathworks.com`	Product enhancement suggestions
`bugs@mathworks.com`	Bug reports
`doc@mathworks.com`	Documentation error reports
`service@mathworks.com`	Order status, license renewals, passcodes
`info@mathworks.com`	Sales, pricing, and general information

508-647-7000 Phone

508-647-7001 Fax

The MathWorks, Inc. Mail
3 Apple Hill Drive
Natick, MA 01760-2098

For contact information about worldwide offices, see the MathWorks Web site.

MATLAB Function Reference Volume 3: P - Z

Printing History:			
	December 1996	First printing	For MATLAB 5.0 (Release 8)
	June 1997	Online only	Revised for MATLAB 5.1 (Release 9)
	October 1997	Online only	Revised for MATLAB 5.2 (Release 10)
	January 1999	Online only	Revised for MATLAB 5.3 (Release 11
	June 1999	Second printing	For MATLAB 5.3 (Release 11)
	June 2001	Online only	Revised for MATLAB 6.1 (Release 12.1)
	July 2002	Online only	Revised for 6.5 (Release 13)
	June 2004	Online only	Revised for 7.0 (Release 14)

Contents

1 Functions — Categorical List

Desktop Tools and Development Environment **1-4**
Startup and Shutdown **1-4**
Command Window and History **1-5**
Help for Using MATLAB **1-5**
Workspace, Search Path, and File Operations **1-5**
Programming Tools **1-7**
System **1-8**

Mathematics **1-9**
Arrays and Matrices **1-10**
Linear Algebra **1-12**
Elementary Math **1-14**
Data Analysis and Fourier Transforms **1-17**
Polynomials **1-18**
Interpolation and Computational Geometry **1-19**
Coordinate System Conversion **1-20**
Nonlinear Numerical Methods **1-20**
Specialized Math **1-22**
Sparse Matrices **1-22**
Math Constants **1-24**

Programming and Data Types **1-25**
Data Types **1-25**
Arrays **1-30**
Operators and Operations **1-32**
Programming in MATLAB **1-35**

File I/O **1-40**
Filename Construction **1-40**
Opening, Loading, Saving Files **1-41**
Low-Level File I/O **1-41**
Text Files **1-41**
XML Documents **1-41**
Spreadsheets **1-42**

Scientific Data 1-42
Audio and Audio/Video 1-43
Images 1-43
Internet Exchange 1-44

Graphics 1-45
Basic Plots and Graphs 1-45
Annotating Plots 1-46
Specialized Plotting 1-46
Bit-Mapped Images 1-49
Printing 1-49
Handle Graphics 1-49

3-D Visualization 1-52
Surface and Mesh Plots 1-52
View Control 1-53
Lighting 1-55
Transparency 1-55
Volume Visualization 1-55

Creating Graphical User Interfaces 1-56
Predefined Dialog Boxes 1-56
Deploying User Interfaces 1-57
Developing User Interfaces 1-57
User Interface Objects 1-57
Finding Objects from Callbacks 1-57

2 Functions — Alphabetical List

1

Functions — Categorical List

The MATLAB® Function Reference contains descriptions of all MATLAB commands and functions.

Select a category from the following table to see a list of related functions.

Desktop Tools and Development Environment	Startup, Command Window, help, editing and debugging, tuning, other general functions
Mathematics	Arrays and matrices, linear algebra, data analysis, other areas of mathematics
Programming and Data Types	Function/expression evaluation, program control, function handles, object oriented programming, error handling, operators, data types, dates and times, timers
File I/O	General and low-level file I/O, plus specific file formats, like audio, spreadsheet, HDF, images
Graphics	Line plots, annotating graphs, specialized plots, images, printing, Handle Graphics®
3-D Visualization	Surface and mesh plots, view control, lighting and transparency, volume visualization.
Creating Graphical User Interface	GUIDE, programming graphical user interfaces.
External Interfaces	Java, COM, Serial Port functions.

See Simulink®, Stateflow®, Real-Time Workshop®, and the individual toolboxes for lists of their functions

Desktop Tools and Development Environment

General functions for working in MATLAB, including functions for startup, Command Window, help, and editing and debugging.

"Startup and Shutdown"	Startup and shutdown options
"Command Window and History"	Controlling Command Window and History
"Help for Using MATLAB"	Finding information
"Workspace, Search Path, and File Operations"	File, search path, variable management
"Programming Tools"	Editing and debugging, source control, Notebook
"System"	Identifying current computer, license, product version, and more

Startup and Shutdown

`exit`	Terminate MATLAB (same as `quit`)
`finish`	MATLAB termination M-file
`genpath`	Generate a path string
`matlab`	Start MATLAB (UNIX systems)
`matlab`	Start MATLAB (Windows systems)
`matlabrc`	MATLAB startup M-file for single user systems or administrators
`prefdir`	Return directory containing preferences, history, and layout files
`preferences`	Display Preferences dialog box for MATLAB and related products
`quit`	Terminate MATLAB
`startup`	MATLAB startup M-file for user-defined options

Command Window and History

`clc`	Clear Command Window
`commandhistory`	Open the Command History, or select it if already open
`commandwindow`	Open the Command Window, or select it if already open
`diary`	Save session to file
`dos`	Execute DOS command and return result
`format`	Control display format for output
`home`	Move cursor to upper left corner of Command Window
`matlab:`	Run specified function via hyperlink (`matlabcolon`)
`more`	Control paged output for Command Window
`perl`	Call Perl script using appropriate operating system executable
`system`	Execute operating system command and return result
`unix`	Execute UNIX command and return result

Help for Using MATLAB

`doc`	Display online documentation in MATLAB Help browser
`demo`	Access product demos via Help browser
`docopt`	Web browser for UNIX platforms
`docsearch`	Open Help browser Search pane and run search for specified term
`help`	Display help for MATLAB functions in Command Window
`helpbrowser`	Display Help browser for access to full online documentation and demos
`helpwin`	Provide access to and display M-file help for all functions
`info`	Display Release Notes for MathWorks products
`lookfor`	Search for specified keyword in all `help` entries
`playshow`	Run published M-file demo
`support`	Open MathWorks Technical Support Web page
`web`	Open Web site or file in Web browser or Help browser
`whatsnew`	Display Release Notes for MathWorks products

Workspace, Search Path, and File Operations

- "Workspace"
- "Search Path"
- "File Operations"

Workspace

`assignin`	Assign value to workspace variable
`clear`	Remove items from workspace, freeing up system memory
`evalin`	Execute string containing MATLAB expression in a workspace
`exist`	Check if variables or functions are defined
`openvar`	Open workspace variable in Array Editor for graphical editing
`pack`	Consolidate workspace memory
`uiimport`	Open Import Wizard, the graphical user interface to import data
`which`	Locate functions and files
`who`, `whos`	List variables in the workspace
`workspace`	Display Workspace browser, a tool for managing the workspace

Search Path

`addpath`	Add directories to MATLAB search path
`genpath`	Generate path string
`partialpath`	Partial pathname
`path`	View or change the MATLAB directory search path
`path2rc`	Replaced by `savepath`
`pathdef`	List of directories in the MATLAB search path
`pathsep`	Return path separator for current platform
`pathtool`	Open **Set Path** dialog box to view and change MATLAB path
`restoredefaultpath`	Restore the default search path
`rmpath`	Remove directories from MATLAB search path
`savepath`	Save current MATLAB search path to `pathdef.m` file

File Operations

`cd`	Change working directory
`copyfile`	Copy file or directory
`delete`	Delete files or graphics objects
`dir`	Display directory listing
`exist`	Check if variables or functions are defined
`fileattrib`	Set or get attributes of file or directory
`filebrowser`	Display Current Directory browser, a tool for viewing files
`lookfor`	Search for specified keyword in all `help` entries
`ls`	List directory on UNIX
`matlabroot`	Return root directory of MATLAB installation
`mkdir`	Make new directory
`movefile`	Move file or directory
`pwd`	Display current directory
`recycle`	Set option to move deleted files to recycle folder
`rehash`	Refresh function and file system path caches
`rmdir`	Remove directory

`type`	List file
`web`	Open Web site or file in Web browser or Help browser
`what`	List MATLAB specific files in current directory
`which`	Locate functions and files

See also "File I/O" functions.

Programming Tools

- "Editing and Debugging"
- "Performance Improvement and Tuning Tools and Techniques"
- "Source Control"
- "Publishing"

Editing and Debugging

`dbclear`	Clear breakpoints
`dbcont`	Resume execution
`dbdown`	Change local workspace context
`dbquit`	Quit debug mode
`dbstack`	Display function call stack
`dbstatus`	List all breakpoints
`dbstep`	Execute one or more lines from current breakpoint
`dbstop`	Set breakpoints
`dbtype`	List M-file with line numbers
`dbup`	Change local workspace context
`debug`	M-file debugging functions
`edit`	Edit or create M-file
`keyboard`	Invoke the keyboard in an M-file

Performance Improvement and Tuning Tools and Techniques

`memory`	Help for memory limitations
`mlint`	Check M-files for possible problems, and report results
`mlintrpt`	Run mlint for file or directory, reporting results in Web browser
`pack`	Consolidate workspace memory
`profile`	Profile the execution time for a function
`profsave`	Save profile report in HTML format
`rehash`	Refresh function and file system path caches
`sparse`	Create sparse matrix
`zeros`	Create array of all zeros

Source Control

`checkin`	Check file into source control system
`checkout`	Check file out of source control system
`cmopts`	Get name of source control system
`customverctrl`	Allow custom source control system
`undocheckout`	Undo previous checkout from source control system
`verctrl`	Version control operations on PC platforms

Publishing

`notebook`	Open M-book in Microsoft Word (Windows only)
`publish`	Run M-file containing cells, and save results to file of specified type

System

`computer`	Identify information about computer on which MATLAB is running
`javachk`	Generate error message based on Java feature support
`license`	Show license number for MATLAB
`prefdir`	Return directory containing preferences, history, and layout files
`usejava`	Determine if a Java feature is supported in MATLAB
`ver`	Display version information for MathWorks products
`version`	Get MATLAB version number

Mathematics

Functions for working with arrays and matrices, linear algebra, data analysis, and other areas of mathematics.

“Arrays and Matrices”	Basic array operators and operations, creation of elementary and specialized arrays and matrices
“Linear Algebra”	Matrix analysis, linear equations, eigenvalues, singular values, logarithms, exponentials, factorization
“Elementary Math”	Trigonometry, exponentials and logarithms, complex values, rounding, remainders, discrete math
“Data Analysis and Fourier Transforms”	Descriptive statistics, finite differences, correlation, filtering and convolution, fourier transforms
“Polynomials”	Multiplication, division, evaluation, roots, derivatives, integration, eigenvalue problem, curve fitting, partial fraction expansion
“Interpolation and Computational Geometry”	Interpolation, Delaunay triangulation and tessellation, convex hulls, Voronoi diagrams, domain generation
“Coordinate System Conversion”	Conversions between Cartesian and polar or spherical coordinates
“Nonlinear Numerical Methods”	Differential equations, optimization, integration
“Specialized Math”	Airy, Bessel, Jacobi, Legendre, beta, elliptic, error, exponential integral, gamma functions
“Sparse Matrices”	Elementary sparse matrices, operations, reordering algorithms, linear algebra, iterative methods, tree operations
“Math Constants”	Pi, imaginary unit, infinity, Not-a-Number, largest and smallest positive floating point numbers, floating point relative accuracy

Arrays and Matrices

- "Basic Information"
- "Operators"
- "Operations and Manipulation"
- "Elementary Matrices and Arrays"
- "Specialized Matrices"

Basic Information

`disp`	Display array
`display`	Display array
`isempty`	True for empty matrix
`isequal`	True if arrays are identical
`isfloat`	True for floating-point arrays
`isinteger`	True for integer arrays
`islogical`	True for logical array
`isnumeric`	True for numeric arrays
`isscalar`	True for scalars
`issparse`	True for sparse matrix
`isvector`	True for vectors
`length`	Length of vector
`ndims`	Number of dimensions
`numel`	Number of elements
`size`	Size of matrix

Operators

`+`	Addition
`+`	Unary plus
`-`	Subtraction
`-`	Unary minus
`*`	Matrix multiplication
`^`	Matrix power
`\`	Backslash or left matrix divide
`/`	Slash or right matrix divide
`'`	Transpose
`.'`	Nonconjugated transpose
`.*`	Array multiplication (element-wise)
`.^`	Array power (element-wise)
`.\`	Left array divide (element-wise)
`./`	Right array divide (element-wise)

Operations and Manipulation

`:` (colon)	Index into array, rearrange array
`accumarray`	Construct an array with accumulation
`blkdiag`	Block diagonal concatenation
`cat`	Concatenate arrays
`cross`	Vector cross product
`cumprod`	Cumulative product
`cumsum`	Cumulative sum
`diag`	Diagonal matrices and diagonals of matrix
`dot`	Vector dot product
`end`	Last index
`find`	Find indices of nonzero elements
`fliplr`	Flip matrices left-right
`flipud`	Flip matrices up-down
`flipdim`	Flip matrix along specified dimension
`horzcat`	Horizontal concatenation
`ind2sub`	Multiple subscripts from linear index
`ipermute`	Inverse permute dimensions of multidimensional array
`kron`	Kronecker tensor product
`max`	Maximum value of array
`min`	Minimum value of array
`permute`	Rearrange dimensions of multidimensional array
`prod`	Product of array elements
`repmat`	Replicate and tile array
`reshape`	Reshape array
`rot90`	Rotate matrix 90 degrees
`sort`	Sort array elements in ascending or descending order
`sortrows`	Sort rows in ascending order
`sum`	Sum of array elements
`sqrtm`	Matrix square root
`sub2ind`	Linear index from multiple subscripts
`tril`	Lower triangular part of matrix
`triu`	Upper triangular part of matrix
`vertcat`	Vertical concatenation

See also “Linear Algebra” for other matrix operations.
See also “Elementary Math” for other array operations.

Elementary Matrices and Arrays

`:` (colon)	Regularly spaced vector
`blkdiag`	Construct block diagonal matrix from input arguments
`diag`	Diagonal matrices and diagonals of matrix
`eye`	Identity matrix
`freqspace`	Frequency spacing for frequency response
`linspace`	Generate linearly spaced vectors
`logspace`	Generate logarithmically spaced vectors
`meshgrid`	Generate X and Y matrices for three-dimensional plots
`ndgrid`	Arrays for multidimensional functions and interpolation
`ones`	Create array of all ones
`rand`	Uniformly distributed random numbers and arrays
`randn`	Normally distributed random numbers and arrays
`repmat`	Replicate and tile array
`zeros`	Create array of all zeros

Specialized Matrices

`compan`	Companion matrix
`gallery`	Test matrices
`hadamard`	Hadamard matrix
`hankel`	Hankel matrix
`hilb`	Hilbert matrix
`invhilb`	Inverse of Hilbert matrix
`magic`	Magic square
`pascal`	Pascal matrix
`rosser`	Classic symmetric eigenvalue test problem
`toeplitz`	Toeplitz matrix
`vander`	Vandermonde matrix
`wilkinson`	Wilkinson's eigenvalue test matrix

Linear Algebra

- "Matrix Analysis"
- "Linear Equations"
- "Eigenvalues and Singular Values"
- "Matrix Logarithms and Exponentials"
- "Factorization"

Matrix Analysis

`cond`	Condition number with respect to inversion
`condeig`	Condition number with respect to eigenvalues
`det`	Determinant
`norm`	Matrix or vector norm
`normest`	Estimate matrix 2-norm
`null`	Null space
`orth`	Orthogonalization
`rank`	Matrix rank
`rcond`	Matrix reciprocal condition number estimate
`rref`	Reduced row echelon form
`subspace`	Angle between two subspaces
`trace`	Sum of diagonal elements

Linear Equations

`\` and `/`	Linear equation solution
`chol`	Cholesky factorization
`cholinc`	Incomplete Cholesky factorization
`cond`	Condition number with respect to inversion
`condest`	1-norm condition number estimate
`funm`	Evaluate general matrix function
`inv`	Matrix inverse
`linsolve`	Solve linear systems of equations
`lscov`	Least squares solution in presence of known covariance
`lsqnonneg`	Nonnegative least squares
`lu`	LU matrix factorization
`luinc`	Incomplete LU factorization
`pinv`	Moore-Penrose pseudoinverse of matrix
`qr`	Orthogonal-triangular decomposition
`rcond`	Matrix reciprocal condition number estimate

Eigenvalues and Singular Values

`balance`	Improve accuracy of computed eigenvalues
`cdf2rdf`	Convert complex diagonal form to real block diagonal form
`condeig`	Condition number with respect to eigenvalues
`eig`	Eigenvalues and eigenvectors
`eigs`	Eigenvalues and eigenvectors of sparse matrix
`gsvd`	Generalized singular value decomposition
`hess`	Hessenberg form of matrix
`poly`	Polynomial with specified roots
`polyeig`	Polynomial eigenvalue problem
`qz`	QZ factorization for generalized eigenvalues

`rsf2csf`	Convert real Schur form to complex Schur form
`schur`	Schur decomposition
`svd`	Singular value decomposition
`svds`	Singular values and vectors of sparse matrix

Matrix Logarithms and Exponentials

`expm`	Matrix exponential
`logm`	Matrix logarithm
`sqrtm`	Matrix square root

Factorization

`balance`	Diagonal scaling to improve eigenvalue accuracy
`cdf2rdf`	Complex diagonal form to real block diagonal form
`chol`	Cholesky factorization
`cholinc`	Incomplete Cholesky factorization
`cholupdate`	Rank 1 update to Cholesky factorization
`lu`	LU matrix factorization
`luinc`	Incomplete LU factorization
`planerot`	Givens plane rotation
`qr`	Orthogonal-triangular decomposition
`qrdelete`	Delete column or row from QR factorization
`qrinsert`	Insert column or row into QR factorization
`qrupdate`	Rank 1 update to QR factorization
`qz`	QZ factorization for generalized eigenvalues
`rsf2csf`	Real block diagonal form to complex diagonal form

Elementary Math

- “Trigonometric”
- “Exponential”
- “Complex”
- “Rounding and Remainder”
- “Discrete Math (e.g., Prime Factors)”

Trigonometric

`acos`	Inverse cosine
`acosd`	Inverse cosine, degrees
`acosh`	Inverse hyperbolic cosine
`acot`	Inverse cotangent
`acotd`	Inverse cotangent, degrees
`acoth`	Inverse hyperbolic cotangent
`acsc`	Inverse cosecant
`acscd`	Inverse cosecant, degrees
`acsch`	Inverse hyperbolic cosecant
`asec`	Inverse secant
`asecd`	Inverse secant, degrees
`asech`	Inverse hyperbolic secant
`asin`	Inverse sine
`asind`	Inverse sine, degrees
`asinh`	Inverse hyperbolic sine
`atan`	Inverse tangent
`atand`	Inverse tangent, degrees
`atanh`	Inverse hyperbolic tangent
`atan2`	Four-quadrant inverse tangent
`cos`	Cosine
`cosd`	Cosine, degrees
`cosh`	Hyperbolic cosine
`cot`	Cotangent
`cotd`	Cotangent, degrees
`coth`	Hyperbolic cotangent
`csc`	Cosecant
`cscd`	Cosecant, degrees
`csch`	Hyperbolic cosecant
`sec`	Secant
`secd`	Secant, degrees
`sech`	Hyperbolic secant
`sin`	Sine
`sind`	Sine, degrees
`sinh`	Hyperbolic sine
`tan`	Tangent
`tand`	Tangent, degrees
`tanh`	Hyperbolic tangent

Exponential

`exp`	Exponential
`expm1`	Exponential of x minus 1
`log`	Natural logarithm
`log1p`	Logarithm of 1+x
`log2`	Base 2 logarithm and dissect floating-point numbers into exponent and mantissa
`log10`	Common (base 10) logarithm
`nextpow2`	Next higher power of 2
`pow2`	Base 2 power and scale floating-point number
`reallog`	Natural logarithm for nonnegative real arrays
`realpow`	Array power for real-only output
`realsqrt`	Square root for nonnegative real arrays
`sqrt`	Square root
`nthroot`	Real nth root

Complex

`abs`	Absolute value
`angle`	Phase angle
`complex`	Construct complex data from real and imaginary parts
`conj`	Complex conjugate
`cplxpair`	Sort numbers into complex conjugate pairs
i	Imaginary unit
`imag`	Complex imaginary part
`isreal`	True for real array
j	Imaginary unit
`real`	Complex real part
`sign`	Signum
`unwrap`	Unwrap phase angle

Rounding and Remainder

`fix`	Round towards zero
`floor`	Round towards minus infinity
`ceil`	Round towards plus infinity
`round`	Round towards nearest integer
`mod`	Modulus after division
`rem`	Remainder after division

Discrete Math (e.g., Prime Factors)

`factor`	Prime factors
`factorial`	Factorial function
`gcd`	Greatest common divisor
`isprime`	True for prime numbers
`lcm`	Least common multiple
`nchoosek`	All combinations of N elements taken K at a time
`perms`	All possible permutations
`primes`	Generate list of prime numbers
`rat`, `rats`	Rational fraction approximation

Data Analysis and Fourier Transforms

- "Basic Operations"
- "Finite Differences"
- "Correlation"
- "Filtering and Convolution"
- "Fourier Transforms"

Basic Operations

`cumprod`	Cumulative product
`cumsum`	Cumulative sum
`cumtrapz`	Cumulative trapezoidal numerical integration
`max`	Maximum elements of array
`mean`	Average or mean value of arrays
`median`	Median value of arrays
`min`	Minimum elements of array
`prod`	Product of array elements
`sort`	Sort array elements in ascending or descending order
`sortrows`	Sort rows in ascending order
`std`	Standard deviation
`sum`	Sum of array elements
`trapz`	Trapezoidal numerical integration
`var`	Variance

Finite Differences

`del2`	Discrete Laplacian
`diff`	Differences and approximate derivatives
`gradient`	Numerical gradient

Correlation

`corrcoef`	Correlation coefficients
`cov`	Covariance matrix
`subspace`	Angle between two subspaces

Filtering and Convolution

`conv`	Convolution and polynomial multiplication
`conv2`	Two-dimensional convolution
`convn`	N-dimensional convolution
`deconv`	Deconvolution and polynomial division
`detrend`	Linear trend removal
`filter`	Filter data with infinite impulse response (IIR) or finite impulse response (FIR) filter
`filter2`	Two-dimensional digital filtering

Fourier Transforms

`abs`	Absolute value and complex magnitude
`angle`	Phase angle
`fft`	One-dimensional discrete Fourier transform
`fft2`	Two-dimensional discrete Fourier transform
`fftn`	N-dimensional discrete Fourier Transform
`fftshift`	Shift DC component of discrete Fourier transform to center of spectrum
`fftw`	Interface to the FFTW library run-time algorithm for tuning FFTs
`ifft`	Inverse one-dimensional discrete Fourier transform
`ifft2`	Inverse two-dimensional discrete Fourier transform
`ifftn`	Inverse multidimensional discrete Fourier transform
`ifftshift`	Inverse fast Fourier transform shift
`nextpow2`	Next power of two
`unwrap`	Correct phase angles

Polynomials

`conv`	Convolution and polynomial multiplication
`deconv`	Deconvolution and polynomial division
`poly`	Polynomial with specified roots
`polyder`	Polynomial derivative
`polyeig`	Polynomial eigenvalue problem
`polyfit`	Polynomial curve fitting
`polyint`	Analytic polynomial integration
`polyval`	Polynomial evaluation
`polyvalm`	Matrix polynomial evaluation
`residue`	Convert between partial fraction expansion and polynomial coefficients
`roots`	Polynomial roots

Interpolation and Computational Geometry

- "Interpolation"
- "Delaunay Triangulation and Tessellation"
- "Convex Hull"
- "Voronoi Diagrams"
- "Domain Generation"

Interpolation

`dsearch`	Search for nearest point
`dsearchn`	Multidimensional closest point search
`griddata`	Data gridding
`griddata3`	Data gridding and hypersurface fitting for three-dimensional data
`griddatan`	Data gridding and hypersurface fitting (dimension >= 2)
`interp1`	One-dimensional data interpolation (table lookup)
`interp2`	Two-dimensional data interpolation (table lookup)
`interp3`	Three-dimensional data interpolation (table lookup)
`interpft`	One-dimensional interpolation using fast Fourier transform method
`interpn`	Multidimensional data interpolation (table lookup)
`meshgrid`	Generate X and Y matrices for three-dimensional plots
`mkpp`	Make piecewise polynomial
`ndgrid`	Generate arrays for multidimensional functions and interpolation
`pchip`	Piecewise Cubic Hermite Interpolating Polynomial (PCHIP)
`ppval`	Piecewise polynomial evaluation
`spline`	Cubic spline data interpolation
`tsearchn`	Multidimensional closest simplex search
`unmkpp`	Piecewise polynomial details

Delaunay Triangulation and Tessellation

`delaunay`	Delaunay triangulation
`delaunay3`	Three-dimensional Delaunay tessellation
`delaunayn`	Multidimensional Delaunay tessellation
`dsearch`	Search for nearest point
`dsearchn`	Multidimensional closest point search
`tetramesh`	Tetrahedron mesh plot
`trimesh`	Triangular mesh plot
`triplot`	Two-dimensional triangular plot
`trisurf`	Triangular surface plot
`tsearch`	Search for enclosing Delaunay triangle
`tsearchn`	Multidimensional closest simplex search

Convex Hull

`convhull`	Convex hull
`convhulln`	Multidimensional convex hull
`patch`	Create patch graphics object
`plot`	Linear two-dimensional plot
`trisurf`	Triangular surface plot

Voronoi Diagrams

`dsearch`	Search for nearest point
`patch`	Create patch graphics object
`plot`	Linear two-dimensional plot
`voronoi`	Voronoi diagram
`voronoin`	Multidimensional Voronoi diagrams

Domain Generation

`meshgrid`	Generate X and Y matrices for three-dimensional plots
`ndgrid`	Generate arrays for multidimensional functions and interpolation

Coordinate System Conversion

Cartesian

`cart2sph`	Transform Cartesian to spherical coordinates
`cart2pol`	Transform Cartesian to polar coordinates
`pol2cart`	Transform polar to Cartesian coordinates
`sph2cart`	Transform spherical to Cartesian coordinates

Nonlinear Numerical Methods

- "Ordinary Differential Equations (IVP)"
- "Delay Differential Equations"
- "Boundary Value Problems"
- "Partial Differential Equations"
- "Optimization"
- "Numerical Integration (Quadrature)"

Ordinary Differential Equations (IVP)

`ode113`	Solve non-stiff differential equations, variable order method
`ode15i`	Solve fully implicit differential equations, variable order method
`ode15s`	Solve stiff ODEs and DAEs Index 1, variable order method
`ode23`	Solve non-stiff differential equations, low order method
`ode23s`	Solve stiff differential equations, low order method
`ode23t`	Solve moderately stiff ODEs and DAEs Index 1, trapezoidal rule
`ode23tb`	Solve stiff differential equations, low order method
`ode45`	Solve non-stiff differential equations, medium order method
`odextend`	Extend the solution of an initial value problem
`odeget`	Get ODE `options` parameters
`odeset`	Create/alter ODE `options` structure
`decic`	Compute consistent initial conditions for `ode15i`
`deval`	Evaluate solution of differential equation problem

Delay Differential Equations

`dde23`	Solve delay differential equations with constant delays
`ddeget`	Get DDE options parameters
`ddeset`	Create/alter DDE `options` structure
`deval`	Evaluate solution of differential equation problem

Boundary Value Problems

`bvp4c`	Solve boundary value problems for ODEs
`bvpget`	Get BVP `options` parameters
`bvpset`	Create/alter BVP `options` structure
`deval`	Evaluate solution of differential equation problem

Partial Differential Equations

`pdepe`	Solve initial-boundary value problems for parabolic-elliptic PDEs
`pdeval`	Evaluates by interpolation solution computed by `pdepe`

Optimization

`fminbnd`	Scalar bounded nonlinear function minimization
`fminsearch`	Multidimensional unconstrained nonlinear minimization, by Nelder-Mead direct search method
`fzero`	Scalar nonlinear zero finding
`lsqnonneg`	Linear least squares with nonnegativity constraints
`optimset`	Create or alter optimization `options` structure
`optimget`	Get optimization parameters from `options` structure

Numerical Integration (Quadrature)

`quad`	Numerically evaluate integral, adaptive Simpson quadrature (low order)
`quadl`	Numerically evaluate integral, adaptive Lobatto quadrature (high order)
`quadv`	Vectorized quadrature
`dblquad`	Numerically evaluate double integral
`triplequad`	Numerically evaluate triple integral

Specialized Math

`airy`	Airy functions
`besselh`	Bessel functions of third kind (Hankel functions)
`besseli`	Modified Bessel function of first kind
`besselj`	Bessel function of first kind
`besselk`	Modified Bessel function of second kind
`bessely`	Bessel function of second kind
`beta`	Beta function
`betainc`	Incomplete beta function
`betaln`	Logarithm of beta function
`ellipj`	Jacobi elliptic functions
`ellipke`	Complete elliptic integrals of first and second kind
`erf`	Error function
`erfc`	Complementary error function
`erfcinv`	Inverse complementary error function
`erfcx`	Scaled complementary error function
`erfinv`	Inverse error function
`expint`	Exponential integral
`gamma`	Gamma function
`gammainc`	Incomplete gamma function
`gammaln`	Logarithm of gamma function
`legendre`	Associated Legendre functions
`psi`	Psi (polygamma) function

Sparse Matrices

- “Elementary Sparse Matrices”
- “Full to Sparse Conversion”
- “Working with Sparse Matrices”
- “Reordering Algorithms”
- “Linear Algebra”
- “Linear Equations (Iterative Methods)”
- “Tree Operations”

Elementary Sparse Matrices

`spdiags`	Sparse matrix formed from diagonals
`speye`	Sparse identity matrix
`sprand`	Sparse uniformly distributed random matrix
`sprandn`	Sparse normally distributed random matrix
`sprandsym`	Sparse random symmetric matrix

Full to Sparse Conversion

`find`	Find indices of nonzero elements
`full`	Convert sparse matrix to full matrix
`sparse`	Create sparse matrix
`spconvert`	Import from sparse matrix external format

Working with Sparse Matrices

`issparse`	True for sparse matrix
`nnz`	Number of nonzero matrix elements
`nonzeros`	Nonzero matrix elements
`nzmax`	Amount of storage allocated for nonzero matrix elements
`spalloc`	Allocate space for sparse matrix
`spfun`	Apply function to nonzero matrix elements
`spones`	Replace nonzero sparse matrix elements with ones
`spparms`	Set parameters for sparse matrix routines
`spy`	Visualize sparsity pattern

Reordering Algorithms

`colamd`	Column approximate minimum degree permutation
`colmmd`	Column minimum degree permutation
`colperm`	Column permutation
`dmperm`	Dulmage-Mendelsohn permutation
`randperm`	Random permutation
`symamd`	Symmetric approximate minimum degree permutation
`symmmd`	Symmetric minimum degree permutation
`symrcm`	Symmetric reverse Cuthill-McKee permutation

Linear Algebra

`cholinc`	Incomplete Cholesky factorization
`condest`	1-norm condition number estimate
`eigs`	Eigenvalues and eigenvectors of sparse matrix
`luinc`	Incomplete LU factorization
`normest`	Estimate matrix 2-norm
`sprank`	Structural rank
`svds`	Singular values and vectors of sparse matrix

Linear Equations (Iterative Methods)

`bicg`	BiConjugate Gradients method
`bicgstab`	BiConjugate Gradients Stabilized method
`cgs`	Conjugate Gradients Squared method
`gmres`	Generalized Minimum Residual method
`lsqr`	LSQR implementation of Conjugate Gradients on Normal Equations
`minres`	Minimum Residual method
`pcg`	Preconditioned Conjugate Gradients method
`qmr`	Quasi-Minimal Residual method
`spaugment`	Form least squares augmented system
`symmlq`	Symmetric LQ method

Tree Operations

`etree`	Elimination tree
`etreeplot`	Plot elimination tree
`gplot`	Plot graph, as in “graph theory”
`symbfact`	Symbolic factorization analysis
`treelayout`	Lay out tree or forest
`treeplot`	Plot picture of tree

Math Constants

`eps`	Floating-point relative accuracy
`i`	Imaginary unit
`Inf`	Infinity, ∞
`intmax`	Largest possible value of specified integer type
`intmin`	Smallest possible value of specified integer type
`j`	Imaginary unit
`NaN`	Not-a-Number
`pi`	Ratio of a circle’s circumference to its diameter, π
`realmax`	Largest positive floating-point number
`realmin`	Smallest positive floating-point number

Programming and Data Types

Functions to store and operate on data at either the MATLAB command line or in programs and scripts. Functions to write, manage, and execute MATLAB programs.

“Data Types”	Numeric, character, structures, cell arrays, and data type conversion
“Arrays”	Basic array operations and manipulation
“Operators and Operations”	Special characters and arithmetic, bit-wise, relational, logical, set, date and time operations
“Programming in MATLAB”	M-files, function/expression evaluation, program control, function handles, object oriented programming, error handling

Data Types

- “Numeric”
- “Characters and Strings”
- “Structures”
- “Cell Arrays”
- “Data Type Conversion”
- “Determine Data Type”

Numeric

`[ ]`	Array constructor
`cat`	Concatenate arrays
`class`	Return object's class name (e.g., numeric)
`find`	Find indices and values of nonzero array elements
`intmax`	Largest possible value of specified integer type
`intmin`	Smallest possible value of specified integer type
`intwarning`	Enable or disable integer warnings
`ipermute`	Inverse permute dimensions of multidimensional array
`isa`	Determine if item is object of given class (e.g., numeric)
`isequal`	Determine if arrays are numerically equal
`isequalwithequalnans`	Test for equality, treating `NaN`s as equal
`isnumeric`	Determine if item is numeric array
`isreal`	Determine if all array elements are real numbers
`isscalar`	True for scalars (1-by-1 matrices)
`isvector`	True for vectors (1-by-N or N-by-1 matrices)
`permute`	Rearrange dimensions of multidimensional array
`realmax`	Largest positive floating-point number
`realmin`	Smallest positive floating-point number
`reshape`	Reshape array
`squeeze`	Remove singleton dimensions from array
`zeros`	Create array of all zeros

Characters and Strings

Description of Strings in MATLAB

`strings`	Describes MATLAB string handling

Creating and Manipulating Strings

`blanks`	Create string of blanks
`char`	Create character array (string)
`cellstr`	Create cell array of strings from character array
`datestr`	Convert to date string format
`deblank`	Strip trailing blanks from the end of string
`lower`	Convert string to lower case
`sprintf`	Write formatted data to string
`sscanf`	Read string under format control
`strcat`	String concatenation

`strjust`	Justify character array
`strread`	Read formatted data from string
`strrep`	String search and replace
`strtrim`	Remove leading and trailing whitespace from string
`strvcat`	Vertical concatenation of strings
`upper`	Convert string to upper case

Comparing and Searching Strings

`class`	Return object's class name (e.g., char)
`findstr`	Find string within another, longer string
`isa`	Determine if item is object of given class (e.g., char)
`iscellstr`	Determine if item is cell array of strings
`ischar`	Determine if item is character array
`isletter`	Detect array elements that are letters of the alphabet
`isscalar`	True for scalars (1-by-1 matrices)
`isspace`	Detect elements that are ASCII white spaces
`isstrprop`	Determine content of each element of string
`isvector`	True for vectors (1-by-N or N-by-1 matrices)
`regexp`	Match regular expression
`regexpi`	Match regular expression, ignoring case
`regexprep`	Replace string using regular expression
`strcmp`	Compare strings
`strcmpi`	Compare strings, ignoring case
`strfind`	Find one string within another
`strmatch`	Find possible matches for string
`strncmp`	Compare first `n` characters of strings
`strncmpi`	Compare first `n` characters of strings, ignoring case
`strtok`	First token in string

Evaluating String Expressions

`eval`	Execute string containing MATLAB expression
`evalc`	Evaluate MATLAB expression with capture
`evalin`	Execute string containing MATLAB expression in workspace

Structures

`cell2struct`	Cell array to structure array conversion
`class`	Return object's class name (e.g., struct)
`deal`	Deal inputs to outputs
`fieldnames`	Field names of structure
`isa`	Determine if item is object of given class (e.g., struct)
`isequal`	Determine if arrays are numerically equal
`isfield`	Determine if item is structure array field
`isscalar`	True for scalars (1-by-1 matrices)
`isstruct`	Determine if item is structure array
`isvector`	True for vectors (1-by-N or N-by-1 matrices)
`orderfields`	Order fields of a structure array
`rmfield`	Remove structure fields
`struct`	Create structure array
`struct2cell`	Structure to cell array conversion

Cell Arrays

`{ }`	Construct cell array
`cell`	Construct cell array
`cellfun`	Apply function to each element in cell array
`cellstr`	Create cell array of strings from character array
`cell2mat`	Convert cell array of matrices into single matrix
`cell2struct`	Cell array to structure array conversion
`celldisp`	Display cell array contents
`cellplot`	Graphically display structure of cell arrays
`class`	Return object's class name (e.g., cell)
`deal`	Deal inputs to outputs
`isa`	Determine if item is object of given class (e.g., cell)
`iscell`	Determine if item is cell array
`iscellstr`	Determine if item is cell array of strings
`isequal`	Determine if arrays are numerically equal
`isscalar`	True for scalars (1-by-1 matrices)
`isvector`	True for vectors (1-by-N or N-by-1 matrices)
`mat2cell`	Divide matrix up into cell array of matrices
`num2cell`	Convert numeric array into cell array
`struct2cell`	Structure to cell array conversion

Data Type Conversion

Numeric

`double`	Convert to double-precision
`int8`	Convert to signed 8-bit integer
`int16`	Convert to signed 16-bit integer
`int32`	Convert to signed 32-bit integer
`int64`	Convert to signed 64-bit integer
`single`	Convert to single-precision
`uint8`	Convert to unsigned 8-bit integer
`uint16`	Convert to unsigned 16-bit integer
`uint32`	Convert to unsigned 32-bit integer
`uint64`	Convert to unsigned 64-bit integer

String to Numeric

`base2dec`	Convert base `N` number string to decimal number
`bin2dec`	Convert binary number string to decimal number
`hex2dec`	Convert hexadecimal number string to decimal number
`hex2num`	Convert hexadecimal number string to double number
`str2double`	Convert string to double-precision number
`str2num`	Convert string to number

Numeric to String

`char`	Convert to character array (string)
`dec2base`	Convert decimal to base `N` number in string
`dec2bin`	Convert decimal to binary number in string
`dec2hex`	Convert decimal to hexadecimal number in string
`int2str`	Convert integer to string
`mat2str`	Convert a matrix to string
`num2str`	Convert number to string

Other Conversions

`cell2mat`	Convert cell array of matrices into single matrix
`cell2struct`	Convert cell array to structure array
`datestr`	Convert serial date number to string
`func2str`	Convert function handle to function name string
`logical`	Convert numeric to logical array
`mat2cell`	Divide matrix up into cell array of matrices
`num2cell`	Convert a numeric array to cell array
`str2func`	Convert function name string to function handle
`struct2cell`	Convert structure to cell array

Determine Data Type

`is*`	Detect state
`isa`	Determine if item is object of given class
`iscell`	Determine if item is cell array
`iscellstr`	Determine if item is cell array of strings
`ischar`	Determine if item is character array
`isfield`	Determine if item is character array
`isfloat`	True for floating-point arrays
`isinteger`	True for integer arrays
`isjava`	Determine if item is Java object
`islogical`	Determine if item is logical array
`isnumeric`	Determine if item is numeric array
`isobject`	Determine if item is MATLAB OOPs object
`isreal`	Determine if all array elements are real numbers
`isstruct`	Determine if item is MATLAB structure array

Arrays

- "Array Operations"
- "Basic Array Information"
- "Array Manipulation"
- "Elementary Arrays"

Array Operations

`[ ]`	Array constructor
`,`	Array row element separator
`;`	Array column element separator
`:`	Specify range of array elements
`end`	Indicate last index of array
`+`	Addition or unary plus
`-`	Subtraction or unary minus
`.*`	Array multiplication
`./`	Array right division
`.\`	Array left division
`.^`	Array power
`.'`	Array (nonconjugated) transpose

Basic Array Information

`disp`	Display text or array
`display`	Overloaded method to display text or array
`isempty`	Determine if array is empty
`isequal`	Determine if arrays are numerically equal
`isequalwithequalnans`	Test for equality, treating `NaN`s as equal
`islogical`	Determine if item is logical array
`isnumeric`	Determine if item is numeric array
`isscalar`	Determine if item is a scalar
`isvector`	Determine if item is a vector
`length`	Length of vector
`ndims`	Number of array dimensions
`numel`	Number of elements in matrix or cell array
`size`	Array dimensions

Array Manipulation

`:`	Specify range of array elements
`blkdiag`	Construct block diagonal matrix from input arguments
`cat`	Concatenate arrays
`circshift`	Shift array circularly
`find`	Find indices and values of nonzero elements
`fliplr`	Flip matrices left-right
`flipud`	Flip matrices up-down
`flipdim`	Flip array along specified dimension
`horzcat`	Horizontal concatenation
`ind2sub`	Subscripts from linear index
`ipermute`	Inverse permute dimensions of multidimensional array
`permute`	Rearrange dimensions of multidimensional array
`repmat`	Replicate and tile array
`reshape`	Reshape array
`rot90`	Rotate matrix 90 degrees
`shiftdim`	Shift dimensions
`sort`	Sort array elements in ascending or descending order
`sortrows`	Sort rows in ascending order
`squeeze`	Remove singleton dimensions
`sub2ind`	Single index from subscripts
`vertcat`	Horizontal concatenation

Elementary Arrays

`:`	Regularly spaced vector
`blkdiag`	Construct block diagonal matrix from input arguments
`eye`	Identity matrix
`linspace`	Generate linearly spaced vectors
`logspace`	Generate logarithmically spaced vectors
`meshgrid`	Generate X and Y matrices for three-dimensional plots
`ndgrid`	Generate arrays for multidimensional functions and interpolation
`ones`	Create array of all ones
`rand`	Uniformly distributed random numbers and arrays
`randn`	Normally distributed random numbers and arrays
`zeros`	Create array of all zeros

Operators and Operations

- "Special Characters"
- "Arithmetic Operations"
- "Bit-wise Operations"
- "Relational Operations"
- "Logical Operations"
- "Set Operations"
- "Date and Time Operations"

Special Characters

`:`	Specify range of array elements
`( )`	Pass function arguments, or prioritize operations
`[ ]`	Construct array
`{ }`	Construct cell array
`.`	Decimal point, or structure field separator
`...`	Continue statement to next line
`,`	Array row element separator
`;`	Array column element separator
`%`	Insert comment line into code
`!`	Command to operating system
`=`	Assignment

Arithmetic Operations

+	Plus
-	Minus
.	Decimal point
=	Assignment
*	Matrix multiplication
/	Matrix right division
\	Matrix left division
^	Matrix power
'	Matrix transpose
.*	Array multiplication (element-wise)
./	Array right division (element-wise)
.\	Array left division (element-wise)
.^	Array power (element-wise)
.'	Array transpose

Bit-wise Operations

bitand	Bit-wise AND
bitcmp	Bit-wise complement
bitor	Bit-wise OR
bitmax	Maximum floating-point integer
bitset	Set bit at specified position
bitshift	Bit-wise shift
bitget	Get bit at specified position
bitxor	Bit-wise XOR

Relational Operations

<	Less than
<=	Less than or equal to
>	Greater than
>=	Greater than or equal to
==	Equal to
~=	Not equal to

Logical Operations

`&&`	Logical AND
`||`	Logical OR
`&`	Logical AND for arrays
`|`	Logical OR for arrays
`~`	Logical NOT
`all`	Test to determine if all elements are nonzero
`any`	Test for any nonzero elements
`false`	False array
`find`	Find indices and values of nonzero elements
`is*`	Detect state
`isa`	Determine if item is object of given class
`iskeyword`	Determine if string is MATLAB keyword
`isvarname`	Determine if string is valid variable name
`logical`	Convert numeric values to logical
`true`	True array
`xor`	Logical EXCLUSIVE OR

Set Operations

`intersect`	Set intersection of two vectors
`ismember`	Detect members of set
`setdiff`	Return set difference of two vectors
`issorted`	Determine if set elements are in sorted order
`setxor`	Set exclusive or of two vectors
`union`	Set union of two vectors
`unique`	Unique elements of vector

Date and Time Operations

`addtodate`	Modify particular field of date number
`calendar`	Calendar for specified month
`clock`	Current time as date vector
`cputime`	Elapsed CPU time
`date`	Current date string
`datenum`	Serial date number
`datestr`	Convert serial date number to string
`datevec`	Date components
`eomday`	End of month
`etime`	Elapsed time
`now`	Current date and time
`tic, toc`	Stopwatch timer
`weekday`	Day of the week

Programming in MATLAB

- "M-File Functions and Scripts"
- "Evaluation of Expressions and Functions"
- "Timer Functions"
- "Variables and Functions in Memory"
- "Control Flow"
- "Function Handles"
- "Object-Oriented Programming"
- "Error Handling"
- "MEX Programming"

M-File Functions and Scripts

`( )`	Pass function arguments
`%`	Insert comment line into code
`...`	Continue statement to next line
`depfun`	List dependent functions of M-file or P-file
`depdir`	List dependent directories of M-file or P-file
`echo`	Echo M-files during execution
`function`	Function M-files
`input`	Request user input
`inputname`	Input argument name
`mfilename`	Name of currently running M-file
`namelengthmax`	Return maximum identifier length
`nargin`	Number of function input arguments
`nargout`	Number of function output arguments
`nargchk`	Check number of input arguments
`nargoutchk`	Validate number of output arguments
`pcode`	Create preparsed pseudocode file (P-file)
`script`	Describes script M-file
`varargin`	Accept variable number of arguments
`varargout`	Return variable number of arguments

Evaluation of Expressions and Functions

`builtin`	Execute built-in function from overloaded method
`cellfun`	Apply function to each element in cell array
`echo`	Echo M-files during execution
`eval`	Interpret strings containing MATLAB expressions
`evalc`	Evaluate MATLAB expression with capture
`evalin`	Evaluate expression in workspace
`feval`	Evaluate function
`iskeyword`	Determine if item is MATLAB keyword
`isvarname`	Determine if item is valid variable name
`pause`	Halt execution temporarily
`run`	Run script that is not on current path
`script`	Describes script M-file
`symvar`	Determine symbolic variables in expression
`tic`, `toc`	Stopwatch timer

Timer Functions

`delete`	Delete timer object from memory
`disp`	Display information about timer object
`get`	Retrieve information about timer object properties
`isvalid`	Determine if timer object is valid
`set`	Display or set timer object properties
`start`	Start a timer
`startat`	Start a timer at a specific timer
`stop`	Stop a timer
`timer`	Create a timer object
`timerfind`	Return an array of all visible timer objects in memory
`timerfindall`	Return an array of all timer objects in memory
`wait`	Block command line until timer completes

Variables and Functions in Memory

`assignin`	Assign value to workspace variable
`genvarname`	Construct valid variable name from string
`global`	Define global variables
`inmem`	Return names of functions in memory
`isglobal`	Determine if item is global variable
`mislocked`	True if M-file cannot be cleared
`mlock`	Prevent clearing M-file from memory
`munlock`	Allow clearing M-file from memory
`namelengthmax`	Return maximum identifier length
`pack`	Consolidate workspace memory
`persistent`	Define persistent variable
`rehash`	Refresh function and file system caches

Control Flow

`break`	Terminate execution of `for` loop or `while` loop
`case`	Case switch
`catch`	Begin catch block
`continue`	Pass control to next iteration of `for` or `while` loop
`else`	Conditionally execute statements
`elseif`	Conditionally execute statements
`end`	Terminate conditional statements, or indicate last index
`error`	Display error messages
`for`	Repeat statements specific number of times
`if`	Conditionally execute statements
`otherwise`	Default part of `switch` statement
`return`	Return to invoking function
`switch`	Switch among several cases based on expression
`try`	Begin `try` block
`while`	Repeat statements indefinite number of times

Function Handles

`class`	Return object's class name (e.g. function_handle)
`feval`	Evaluate function
`function_handle`	Describes function handle data type
`functions`	Return information about function handle
`func2str`	Constructs function name string from function handle
`isa`	Determine if item is object of given class (e.g. function_handle)
`isequal`	Determine if function handles are equal
`str2func`	Constructs function handle from function name string

Object-Oriented Programming

MATLAB Classes and Objects

`class`	Create object or return class of object
`fieldnames`	List public fields belonging to object,
`inferiorto`	Establish inferior class relationship
`isa`	Determine if item is object of given class
`isobject`	Determine if item is MATLAB OOPs object
`loadobj`	User-defined extension of `load` function for user objects
`methods`	Display information on class methods
`methodsview`	Display information on class methods in separate window
`saveobj`	User-defined extension of `save` function for user objects
`subsasgn`	Overloaded method for `A(I)=B`, `A{I}=B`, and `A.field=B`

`subsindex`	Overloaded method for `X(A)`
`subsref`	Overloaded method for `A(I)`, `A{I}` and `A.field`
`substruct`	Create structure argument for subsasgn or subsref
`superiorto`	Establish superior class relationship

Java Classes and Objects

`cell`	Convert Java array object to cell array
`class`	Return class name of Java object
`clear`	Clear Java import list or Java class definitions
`depfun`	List Java classes used by M-file
`exist`	Determine if item is Java class
`fieldnames`	List public fields belonging to object
`im2java`	Convert image to instance of Java image object
`import`	Add package or class to current Java import list
`inmem`	List names of Java classes loaded into memory
`isa`	Determine if item is object of given class
`isjava`	Determine if item is Java object
`javaaddpath`	Add entries to dynamic Java class path
javaArray	Construct Java array
`javachk`	Generate error message based on Java feature support
`javaclasspath`	Set and get dynamic Java class path
javaMethod	Invoke Java method
javaObject	Construct Java object
`javarmpath`	Remove entries from dynamic Java class path
`methods`	Display information on class methods
`methodsview`	Display information on class methods in separate window
`usejava`	Determine if a Java feature is supported in MATLAB
`which`	Display package and class name for method

Error Handling

`catch`	Begin `catch` block of `try/catch` statement
`error`	Display error message
`ferror`	Query MATLAB about errors in file input or output
`intwarning`	Enable or disable integer warnings
`lasterr`	Return last error message generated by MATLAB
`lasterror`	Last error message and related information
`lastwarn`	Return last warning message issued by MATLAB
`rethrow`	Reissue error
`try`	Begin `try` block of `try/catch` statement
`warning`	Display warning message

MEX Programming

`dbmex`	Enable MEX-file debugging
`inmem`	Return names of currently loaded MEX-files
`mex`	Compile MEX-function from C or Fortran source code
`mexext`	Return MEX-filename extension

File I/O

Functions to read and write data to files of different format types.

"Filename Construction"	Get path, directory, filename information; construct filenames
"Opening, Loading, Saving Files"	Open files; transfer data between files and MATLAB workspace
"Low-Level File I/O"	Low-level operations that use a file identifier (e.g., fopen, fseek, fread)
"Text Files"	Delimited or formatted I/O to text files
"XML Documents"	Documents written in Extensible Markup Language
"Spreadsheets"	Excel and Lotus 123 files
"Scientific Data"	CDF, FITS, HDF formats
"Audio and Audio/Video"	General audio functions; SparcStation, WAVE, AVI files
"Images"	Graphics files
"Internet Exchange"	URL, zip, and e-mail

To see a listing of file formats that are readable from MATLAB, go to `file formats`.

Filename Construction

`fileparts`	Return parts of filename
`filesep`	Return directory separator for this platform
`fullfile`	Build full filename from parts
`tempdir`	Return name of system's temporary directory
`tempname`	Return unique string for use as temporary filename

Opening, Loading, Saving Files

`importdata`	Load data from various types of files
`load`	Load all or specific data from MAT or ASCII file
`open`	Open files of various types using appropriate editor or program
`save`	Save all or specific data to MAT or ASCII file
`uiimport`	Open Import Wizard, the graphical user interface to import data
`winopen`	Open file in appropriate application (Windows only)

Low-Level File I/O

`fclose`	Close one or more open files
`feof`	Test for end-of-file
`ferror`	Query MATLAB about errors in file input or output
`fgetl`	Return next line of file as string without line terminator(s)
`fgets`	Return next line of file as string with line terminator(s)
`fopen`	Open file or obtain information about open files
`fprintf`	Write formatted data to file
`fread`	Read binary data from file
`frewind`	Rewind open file
`fscanf`	Read formatted data from file
`fseek`	Set file position indicator
`ftell`	Get file position indicator
`fwrite`	Write binary data to file

Text Files

`csvread`	Read numeric data from text file, using comma delimiter
`csvwrite`	Write numeric data to text file, using comma delimiter
`dlmread`	Read numeric data from text file, specifying your own delimiter
`dlmwrite`	Write numeric data to text file, specifying your own delimiter
`textread`	Read data from text file, write to multiple outputs
`textscan`	Read data from text file, convert and write to cell array

XML Documents

`xmlread`	Parse XML document
`xmlwrite`	Serialize XML Document Object Model node
`xslt`	Transform XML document using XSLT engine

Spreadsheets

Microsoft Excel Functions

`xlsfinfo`	Determine if file contains Microsoft Excel (`.xls`) spreadsheet
`xlsread`	Read Microsoft Excel spreadsheet file (`.xls`)
`xlswrite`	Write Microsoft Excel spreadsheet file (`.xls`)

Lotus123 Functions

`wk1read`	Read Lotus123 WK1 spreadsheet file into matrix
`wk1write`	Write matrix to Lotus123 WK1 spreadsheet file

Scientific Data

Common Data Format (CDF)

`cdfepoch`	Convert MATLAB date number or date string into CDF epoch
`cdfinfo`	Return information about CDF file
`cdfread`	Read CDF file
`cdfwrite`	Write CDF file

Flexible Image Transport System

`fitsinfo`	Return information about FITS file
`fitsread`	Read FITS file

Hierarchical Data Format (HDF)

`hdf`	Interface to HDF4 files
`hdfinfo`	Return information about HDF4 or HDF-EOS file
`hdfread`	Read HDF4 file
`hdftool`	Start HDF4 Import Tool
`hdf5`	Describes HDF5 data type objects
`hdf5info`	Return information about HDF5 file
`hdf5read`	Read HDF5 file
`hdf5write`	Write data to file in HDF5 format

Band-Interleaved Data

`multibandread`	Read band-interleaved data from file
`multibandwrite`	Write band-interleaved data to file

Audio and Audio/Video

General

`audioplayer`	Create audio player object
`audiorecorder`	Perform real-time audio capture
`beep`	Produce beep sound
`lin2mu`	Convert linear audio signal to mu-law
`mmfileinfo`	Information about a multimedia file
`mu2lin`	Convert mu-law audio signal to linear
`sound`	Convert vector into sound
`soundsc`	Scale data and play as sound

SPARCstation-Specific Sound Functions

`auread`	Read NeXT/SUN (`.au`) sound file
`auwrite`	Write NeXT/SUN (`.au`) sound file

Microsoft WAVE Sound Functions

`wavplay`	Play sound on PC-based audio output device
`wavread`	Read Microsoft WAVE (`.wav`) sound file
`wavrecord`	Record sound using PC-based audio input device
`wavwrite`	Write Microsoft WAVE (`.wav`) sound file

Audio/Video Interleaved (AVI) Functions

`addframe`	Add frame to AVI file
`avifile`	Create new AVI file
`aviinfo`	Return information about AVI file
`aviread`	Read AVI file
`close`	Close AVI file
`movie2avi`	Create AVI movie from MATLAB movie

Images

`im2java`	Convert image to instance of Java image object
`imfinfo`	Return information about graphics file
`imread`	Read image from graphics file
`imwrite`	Write image to graphics file

Internet Exchange

`ftp`	Connect to FTP server, creating an FTP object
`sendmail`	Send e-mail message (attachments optional) to list of addresses
`unzip`	Extract contents of zip file
`urlread`	Read contents at URL
`urlwrite`	Save contents of URL to file
`zip`	Create compressed version of files in zip format

Graphics

2-D graphs, specialized plots (e.g., pie charts, histograms, and contour plots), function plotters, and Handle Graphics functions.

Basic Plots and Graphs	Linear line plots, log and semilog plots
Annotating Plots	Titles, axes labels, legends, mathematical symbols
Specialized Plotting	Bar graphs, histograms, pie charts, contour plots, function plotters
Bit-Mapped Images	Display image object, read and write graphics file, convert to movie frames
Printing	Printing and exporting figures to standard formats
Handle Graphics	Creating graphics objects, setting properties, finding handles

Basic Plots and Graphs

`box`	Axis box for 2-D and 3-D plots
`errorbar`	Plot graph with error bars
`hold`	Hold current graph
`LineSpec`	Line specification syntax
`loglog`	Plot using log-log scales
`polar`	Polar coordinate plot
`plot`	Plot vectors or matrices.
`plot3`	Plot lines and points in 3-D space
`plotyy`	Plot graphs with Y tick labels on the left and right
`semilogx`	Semi-log scale plot
`semilogy`	Semi-log scale plot
`subplot`	Create axes in tiled positions

Plotting Tools

`figurepalette`	Display figure palette on figure
`pan`	Turn panning on or off.
`plotbrowser`	Display plot browser on figure
`plottools`	Start plotting tools
`propertyeditor`	Display property editor on figure
`zoom`	Turn zooming on or off

Annotating Plots

`annotation`	Create annotation objects
`clabel`	Add contour labels to contour plot
`datetick`	Date formatted tick labels
`gtext`	Place text on 2-D graph using mouse
`legend`	Graph legend for lines and patches
`texlabel`	Produce the TeX format from character string
`title`	Titles for 2-D and 3-D plots
`xlabel`	X-axis labels for 2-D and 3-D plots
`ylabel`	Y-axis labels for 2-D and 3-D plots
`zlabel`	Z-axis labels for 3-D plots

Annotation Object Properties

`arrow`	Properties for annotation arrows
`doublearrow`	Properties for double-headed annotation arrows
`ellipse`	Properties for annotation ellipses
`line`	Properties for annotation lines
`rectangle`	Properties for annotation rectangles
`textarrow`	Properties for annotation textbox

Specialized Plotting

- "Area, Bar, and Pie Plots"
- "Contour Plots"
- "Direction and Velocity Plots"
- "Discrete Data Plots"
- "Function Plots"
- "Histograms"
- "Polygons and Surfaces"
- "Scatter/Bubble Plots"
- "Animation"

Area, Bar, and Pie Plots

`area`	Area plot
`bar`	Vertical bar chart
`barh`	Horizontal bar chart
`bar3`	Vertical 3-D bar chart
`bar3h`	Horizontal 3-D bar chart
`pareto`	Pareto char
`pie`	Pie plot
`pie3`	3-D pie plot

Contour Plots

`contour`	Contour (level curves) plot
`contour3`	3-D contour plot
`contourc`	Contour computation
`contourf`	Filled contour plot
`ezcontour`	Easy to use contour plotter
`ezcontourf`	Easy to use filled contour plotter

Direction and Velocity Plots

`comet`	Comet plot
`comet3`	3-D comet plot
`compass`	Compass plot
`feather`	Feather plot
`quiver`	Quiver (or velocity) plot
`quiver3`	3-D quiver (or velocity) plot

Discrete Data Plots

`stem`	Plot discrete sequence data
`stem3`	Plot discrete surface data
`stairs`	Stairstep graph

Function Plots

`ezcontour`	Easy to use contour plotter
`ezcontourf`	Easy to use filled contour plotter
`ezmesh`	Easy to use 3-D mesh plotter
`ezmeshc`	Easy to use combination mesh/contour plotter
`ezplot`	Easy to use function plotter
`ezplot3`	Easy to use 3-D parametric curve plotter
`ezpolar`	Easy to use polar coordinate plotter
`ezsurf`	Easy to use 3-D colored surface plotter
`ezsurfc`	Easy to use combination surface/contour plotter
`fplot`	Plot a function

Histograms

`hist`	Plot histograms
`histc`	Histogram count
`rose`	Plot rose or angle histogram

Polygons and Surfaces

`convhull`	Convex hull
`cylinder`	Generate cylinder
`delaunay`	Delaunay triangulation
`dsearch`	Search Delaunay triangulation for nearest point
`ellipsoid`	Generate ellipsoid
`fill`	Draw filled 2-D polygons
`fill3`	Draw filled 3-D polygons in 3-space
`inpolygon`	True for points inside a polygonal region
`pcolor`	Pseudocolor (checkerboard) plot
`polyarea`	Area of polygon
`ribbon`	Ribbon plot
`slice`	Volumetric slice plot
`sphere`	Generate sphere
`tsearch`	Search for enclosing Delaunay triangle
`voronoi`	Voronoi diagram
`waterfall`	Waterfall plot

Scatter/Bubble Plots

`plotmatrix`	Scatter plot matrix
`scatter`	Scatter plot
`scatter3`	3-D scatter plot

Animation

`frame2im`	Convert movie frame to indexed image
`getframe`	Capture movie frame
`im2frame`	Convert image to movie frame
`movie`	Play recorded movie frames
`noanimate`	Change `EraseMode` of all objects to `normal`

Bit-Mapped Images

`frame2im`	Convert movie frame to indexed image
`image`	Display image object
`imagesc`	Scale data and display image object
`imfinfo`	Information about graphics file
`imformats`	Manage file format registry
`im2frame`	Convert image to movie frame
`im2java`	Convert image to instance of Java image object
`imread`	Read image from graphics file
`imwrite`	Write image to graphics file
`ind2rgb`	Convert indexed image to RGB image

Printing

`frameedit`	Edit print frame for Simulink and Stateflow diagram
`orient`	Hardcopy paper orientation
`pagesetupdlg`	Page setup dialog box
`print`	Print graph or save graph to file
`printdlg`	Print dialog box
`printopt`	Configure local printer defaults
`printpreview`	Preview figure to be printed
`saveas`	Save figure to graphic file

Handle Graphics

- Finding and Identifying Graphics Objects
- Object Creation Functions
- Figure Windows
- Axes Operations

Finding and Identifying Graphics Objects

`allchild`	Find all children of specified objects
`ancestor`	Find ancestor of graphics object
`copyobj`	Make copy of graphics object and its children
`delete`	Delete files or graphics objects
`findall`	Find all graphics objects (including hidden handles)
`figflag`	Test if figure is on screen
`findfigs`	Display off-screen visible figure windows
`findobj`	Find objects with specified property values
`gca`	Get current Axes handle
`gcbo`	Return object whose callback is currently executing
`gcbf`	Return handle of figure containing callback object
`gco`	Return handle of current object
`get`	Get object properties
`ishandle`	True if value is valid object handle
`set`	Set object properties

Object Creation Functions

`axes`	Create axes object
`figure`	Create figure (graph) windows
`hggroup`	Create a group object
`hgtransform`	Create a group to transform
`image`	Create image (2-D matrix)
`light`	Create light object (illuminates Patch and Surface)
`line`	Create line object (3-D polylines)
`patch`	Create patch object (polygons)
`rectangle`	Create rectangle object (2-D rectangle)
`rootobject`	List of root properties
`surface`	Create surface (quadrilaterals)
`text`	Create text object (character strings)
`uicontextmenu`	Create context menu (popup associated with object)

Plot Objects

`areaseries`	Property list
`barseries`	Property list
`contourgroup`	Property list
`errorbarseries`	Property list
`lineseries`	Property list
`quivergroup`	Property list
`scattergroup`	Property list
`stairseries`	Property list
`stemseries`	Property list
`surfaceplot`	Property list

Figure Windows

`clc`	Clear figure window
`clf`	Clear figure
`close`	Close specified window
`closereq`	Default close request function
`drawnow`	Complete any pending drawing
`figflag`	Test if figure is on screen
`gcf`	Get current figure handle
`hgload`	Load graphics object hierarchy from a FIG-file
`hgsave`	Save graphics object hierarchy to a FIG-file
`newplot`	Graphics M-file preamble for `NextPlot` property
`opengl`	Change automatic selection mode of OpenGL rendering
`refresh`	Refresh figure
`saveas`	Save figure or model to desired output format

Axes Operations

`axis`	Plot axis scaling and appearance
`box`	Display axes border
`cla`	Clear Axes
`gca`	Get current Axes handle
`grid`	Grid lines for 2-D and 3-D plots
`ishold`	Get the current hold state
`makehgtform`	Create a transform matrix

Operating on Object Properties

`get`	Get object properties
linkaxes	Synchronize limits of specified axes
linkprop	Maintain same value for corresponding properties
`set`	Set object properties

3-D Visualization

Create and manipulate graphics that display 2-D matrix and 3-D volume data, controlling the view, lighting and transparency.

Surface and Mesh Plots	Plot matrices, visualize functions of two variables, specify colormap
View Control	Control the camera viewpoint, zooming, rotation, aspect ratio, set axis limits
Lighting	Add and control scene lighting
Transparency	Specify and control object transparency
Volume Visualization	Visualize gridded volume data

Surface and Mesh Plots

- Creating Surfaces and Meshes
- Domain Generation
- Color Operations
- Colormaps

Creating Surfaces and Meshes

`hidden`	Mesh hidden line removal mode
`meshc`	Combination mesh/contourplot
`mesh`	3-D mesh with reference plane
`peaks`	A sample function of two variables
`surf`	3-D shaded surface graph
`surface`	Create surface low-level objects
`surfc`	Combination surf/contourplot
`surfl`	3-D shaded surface with lighting
`tetramesh`	Tetrahedron mesh plot
`trimesh`	Triangular mesh plot
`triplot`	2-D triangular plot
`trisurf`	Triangular surface plot

Domain Generation

`griddata`	Data gridding and surface fitting
`meshgrid`	Generation of X and Y arrays for 3-D plots

Color Operations

`brighten`	Brighten or darken colormap
`caxis`	Pseudocolor axis scaling
`colormapeditor`	Start colormap editor
`colorbar`	Display color bar (color scale)
`colordef`	Set up color defaults
`colormap`	Set the color look-up table (list of colormaps)
`ColorSpec`	Ways to specify color
`graymon`	Graphics figure defaults set for grayscale monitor
`hsv2rgb`	Hue-saturation-value to red-green-blue conversion
`rgb2hsv`	RGB to HSVconversion
`rgbplot`	Plot colormap
`shading`	Color shading mode
`spinmap`	Spin the colormap
`surfnorm`	3-D surface normals
`whitebg`	Change axes background color for plots

Colormaps

`autumn`	Shades of red and yellow colormap
`bone`	Gray-scale with a tinge of blue colormap
`contrast`	Gray colormap to enhance image contrast
`cool`	Shades of cyan and magenta colormap
`copper`	Linear copper-tone colormap
`flag`	Alternating red, white, blue, and black colormap
`gray`	Linear gray-scale colormap
`hot`	Black-red-yellow-white colormap
`hsv`	Hue-saturation-value (HSV) colormap
`jet`	Variant of HSV
`lines`	Line color colormap
`prism`	Colormap of prism colors
`spring`	Shades of magenta and yellow colormap
`summer`	Shades of green and yellow colormap
`winter`	Shades of blue and green colormap

View Control

- Controlling the Camera Viewpoint
- Setting the Aspect Ratio and Axis Limits
- Object Manipulation
- Selecting Region of Interest

Controlling the Camera Viewpoint

`camdolly`	Move camera position and target
`camlookat`	View specific objects
`camorbit`	Orbit about camera target
`campan`	Rotate camera target about camera position
`campos`	Set or get camera position
`camproj`	Set or get projection type
`camroll`	Rotate camera about viewing axis
`camtarget`	Set or get camera target
`cameratoolbar`	Control camera toolbar programmatically
`camup`	Set or get camera up-vector
`camva`	Set or get camera view angle
`camzoom`	Zoom camera in or out
`view`	3-D graph viewpoint specification.
`viewmtx`	Generate view transformation matrices
`makehgtform`	Create a transform matrix

Setting the Aspect Ratio and Axis Limits

`daspect`	Set or get data aspect ratio
`pbaspect`	Set or get plot box aspect ratio
`xlim`	Set or get the current *x*-axis limits
`ylim`	Set or get the current *y*-axis limits
`zlim`	Set or get the current *z*-axis limits

Object Manipulation

`pan`	Turns panning on or off
`reset`	Reset axis or figure
`rotate`	Rotate objects about specified origin and direction
`rotate3d`	Interactively rotate the view of a 3-D plot
`selectmoveresize`	Interactively select, move, or resize objects
`zoom`	Zoom in and out on a 2-D plot

Selecting Region of Interest

`dragrect`	Drag XOR rectangles with mouse
`rbbox`	Rubberband box

Lighting

`camlight`	Cerate or position Light
`light`	Light object creation function
`lightangle`	Position light in sphereical coordinates
`lighting`	Lighting mode
`material`	Material reflectance mode

Transparency

`alpha`	Set or query transparency properties for objects in current axes
`alphamap`	Specify the figure alphamap
`alim`	Set or query the axes alpha limits

Volume Visualization

`coneplot`	Plot velocity vectors as cones in 3-D vector field
`contourslice`	Draw contours in volume slice plane
`curl`	Compute curl and angular velocity of vector field
`divergence`	Compute divergence of vector field
`flow`	Generate scalar volume data
`interpstreamspeed`	Interpolate streamline vertices from vector-field magnitudes
`isocaps`	Compute isosurface end-cap geometry
`isocolors`	Compute colors of isosurface vertices
`isonormals`	Compute normals of isosurface vertices
`isosurface`	Extract isosurface data from volume data
`reducepatch`	Reduce number of patch faces
`reducevolume`	Reduce number of elements in volume data set
`shrinkfaces`	Reduce size of patch faces
`slice`	Draw slice planes in volume
`smooth3`	Smooth 3-D data
`stream2`	Compute 2-D stream line data
`stream3`	Compute 3-D stream line data
`streamline`	Draw stream lines from 2- or 3-D vector data
`streamparticles`	Draws stream particles from vector volume data
`streamribbon`	Draws stream ribbons from vector volume data
`streamslice`	Draws well-spaced stream lines from vector volume data
`streamtube`	Draws stream tubes from vector volume data
`surf2patch`	Convert surface data to patch data
`subvolume`	Extract subset of volume data set
`volumebounds`	Return coordinate and color limits for volume (scalar and vector)

Creating Graphical User Interfaces

Predefined dialog boxes and functions to control GUI programs.

Predefined Dialog Boxes	Dialog boxes for error, user input, waiting, etc.
Deploying User Interfaces	Launching GUIs, creating the handles structure
Developing User Interfaces	Starting GUIDE, managing application data, getting user input
User Interface Objects	Creating GUI components
Finding Objects from Callbacks	Finding object handles from within callbacks functions
GUI Utility Functions	Moving objects, text wrapping
Controlling Program Execution	Wait and resume based on user input

Predefined Dialog Boxes

`dialog`	Create dialog box
`errordlg`	Create error dialog box
`helpdlg`	Display help dialog box
`inputdlg`	Create input dialog box
`listdlg`	Create list selection dialog box
`msgbox`	Create message dialog box
`pagesetupdlg`	Page setup dialog box
`printdlg`	Display print dialog box
`questdlg`	Create question dialog box
`uigetdir`	Display dialog box to retrieve name of directory
`uigetfile`	Display dialog box to retrieve name of file for reading
`uiputfile`	Display dialog box to retrieve name of file for writing
`uisetcolor`	Set `ColorSpec` using dialog box
`uisetfont`	Set font using dialog box
`waitbar`	Display wait bar
`warndlg`	Create warning dialog box

Deploying User Interfaces

`guidata`	Store or retrieve application data
`guihandles`	Create a structure of handles
`movegui`	Move GUI figure onscreen
`openfig`	Open or raise GUI figure

Developing User Interfaces

`guide`	Open GUI Layout Editor
`inspect`	Display Property Inspector

Working with Application Data

`getappdata`	Get value of application data
`isappdata`	True if application data exists
`rmappdata`	Remove application data
`setappdata`	Specify application data

Interactive User Input

`ginput`	Graphical input from a mouse or cursor
`waitfor`	Wait for conditions before resuming execution
`waitforbuttonpress`	Wait for key/buttonpress over figure

User Interface Objects

`menu`	Generate menu of choices for user input
`uibuttongroup`	Create component to exclusively manage radiobuttons and togglebuttons
`uicontextmenu`	Create context menu
`uicontrol`	Create user interface control
`uimenu`	Create user interface menu
`uipanel`	Create panel container object
`uipushtool`	Create toolbar push button
`uitoggletool`	Create toolbar toggle button
`uitoolbar`	Create toolbar

Finding Objects from Callbacks

`findall`	Find all graphics objects
`findfigs`	Display off-screen visible figure windows
`findobj`	Find specific graphics object
`gcbf`	Return handle of figure containing callback object
`gcbo`	Return handle of object whose callback is executing

2

Functions — Alphabetical List

pack

2pack

Purpose

Consolidate workspace memory

Syntax

```
pack
pack filename
pack('filename')
```

Description

`pack` frees up needed space by reorganizing information so it only uses the minimum memory required. You must run `pack` from a directory for which you have write permission. Running `pack` clears all variables not in the base workspace, so persistent variables, for example, will be cleared.

`pack filename` accepts an optional `filename` for the temporary file used to hold the variables. Otherwise, it uses the file named `pack.tmp`. You must run `pack` from a directory for which you have write permission.

`pack('filename')` is the function form of `pack`.

Remarks

The `pack` function does not affect the amount of memory allocated to the MATLAB process. You must quit MATLAB to free up this memory.

Since MATLAB uses a heap method of memory management, extended MATLAB sessions may cause memory to become fragmented. When memory is fragmented, there may be plenty of free space, but not enough contiguous memory to store a new large variable.

If you get the `Out of memory` message from MATLAB, the `pack` function may find you some free memory without forcing you to delete variables.

The `pack` function frees space by:

- Saving all variables in the base workspace to disk in a temporary file called `pack.tmp`
- Clearing all variables and functions from memory
- Reloading the base workspace variables back from `pack.tmp`
- Deleting the temporary file `pack.tmp`

If you use `pack` and there is still not enough free memory to proceed, you must clear some variables. If you run out of memory often, you can allocate larger matrices earlier in the MATLAB session and use these system-specific tips:

- UNIX: Ask your system manager to increase your swap space.
- Windows: Increase virtual memory using the Windows Control Panel.

To maintain persistent variables when you run pack, use `mlock` in the function.

Examples

Change the current directory to one that is writable, run `pack`, and return to the previous directory.

```
cwd = pwd;
cd(tempdir);
pack
cd(cwd)
```

See Also

`clear`, `memory`

pagesetupdlg

Purpose

Page position dialog box

Syntax

```
dlg = pagesetupdlg(fig)
```

Description

`dlg = pagesetupdlg(fig)` creates a dialog box from which a set of pagelayout properties for the figure window, `fig`, can be set.

`pagesetupdlg` implements the "Page Setup..." option in the **Figure File Menu**.

Unlike `pagedlg`, `pagesetupdlg` currently only supports setting the layout for a single figure. `fig` must be a single figure handle, not a vector of figures or a simulink diagram.



See Also

`printpreview`, `printopt`

Purpose

Pan the view of a graph interactively

Syntax

```
pan on
pan xon
pan yon
pan off
pan
pan(figure_handle,...)
```

Description

`pan on` truns on mouse-based panning in the current figure.

`pan xon` turns on panning only in the *x* direction in the current figure.

`pan yon` turns on panning only in the *y* direction in the current figure.

`pan off` turns panning off in the current figure.

`pan` toggles the pan state in the current figure `on` or `off`.

`pan(figure_handle,...)` sets the pan state in the specified figure.

See Also

`zoom`, `linkaxes`

"Object Manipulation" for related functions

pareto

Purpose

Pareto chart

Syntax

```
pareto(Y)
pareto(Y,names)
pareto(Y,X)
H = pareto(...)
```

Description

Pareto charts display the values in the vector `Y` as bars drawn in descending order.

`pareto(Y)` labels each bar with its element index in `Y`.

`pareto(Y,names)` labels each bar with the associated name in the string matrix or cell array `names`.

`pareto(Y,X)` labels each bar with the associated value from `X`.

`H = pareto(...)` returns a combination of patch and line object handles.

See Also

`hist`, `bar`

Purpose

Partial pathname

Description

A partial pathname is a pathname relative to the MATLAB path, `matlabpath`. It is used to locate private and method files, which are usually hidden, or to restrict the search for files when more than one file with the given name exists.

A partial pathname contains the last component, or last several components, of the full pathname separated by `/`. For example, `matfun/trace`, `private/children`, and `demos/clown.mat` are valid partial pathnames. Specifying the `@` in method directory names is optional.

Partial pathnames make it easy to find toolbox or MATLAB relative files on your path, independent of the location where MATLAB is installed.

Many commands accept partial pathnames instead of a full pathname. Some of these commands are

```
help, type, load, exist, what, which, edit, dbtype, dbstop,
dbclear, and fopen
```

Examples

The following example uses a partial pathname:

```
what graph2d/@figobj

M-files in directory matlabroot\toolbox\matlab\graph2d\@figobj

deselectall    doresize     figobj     middrag     subsasgn
doclick        enddrag      get        set         subsref

P-files in directory matlabroot\toolbox\matlab\graph2d\@figobj

deselectall    doresize     figobj     middrag     subsasgn
doclick        enddrag      get        set         subsref
```

The `@` in the class directory name `@figobj` is not necessary. You get the same response from the following command:

```
what graph2d/figobj
```

See Also

`fileparts`, `matlabroot`, `path`

pascal

Purpose

Pascal matrix

Syntax

```
A = pascal(n)
A = pascal(n,1)
A = pascal(n,2)
```

Description

`A = pascal(n)` returns the Pascal matrix of order `n`: a symmetric positive definite matrix with integer entries taken from Pascal's triangle. The inverse of `A` has integer entries.

`A = pascal(n,1)` returns the lower triangular Cholesky factor (up to the signs of the columns) of the Pascal matrix. It is *involutary*, that is, it is its own inverse.

`A = pascal(n,2)` returns a transposed and permuted version of `pascal(n,1)`. `A` is a cube root of the identity matrix.

Examples

`pascal(4)` returns

```
   1     1     1     1
   1     2     3     4
   1     3     6    10
   1     4    10    20
```

`A = pascal(3,2)` produces

```
   A =
        1     1     1
       -2    -1     0
        1     0     0
```

See Also

`chol`

Purpose

Create patch graphics object

Syntax

```
patch(X,Y,C)
patch(X,Y,Z,C)
patch(FV)
patch(...'PropertyName',PropertyValue...)
patch('PropertyName',PropertyValue...) PN/PV pairs only
handle = patch(...)
```

Description

`patch` is the low-level graphics function for creating patch graphics objects. A patch object is one or more polygons defined by the coordinates of its vertices. You can specify the coloring and lighting of the patch. See Creating 3-D Models with Patches for more information on using patch objects.

`patch(X,Y,C)` adds the filled two-dimensional patch to the current axes. The elements of `X` and `Y` specify the vertices of a polygon. If `X` and `Y` are matrices, MATLAB draws one polygon per column. `C` determines the color of the patch. It can be a single `ColorSpec`, one color per face, or one color per vertex (see "Remarks"). If C is a 1-by-3 vector, it is assumed to be an RGB triplet, specifying a color directly.

`patch(X,Y,Z,C)` creates a patch in three-dimensional coordinates.

`patch(FV)` creates a patch using structure `FV`, which contains the fields `vertices`, `faces`, and optionally `facevertexdata`. These fields correspond to the `Vertices`, `Faces`, and `FaceVertexCData` patch properties.

`patch(...'PropertyName',PropertyValue...)` follows the `X`, `Y`, `(Z)`, and `C` arguments with property name/property value pairs to specify additional patch properties.

`patch('PropertyName',PropertyValue,...)` specifies all properties using property name/property value pairs. This form enables you to omit the color specification because MATLAB uses the default face color and edge color unless you explicitly assign a value to the `FaceColor` and `EdgeColor` properties. This form also allows you to specify the patch using the `Faces` and `Vertices` properties instead of *x*-, *y*-, and *z*-coordinates. See the "Examples" section for more information.

`handle = patch(...)` returns the handle of the patch object it creates.

Remarks

Unlike high-level area creation functions, such as `fill` or `area`, `patch` does not check the settings of the figure and axes `NextPlot` properties. It simply adds the patch object to the current axes.

If the coordinate data does not define closed polygons, `patch` closes the polygons. The data can define concave or intersecting polygons. However, if the edges of an individual patch face intersect themselves, the resulting face may or may not be completely filled. In that case, it is better to break up the face into smaller polygons.

Specifying Patch Properties

You can specify properties as property name/property value pairs, structure arrays, and cell arrays (see the `set` and `get` reference pages for examples of how to specify these data types).

There are two patch properties that specify color:

- `CData` — Use when specifying *x*-, *y*-, and *z*-coordinates (`XData`, `YData`, `ZData`).
- `FaceVertexCData` — Use when specifying vertices and connection matrix (`Vertices` and `Faces`).

The `CData` and `FaceVertexCData` properties accept color data as indexed or true color (RGB) values. See the `CData` and `FaceVertexCData` property descriptions for information on how to specify color.

Indexed color data can represent either direct indices into the colormap or scaled values that map the data linearly to the entire colormap (see the `caxis` function for more information on this scaling). The `CDataMapping` property determines how MATLAB interprets indexed color data.



Color Data Interpretation

You can specify patch colors as

- A single color for all faces
- One color for each face, enabling flat coloring
- One color for each vertex, enabling interpolated coloring

The following tables summarize how MATLAB interprets color data defined by the `CData` and `FaceVertexCData` properties.

Interpretation of the CData Property

[X,Y,Z]Data Dimensions	CData Required for Indexed	CData Required for True Color	Results Obtained
m-by-n	scalar	1-by-1-by-3	Use the single color specified for all patch faces. Edges can be only a single color.

[X,Y,Z]Data Dimensions	CData Required for Indexed	CData Required for True Color	Results Obtained
m-by-n	1-by-n (n >= 4)	1-by-n-by-3	Use one color for each patch face. Edges can be only a single color.
m-by-n	m-by-n	m-by-n-3	Assign a color to each vertex. Patch faces can be flat (a single color) or interpolated. Edges can be flat or interpolated.

Interpretation of the FaceVertexCData Property

Vertices Dimensions	Faces Dimensions	FaceVertexCData Required for Indexed	FaceVertexCData Required for True Color	Results Obtained
m-by-n	k-by-3	scalar	1-by-3	Use the single color specified for all patch faces. Edges can be only a single color.
m-by-n	k-by-3	k-by-1	k-by-3	Use one color for each patch face. Edges can be only a single color.
m-by-n	k-by-3	m-by-1	m-by-3	Assign a color to each vertex. Patch faces can be flat (a single color) or interpolated. Edges can be flat or interpolated.

Examples

This example creates a patch object using two different methods:

- Specifying *x*-, *y*-, and *z*-coordinates and color data (`XData`, `YData`, `ZData`, and `CData` properties)
- Specifying vertices, the connection matrix, and color data (`Vertices`, `Faces`, `FaceVertexCData`, and `FaceColor` properties)

Specifying X, Y, and Z Coordinates

The first approach specifies the coordinates of each vertex. In this example, the coordinate data defines two triangular faces, each having three vertices. Using true color, the top face is set to white and the bottom face to gray.

```
x = [0 0;0 1;1 1];
y = [1 1;2 2;2 1];
z = [1 1;1 1;1 1];
tcolor(1,1,1:3) = [1 1 1];
tcolor(1,2,1:3) = [.7 .7 .7];
patch(x,y,z,tcolor)
```



Notice that each face shares two vertices with the other face (V_1-V_4 and V_3-V_5).

Specifying Vertices and Faces

The `Vertices` property contains the coordinates of each *unique* vertex defining the patch. The `Faces` property specifies how to connect these vertices to form each face of the patch. For this example, two vertices share the same location so you need to specify only four of the six vertices. Each row contains the *x*-, *y*-, and *z*-coordinates of each vertex.

```
vert = [0 1 1;0 2 1;1 2 1;1 1 1];
```

There are only two faces, defined by connecting the vertices in the order indicated.

```
fac = [1 2 3;1 3 4];
```

To specify the face colors, define a 2-by-3 matrix containing two RGB color definitions.

```
tcolor = [1 1 1;.7 .7 .7];
```

With two faces and two colors, MATLAB can color each face with flat shading. This means you must set the `FaceColor` property to `flat`, since the faces/vertices technique is available only as a low-level function call (i.e., only by specifying property name/property value pairs).

Create the patch by specifying the `Faces`, `Vertices`, and `FaceVertexCData` properties as well as the `FaceColor` property.

```
patch('Faces',fac,'Vertices',vert,'FaceVertexCData',tcolor,...
      'FaceColor','flat')
```



Specifying only unique vertices and their connection matrix can reduce the size of the data for patches having many faces. See the descriptions of the `Faces`, `Vertices`, and `FaceVertexCData` properties for information on how to define them.

MATLAB does not require each face to have the same number of vertices. In cases where they do not, pad the `Faces` matrix with `NaNs`. To define a patch

with faces that do not close, add one or more `NaNs` to the row in the `Vertices` matrix that defines the vertex you do not want connected.

Object Hierarchy



Setting Default Properties

You can set default patch properties on the axes, figure, and root levels:

```
set(0,'DefaultPatchPropertyName',PropertyValue...)
set(gcf,'DefaultPatchPropertyName',PropertyValue...)
set(gca,'DefaultPatchPropertyName',PropertyValue...)
```

PropertyName is the name of the patch property and `PropertyValue` is the value you are specifying. Use `set` and `get` to access patch properties.

Property List

The following table lists all patch properties and provides a brief description of each. The property name links take you to an expanded description of the properties.

Property Name	Property Description	Property Value
Data Defining the Object		
`Faces`	Connection matrix for `Vertices`	Values: `m`-by-`n` matrix Default: `[1,2,3]`
`Vertices`	Matrix of *x*-, *y*-, and *z*-coordinates of the vertices (used with `Faces`)	Value: matrix Default: `[0,1;1,1;0,0]`
`XData`	The *x*-coordinates of the vertices of the patch	Value: vector or matrix Default: `[0;1;0]`

Property Name	Property Description	Property Value
YData	The *y*-coordinates of the vertices of the patch	Value: vector or matrix Default: `[1;1;0]`
ZData	The *z*-coordinates of the vertices of the patch	Value: vector or matrix Default: `[]` (empty matrix)
Specifying Color		
CData	Color data for use with the `XData/YData/ZData` method	Value: scalar, vector, or matrix Default: `[]` (empty matrix)
CDataMapping	Controls mapping of `CData` to colormap	Values: `scaled`, `direct` Default: `scaled`
EdgeColor	Color of face edges	Values: `ColorSpec`, `none`, `flat`, `interp` Default: `ColorSpec`
FaceColor	Color of face	Values: `ColorSpec`, `none`, `flat`, `interp` Default: `ColorSpec`
FaceVertexCData	Color data for use with `Faces/Vertices` method	Value: matrix Default: `[]` (empty matrix)
MarkerEdgeColor	Color of marker or the edge color for filled markers	Values: `ColorSpec`, `none`, `auto` Default: `auto`
MarkerFaceColor	Fill color for markers that are closed shapes	Values: `ColorSpec`, `none`, `auto` Default: `none`
Controlling the Effects of Lights		
AmbientStrength	Intensity of the ambient light	Value: scalar `>=0` and `<=1` Default: `0.3`

Property Name	Property Description	Property Value
BackFaceLighting	Controls lighting of faces pointing away from camera	Values: unlit, lit, reverselit Default: reverselit
DiffuseStrength	Intensity of diffuse light	Value: scalar >=0 and <=1 Default: 0.6
EdgeLighting	Method used to light edges	Values: none, flat, gouraud, phong Default: none
FaceLighting	Method used to light edges	Values: none, flat, gouraud, phong Default: none
NormalMode	MATLAB generated or user-specified normal vectors	Values: auto, manual Default: auto
SpecularColorReflectance	Composite color of specularly reflected light	Value: scalar 0 to 1 Default: 1
SpecularExponent	Harshness of specular reflection	Value: scalar >= 1 Default: 10
SpecularStrength	Intensity of specular light	Value: scalar >=0 and <=1 Default: 0.9
VertexNormals	Vertex normal vectors	Value: matrix
Defining Edges and Markers		
LineStyle	Select from five line styles.	Values: –, ––, :, –., none Default: –
LineWidth	The width of the edge in points	Value: scalar Default: 0.5 points
Marker	Marker symbol to plot at data points	Values: see Marker property Default: none

Property Name	Property Description	Property Value
MarkerSize	Size of marker in points	Value: size in points Default: 6
Specifying Transparency		
AlphaDataMapping	Transparency mapping method	Values: none, direct, scaled Default: scaled
EdgeAlpha	Transparency of the edges of patch faces	Values: scalar, flat, interp Default: 1 (opaque)
FaceAlpha	Transparency of the patch face	Values: scalar, flat, interp Default: 1 (opaque)
FaceVertexAlphaData	Face and vertex transparency data	Value: m-by-1 matrix
Controlling the Appearance		
Clipping	Clipping to axes rectangle	Values: on, off Default: on
EraseMode	Method of drawing and erasing the patch (useful for animation)	Values: normal, none, xor, background Default: normal
SelectionHighlight	Highlights patch when selected (Selected property set to on)	Values: on, off Default: on
Visible	Makes the patch visible or invisible	Values: on, off Default: on
Controlling Access to Objects		
HandleVisibility	Determines if and when the patch's handle is visible to other functions	Values: on, callback, off Default: on

Property Name	Property Description	Property Value
`HitTest`	Determines if the patch can become the current object (see the figure `CurrentObject` property)	Values: `on`, `off` Default: `on`
Controlling Callback Routine Execution		
`BeingDeleted`	Query to see if object is being deleted.	Values: on | off Read only
`BusyAction`	Specifies how to handle callback routine interruption	Values: `cancel`, `queue` Default: `queue`
`ButtonDownFcn`	Defines a callback routine that executes when a mouse button is pressed on over the patch	Value: string or function handle Default: `''` (empty string)
`CreateFcn`	Defines a callback routine that executes when a patch is created	Value: string or function handle Default: `''` (empty string)
`DeleteFcn`	Defines a callback routine that executes when the patch is deleted (via `close` or `delete`)	Value: string or function handle Default: `''` (empty string)
`Interruptible`	Determines if callback routine can be interrupted	Values: `on`, `off` Default: `on` (can be interrupted)
`UIContextMenu`	Associates a context menu with the patch	Value: handle of a Uicontrextmenu
General Information About the Patch		
`Children`	Patch objects have no children.	Value: `[]` (empty matrix)
`Parent`	The parent of a patch object is an axes, hggroup, or hgtransform object.	Value: object handle

Property Name	Property Description	Property Value
`Selected`	Indicates whether the patch is in a selected state	Values: `on`, `off` Default: `on`
`Tag`	User-specified label	Value: any string Default: `''` (empty string)
`Type`	The type of graphics object (read only)	Value: the string `'patch'`
`UserData`	User-specified data	Value: any matrix Default: `[]` (empty matrix)

See Also `area`, `caxis`, `fill`, `fill3`, `isosurface`, `surface`

Modifying Properties

You can set and query graphics object properties in two ways:

- The Property Editor is an interactive tool that enables you to see and change object property values.
- The `set` and `get` commands enable you to set and query the values of properties.

To change the default values of properties, see Setting Default Property Values.

See Core Objects for general information about this type of object.

Patch Property Descriptions

This section lists property names along with the type of values each accepts. Curly braces { } enclose default values.

`AlphaDataMapping` `none | direct | {scaled}`

Transparency mapping method. This property determines how MATLAB interprets indexed alpha data. This property can be any of the following:

- `none` — The transparency values of `FaceVertexAlphaData` are between 0 and 1 or are clamped to this range (the default).
- `scaled` — Transform the `FaceVertexAlphaData` to span the portion of the alphamap indicated by the axes `ALim` property, linearly mapping data values to alpha values.
- `direct` — Use the `FaceVertexAlphaData` as indices directly into the alphamap. When not scaled, the data are usually integer values ranging from `1` to `length(alphamap)`. MATLAB maps values less than `1` to the first alpha value in the alphamap, and values greater than `length(alphamap)` to the last alpha value in the alphamap. Values with a decimal portion are fixed to the nearest lower integer. If `FaceVertexAlphaData` is an array of `uint8` integers, then the indexing begins at `0` (i.e., MATLAB maps a value of `0` to the first alpha value in the alphamap).

`AmbientStrength` scalar >= 0 and <= 1

Strength of ambient light. This property sets the strength of the ambient light, which is a nondirectional light source that illuminates the entire scene. You must have at least one visible light object in the axes for the ambient light to be visible. The axes `AmbientColor` property sets the color of the ambient light, which is therefore the same on all objects in the axes.

You can also set the strength of the diffuse and specular contribution of light objects. See the `DiffuseStrength` and `SpecularStrength` properties.

`BackFaceLighting` `unlit | lit | {reverselit}`

Face lighting control. This property determines how faces are lit when their vertex normals point away from the camera:

- `unlit` — Face is not lit.
- `lit` — Face is lit in normal way.
- `reverselit` — Face is lit as if the vertex pointed towards the camera.

This property is useful for discriminating between the internal and external surfaces of an object. See the Using MATLAB Graphics manual for an example.

`BeingDeleted` `on | {off}` Read Only

This object is being deleted. The `BeingDeleted` property provides a mechanism that you can use to determine if objects are in the process of being deleted. MATLAB sets the `BeingDeleted` property to `on` when the object's delete function callback is called (see the `DeleteFcn` property) It remains set to `on` while the delete function executes, after which the object no longer exists.

For example, an object's delete function might call other functions that act on a number of different objects. These functions may not need to perform actions on objects that are going to be deleted, and therefore, can check the object's `BeingDeleted` property before acting.

`BusyAction` `cancel | {queue}`

Callback routine interruption. The `BusyAction` property enables you to control how MATLAB handles events that potentially interrupt executing callback routines. If there is a callback routine executing, callback routines invoked subsequently always attempt to interrupt it. If the `Interruptible` property of the object whose callback is executing is set to `on` (the default), then interruption occurs at the next point where the event queue is processed. If the `Interruptible` property is `off`, the `BusyAction` property (of the object owning the executing callback) determines how MATLAB handles the event. The choices are

- `cancel` — Discard the event that attempted to execute a second callback routine.

- queue — Queue the event that attempted to execute a second callback routine until the current callback finishes.

ButtonDownFcn string or function handle

Button press callback routine. A callback routine that executes whenever you press a mouse button while the pointer is over the patch object. Define this routine as a string that is a valid MATLAB expression or the name of an M-file. The expression executes in the MATLAB workspace.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

CData scalar, vector, or matrix

Patch colors. This property specifies the color of the patch. You can specify color for each vertex, each face, or a single color for the entire patch. The way MATLAB interprets `CData` depends on the type of data supplied. The data can be numeric values that are scaled to map linearly into the current colormap, integer values that are used directly as indices into the current colormap, or arrays of RGB values. RGB values are not mapped into the current colormap, but interpreted as the colors defined. On true color systems, MATLAB uses the actual colors defined by the RGB triples.

The following two diagrams illustrate the dimensions of `CData` with respect to the coordinate data arrays, `XData`, `YData`, and `ZData`. The first diagram illustrates the use of indexed color.



The second diagram illustrates the use of true color. True color requires *m*-by-*n*-by-3 arrays to define red, green, and blue components for each color.



Note that if `CData` contains `NaNs`, MATLAB does not color the faces.

See also the `Faces`, `Vertices`, and `FaceVertexCData` properties for an alternative method of patch definition.

`CDataMapping` `{scaled} | direct`

Direct or scaled color mapping. This property determines how MATLAB interprets indexed color data used to color the patch. (If you use true color specification for `CData` or `FaceVertexCData`, this property has no effect.)

- `scaled` — Transform the color data to span the portion of the colormap indicated by the axes `CLim` property, linearly mapping data values to colors. See the `caxis` command for more information on this mapping.
- `direct` — Use the color data as indices directly into the colormap. When not scaled, the data are usually integer values ranging from 1 to `length(colormap)`. MATLAB maps values less than 1 to the first color in the colormap, and values greater than `length(colormap)` to the last color in the

colormap. Values with a decimal portion are fixed to the nearest lower integer.

`Children` matrix of handles

Always the empty matrix; patch objects have no children.

`Clipping` `{on} | off`

Clipping to axes rectangle. When `Clipping` is `on`, MATLAB does not display any portion of the patch outside the axes rectangle.

`CreateFcn` string or function handle

Callback routine executed during object creation. This property defines a callback routine that executes when MATLAB creates a patch object. You must define this property as a default value for patches or in a call to the `patch` function that creates a new object.

For example, the following statement creates a patch (assuming `x`, `y`, `z`, and `c` are defined), and executes the function referenced by the function handle `@myCreateFcn`.

```
patch(x,y,z,c,'CreateFcn',@myCreateFcn)
```

MATLAB executes the create function after setting all properties for the patch created. Setting this property on an existing patch object has no effect.

The handle of the object whose `CreateFcn` is being executed is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

`DeleteFcn` string or function handle

Delete patch callback routine. A callback routine that executes when you delete the patch object (e.g., when you issue a `delete` command or clear the axes (`cla`) or figure (`clf`) containing the patch). MATLAB executes the routine before deleting the object's properties so these values are available to the callback routine.

The handle of the object whose `DeleteFcn` is being executed is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

`DiffuseStrength` scalar >= 0 and <= 1

Intensity of diffuse light. This property sets the intensity of the diffuse component of the light falling on the patch. Diffuse light comes from light objects in the axes.

You can also set the intensity of the ambient and specular components of the light on the patch object. See the `AmbientStrength` and `SpecularStrength` properties.

`EdgeAlpha` `{scalar = 1} | flat | interp`

Transparency of the edges of patch faces. This property can be any of the following:

- scalar — A single non-NaN scalar value between `0` and `1` that controls the transparency of all the edges of the object. `1` (the default) means fully opaque and `0` means completely transparent.
- `flat` — The alpha data (`FaceVertexAlphaData`) of each vertex controls the transparency of the edge that follows it.
- `interp` — Linear interpolation of the alpha data (`FaceVertexAlphaData`) at each vertex determines the transparency of the edge.

Note that you cannot specify `flat` or `interp` `EdgeAlpha` without first setting `FaceVertexAlphaData` to a matrix containing one alpha value per face (`flat`) or one alpha value per vertex (`interp`).

`EdgeColor` `{ColorSpec} | none | flat | interp`

Color of the patch edge. This property determines how MATLAB colors the edges of the individual faces that make up the patch.

- `ColorSpec` — A three-element RGB vector or one of the MATLAB predefined names, specifying a single color for edges. The default edge color is black. See `ColorSpec` for more information on specifying color.
- `none` — Edges are not drawn.
- `flat` — The color of each vertex controls the color of the edge that follows it. This means `flat` edge coloring is dependent on the order in which you specify the vertices:



- `interp` — Linear interpolation of the `CData` or `FaceVertexCData` values at the vertices determines the edge color.

`EdgeLighting` `{none} | flat | gouraud | phong`

Algorithm used for lighting calculations. This property selects the algorithm used to calculate the effect of light objects on patch edges. Choices are

- `none` — Lights do not affect the edges of this object.
- `flat` — The effect of light objects is uniform across each edge of the patch.
- `gouraud` — The effect of light objects is calculated at the vertices and then linearly interpolated across the edge lines.
- `phong` — The effect of light objects is determined by interpolating the vertex normals across each edge line and calculating the reflectance at each pixel. Phong lighting generally produces better results than Gouraud lighting, but takes longer to render.

`EraseMode` `{normal} | none | xor | background`

Erase mode. This property controls the technique MATLAB uses to draw and erase patch objects. Alternative erase modes are useful in creating animated sequences, where control of the way individual objects redraw is necessary to improve performance and obtain the desired effect.

- `normal` — Redraw the affected region of the display, performing the three-dimensional analysis necessary to ensure that all objects are rendered correctly. This mode produces the most accurate picture, but is the slowest. The other modes are faster, but do not perform a complete redraw and are therefore less accurate.

- `none` — Do not erase the patch when it is moved or destroyed. While the object is still visible on the screen after erasing with `EraseMode none`, you cannot print it because MATLAB stores no information about its former location.
- `xor`— Draw and erase the patch by performing an exclusive OR (XOR) with each pixel index of the screen behind it. Erasing the patch does not damage the color of the objects behind it. However, patch color depends on the color of the screen behind it and is correctly colored only when over the axes background `Color`, or the figure background `Color` if the axes `Color` is set to `none`.
- `background` — Erase the patch by drawing it in the axes background `Color`, or the figure background `Color` if the axes `Color` is set to `none`. This damages objects that are behind the erased patch, but the patch is always properly colored.

Printing with Nonnormal Erase Modes. MATLAB always prints figures as if the `EraseMode` of all objects is `normal`. This means graphics objects created with `EraseMode` set to `none`, `xor`, or `background` can look different on screen than on paper. On screen, MATLAB may mathematically combine layers of colors (e.g., perform an XOR of a pixel color with that of the pixel behind it) and ignore three-dimensional sorting to obtain greater rendering speed. However, these techniques are not applied to the printed output.

You can use the MATLAB `getframe` command or other screen capture application to create an image of a figure containing nonnormal mode objects.

`FaceAlpha` `{scalar = 1} | flat | interp`

Transparency of the patch face. This property can be any of the following:

- A scalar — A single non-NaN value between `0` and `1` that controls the transparency of all the faces of the object. `1` (the default) means fully opaque and `0` means completely transparent (invisible).
- `flat` — The values of the alpha data (`FaceVertexAlphaData`) determine the transparency for each face. The alpha data at the first vertex determines the transparency of the entire face.
- `interp` — Bilinear interpolation of the alpha data (`FaceVertexAlphaData`) at each vertex determines the transparency of each face.

Note that you cannot specify `flat` or `interp` `FaceAlpha` without first setting `FaceVertexAlphaData` to a matrix containing one alpha value per face (`flat`) or one alpha value per vertex (`interp`).

`FaceColor` `{ColorSpec} | none | flat | interp`

Color of the patch face. This property can be any of the following:

- `ColorSpec` — A three-element RGB vector or one of the MATLAB predefined names, specifying a single color for faces. See `ColorSpec` for more information on specifying color.
- `none` — Do not draw faces. Note that edges are drawn independently of faces.
- `flat` — The `CData` or `FaceVertexCData` property must contain one value per face and determines the color for each face in the patch. The color data at the first vertex determines the color of the entire face.
- `interp` — Bilinear interpolation of the color at each vertex determines the coloring of each face.The `CData` or `FaceVertexCData` property must contain one value per vertex.

`FaceLighting` `{none} | flat | gouraud | phong`

Algorithm used for lighting calculations. This property selects the algorithm used to calculate the effect of light objects on patch faces. Choices are

- `none` — Lights do not affect the faces of this object.
- `flat` — The effect of light objects is uniform across the faces of the patch. Select this choice to view faceted objects.
- `gouraud` — The effect of light objects is calculated at the vertices and then linearly interpolated across the faces. Select this choice to view curved surfaces.
- `phong` — The effect of light objects is determined by interpolating the vertex normals across each face and calculating the reflectance at each pixel. Select this choice to view curved surfaces. Phong lighting generally produces better results than Gouraud lighting, but takes longer to render.

`Faces` m-by-n matrix

Vertex connection defining each face. This property is the connection matrix specifying which vertices in the `Vertices` property are connected. The `Faces` matrix defines *m* faces with up to *n* vertices each. Each row designates the

connections for a single face, and the number of elements in that row that are not `NaN` defines the number of vertices for that face.

The `Faces` and `Vertices` properties provide an alternative way to specify a patch that can be more efficient than using x, y, and z coordinates in most cases. For example, consider the following patch. It is composed of eight triangular faces defined by nine vertices.



`Faces` property

F_1	V_1	V_4	V_5
F_2	V_1	V_5	V_2
F_3	V_2	V_5	V_6
F_4	V_2	V_6	V_3
F_5	V_4	V_7	V_8
F_6	V_4	V_8	V_5
F_7	V_5	V_8	V_9
F8	V_5	V_9	V_6

`Vertices` property

V_1	X_1	Y_1	Z_1
V_2	X_2	Y_2	Z_2
V_3	X_3	Y_3	Z_3
V_4	X_4	Y_4	Z_4
V_5	$\mathbf{X_5}$	$\mathbf{Y_5}$	$\mathbf{Z_5}$
V_6	X_6	Y_6	Z_6
V_7	X_7	Y_7	Z_7
V_8	X_8	Y_8	Z_8
V_9	X_9	Y_9	Z_9

The corresponding `Faces` and `Vertices` properties are shown to the right of the patch. Note how some faces share vertices with other faces. For example, the fifth vertex (V5) is used six times, once each by faces one, two, and three and six, seven, and eight. Without sharing vertices, this same patch requires 24 vertex definitions.

`FaceVertexAlphaData` m-by-1 matrix

Face and vertex transparency data. The `FaceVertexAlphaData` property specifies the transparency of patches that have been defined by the `Faces` and `Vertices` properties. The interpretation of the values specified for `FaceVertexAlphaData` depends on the dimensions of the data.

`FaceVertexAlphaData` can be one of the following:

- A single value, which applies the same transparency to the entire patch. The `FaceAlpha` property must be set to `flat`.
- An m-by-1 matrix (where m is the number of rows in the `Faces` property), which specifies one transparency value per face. The `FaceAlpha` property must be set to `flat`.
- An m-by-1 matrix (where m is the number of rows in the `Vertices` property), which specifies one transparency value per vertex. The `FaceAlpha` property must be set to `interp`.

The `AlphaDataMapping` property determines how MATLAB interprets the `FaceVertexAlphaData` property values.

`FaceVertexCData` matrix

Face and vertex colors. The `FaceVertexCData` property specifies the color of patches defined by the `Faces` and `Vertices` properties. You must also set the values of the `FaceColor`, `EdgeColor`, `MarkerFaceColor`, or `MarkerEdgeColor` are set appropriately. The interpretation of the values specified for `FaceVertexCData` depends on the dimensions of the data.

For indexed colors, `FaceVertexCData` can be

- A single value, which applies a single color to the entire patch
- An *n*-by-1 matrix, where *n* is the number of rows in the `Faces` property, which specifies one color per face
- An *n*-by-1 matrix, where *n* is the number of rows in the `Vertices` property, which specifies one color per vertex

For true colors, `FaceVertexCData` can be

- A 1-by-3 matrix, which applies a single color to the entire patch
- An *n*-by-3 matrix, where *n* is the number of rows in the `Faces` property, which specifies one color per face
- An *n*-by-3 matrix, where *n* is the number of rows in the `Vertices` property, which specifies one color per vertex

The following diagram illustrates the various forms of the `FaceVertexCData` property for a patch having eight faces and nine vertices. The `CDataMapping` property determines how MATLAB interprets the `FaceVertexCData` property when you specify indexed colors



HandleVisibility `{on} | callback | off`

Control access to object's handle by command-line users and GUIs. This property determines when an object's handle is visible in its parent's list of children. `HandleVisibility` is useful for preventing command-line users from accidentally drawing into or deleting a figure that contains only user interface devices (such as a dialog box).

Handles are always visible when `HandleVisibility` is `on`.

Setting `HandleVisibility` to `callback` causes handles to be visible from within callback routines or functions invoked by callback routines, but not from within functions invoked from the command line. This provides a means to

protect GUIs from command-line users, while allowing callback routines to have complete access to object handles.

Setting `HandleVisibility` to `off` makes handles invisible at all times. This may be necessary when a callback routine invokes a function that might potentially damage the GUI (such as evaluating a user-typed string), and so temporarily hides its own handles during the execution of that function.

When a handle is not visible in its parent's list of children, it cannot be returned by functions that obtain handles by searching the object hierarchy or querying handle properties. This includes `get`, `findobj`, `gca`, `gcf`, `gco`, `newplot`, `cla`, `clf`, and `close`.

When a handle's visibility is restricted using `callback` or `off`, the object's handle does not appear in its parent's `Children` property, figures do not appear in the root's `CurrentFigure` property, objects do not appear in the root's `CallbackObject` property or in the figure's `CurrentObject` property, and axes do not appear in their parent's `CurrentAxes` property.

You can set the root `ShowHiddenHandles` property to `on` to make all handles visible regardless of their `HandleVisibility` settings (this does not affect the values of the `HandleVisibility` properties).

Handles that are hidden are still valid. If you know an object's handle, you can `set` and `get` its properties, and pass it to any function that operates on handles.

`HitTest` `{on} | off`

Selectable by mouse click. `HitTest` determines if the patch can become the current object (as returned by the `gco` command and the figure `CurrentObject` property) as a result of a mouse click on the patch. If `HitTest` is `off`, clicking the patch selects the object below it (which may be the axes containing it).

`Interruptible` `{on} | off`

Callback routine interruption mode. The `Interruptible` property controls whether a patch callback routine can be interrupted by subsequently invoked callback routines. Only callback routines defined for the `ButtonDownFcn` are affected by the `Interruptible` property. MATLAB checks for events that can interrupt a callback routine only when it encounters a `drawnow`, `figure`, `getframe`, or `pause` command in the routine. See the `BusyAction` property for related information.

`LineStyle` `{-} | -- | : | -. | none`

Edge linestyle. This property specifies the line style of the patch edges. The following table lists the available line styles.

Symbol	Line Style
-	Solid line (default)
--	Dashed line
:	Dotted line
-.	Dash-dot line
none	No line

You can use `LineStyle none` when you want to place a marker at each point but do not want the points connected with a line (see the `Marker` property).

`LineWidth` scalar

Edge line width. The width, in points, of the patch edges (1 point = $^1/_{72}$ inch). The default `LineWidth` is 0.5 points.

`Marker` character (see table)

Marker symbol. The `Marker` property specifies marks that locate vertices. You can set values for the `Marker` property independently from the `LineStyle` property. The following tables lists the available markers.

Marker Specifier	Description
+	Plus sign
o	Circle
*	Asterisk
.	Point
x	Cross
s	Square

Marker Specifier	Description
`d`	Diamond
`^`	Upward-pointing triangle
`v`	Downward-pointing triangle
`>`	Right-pointing triangle
`<`	Left-pointing triangle
`p`	Five-pointed star (pentagram)
`h`	Six-pointed star (hexagram)
`none`	No marker (default)

`MarkerEdgeColor` `ColorSpec | none | {auto} | flat`

Marker edge color. The color of the marker or the edge color for filled markers (circle, square, diamond, pentagram, hexagram, and the four triangles).

- `ColorSpec` — Defines the color to use.
- `none` — Specifies no color, which makes nonfilled markers invisible.
- `auto` — Sets `MarkerEdgeColor` to the same color as the `EdgeColor` property.

`MarkerFaceColor` `ColorSpec | {none} | auto | flat`

Marker face color. The fill color for markers that are closed shapes (circle, square, diamond, pentagram, hexagram, and the four triangles).

- `ColorSpec` — Defines the color to use.
- `none` — Makes the interior of the marker transparent, allowing the background to show through.
- `auto` — Sets the fill color to the axes color, or the figure color, if the axes `Color` property is set to `none`.

`MarkerSize` size in points

Marker size. A scalar specifying the size of the marker, in points. The default value for `MarkerSize` is 6 points (1 point = $1/72$ inch). Note that MATLAB draws the `point` marker at 1/3 of the specified size.

NormalMode {auto} | manual

MATLAB generated or user-specified normal vectors. When this property is auto, MATLAB calculates vertex normals based on the coordinate data. If you specify your own vertex normals, MATLAB sets this property to manual and does not generate its own data. See also the VertexNormals property.

Parent handle of axes, hggroup, or hgtransform

Parent of patch object. This property contains the handle of the patch object's parent. The parent of a patch object is the axes, hggroup, or hgtransform object that contains it.

See Objects That Can Contain Other Objects for more information on parenting graphics objects.

Selected on | {off}

Is object selected? When this property is on, MATLAB displays selection handles or a dashed box (depending on the number of faces) if the SelectionHighlight property is also on. You can, for example, define the ButtonDownFcn to set this property, allowing users to select the object with the mouse.

SelectionHighlight {on} | off

Objects are highlighted when selected. When the Selected property is on, MATLAB indicates the selected state by

- Drawing handles at each vertex for a single-faced patch
- Drawing a dashed bounding box for a multifaced patch

When SelectionHighlight is off, MATLAB does not draw the handles.

SpecularColorReflectance scalar in the range 0 to 1

Color of specularly reflected light. When this property is 0, the color of the specularly reflected light depends on both the color of the object from which it reflects and the color of the light source. When set to 1, the color of the specularly reflected light depends only on the color of the light source (i.e., the light object Color property). The proportions vary linearly for values in between.

SpecularExponent scalar >= 1

Harshness of specular reflection. This property controls the size of the specular spot. Most materials have exponents in the range of 5 to 20.

SpecularStrength scalar >= 0 and <= 1

Intensity of specular light. This property sets the intensity of the specular component of the light falling on the patch. Specular light comes from light objects in the axes.

You can also set the intensity of the ambient and diffuse components of the light on the patch object. See the `AmbientStrength` and `DiffuseStrength` properties.

Tag string

User-specified object label. The `Tag` property provides a means to identify graphics objects with a user-specified label. This is particularly useful when you are constructing interactive graphics programs that would otherwise need to define object handles as global variables or pass them as arguments between callback routines.

For example, suppose you use patch objects to create borders for a group of uicontrol objects and want to change the color of the borders in a uicontrol's callback routine. You can specify a `Tag` with the patch definition

```
patch(X,Y,'k','Tag','PatchBorder')
```

Then use `findobj` in the uicontrol's callback routine to obtain the handle of the patch and set its `FaceColor` property.

```
set(findobj('Tag','PatchBorder'),'FaceColor','w')
```

Type string (read only)

Class of the graphics object. For patch objects, `Type` is always the string `'patch'`.

UIContextMenu handle of a uicontextmenu object

Associate a context menu with the patch. Assign this property the handle of a uicontextmenu object created in the same figure as the patch. Use the `uicontextmenu` function to create the context menu. MATLAB displays the context menu whenever you right-click over the patch.

`UserData` matrix

User-specified data. Any matrix you want to associate with the patch object. MATLAB does not use this data, but you can access it using `set` and `get`.

`VertexNormals` matrix

Surface normal vectors. This property contains the vertex normals for the patch. MATLAB generates this data to perform lighting calculations. You can supply your own vertex normal data, even if it does not match the coordinate data. This can be useful to produce interesting lighting effects.

`Vertices` matrix

Vertex coordinates. A matrix containing the *x*-, *y*-, *z*-coordinates for each vertex. See the `Faces` property for more information.

`Visible` `{on} | off`

Patch object visibility. By default, all patches are visible. When set to `off`, the patch is not visible, but still exists, and you can query and set its properties.

`XData` vector or matrix

X-coordinates. The *x*-coordinates of the patch vertices. If `XData` is a matrix, each column represents the *x*-coordinates of a single face of the patch. In this case, `XData`, `YData`, and `ZData` must have the same dimensions.

`YData` vector or matrix

Y-coordinates. The *y*-coordinates of the patch vertices. If `YData` is a matrix, each column represents the *y*-coordinates of a single face of the patch. In this case, `XData`, `YData`, and `ZData` must have the same dimensions.

`ZData` vector or matrix

Z-coordinates. The *z*-coordinates of the patch vertices. If `ZData` is a matrix, each column represents the *z*-coordinates of a single face of the patch. In this case, `XData`, `YData`, and `ZData` must have the same dimensions.

See Also

`patch`

path

Purpose

View or change the MATLAB directory search path

Graphical Interface

As an alternative to the `path` function, use the **Set Path** dialog box. To open it, select **Set Path** from the **File** menu in the MATLAB desktop.

Syntax

```
path
path('newpath')
path(path,'newpath')
path('newpath',path)
p = path(...)
```

Description

`path` displays the current MATLAB search path. The initial search path list is defined by `toolbox/local/pathdef.m`.

`path('newpath')` changes the search path to `newpath`, where `newpath` is a string array of directories.

`path(path,'newpath')` appends the `newpath` directory to the current search path.

`path('newpath',path)` prepends the `newpath` directory to the current search path.

`p = path(...)` returns the specified path in string variable `p`.

Note Save any M-files you create and any MathWorks-supplied M-files that you edit in a directory that is not in the `$matlabroot/toolbox` directory tree. If you keep your files in `$matlabroot/toolbox` directories, they can be overwritten when you install a new version of MATLAB. Also note that locations of files in the `$matlabroot/toolbox` directory tree are loaded and cached in memory at the beginning of each MATLAB session to improve performance. If you save files to `$matlabroot/toolbox` directories using an external editor or add or remove in from these directories using file system operations, run `rehash toolbox` before you use the files in the current session. If you make changes to existing files in `$matlabroot/toolbox` directories using an external editor, run `clear functionname` before you use the files in

the current session. For more information, see `rehash` or Toolbox Path Caching.

Examples

Add a new directory to the search path on Windows.

```
path(path,'c:/tools/goodstuff')
```

Add a new directory to the search path on UNIX.

```
path(path,'/home/tools/goodstuff')
```

See Also

`addpath`, `cd`, `dir`, `genpath`, `matlabroot`, `partialpath`, `pathdef`, `pathsep`, `pathtool`, `rehash`, `restoredefaultpath`, `rmpath`, `savepath`, `startup`, `what`

Search Path

path2rc

Purpose

Save current MATLAB search path to `pathdef.m` file

Syntax

```
path2rc
```

Description

`path2rc` runs `savepath`. The `savepath` function is replacing `path2rc`. Use `savepath` instead of `path2rc` and replace instances of `path2rc` with `savepath`.

Purpose

List of directories in the MATLAB search path

Tropical Interface

As an alternative to using the `pathdef.m` file directly, use the **Set Path** dialog box. To open it, select **Set Path** from the **File** menu in the MATLAB desktop.

Syntax

```
pathdef
```

Description

`pathdef` returns a string listing of the directories in the MATLAB search path. Use `path` to view each directory in `pathdef.m` on a separate line.

When you start a new session, MATLAB creates the search path defined in the `pathdef.m` file located in the MATLAB startup directory. If that directory does not contain a `pathdef.m` file, MATLAB uses the search path defined in `$matlabroot/toolbox/local/pathdef.m`.

Make changes to the path using the **Set Path** dialog box and `addpath` and `rmpath`. While you can edit `pathdef.m` directly, use caution so you do not accidentally make MATLAB supplied directories unusable. Use `savepath` to save `pathdef.m`, and to use that path in future sessions, specify the MATLAB startup directory as its location.

See Also

`addpath`, `cd`, `dir`, `genpath`, `matlabroot`, `partialpath`, `path`, `pathsep`, `pathtool`, `rehash`, `restoredefaultpath`, `rmpath`, `savepath`, `startup`, `what`

Search Path documentation, including:

- “How MATLAB Finds the Search Path, pathdef.m”
- “Saving Settings to the Path”
- “Using the Path in Future Sessions”
- “Recovering from Problems with the Search Path”

pathsep

Purpose

Return path separator for current platform

Syntax

```
c = pathsep
```

Description

`c = pathsep` returns the path separator character for this platform. The path separator is the character that separates directories in the string returned by the `matlabpath` function.

Examples

Extract each individual path from the string returned by `matlabpath`. Use `pathsep` to define the path separator:

```
s = matlabpath;
p = 1;

while true
   t = strtok(s(p:end), pathsep);
   disp(sprintf('%s', t))
   p = p + length(t) + 1;
   if isempty(strfind(s(p:end),';')) break, end;
   end
```

Here is the output:

```
D:\Applications\matlabR14beta2\toolbox\matlab\general
D:\Applications\matlabR14beta2\toolbox\matlab\ops
D:\Applications\matlabR14beta2\toolbox\matlab\lang
D:\Applications\matlabR14beta2\toolbox\matlab\elmat
D:\Applications\matlabR14beta2\toolbox\matlab\elfun
       .
       .
       .
```

See Also

`filesep`, `fullfile`, `fileparts`

Purpose

Open **Set Path** dialog box to view and change MATLAB path

Graphical Interface

As an alternative to the `pathtool` function, select **Set Path** from the **File** menu in the MATLAB desktop.

Syntax

```
pathtool
```

Description

`pathtool` opens the **Set Path** dialog box, a graphical user interface you use to view and modify the MATLAB search path.



See Also

`addpath`, `cd`, `dir`, `genpath`, `matlabroot`, `partialpath`, `path`, `pathdef`, `pathsep`, `rehash`, `restoredefaultpath`, `rmpath`, `savepath`, `startup`, `what`

Search Path documentation, including, “Setting the Search Path”

Purpose

Halt execution temporarily

Syntax

```
pause
pause(n)
pause on
pause off
```

Description

`pause`, by itself, causes M-files to stop and wait for you to press any key before continuing.

`pause(n)` pauses execution for `n` seconds before continuing, where `n` can be any nonnegative real number. The resolution of the clock is platform specific. A fractional pause of 0.01 seconds should be supported on most platforms.

`pause on` allows subsequent `pause` commands to pause execution.

`pause off` ensures that any subsequent `pause` or `pause(n)` statements do not pause execution. This allows normally interactive scripts to run unattended.

See Also

`drawnow`

pbaspect

Purpose

Set or query the plot box aspect ratio

Syntax

```
pbaspect
pbaspect([aspect_ratio])
pbaspect('mode')
pbaspect('auto')
pbaspect('manual')
pbaspect(axes_handle,...)
```

Description

The plot box aspect ratio determines the relative size of the *x*-, *y*-, and *z*-axes.

`pbaspect` with no arguments returns the plot box aspect ratio of the current axes.

`pbaspect([aspect_ratio])` sets the plot box aspect ratio in the current axes to the specified value. Specify the aspect ratio as three relative values representing the ratio of the *x*-, *y*-, and *z*-axes size. For example, a value of `[1 1 1]` (the default) means the plot box is a cube (although with stretch-to-fill enabled, it may not appear as a cube). See Remarks.

`pbaspect('mode')` returns the current value of the plot box aspect ratio mode, which can be either `auto` (the default) or `manual`. See Remarks.

`pbaspect('auto')` sets the plot box aspect ratio mode to `auto`.

`pbaspect('manual')` sets the plot box aspect ratio mode to `manual`.

`pbaspect(axes_handle,...)` performs the set or query on the axes identified by the first argument, `axes_handle`. If you do not specify an axes handle, `pbaspect` operates on the current axes.

Remarks

`pbaspect` sets or queries values of the axes object `PlotBoxAspectRatio` and `PlotBoxAspectRatioMode` properties.

When the plot box aspect ratio mode is `auto`, MATLAB sets the ratio to `[1 1 1]`, but may change it to accommodate manual settings of the data aspect ratio, camera view angle, or axis limits. See the axes `DataAspectRatio` property for a table listing the interactions between various properties.

Setting a value for the plot box aspect ratio or setting the plot box aspect ratio mode to `manual` disables the MATLAB stretch-to-fill feature (stretching of the axes to fit the window). This means setting the plot box aspect ratio to its current value,

```
pbaspect(pbaspect)
```

can cause a change in the way the graphs look. See the Remarks section of the `axes` reference description and the "Aspect Ratio" section in the Using MATLAB Graphics manual for a discussion of stretch-to-fill.

Examples

The following surface plot of the function $z = xe^{(-x^2 - y^2)}$ is useful to illustrate the plot box aspect ratio. First plot the function over the range $-2 \le x \le 2$, $-2 \le y \le 2$,

```
[x,y] = meshgrid([-2:.2:2]);
z = x.*exp(-x.^2 - y.^2);
surf(x,y,z)
```



Querying the plot box aspect ratio shows that the plot box is square.

```
pbaspect
ans =
```

```
     1   1   1
```

It is also interesting to look at the data aspect ratio selected by MATLAB.

```
daspect
ans =
     4   4   1
```

To illustrate the interaction between the plot box and data aspect ratios, set the data aspect ratio to `[1 1 1]` and again query the plot box aspect ratio.

```
daspect([1 1 1])
```




```
pbaspect
ans =
     4   4   1
```

The plot box aspect ratio has changed to accommodate the specified data aspect ratio. Now suppose you want the plot box aspect ratio to be `[1 1 1]` as well.

```
pbaspect([1 1 1])
```



Notice how MATLAB changed the axes limits because of the constraints introduced by specifying both the plot box and data aspect ratios.

You can also use `pbaspect` to disable stretch-to-fill. For example, displaying two subplots in one figure can give surface plots a squashed appearance. Disabling stretch-to-fill,

```
upper_plot = subplot(211);
surf(x,y,z)
lower_plot = subplot(212);
surf(x,y,z)
pbaspect(upper_plot,'manual')
```



See Also

`axis`, `daspect`, `xlim`, `ylim`, `zlim`

The axes properties `DataAspectRatio`, `PlotBoxAspectRatio`, `XLim`, `YLim`, `ZLim`

The “Aspect Ratio” section in the Using MATLAB Graphics manual

Purpose

Preconditioned Conjugate Gradients method

Syntax

```
x = pcg(A,b)
pcg(A,b,tol)
pcg(A,b,tol,maxit)
pcg(A,b,tol,maxit,M)
pcg(A,b,tol,maxit,M1,M2)
pcg(A,b,tol,maxit,M1,M2,x0)
pcg(A,b,tol,maxit,M1,M2,x0,p1,p2,...)
[x,flag] = pcg(A,b,tol,maxit,M1,M2,x0,p1,p2,...)
[x,flag,relres] = pcg(A,b,tol,maxit,M1,M2,x0,p1,p2,...)
[x,flag,relres,iter] = pcg(A,b,tol,maxit,M1,M2,x0,p1,p2,...)
[x,flag,relres,iter,resvec] = pcg(A,b,tol,maxit,M1,M2,x0,p1,p2,...)
```

Description

`x = pcg(A,b)` attempts to solve the system of linear equations `A*x=b` for `x`. The `n`-by-`n` coefficient matrix `A` must be symmetric and positive definite, and should also be large and sparse. The column vector `b` must have length `n`. `A` can be a function `afun` such that `afun(x)` returns `A*x`.

If `pcg` converges, a message to that effect is displayed. If `pcg` fails to converge after the maximum number of iterations or halts for any reason, a warning message is printed displaying the relative residual `norm(b-A*x)/norm(b)` and the iteration number at which the method stopped or failed.

`pcg(A,b,tol)` specifies the tolerance of the method. If `tol` is `[]`, then `pcg` uses the default, `1e-6`.

`pcg(A,b,tol,maxit)` specifies the maximum number of iterations. If `maxit` is `[]`, then `pcg` uses the default, `min(n,20)`.

`pcg(A,b,tol,maxit,M)` and `pcg(A,b,tol,maxit,M1,M2)` use symmetric positive definite preconditioner `M` or `M = M1*M2` and effectively solve the system `inv(M)*A*x = inv(M)*b` for `x`. If `M` is `[]` then `pcg` applies no preconditioner. `M` can be a function that returns `M\x`.

`pcg(A,b,tol,maxit,M1,M2,x0)` specifies the initial guess. If `x0` is `[]`, then `pcg` uses the default, an all-zero vector.

`pcg(afun,b,tol,maxit,m1fun,m2fun,x0,p1,p2,...)` passes parameters `p1,p2,...` to functions `afun(x,p1,p2,...)`, `m1fun(x,p1,p2,...)`, and `m2fun(x,p1,p2,...)`.

`[x,flag] = pcg(A,b,tol,maxit,M1,M2,x0)` also returns a convergence flag.

Flag	Convergence
0	`pcg` converged to the desired tolerance `tol` within `maxit` iterations.
1	`pcg` iterated `maxit` times but did not converge.
2	Preconditioner `M` was ill-conditioned.
3	`pcg` stagnated. (Two consecutive iterates were the same.)
4	One of the scalar quantities calculated during `pcg` became too small or too large to continue computing.

Whenever `flag` is not `0`, the solution `x` returned is that with minimal norm residual computed over all the iterations. No messages are displayed if the `flag` output is specified.

`[x,flag,relres] = pcg(A,b,tol,maxit,M1,M2,x0)` also returns the relative residual `norm(b-A*x)/norm(b)`. If `flag` is `0`, `relres <= tol`.

`[x,flag,relres,iter] = pcg(A,b,tol,maxit,M1,M2,x0)` also returns the iteration number at which `x` was computed, where `0 <= iter <= maxit`.

`[x,flag,relres,iter,resvec] = pcg(A,b,tol,maxit,M1,M2,x0)` also returns a vector of the residual norms at each iteration including `norm(b-A*x0)`.

Examples

Example 1.

```
A = gallery('wilk',21);
b = sum(A,2);
tol = 1e-12;
maxit = 15;
M = diag([10:-1:1 1 1:10]);
```

```
[x,flag,rr,iter,rv] = pcg(A,b,tol,maxit,M);
```

Alternatively, use this one-line matrix-vector product function

```
function y = afun(x,n)
y = [0;
     x(1:n-1)] + [((n-1)/2:-1:0)';
     (1:(n-1)/2)'].*x + [x(2:n);
     0];
```

and this one-line preconditioner backsolve function

```
function y = mfun(r,n)
y = r ./ [((n-1)/2:-1:1)'; 1; (1:(n-1)/2)'];
```

as inputs to `pcg`

```
[x1,flag1,rr1,iter1,rv1] = pcg(@afun,b,tol,maxit,@mfun,...
                               [],[],21);
```

Example 2.

```
A = delsq(numgrid('C',25));
b = ones(length(A),1);
[x,flag] = pcg(A,b)
```

`flag` is `1` because `pcg` does not converge to the default tolerance of `1e-6` within the default 20 iterations.

```
R = cholinc(A,1e-3);
[x2,flag2,relres2,iter2,resvec2] = pcg(A,b,1e-8,10,R',R)
```

`flag2` is `0` because `pcg` converges to the tolerance of `1.2e-9` (the value of `relres2`) at the sixth iteration (the value of `iter2`) when preconditioned by the incomplete Cholesky factorization with a drop tolerance of `1e-3`. `resvec2(1) = norm(b)` and `resvec2(7) = norm(b-A*x2)`. You can follow the progress of `pcg` by plotting the relative residuals at each iteration starting from the initial estimate (iterate number 0).

```
semilogy(0:iter2,resvec2/norm(b),'-o')
xlabel('iteration number')
ylabel('relative residual')
```



See Also

`bicg`, `bicgstab`, `cgs`, `cholinc`, `gmres`, `lsqr`, `minres`, `qmr`, `symmlq`

`@` (function handle), `\` (backslash)

References

[1] Barrett, R., M. Berry, T. F. Chan, et al., *Templates for the Solution of Linear Systems: Building Blocks for Iterative Methods*, SIAM, Philadelphia, 1994.

Purpose

Piecewise Cubic Hermite Interpolating Polynomial (PCHIP)

Syntax

```
yi = pchip(x,y,xi)
pp = pchip(x,y)
```

Description

`yi = pchip(x,y,xi)` returns vector `yi` containing elements corresponding to the elements of `xi` and determined by piecewise cubic interpolation within vectors `x` and `y`. The vector `x` specifies the points at which the data `y` is given. If `y` is a matrix, then the interpolation is performed for each column of `y` and `yi` is `length(xi)`-by-`size(y,2)`.

`pp = pchip(x,y)` returns a piecewise polynomial structure for use by `ppval`. `x` can be a row or column vector. `y` is a row or column vector of the same length as `x`, or a matrix with `length(x)` columns.

`pchip` finds values of an underlying interpolating function $P(x)$ at intermediate points, such that:

- On each subinterval $x_k \le x \le x_{k+1}$, $P(x)$ is the cubic Hermite interpolant to the given values and certain slopes at the two endpoints.
- $P(x)$ interpolates y, i.e., $P(x_j) = y_j$, and the first derivative $P'(x)$ is continuous. $P''(x)$ is probably not continuous; there may be jumps at the x_j.
- The slopes at the x_j are chosen in such a way that $P(x)$ preserves the shape of the data and respects monotonicity. This means that, on intervals where the data are monotonic, so is $P(x)$; at points where the data has a local extremum, so does $P(x)$.

Note If y is a matrix, $P(x)$ satisfies the above for each column of y.

Remarks

`spline` constructs $S(x)$ in almost the same way `pchip` constructs $P(x)$. However, `spline` chooses the slopes at the x_j differently, namely to make even $S''(x)$ continuous. This has the following effects:

- `spline` produces a smoother result, i.e. $S''(x)$ is continuous.
- `spline` produces a more accurate result if the data consists of values of a smooth function.

- `pchip` has no overshoots and less oscillation if the data are not smooth.
- `pchip` is less expensive to set up.
- The two are equally expensive to evaluate.

Examples

```
x = -3:3;
y = [-1 -1 -1 0 1 1 1];
t = -3:.01:3;
p = pchip(x,y,t);
s = spline(x,y,t);
plot(x,y,'o',t,p,'-',t,s,'-.')
legend('data','pchip','spline',4)
```



See Also

`interp1`, `spline`, `ppval`

References

[1] Fritsch, F. N. and R. E. Carlson, “Monotone Piecewise Cubic Interpolation,” *SIAM J. Numerical Analysis*, Vol. 17, 1980, pp.238-246.

[2] Kahaner, David, Cleve Moler, Stephen Nash, *Numerical Methods and Software*, Prentice Hall, 1988.

Purpose

Create preparsed pseudocode file (P-file)

Syntax

```
pcode fun
pcode *.m
pcode fun1 fun2 ...
pcode... -inplace
```

Description

`pcode fun` parses the M-file `fun.m` into the P-file `fun.p` and puts it into the current directory. The original M-file can be anywhere on the search path.

`pcode *.m` creates P-files for all the M-files in the current directory.

`pcode fun1 fun2 ...` creates P-files for the listed functions.

`pcode... -inplace` creates P-files in the same directory as the M-files. An error occurs if the files can't be created.

pcolor

Purpose

Pseudocolor plot

Syntax

```
pcolor(C)
pcolor(X,Y,C)
pcolor(axes_handle,...)
h = pcolor(...)
```

Description

A pseudocolor plot is a rectangular array of cells with colors determined by `C`. MATLAB creates a pseudocolor plot using each set of four adjacent points in `C` to define a surface rectangle (i.e., cell).

The default `shading` is `faceted`, which colors each cell with a single color. The last row and column of `C` are not used in this case. With `shading interp`, each cell is colored by bilinear interpolation of the colors at its four vertices, using all elements of `C`.

The minimum and maximum elements of `C` are assigned the first and last colors in the colormap. Colors for the remaining elements in `C` are determined by a linear mapping from value to colormap element.

`pcolor(C)` draws a pseudocolor plot. The elements of `C` are linearly mapped to an index into the current colormap. The mapping from `C` to the current colormap is defined by `colormap` and `caxis`.

`pcolor(X,Y,C)` draws a pseudocolor plot of the elements of `C` at the locations specified by `X` and `Y`. The plot is a logically rectangular, two-dimensional grid with vertices at the points `[X(i,j), Y(i,j)]`. `X` and `Y` are vectors or matrices that specify the spacing of the grid lines. If `X` and `Y` are vectors, `X` corresponds to the columns of `C` and `Y` corresponds to the rows. If `X` and `Y` are matrices, they must be the same size as `C`.

`pcolor(axes_handles,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = pcolor(...)` returns a handle to a surface graphics object.

Remarks

A pseudocolor plot is a flat surface plot viewed from above. `pcolor(X,Y,C)` is the same as viewing `surf(X,Y,0*Z,C)` using `view([0 90])`.

When you use `shading faceted` or `shading flat`, the constant color of each cell is the color associated with the corner having the smallest *x*-*y* coordinates. Therefore, `C(i,j)` determines the color of the cell in the *i*th row and *j*th column. The last row and column of `C` are not used.

When you use `shading interp`, each cell's color results from a bilinear interpolation of the colors at its four vertices, and all elements of `C` are used.

Examples

A Hadamard matrix has elements that are `+1` and `-1`. A colormap with only two entries is appropriate when displaying a pseudocolor plot of this matrix.

```
pcolor(hadamard(20))
colormap(gray(2))
axis ij
axis square
```



A simple color wheel illustrates a polar coordinate system.

```
n = 6;
r = (0:n)'/n;
theta = pi*(-n:n)/n;
X = r*cos(theta);
Y = r*sin(theta);
C = r*cos(2*theta);
pcolor(X,Y,C)
```

```
axis equal tight
```



Algorithm

The number of vertex colors for `pcolor(C)` is the same as the number of cells for `image(C)`. `pcolor` differs from `image` in that `pcolor(C)` specifies the colors of vertices, which are scaled to fit the colormap; changing the axes `clim` property changes this color mapping. `image(C)` specifies the colors of cells and directly indexes into the colormap without scaling. Additionally, `pcolor(X,Y,C)` can produce parametric grids, which is not possible with `image`.

See Also

`caxis`, `image`, `mesh`, `shading`, `surf`, `view`

Purpose

Solve initial-boundary value problems for systems of parabolic and elliptic partial differential equations (PDEs) in one space variable and time

Syntax

```
sol = pdepe(m,pdefun,icfun,bcfun,xmesh,tspan)
sol = pdepe(m,pdefun,icfun,bcfun,xmesh,tspan,options)
sol = pdepe(m,pdefun,icfun,bcfun,xmesh,tspan,options,p1,p2...)
```

Arguments

`m`	A parameter corresponding to the symmetry of the problem. `m` can be slab = `0`, cylindrical = `1`, or spherical = `2`.
`pdefun`	A function that defines the components of the PDE.
`icfun`	A function that defines the initial conditions.
`bcfun`	A function that defines the boundary conditions.
`xmesh`	A vector [`x0`, `x1`, ..., `xn`] specifying the points at which a numerical solution is requested for every value in `tspan`. The elements of `xmesh` must satisfy `x0 < x1 < ... < xn`. The length of `xmesh` must be `>= 3`.
`tspan`	A vector [`t0`, `t1`, ..., `tf`] specifying the points at which a solution is requested for every value in `xmesh`. The elements of `tspan` must satisfy `t0 < t1 < ... < tf`. The length of `tspan` must be `>= 3`.
`options`	Some options of the underlying ODE solver are available in `pdepe`: `RelTol`, `AbsTol`, `NormControl`, `InitialStep`, and `MaxStep`. In most cases, default values for these options provide satisfactory solutions. See `odeset` for details.
`p1,p2,...`	Optional parameters to be passed to `pdefun`, `icfun`, and `bcfun`.

Description

`sol = pdepe(m,pdefun,icfun,bcfun,xmesh,tspan)` solves initial-boundary value problems for systems of parabolic and elliptic PDEs in the one space variable x and time t. The ordinary differential equations (ODEs) resulting from discretization in space are integrated to obtain approximate solutions at times specified in `tspan`. The `pdepe` function returns values of the solution on a mesh provided in `xmesh`.

`pdepe` solves PDEs of the form:

$$c\left(x,t,u,\frac{\partial u}{\partial x}\right)\frac{\partial u}{\partial t} = x^{-m}\frac{\partial}{\partial x}\left(x^m f\left(x,t,u,\frac{\partial u}{\partial x}\right)\right) + s\left(x,t,u,\frac{\partial u}{\partial x}\right) \quad \textbf{(2-1)}$$

The PDEs hold for $t_0 \le t \le t_f$ and $a \le x \le b$. The interval $[a, b]$ must be finite. m can be 0, 1, or 2, corresponding to slab, cylindrical, or spherical symmetry, respectively. If $m > 0$, then a must be >= 0.

In Equation 2-1, $f(x, t, u, \partial u/\partial x)$ is a flux term and $s(x, t, u, \partial u/\partial x)$ is a source term. The coupling of the partial derivatives with respect to time is restricted to multiplication by a diagonal matrix $c(x, t, u, \partial u/\partial x)$. The diagonal elements of this matrix are either identically zero or positive. An element that is identically zero corresponds to an elliptic equation and otherwise to a parabolic equation. There must be at least one parabolic equation. An element of c that corresponds to a parabolic equation can vanish at isolated values of x if those values of x are mesh points. Discontinuities in c and/or s due to material interfaces are permitted provided that a mesh point is placed at each interface.

For $t = t_0$ and all x, the solution components satisfy initial conditions of the form

$$u(x, t_0) = u_0(x) \quad \textbf{(2-2)}$$

For all t and either $x = a$ or $x = b$, the solution components satisfy a boundary condition of the form

$$p(x, t, u) + q(x, t) f\left(x, t, u, \frac{\partial u}{\partial x}\right) = 0 \quad \textbf{(2-3)}$$

Elements of q are either identically zero or never zero. Note that the boundary conditions are expressed in terms of the flux f rather than $\partial u/\partial x$. Also, of the two coefficients, only p can depend on u.

In the call `sol = pdepe(m,pdefun,icfun,bcfun,xmesh,tspan)`:

- `m` corresponds to m.
- `xmesh(1)` and `xmesh(end)` correspond to a and b.
- `tspan(1)` and `tspan(end)` correspond to t_0 and t_f.

- pdefun computes the terms c, f, and s (Equation 2-1). It has the form

  ```
  [c,f,s] = pdefun(x,t,u,dudx)
  ```

  The input arguments are scalars x and t and vectors u and dudx that approximate the solution u and its partial derivative with respect to x, respectively. c, f, and s are column vectors. c stores the diagonal elements of the matrix c (Equation 2-1).
- icfun evaluates the initial conditions. It has the form

  ```
  u = icfun(x)
  ```

  When called with an argument x, icfun evaluates and returns the initial values of the solution components at x in the column vector u.
- bcfun evaluates the terms p and q of the boundary conditions (Equation 2-3). It has the form

  ```
  [pl,ql,pr,qr] = bcfun(xl,ul,xr,ur,t)
  ```

  ul is the approximate solution at the left boundary xl = a and ur is the approximate solution at the right boundary xr = b. pl and ql are column vectors corresponding to p and q evaluated at xl, similarly pr and qr correspond to xr. When $m > 0$ and $a = 0$, boundedness of the solution near $x = 0$ requires that the flux f vanish at $a = 0$. pdepe imposes this boundary condition automatically and it ignores values returned in pl and ql.

pdepe returns the solution as a multidimensional array sol.
u_i = ui = sol(:,:,i) is an approximation to the ith component of the solution vector u. The element ui(j,k) = sol(j,k,i) approximates u_i at (t, x) = (tspan(j),xmesh(k)).

ui = sol(j,:,i) approximates component i of the solution at time tspan(j) and mesh points xmesh(:). Use pdeval to compute the approximation and its partial derivative $\partial u_i/\partial x$ at points not included in xmesh. See pdeval for details.

sol = pdepe(m,pdefun,icfun,bcfun,xmesh,tspan,options) solves as above with default integration parameters replaced by values in options, an argument created with the odeset function. Only some of the options of the underlying ODE solver are available in pdepe: RelTol, AbsTol, NormControl,

InitialStep, and MaxStep. The defaults obtained by leaving off the input argument options will generally be satisfactory. See odeset for details.

sol = pdepe(m,pdefun,icfun,bcfun,xmesh,tspan,options,p1,p2...) passes the additional parameters p1, p2, ... to the functions pdefun, icfun, and bcfun. Use options = [] as a placeholder if no options are set.

Remarks

- The arrays xmesh and tspan play different roles in pdepe.

  tspan The pdepe function performs the time integration with an ODE solver that selects both the time step and formula dynamically. The elements of tspan merely specify where you want answers and the cost depends weakly on the length of tspan.

  xmesh Second order approximations to the solution are made on the mesh specified in xmesh. Generally, it is best to use closely spaced mesh points where the solution changes rapidly. pdepe does *not* select the mesh in x automatically. You must provide an appropriate fixed mesh in xmesh. The cost depends strongly on the length of xmesh. When $m > 0$, it is not necessary to use a fine mesh near $x = 0$ to account for the coordinate singularity.
- The time integration is done with ode15s. pdepe exploits the capabilities of ode15s for solving the differential-algebraic equations that arise when Equation 2-1 contains elliptic equations, and for handling Jacobians with a specified sparsity pattern.
- After discretization, elliptic equations give rise to algebraic equations. If the elements of the initial conditions vector that correspond to elliptic equations are not "consistent" with the discretization, pdepe tries to adjust them before beginning the time integration. For this reason, the solution returned for the initial time may have a discretization error comparable to that at any other time. If the mesh is sufficiently fine, pdepe can find consistent initial conditions close to the given ones. If pdepe displays a message that it has difficulty finding consistent initial conditions, try refining the mesh.

  No adjustment is necessary for elements of the initial conditions vector that correspond to parabolic equations.

Examples

Example 1. This example illustrates the straightforward formulation, computation, and plotting of the solution of a single PDE.

$$\pi^2 \frac{\partial u}{\partial t} = \frac{\partial}{\partial x}\left(\frac{\partial u}{\partial x}\right)$$

This equation holds on an interval $0 \le x \le 1$ for times $t \ge 0$.

The PDE satisfies the initial condition

$$u(x, 0) = \sin \pi x$$

and boundary conditions

$$u(0, t) \equiv 0$$
$$\pi e^{-t} + \frac{\partial u}{\partial x}(1, t) = 0$$

It is convenient to use subfunctions to place all the functions required by `pdepe` in a single M-file.

```
function pdex1

m = 0;
x = linspace(0,1,20);
t = linspace(0,2,5);

sol = pdepe(m,@pdex1pde,@pdex1ic,@pdex1bc,x,t);
% Extract the first solution component as u.
u = sol(:,:,1);

% A surface plot is often a good way to study a solution.
surf(x,t,u)
title('Numerical solution computed with 20 mesh points.')
xlabel('Distance x')
ylabel('Time t')

% A solution profile can also be illuminating.
figure
plot(x,u(end,:))
title('Solution at t = 2')
xlabel('Distance x')
```

```
ylabel('u(x,2)')
% --------------------------------------------------------------
function [c,f,s] = pdex1pde(x,t,u,DuDx)
c = pi^2;
f = DuDx;
s = 0;
% --------------------------------------------------------------
function u0 = pdex1ic(x)
u0 = sin(pi*x);
% --------------------------------------------------------------
function [pl,ql,pr,qr] = pdex1bc(xl,ul,xr,ur,t)
pl = ul;
ql = 0;
pr = pi * exp(-t);
qr = 1;
```

In this example, the PDE, initial condition, and boundary conditions are coded in subfunctions `pdex1pde`, `pdex1ic`, and `pdex1bc`.

The surface plot shows the behavior of the solution.



The following plot shows the solution profile at the final value of `t` (i.e., `t = 2`).



Example 2. This example illustrates the solution of a system of PDEs. The problem has boundary layers at both ends of the interval. The solution changes rapidly for small t.

The PDEs are

$$\frac{\partial u_1}{\partial t} = 0.024 \frac{\partial^2 u_1}{\partial x^2} - F(u_1 - u_2)$$

$$\frac{\partial u_2}{\partial t} = 0.170 \frac{\partial^2 u_2}{\partial x^2} + F(u_1 - u_2)$$

where $F(y) = \exp(5.73y) - \exp(-11.46y)$.

This equation holds on an interval $0 \le x \le 1$ for times $t \ge 0$.

The PDE satisfies the initial conditions

$$u_1(x, 0) \equiv 1$$
$$u_2(x, 0) \equiv 0$$

and boundary conditions

$$\frac{\partial u_1}{\partial x}(0, t) \equiv 0$$
$$u_2(0, t) \equiv 0$$
$$u_1(1, t) \equiv 1$$
$$\frac{\partial u_2}{\partial x}(1, t) \equiv 0$$

In the form expected by `pdepe`, the equations are

$$\begin{bmatrix} 1 \\ 1 \end{bmatrix} .* \frac{\partial}{\partial t}\begin{bmatrix} u_1 \\ u_2 \end{bmatrix} = \frac{\partial}{\partial x}\begin{bmatrix} 0.024(\partial u_1/\partial x) \\ 0.170(\partial u_2/\partial x) \end{bmatrix} + \begin{bmatrix} -F(u_1 - u_2) \\ F(u_1 - u_2) \end{bmatrix}$$

The boundary conditions on the partial derivatives of u have to be written in terms of the flux. In the form expected by `pdepe`, the left boundary condition is

$$\begin{bmatrix} 0 \\ u_2 \end{bmatrix} + \begin{bmatrix} 1 \\ 0 \end{bmatrix} .* \begin{bmatrix} 0.024(\partial u_1/\partial x) \\ 0.170(\partial u_2/\partial x) \end{bmatrix} = \begin{bmatrix} 0 \\ 0 \end{bmatrix}$$

and the right boundary condition is

$$\begin{bmatrix} u_1 - 1 \\ 0 \end{bmatrix} + \begin{bmatrix} 0 \\ 1 \end{bmatrix} .* \begin{bmatrix} 0.024(\partial u_1/\partial x) \\ 0.170(\partial u_2/\partial x) \end{bmatrix} = \begin{bmatrix} 0 \\ 0 \end{bmatrix}$$

The solution changes rapidly for small t. The program selects the step size in time to resolve this sharp change, but to see this behavior in the plots, the example must select the output times accordingly. There are boundary layers in the solution at both ends of [0,1], so the example places mesh points near `0` and `1` to resolve these sharp changes. Often some experimentation is needed to select a mesh that reveals the behavior of the solution.

```
function pdex4
m = 0;
x = [0 0.005 0.01 0.05 0.1 0.2 0.5 0.7 0.9 0.95 0.99 0.995 1];
t = [0 0.005 0.01 0.05 0.1 0.5 1 1.5 2];

sol = pdepe(m,@pdex4pde,@pdex4ic,@pdex4bc,x,t);
u1 = sol(:,:,1);
u2 = sol(:,:,2);

figure
surf(x,t,u1)
title('u1(x,t)')
xlabel('Distance x')
ylabel('Time t')

figure
surf(x,t,u2)
title('u2(x,t)')
xlabel('Distance x')
ylabel('Time t')
% --------------------------------------------------------------
function [c,f,s] = pdex4pde(x,t,u,DuDx)
c = [1; 1];
f = [0.024; 0.17] .* DuDx;
y = u(1) - u(2);
F = exp(5.73*y)-exp(-11.47*y);
s = [-F; F];
% --------------------------------------------------------------
function u0 = pdex4ic(x);
u0 = [1; 0];
% --------------------------------------------------------------
function [pl,ql,pr,qr] = pdex4bc(xl,ul,xr,ur,t)
pl = [0; ul(2)];
ql = [1; 0];
pr = [ur(1)-1; 0];
qr = [0; 1];
```

In this example, the PDEs, intial conditions, and boundary conditions are coded in subfunctions `pdex4pde`, `pdex4ic`, and `pdex4bc`.

The surface plots show the behavior of the solution components.





See Also

`function_handle`, `pdeval`, `ode15s`, `odeset`, `odeget`

References

[1] Skeel, R. D. and M. Berzins, "A Method for the Spatial Discretization of Parabolic Equations in One Space Variable," *SIAM Journal on Scientific and Statistical Computing*, Vol. 11, 1990, pp.1-32.

pdeval

Purpose

Evaluate the numerical solution of a PDE using the output of `pdepe`

Syntax

```
[uout,duoutdx] = pdeval(m,xmesh,ui,xout)
```

Arguments

`m`	Symmetry of the problem: slab = `0`, cylindrical = `1`, spherical = `2`. This is the first input argument used in the call to `pdepe`.
`xmesh`	A vector [`x0`, `x1`, ..., `xn`] specifying the points at which the elements of `ui` were computed. This is the same vector with which `pdepe` was called.
`ui`	A vector `sol(j,:,i)` that approximates component `i` of the solution at time t_f and mesh points `xmesh`, where `sol` is the solution returned by `pdepe`.
`xout`	A vector of points from the interval [`x0`,`xn`] at which the interpolated solution is requested.

Description

`[uout,duoutdx] = pdeval(m,x,ui,xout)` approximates the solution u_i and its partial derivative $\partial u_i/\partial x$ at points from the interval [`x0`,`xn`]. The `pdeval` function returns the computed values in `uout` and `duoutdx`, respectively.

Note `pdeval` evaluates the partial derivative $\partial u_i/\partial x$ rather than the flux f. Although the flux is continuous, the partial derivative may have a jump at a material interface.

See Also

`pdepe`

Purpose

A sample function of two variables.

Syntax

```
Z = peaks;
Z = peaks(n);
Z = peaks(V);
Z = peaks(X,Y);

peaks;
peaks(N);
peaks(V);
peaks(X,Y);

[X,Y,Z] = peaks;
[X,Y,Z] = peaks(n);
[X,Y,Z] = peaks(V);
```

Description

`peaks` is a function of two variables, obtained by translating and scaling Gaussian distributions, which is useful for demonstrating `mesh`, `surf`, `pcolor`, `contour`, and so on.

`Z = peaks;` returns a 49-by-49 matrix.

`Z = peaks(n);` returns an `n`-by-`n` matrix.

`Z = peaks(V);` returns an `n`-by-`n` matrix, where `n = length(V)`.

`Z = peaks(X,Y);` evaluates `peaks` at the given `X` and `Y` (which must be the same size) and returns a matrix the same size.

`peaks(...)` (with no output argument) plots the peaks function with `surf`.

`[X,Y,Z] = peaks(...);` returns two additional matrices, `X` and `Y`, for parametric plots, for example, `surf(X,Y,Z,del2(Z))`. If not given as input, the underlying matrices `X` and `Y` are

```
[X,Y] = meshgrid(V,V)
```

where `V` is a given vector, or `V` is a vector of length `n` with elements equally spaced from –3 to 3. If no input argument is given, the default `n` is 49.

See Also

`meshgrid`, `surf`

perl

Purpose

Call Perl script using appropriate operating system executable

Syntax

```
perl('perlfile')
perl('perlfile',arg1,arg2,...)
result = perl(...)
```

Description

`perl('perlfile')` calls the Perl script `perlfile`, using the appropriate operating system Perl executable. Perl is included with MATLAB, so MATLAB users can run M-files containing the `perl` function.

`perl('perlfile',arg1,arg2,...)` calls the Perl script `perlfile`, using the appropriate operating system Perl executable, and passes the arguments `arg1`, `arg2`, and so on, to `perlfile`.

`result = perl(...)` returns the results of attempted Perl call to `result`.

Examples

Given the Perl script, `hello.pl`

```
$input = $ARGV[0];
print "Hello $input.";
```

run the following statement in MATLAB

```
perl('hello.pl','World')
```

MATLAB returns

```
ans =
Hello World.
```

It is sometimes beneficial to use Perl scripts instead of MATLAB code. The `perl` function allows you to run those scripts from within MATLAB. Specific examples where you might choose to use a Perl script include:

- Perl script already exists
- Perl script preprocesses data quickly, formatting it in a way more easily read by MATLAB
- Perl has features not supported by MATLAB

See Also

`!` (exclamation point), `dos`, `regexp`, `system`, `unix`

Purpose

All possible permutations

Syntax

```
P = perms(v)
```

Description

`P = perms(v)`, where `v` is a row vector of length `n`, creates a matrix whose rows consist of all possible permutations of the `n` elements of `v`. Matrix `P` contains `n!` rows and `n` columns.

Examples

The command `perms(2:2:6)` returns *all* the permutations of the numbers 2, 4, and 6:

```
6     4     2
6     2     4
4     6     2
4     2     6
2     4     6
2     6     4
```

Limitations

This function is only practical for situations where `n` is less than about 15.

See Also

`nchoosek`, `permute`, `randperm`

permute

Purpose

Rearrange the dimensions of a multidimensional array

Syntax

```
B = permute(A,order)
```

Description

`B = permute(A,order)` rearranges the dimensions of `A` so that they are in the order specified by the vector `order`. `B` has the same values of `A` but the order of the subscripts needed to access any particular element is rearranged as specified by `order`. All the elements of `order` must be unique.

Remarks

`permute` and `ipermute` are a generalization of transpose (`.'`) for multidimensional arrays.

Examples

Given any matrix `A`, the statement

```
permute(A,[2 1])
```

is the same as `A'`.

For example:

```
A = [1 2; 3 4]; permute(A,[2 1])
ans =
     1     3
     2     4
```

The following code permutes a three-dimensional array:

```
X = rand(12,13,14);
Y = permute(X,[2 3 1]);
size(Y)
ans =
    13    14    12
```

See Also

`ipermute`

Purpose

Define persistent variable

Syntax

```
persistent X Y Z
```

Description

`persistent X Y Z` defines `X`, `Y`, and `Z` as variables that are local to the function in which they are declared; yet their values are retained in memory between calls to the function. Persistent variables are similar to global variables because MATLAB creates permanent storage for both. They differ from global variables in that persistent variables are known only to the function in which they are declared. This prevents persistent variables from being changed by other functions or from the MATLAB command line.

Persistent variables are cleared when the M-file is cleared from memory or when the M-file is changed. To keep an M-file in memory until MATLAB quits, use `mlock`.

If the persistent variable does not exist the first time you issue the `persistent` statement, it is initialized to the empty matrix.

It is an error to declare a variable persistent if a variable with the same name exists in the current workspace.

Remarks

There is no function form of the `persistent` command (i.e., you cannot use parentheses and quote the variable names).

See Also

`clear`, `global`, `mislocked`, `mlock`, `munlock`

pi

Purpose

Ratio of a circle's circumference to its diameter, π

Syntax

```
pi
```

Description

`pi` returns the floating-point number nearest the value of π. The expressions `4*atan(1)` and `imag(log(-1))` provide the same value.

Examples

The expression `sin(pi)` is not exactly zero because `pi` is not exactly π.

```
sin(pi)

ans =

   1.2246e-16
```

See Also

`ans`, `eps`, `i`, `Inf`, `j`, `NaN`

Purpose

Pie chart

Syntax

```
pie(X)
pie(X,explode)
pie(...,labels)
pie(axes_handle,...)
h = pie(...)
```

Description

`pie(X)` draws a pie chart using the data in `X`. Each element in `X` is represented as a slice in the pie chart.

`pie(X,explode)` offsets a slice from the pie. `explode` is a vector or matrix of zeros and nonzeros that correspond to `X`. A nonzero value offsets the corresponding slice from the center of the pie chart, so that `X(i,j)` is offset from the center if `explode(i,j)` is nonzero. `explode` must be the same size as `X`.

`pie(...,labels)` specifies text labels for the slices. The number of labels must equal the number of elements in `X`. For example,

```
pie(1:3,{'Taxes','Expenses','Profit'})
```

`pie(axes_handle,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = pie(...)` returns a vector of handles to patch and text graphics objects.

Remarks

The values in `X` are normalized via `X/sum(X)` to determine the area of each slice of the pie. If `sum(X)≤1`, the values in `X` directly specify the area of the pie slices. MATLAB draws only a partial pie if `sum(X)<1`.

Examples

Emphasize the second slice in the chart by setting its corresponding `explode` element to 1.

```
x = [1 3 0.5 2.5 2];
explode = [0 1 0 0 0];
pie(x,explode)
colormap jet
```



See Also

`pie3`

Purpose

Three-dimensional pie chart

Syntax

```
pie3(X)
pie3(X,explode)
pie3(...,labels)
pie3(axes_handle,...)
h = pie3(...)
```

Description

`pie3(X)` draws a three-dimensional pie chart using the data in `X`. Each element in `X` is represented as a slice in the pie chart.

`pie3(X,explode)` specifies whether to offset a slice from the center of the pie chart. `X(i,j)` is offset from the center of the pie chart if `explode(i,j)` is nonzero. `explode` must be the same size as `X`.

`pie3(...,labels)` specifies text labels for the slices. The number of labels must equal the number of elements in `X`. For example,

```
pie3(1:3,{'Taxes','Expenses','Profit'})
```

`pie3(axes_handle,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = pie(...)` returns a vector of handles to patch, surface, and text graphics objects.

Remarks

The values in `X` are normalized via `X/sum(X)` to determine the area of each slice of the pie. If `sum(X)`≤1, the values in `X` directly specify the area of the pie slices. MATLAB draws only a partial pie if `sum(X)`<1.

Examples

Offset a slice in the pie chart by setting the corresponding `explode` element to 1:

```
x = [1 3 0.5 2.5 2]
explode = [0 1 0 0 0]
pie3(x,explode)
colormap hsv
```

pie3



See Also `pie`

Purpose

Moore-Penrose pseudoinverse of a matrix

Syntax

```
B = pinv(A)
B = pinv(A,tol)
```

Definition

The Moore-Penrose pseudoinverse is a matrix `B` of the same dimensions as `A'` satisfying four conditions:

```
A*B*A = A
B*A*B = B
A*B is Hermitian
B*A is Hermitian
```

The computation is based on `svd(A)` and any singular values less than `tol` are treated as zero.

Description

`B = pinv(A)` returns the Moore-Penrose pseudoinverse of `A`.

`B = pinv(A,tol)` returns the Moore-Penrose pseudoinverse and overrides the default tolerance, `max(size(A))*norm(A)*eps`.

Examples

If `A` is square and not singular, then `pinv(A)` is an expensive way to compute `inv(A)`. If `A` is not square, or is square and singular, then `inv(A)` does not exist. In these cases, `pinv(A)` has some of, but not all, the properties of `inv(A)`.

If `A` has more rows than columns and is not of full rank, then the overdetermined least squares problem

```
minimize norm(A*x-b)
```

does not have a unique solution. Two of the infinitely many solutions are

```
x = pinv(A)*b
```

and

```
y = A\b
```

These two are distinguished by the facts that `norm(x)` is smaller than the norm of any other solution and that `y` has the fewest possible nonzero components.

For example, the matrix generated by

```
A = magic(8); A = A(:,1:6)
```

is an 8-by-6 matrix that happens to have `rank(A) = 3`.

```
A =
    64     2     3    61    60     6
     9    55    54    12    13    51
    17    47    46    20    21    43
    40    26    27    37    36    30
    32    34    35    29    28    38
    41    23    22    44    45    19
    49    15    14    52    53    11
     8    58    59     5     4    62
```

The right-hand side is `b = 260*ones(8,1)`,

```
b =
     260
     260
     260
     260
     260
     260
     260
     260
```

The scale factor 260 is the 8-by-8 magic sum. With all eight columns, one solution to `A*x = b` would be a vector of all 1's. With only six columns, the equations are still consistent, so a solution exists, but it is not all 1's. Since the matrix is rank deficient, there are infinitely many solutions. Two of them are

```
x = pinv(A)*b
```

which is

```
x =
    1.1538
    1.4615
    1.3846
    1.3846
    1.4615
    1.1538
```

and

```
y = A\b
```

which produces this result.

```
Warning: Rank deficient, rank = 3  tol =   1.8829e-013.
y =
    4.0000
    5.0000
         0
         0
         0
   -1.0000
```

Both of these are exact solutions in the sense that `norm(A*x-b)` and `norm(A*y-b)` are on the order of roundoff error. The solution `x` is special because

```
norm(x) = 3.2817
```

is smaller than the norm of any other solution, including

```
norm(y) = 6.4807
```

On the other hand, the solution `y` is special because it has only three nonzero components.

See Also

`inv`, `qr`, `rank`, `svd`

planerot

Purpose

Givens plane rotation

Syntax

```
[G,y] = planerot(x)
```

Description

`[G,y] = planerot(x)` where `x` is a 2-component column vector, returns a 2-by-2 orthogonal matrix G so that `y = G*x` has `y(2) = 0`.

Examples

```
x = [3 4];
[G,y] = planerot(x')

G  =
    0.6000    0.8000
   -0.8000    0.6000

y =
     5
     0
```

See Also

`qrdelete`, `qrinsert`

Purpose

Run published M-file demo

Syntax

```
playshow demoname
```

Description

`playshow` runs the published M-file demo `demoname`. To determine if a demo is a published M-file type, view the H1 line for the demo M-file, that is, the first comment line. If it begins with two comment symbols (`%%`), it is a published M-file demo.

Examples

The first line in `nesteddemo` begins with two comment symbols:

```
%% Nested Function Examples
```

Therefore, type `playshow nesteddemo` to run the demo.

See Also

`demo`, `helpbrowser`

plot

Purpose

Linear 2-D plot

Syntax

```
plot(Y)
plot(X1,Y1,...)
plot(X1,Y1,LineSpec,...)
plot(...,'PropertyName',PropertyValue,...)
plot(axes_handle,...)
h = plot(...)
hlines = plot('v6',...)
```

Description

`plot(Y)` plots the columns of `Y` versus their index if `Y` is a real number. If `Y` is complex, `plot(Y)` is equivalent to `plot(real(Y),imag(Y))`. In all other uses of `plot`, the imaginary component is ignored.

`plot(X1,Y1,...)` plots all lines defined by `Xn` versus `Yn` pairs. If only `Xn` or `Yn` is a matrix, the vector is plotted versus the rows or columns of the matrix, depending on whether the vector's row or column dimension matches the matrix.

`plot(X1,Y1,LineSpec,...)` plots all lines defined by the `Xn,Yn,LineSpec` triples, where `LineSpec` is a line specification that determines line type, marker symbol, and color of the plotted lines. You can mix `Xn,Yn,LineSpec` triples with `Xn,Yn` pairs: `plot(X1,Y1,X2,Y2,LineSpec,X3,Y3)`.

Note See `LineSpec` for a list of line style, marker, and color specifiers.

`plot(...,'PropertyName',PropertyValue,...)` sets properties to the specified property values for all lineseries graphics objects created by `plot`. (See the "Examples" section for examples.)

`plot(axes_handle,...)` plots into the axes with handle axes_handle instead of the current axes (`gca`).

`h = plot(...)` returns a column vector of handles to lineseries graphics objects, one handle per line.

Backward Compatible Version

`hlines = plot('v6',...)` returns the handles to line objects instead of lineseries objects.

Remarks

If you do not specify a color when plotting more than one line, `plot` automatically cycles through the colors in the order specified by the current axes `ColorOrder` property. After cycling through all the colors defined by `ColorOrder`, `plot` then cycles through the line styles defined in the axes `LineStyleOrder` property.

The default `LineStyleOrder` property has a single entry (a solid line with no marker).

Cycling Through Line Colors and Styles

By default, MATLAB resets the `ColorOrder` and `LineStyleOrder` properties each time you call `plot`. If you want changes you make to these properties to persist, then you must define these changes as default values. For example,

```
set(0,'DefaultAxesColorOrder',[0 0 0],...
      'DefaultAxesLineStyleOrder','-|-.|--|:')
```

sets the default `ColorOrder` to use only the color black and sets the `LineStyleOrder` to use solid, dash-dot, dash-dash, and dotted line styles.

Prevent Resetting of Color and Styles with hold all

The `all` option to the `hold` command prevents the `ColorOrder` and `LineStyleOrder` from being reset in subsequent `plot` commands. In the following sequence of commands, MATLAB continues to cycle through the colors defined by the axes `ColorOrder` property (see above).

```
plot(rand(12,2))
hold all
plot(randn(12,2))
```

Additional Information

- See Creating Line Plots and Annotating Graphs for more information on plotting.
- See `LineSpec` for more information on specifying line styles and colors.

Examples

Specifying the Color and Size of Markers

You can also specify other line characteristics using graphics properties (see `line` for a description of these properties):

- `LineWidth` — Specifies the width (in points) of the line.
- `MarkerEdgeColor` — Specifies the color of the marker or the edge color for filled markers (circle, square, diamond, pentagram, hexagram, and the four triangles).
- `MarkerFaceColor` — Specifies the color of the face of filled markers.
- `MarkerSize` — Specifies the size of the marker in units of points.

For example, these statements,

```
x = -pi:pi/10:pi;
y = tan(sin(x)) - sin(tan(x));
plot(x,y,'--rs','LineWidth',2,...
                'MarkerEdgeColor','k',...
                'MarkerFaceColor','g',...
                'MarkerSize',10)
```

produce this graph.



Specifying Tick-Mark Location and Labeling

You can adjust the axis tick-mark locations and the labels appearing at each tick. For example, this plot of the sine function relabels the *x*-axis with more meaningful values:

```
x = -pi:.1:pi;
y = sin(x);
plot(x,y)
set(gca,'XTick',-pi:pi/2:pi)
set(gca,'XTickLabel',{'-pi','-pi/2','0','pi/2','pi'})
```

Now add axis labels and annotate the point –pi/4, sin(–pi/4).



Adding Titles, Axis Labels, and Annotations

MATLAB enables you to add axis labels and titles. For example, using the graph from the previous example, add an *x*- and *y*-axis label:

```
xlabel('-\pi \leq \Theta \leq \pi')
ylabel('sin(\Theta)')
title('Plot of sin(\Theta)')
text(-pi/4,sin(-pi/4),'\leftarrow sin(-\pi\div4)',...
     'HorizontalAlignment','left')
```

Now change the line color to red by first finding the handle of the line object created by `plot` and then setting its `Color` property. In the same statement, set the `LineWidth` property to 2 points.

```
set(findobj(gca,'Type','line','Color',[0 0 1]),...
    'Color','red',...
    'LineWidth',2)
```



See Also

`axis`, `bar`, `grid`, `hold`, `legend`, `line`, `LineSpec`, `loglog`, `plot3`, `plotyy`, `semilogx`, `semilogy`, `subplot`, `title`, `xlabel`, `xlim`, `ylabel`, `ylim`, `zlabel`, `zlim`, `stem`

See the `text` `String` property for a list of symbols and how to display them.

See the Plot Editor for information on plot annotation tools in the figure window toolbar.

See Basic Plots and Graphs for related functions.

plot3

Purpose

3-D line plot

Syntax

```
plot3(X1,Y1,Z1,...)
plot3(X1,Y1,Z1,LineSpec,...)
plot3(...,'PropertyName',PropertyValue,...)
h = plot3(...)
```

Description

The `plot3` function displays a three-dimensional plot of a set of data points.

`plot3(X1,Y1,Z1,...)`, where `X1`, `Y1`, `Z1` are vectors or matrices, plots one or more lines in three-dimensional space through the points whose coordinates are the elements of `X1`, `Y1`, and `Z1`.

`plot3(X1,Y1,Z1,LineSpec,...)` creates and displays all lines defined by the `Xn,Yn,Zn,LineSpec` quads, where `LineSpec` is a line specification that determines line style, marker symbol, and color of the plotted lines.

`plot3(...,'PropertyName',PropertyValue,...)` sets properties to the specified property values for all line graphics objects created by `plot3`.

`h = plot3(...)` returns a column vector of handles to lineseries graphics objects, with one handle per object.

Remarks

If one or more of `X1`, `Y1`, `Z1` is a vector, the vectors are plotted versus the rows or columns of the matrix, depending whether the vectors' lengths equal the number of rows or the number of columns.

You can mix `Xn,Yn,Zn` triples with `Xn,Yn,Zn,LineSpec` quads, for example,

```
plot3(X1,Y1,Z1,X2,Y2,Z2,LineSpec,X3,Y3,Z3)
```

See `LineSpec` and `plot` for information on line types and markers.

Examples

Plot a three-dimensional helix.

```
t = 0:pi/50:10*pi;
plot3(sin(t),cos(t),t)
grid on
axis square
```



See Also axis, bar3, grid, line, LineSpec, loglog, plot, semilogx, semilogy, subplot

plotbrowser

Purpose

Show or hide figure plotbrowser

Syntax

```
plotbrowser('on')
plotbrowser('off')
plotbrowser('toggle')
plotbrowser(figure_handle,...)
```

Description

`plotbrowser('on')` displays the Plot Browser on the current figure.

`plotbrowser('off')` hides the Plot Browser on the current figure.

`plotbrowser('toggle')` or `plotbrowser` toggles the visibility of the Plot Browser on the current figure.

`plotbrowser(figure_handle,...)` shows or hides the Plot Browser on the figure specified by `figure_handle`.

See Also

`figurepalette`, `propertyeditor`

Purpose

Start plot edit mode to allow editing and annotation of plots

Syntax

```
plotedit on
plotedit off
plotedit
plotedit('state')
plotedit(h)
plotedit(h,'state')
```

Description

`plotedit on` starts plot edit mode for the current figure, allowing you to use a graphical interface to annotate and edit plots easily. In plot edit mode, you can label axes, change line styles, and add text, line, and arrow annotations.

`plotedit off` ends plot mode for the current figure.

`plotedit` toggles the plot edit mode for the current figure.

`plotedit(h)` toggles the plot edit mode for the figure specified by figure handle `h`.

`plotedit('state')` specifies the `plotedit` state for the current figure. Values for `state` can be as shown.

Value for *state*	Description
`on`	Starts plot edit mode
`off`	Ends plot edit mode
`showtoolsmenu`	Displays the **Tools** menu in the menu bar
`hidetoolsmenu`	Removes the **Tools** menu from the menu bar

Note `hidetoolsmenu` is intended for GUI developers who do not want the **Tools** menu to appear in applications that use the figure window.

`plotedit(h,'state')` specifies the `plotedit state` for figure handle `h`.

Remarks

Plot Editing Mode Graphical Interface Components



Examples

Start plot edit mode for figure 2.

```
plotedit(2)
```

End plot edit mode for figure 2.

```
plotedit(2, 'off')
```

Hide the **Tools** menu for the current figure:

```
plotedit('hidetoolsmenu')
```

See Also

`axes`, `line`, `open`, `plot`, `print`, `saveas`, `text`, `propedit`

plotmatrix

Purpose

Draw scatter plots

Syntax

```
plotmatrix(X,Y)
plotmatrix(...,'LineSpec')
[H,AX,BigAx,P] = plotmatrix(...)
```

Description

`plotmatrix(X,Y)` scatter plots the columns of `X` against the columns of `Y`. If `X` is *p*-by-*m* and `Y` is *p*-by-*n*, `plotmatrix` produces an *n*-by-*m* matrix of axes. `plotmatrix(Y)` is the same as `plotmatrix(Y,Y)` except that the diagonal is replaced by `hist(Y(:,i))`.

`plotmatrix(...,'LineSpec')` uses a `LineSpec` to create the scatter plot. The default is `'.'`.

`[H,AX,BigAx,P] = plotmatrix(...)` returns a matrix of handles to the objects created in `H`, a matrix of handles to the individual subaxes in `AX`, a handle to a big (invisible) axes that frames the subaxes in `BigAx`, and a matrix of handles for the histogram plots in `P`. `BigAx` is left as the current axes so that a subsequent `title`, `xlabel`, or `ylabel` command is centered with respect to the matrix of axes.

Examples

Generate plots of random data.

```
x = randn(50,3); y = x*[-1 2 1;2 0 1;1 -2 3;]';
plotmatrix(y,'*r')
```



See Also scatter, scatter3

plottools

Purpose

Show or hide the plot tools

Syntax

```
plottools('on')
plottools('off')
plottools
plottools(figure_handle,...)
plottools(...,'tool')
```

Description

`plottools('on')` displays the Figure Palette, Plot Browser, and Property Editor on the current figure.

`plottools('off')` hides the Figure Palette, Plot Browser, and Property Editor on the current figure.

`plottools` with no arguments, is the same as `plottools('on')`

`plottools(figure_handle,...)` displays or hides the plot tools on the specified figure instead of the current figure.

`plottools(...,'tool')` operates on the specified tool only. *`tool`* can be one of the following strings:

- `figurepalette`
- `plotbrowser`
- `propertyeditor`

See Also

`figurepalette`, `plotbrowser`, `propertyeditor`

Purpose

Create graphs with *y*-axes on both left and right side

Syntax

```
plotyy(X1,Y1,X2,Y2)
plotyy(X1,Y1,X2,Y2,'function')
plotyy(X1,Y1,X2,Y2,'function1','function2')
[AX,H1,H2] = plotyy(...)
```

Description

`plotyy(X1,Y1,X2,Y2)` plots `X1` versus `Y1` with *y*-axis labeling on the left and plots `X2` versus `Y2` with *y*-axis labeling on the right.

`plotyy(X1,Y1,X2,Y2,function)` uses the specified plotting function to produce the graph.

`function` can be either a function handle or a string specifying `plot`, `semilogx`, `semilogy`, `loglog`, `stem`, or any MATLAB function that accepts the syntax

```
h = function(x,y)
```

For example,

```
plotyy(x1,y1,x2,y2,@loglog) % function handle
plotyyx1,y1,x2,y2,'loglog') % string
```

Function handles enable you to access user-defined subfunctions and can provide other advantages. See @ for more information on using function handles.

`plotyy(X1,Y1,X2,Y2,'function1','function2')` uses `function1(X1,Y1)` to plot the data for the left axis and `function2(X2,Y2)` to plot the data for the right axis.

`[AX,H1,H2] = plotyy(...)` returns the handles of the two axes created in `AX` and the handles of the graphics objects from each plot in `H1` and `H2`. `AX(1)` is the left axes and `AX(2)` is the right axes.

Examples

This example graphs two mathematical functions using `plot` as the plotting function. The two *y*-axes enable you to display both sets of data on one graph even though relative values of the data are quite different.

```
x = 0:0.01:20;
y1 = 200*exp(-0.05*x).*sin(x);
```

```
y2 = 0.8*exp(-0.5*x).*sin(10*x);
[AX,H1,H2] = plotyy(x,y1,x,y2,'plot');
```

You can use the handles returned by `plotyy` to label the axes and set the line styles used for plotting. With the axes handles you can specify the `YLabel` properties of the left- and right-side *y*-axis:

```
set(get(AX(1),'Ylabel'),'String','Left Y-axis')
set(get(AX(2),'Ylabel'),'String','Right Y-axis')
```

Use the `xlabel` and `title` commands to label the *x*-axis and add a title:

```
xlabel('Zero to 20 \musec.')
title('Labeling plotyy')
```

Use the line handles to set the `LineStyle` properties of the left- and right-side plots:

```
set(H1,'LineStyle','--')
set(H2,'LineStyle',':')
```



See Also

`plot`, `loglog`, `semilogx`, `semilogy`, axes properties `XAxisLocation`, `YAxisLocation`

See Using Multiple X- and Y-Axes for more information.

pol2cart

Purpose

Transform polar or cylindrical coordinates to Cartesian

Syntax

```
[X,Y] = pol2cart(THETA,RHO)
[X,Y,Z] = pol2cart(THETA,RHO,Z)
```

Description

`[X,Y] = pol2cart(THETA,RHO)` transforms the polar coordinate data stored in corresponding elements of `THETA` and `RHO` to two-dimensional Cartesian, or *xy*, coordinates. The arrays `THETA` and `RHO` must be the same size (or either can be scalar). The values in `THETA` must be in radians.

`[X,Y,Z] = pol2cart(THETA,RHO,Z)` transforms the cylindrical coordinate data stored in corresponding elements of `THETA`, `RHO`, and `Z` to three-dimensional Cartesian, or *xyz*, coordinates. The arrays `THETA` , `RHO`, and `Z` must be the same size (or any can be scalar). The values in `THETA` must be in radians.

Algorithm

The mapping from polar and cylindrical coordinates to Cartesian coordinates is:



Polar to Cartesian Mapping

```
theta = atan2(y,x)
rho = sqrt(x.^2 + y.^2)
```



Cylindrical to Cartesian Mapping

```
theta = atan2(y,x)
rho = sqrt(x.^2 + y.^2)
    z = z
```

See Also

`cart2pol`, `cart2sph`, `sph2cart`

Purpose

Plot polar coordinates

Syntax

```
polar(theta,rho)
polar(theta,rho,LineSpec)
polar(axes_handle,...)
h = polar(...)
```

Description

The `polar` function accepts polar coordinates, plots them in a Cartesian plane, and draws the polar grid on the plane.

`polar(theta,rho)` creates a polar coordinate plot of the angle `theta` versus the radius `rho`. `theta` is the angle from the *x*-axis to the radius vector specified in radians; `rho` is the length of the radius vector specified in dataspace units.

`polar(theta,rho,LineSpec)` `LineSpec` specifies the line type, plot symbol, and color for the lines drawn in the polar plot.

`polar(axes_handle,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = polar(...)` returns the handle of a line object in `h`.

Examples

Create a simple polar plot using a dashed red line:

```
t = 0:.01:2*pi;

polar(t,sin(2*t).*cos(2*t),'--r')
```



See Also cart2pol, compass, LineSpec, plot, pol2cart, rose

Purpose

Polynomial with specified roots

Syntax

```
p = poly(A)
p = poly(r)
```

Description

`p = poly(A)` where `A` is an `n`-by-`n` matrix returns an `n+1` element row vector whose elements are the coefficients of the characteristic polynomial, $\det(sI - A)$. The coefficients are ordered in descending powers: if a vector `c` has `n+1` components, the polynomial it represents is $c_1 s^n + \ldots + c_n s + c_{n+1}$

`p = poly(r)` where `r` is a vector returns a row vector whose elements are the coefficients of the polynomial whose roots are the elements of `r`.

Remarks

Note the relationship of this command to

```
r = roots(p)
```

which returns a column vector whose elements are the roots of the polynomial specified by the coefficients row vector `p`. For vectors, `roots` and `poly` are inverse functions of each other, up to ordering, scaling, and roundoff error.

Examples

MATLAB displays polynomials as row vectors containing the coefficients ordered by descending powers. The characteristic equation of the matrix

```
A =

     1     2     3
     4     5     6
     7     8     0
```

is returned in a row vector by `poly`:

```
p = poly(A)

p =
     1    -6    -72    -27
```

The roots of this polynomial (eigenvalues of matrix `A`) are returned in a column vector by `roots`:

```
r = roots(p)
```

```
r =

    12.1229
    -5.7345
    -0.3884
```

Algorithm

The algorithms employed for `poly` and `roots` illustrate an interesting aspect of the modern approach to eigenvalue computation. `poly(A)` generates the characteristic polynomial of `A`, and `roots(poly(A))` finds the roots of that polynomial, which are the eigenvalues of `A`. But both `poly` and `roots` use `eig`, which is based on similarity transformations. The classical approach, which characterizes eigenvalues as roots of the characteristic polynomial, is actually reversed.

If `A` is an `n`-by-`n` matrix, `poly(A)` produces the coefficients `c(1)` through `c(n+1)`, with `c(1) = 1`, in

$$det(\lambda I - A) = c_1\lambda^n + \ldots + c_n\lambda + c_{n+1}$$

The algorithm is

```
z = eig(A);
c = zeros(n+1,1); c(1) = 1;
for j = 1:n
    c(2:j+1) = c(2:j+1)-z(j)*c(1:j);
end
```

This recursion is easily derived by expanding the product.

$$(\lambda - \lambda_1)(\lambda - \lambda_2)\ldots(\lambda - \lambda_n)$$

It is possible to prove that `poly(A)` produces the coefficients in the characteristic polynomial of a matrix within roundoff error of `A`. This is true even if the eigenvalues of `A` are badly conditioned. The traditional algorithms for obtaining the characteristic polynomial, which do not use the eigenvalues, do not have such satisfactory numerical properties.

See Also

`conv`, `polyval`, `residue`, `roots`

Purpose

Area of polygon

Syntax

```
A = polyarea(X,Y)
A = polyarea(X,Y,dim)
```

Description

`A = polyarea(X,Y)` returns the area of the polygon specified by the vertices in the vectors `X` and `Y`.

If `X` and `Y` are matrices of the same size, then `polyarea` returns the area of polygons defined by the columns `X` and `Y`.

If `X` and `Y` are multidimensional arrays, `polyarea` returns the area of the polygons in the first nonsingleton dimension of `X` and `Y`.

`A = polyarea(X,Y,dim)` operates along the dimension specified by scalar `dim`.

Examples

```
L = linspace(0,2.*pi,6); xv = cos(L)';yv = sin(L)';
xv = [xv ; xv(1)]; yv = [yv ; yv(1)];
A = polyarea(xv,yv);
plot(xv,yv); title(['Area = ' num2str(A)]); axis image
```



See Also

`convhull`, `inpolygon`, `rectint`

polyder

Purpose

Polynomial derivative

Syntax

```
k = polyder(p)
k = polyder(a,b)
[q,d] = polyder(b,a)
```

Description

The `polyder` function calculates the derivative of polynomials, polynomial products, and polynomial quotients. The operands `a`, `b`, and `p` are vectors whose elements are the coefficients of a polynomial in descending powers.

`k = polyder(p)` returns the derivative of the polynomial `p`.

`k = polyder(a,b)` returns the derivative of the product of the polynomials `a` and `b`.

`[q,d] = polyder(b,a)` returns the numerator `q` and denominator `d` of the derivative of the polynomial quotient `b/a`.

Examples

The derivative of the product

$$(3x^2 + 6x + 9)(x^2 + 2x)$$

is obtained with

```
a = [3 6 9];
b = [1 2 0];
k = polyder(a,b)
k =
    12    36    42    18
```

This result represents the polynomial

$$12x^3 + 36x^2 + 42x + 18$$

See Also

`conv`, `deconv`

Purpose

Polynomial eigenvalue problem

Syntax

```
[X,e] = polyeig(A0,A1,...Ap)
e = polyeig(A0,A1,..,Ap)
[X, e, s] = polyeig(A0,A1,..,AP)
```

Description

`[X,e] = polyeig(A0,A1,...Ap)` solves the polynomial eigenvalue problem of degree `p`

$$(A_0 + \lambda A_1 + \ldots + \lambda^P A_p)x = 0$$

where polynomial degree `p` is a non-negative integer, and `A0,A1,...Ap` are input matrices of order `n`. The output consists of a matrix `X`, of size `n`-by-`n*p`, whose columns are the eigenvectors, and a vector `e`, of length `n*p`, containing the eigenvalues.

If `lambda` is the `j`th eigenvalue in `e`, and `x` is the `j`th column of eigenvectors in `X`, then `(A0 + lambda*A1 + ... + lambda^p*Ap)*x` is approximately `0`.

`e = polyeig(A0,A1,..,Ap)` is a vector of length `n*p` whose elements are the eigenvalues of the polynomial eigenvalue problem.

`[X, e, s] = polyeig(A0,A1,..,AP)` also returns a `p*n` length vector `s`, of length `p*n`, containing condition numbers for the eigenvalues. At least one of `A0` and `AP` must be nonsingular. Large condition numbers imply that the problem is close to a problem with multiple eigenvalues.

Remarks

Based on the values of `p` and `n`, `polyeig` handles several special cases:

- `p = 0`, or `polyeig(A)` is the standard eigenvalue problem: `eig(A)`.
- `p = 1`, or `polyeig(A,B)` is the generalized eigenvalue problem: `eig(A,-B)`.
- `n = 1`, or `polyeig(a0,a1,...ap)` for scalars `a0`, `a1` ..., `ap` is the standard polynomial problem: `roots([ap ... a1 a0])`.

If both `A0` and `Ap` are singular the problem is potentially ill-posed. Theoretically, the solutions might not exist or might not be unique. Computationally, the computed solutions might be inaccurate. If one, but not both, of `A0` and `Ap` is singular, the problem is well posed, but some of the eigenvalues might be zero or infinite.

Algorithm

The `polyeig` function uses the QZ factorization to find intermediate results in the computation of generalized eigenvalues. It uses these intermediate results to determine if the eigenvalues are well-determined. See the descriptions of `eig` and `qz` for more on this.

See Also

`coneig`, `eig`, `qz`

References

[1] Dedieu, Jean-Pierre Dedieu and Francoise Tisseur, “Perturbation theory for homogeneous polynomial eigenvalue problems,” *Linear Algebra Appl.*, Vol. 358, pp. 71-94, 2003.

[2] Tisseur, Francoise and Karl Meerbergen, “The quadratic eigenvalue problem,” *SIAM Rev.*, Vol. 43, Number 2, pp. 235-286, 2001.

Purpose

Polynomial curve fitting

Syntax

```
p = polyfit(x,y,n)
[p,S] = polyfit(x,y,n)
[p,S,mu] = polyfit(x,y,n)
```

Description

`p = polyfit(x,y,n)` finds the coefficients of a polynomial `p(x)` of degree `n` that fits the data, `p(x(i))` to `y(i)`, in a least squares sense. The result `p` is a row vector of length `n+1` containing the polynomial coefficients in descending powers

$$p(x) = p_1 x^n + p_2 x^{n-1} + \ldots + p_n x + p_{n+1}$$

`[p,S] = polyfit(x,y,n)` returns the polynomial coefficients `p` and a structure `S` for use with `polyval` to obtain error estimates or predictions. If the errors in the data `y` are independent normal with constant variance, `polyval` produces error bounds that contain at least 50% of the predictions.

`[p,S,mu] = polyfit(x,y,n)` finds the coefficients of a polynomial in

$$\hat{x} = \frac{x - \mu_1}{\mu_2}$$

where $\mu_1 = \text{mean}(x)$ and $\mu_2 = \text{std}(x)$. `mu` is the two-element vector $[\mu_1, \mu_2]$. This centering and scaling transformation improves the numerical properties of both the polynomial and the fitting algorithm.

Examples

This example involves fitting the error function, `erf(x)`, by a polynomial in `x`. This is a risky project because `erf(x)` is a bounded function, while polynomials are unbounded, so the fit might not be very good.

First generate a vector of `x` points, equally spaced in the interval $[0, 2.5]$; then evaluate `erf(x)` at those points.

```
x = (0: 0.1: 2.5)';
y = erf(x);
```

The coefficients in the approximating polynomial of degree 6 are

```
p = polyfit(x,y,6)
```

```
p =

 0.0084   -0.0983    0.4217    -0.7435   0.1471    1.1064   0.0004
```

There are seven coefficients and the polynomial is

$$0.0084x^6 - 0.0983x^5 + 0.4217x^4 - 0.7435x^3 + 0.1471x^2 + 1.1064x + 0.0004$$

To see how good the fit is, evaluate the polynomial at the data points with

```
f = polyval(p,x);
```

A table showing the data, fit, and error is

```
table = [x y f y-f]

table =

   0          0          0.0004    -0.0004
   0.1000     0.1125     0.1119     0.0006
   0.2000     0.2227     0.2223     0.0004
   0.3000     0.3286     0.3287    -0.0001
   0.4000     0.4284     0.4288    -0.0004
   ...
   2.1000     0.9970     0.9969     0.0001
   2.2000     0.9981     0.9982    -0.0001
   2.3000     0.9989     0.9991    -0.0003
   2.4000     0.9993     0.9995    -0.0002
   2.5000     0.9996     0.9994     0.0002
```

So, on this interval, the fit is good to between three and four digits. Beyond this interval the graph shows that the polynomial behavior takes over and the approximation quickly deteriorates.

```
x = (0: 0.1: 5)';
y = erf(x);
f = polyval(p,x);
plot(x,y,'o',x,f,'-')
axis([0  5  0  2])
```



Algorithm

The `polyfit` M-file forms the Vandermonde matrix, V, whose elements are powers of x.

$$v_{i,j} = x_i^{n-j}$$

It then uses the backslash operator, `\`, to solve the least squares problem

$$Vp \cong y$$

You can modify the M-file to use other functions of x as the basis functions.

See Also

`poly`, `polyval`, `roots`

polyint

Purpose

Integrate polynomial analytically

Syntax

```
polyint(p,k)
polyint(p)
```

Description

`polyint(p,k)` returns a polynomial representing the integral of polynomial `p`, using a scalar constant of integration `k`.

`polyint(p)` assumes a constant of integration `k=0`.

See Also

`polyder`, `polyval`, `polyvalm`, `polyfit`

Purpose

Polynomial evaluation

Syntax

```
y = polyval(p,x)
y = polyval(p,x,[],mu)
[y,delta] = polyval(p,x,S)
[y,delta] = polyval(p,x,S,mu)
```

Description

`y = polyval(p,x)` returns the value of a polynomial of degree `n` evaluated at `x`. The input argument `p` is a vector of length `n+1` whose elements are the coefficients in descending powers of the polynomial to be evaluated.

$$y = p_1 x^n + p_2 x^{n-1} + \ldots + p_n x + p_{n+1}$$

`x` can be a matrix or a vector. In either case, `polyval` evaluates `p` at each element of `x`.

`y = polyval(p,x,[],mu)` uses $\hat{x} = (x - \mu_1)/\mu_2$ in place of x. In this equation, $\mu_1 = \text{mean}(x)$ and $\mu_2 = \text{std}(x)$. The centering and scaling parameters `mu` $= [\mu_1, \mu_2]$ are optional output computed by `polyfit`.

`[y,delta] = polyval(p,x,S)` and `[y,delta] = polyval(p,x,S,mu)` use the optional output structure `S` generated by `polyfit` to generate error estimates, `y±delta`. If the errors in the data input to `polyfit` are independent normal with constant variance, `y±delta` contains at least 50% of the predictions.

Remarks

The `polyvalm(p,x)` function, with `x` a matrix, evaluates the polynomial in a matrix sense. See `polyvalm` for more information.

Examples

The polynomial $p(x) = 3x^2 + 2x + 1$ is evaluated at $x = 5$, 7, and 9 with

```
p = [3 2 1];
polyval(p,[5 7 9])
```

which results in

```
ans =

    86   162   262
```

For another example, see `polyfit`.

See Also `polyfit`, `polyvalm`

Purpose

Matrix polynomial evaluation

Syntax

```
Y = polyvalm(p,X)
```

Description

`Y = polyvalm(p,X)` evaluates a polynomial in a matrix sense. This is the same as substituting matrix `X` in the polynomial `p`.

Polynomial `p` is a vector whose elements are the coefficients of a polynomial in descending powers, and `X` must be a square matrix.

Examples

The Pascal matrices are formed from Pascal's triangle of binomial coefficients. Here is the Pascal matrix of order 4.

```
X = pascal(4)
X =
     1     1     1     1
     1     2     3     4
     1     3     6    10
     1     4    10    20
```

Its characteristic polynomial can be generated with the `poly` function.

```
p = poly(X)
p =
   1   -29    72   -29    1
```

This represents the polynomial $x^4 - 29x^3 + 72x^2 - 29x + 1$.

Pascal matrices have the curious property that the vector of coefficients of the characteristic polynomial is palindromic; it is the same forward and backward.

Evaluating this polynomial at each element is not very interesting.

```
polyval(p,X)
ans =
   16      16      16      16
   16      15    -140    -563
   16    -140   -2549  -12089
   16    -563  -12089  -43779
```

But evaluating it in a matrix sense is interesting.

```
polyvalm(p,X)
```

```
ans =
   0    0    0    0
   0    0    0    0
   0    0    0    0
   0    0    0    0
```

The result is the zero matrix. This is an instance of the Cayley-Hamilton theorem: a matrix satisfies its own characteristic equation.

See Also

`polyfit`, `polyval`

Purpose

Base 2 power and scale floating-point numbers

Syntax

```
X = pow2(Y)
X = pow2(F,E)
```

Description

`X = pow2(Y)` returns an array `X` whose elements are 2 raised to the power `Y`.

`X = pow2(F,E)` computes $x = f * 2^e$ for corresponding elements of `F` and `E`. The result is computed quickly by simply adding `E` to the floating-point exponent of `F`. Arguments `F` and `E` are real and integer arrays, respectively.

Remarks

This function corresponds to the ANSI C function `ldexp()` and the IEEE floating-point standard function `scalbn()`.

Examples

For IEEE arithmetic, the statement `X = pow2(F,E)` yields the values:

```
F          E         X
1/2        1         1
pi/4       2         pi
-3/4       2         -3
1/2        -51       eps
1-eps/2    1024      realmax
1/2        -1021     realmin
```

See Also

`log2`, `exp`, `hex2num`, `realmax`, `realmin`

The arithmetic operators `^` and `.^`

ppval

Purpose

Evaluate piecewise polynomial.

Syntax

```
v = ppval(pp,xx)
v = ppval(xx,pp)
```

Description

`v = ppval(pp,xx)` returns the value at the points `xx` of the piecewise polynomial contained in `pp`, as constructed by `spline` or the spline utility `mkpp`.

`v = ppval(xx,pp)` returns the same result but can be used with functions like `fminbnd`, `fzero` and `quad` that take a function as an argument.

Examples

Compare the results of integrating the function `cos`

```
a = 0; b = 10;
int1 = quad(@cos,a,b,[],[])

int1 =
   -0.5440
```

with the results of integrating the piecewise polynomial `pp` that approximates the cosine function by interpolating the computed values `x` and `y`.

```
x = a:b;
y = cos(x);
pp = spline(x,y);
int2 = quad(@ppval,a,b,[],[],pp)

int2 =
   -0.5485
```

`int1` provides the integral of the cosine function over the interval `[a,b]`, while `int2` provides the integral over the same interval of the piecewise polynomial `pp`.

See Also

`mkpp`, `spline`, `unmkpp`

Purpose

Return directory containing preferences, history, and layout files

Syntax

```
prefdir
d = prefdir
d = prefdir(1)
```

Description

`prefdir` returns the directory that contains preferences for MATLAB and related products (`matlab.prf`), the command history (`history.m`), the MATLAB shortcuts (`shortcuts.xml`), and the MATLAB desktop layout files (`MATLABDesktop.xml` and `Your_Saved_LayoutMATLABLayout.xml`).

On Macintosh platforms, the directory might be in a hidden folder, for example, `myname/.matlab/R14`. To access the directory, select **Go -> Go to Folder** in the Finder. In the resulting dialog box, type the path returned by `prefdir` and press **Enter**.

`d = prefdir` returns the name of the directory containing preferences and related files, but does not ensure its existence.

`d = prefdir(1)` creates a directory for preferences and related files if one does not exist.

Examples

Run

```
prefdir
```

MATLAB returns

```
ans =

C:\WINNT\Profiles\tbear.MATHWORKS
\Application Data\MathWorks\MATLAB\R14
```

Running `dir` for the directory shows

```
.                   history.m
..                  matlab.prf
cwdhistory.m        MATLABDesktop.xml
shortcuts.xml
```

and possibly other files for other MathWorks products and any desktop layouts you saved.

See Also Fonts, Colors, and Other Preferences

Purpose

Display **Preferences** dialog box for MATLAB and related products

Graphical Interface

As an alternative to the `preferences` function, select **Preferences** from the **File** menu in the MATLAB desktop or any desktop tool.

Syntax

```
preferences
```

Description

`preferences` displays the **Preferences** dialog box, from which you can make changes to options for MATLAB and related products. For more information, see Fonts, Colors, and Other Preferences.

primes

Purpose

Generate list of prime numbers

Syntax

```
p = primes(n)
```

Description

`p = primes(n)` returns a row vector of the prime numbers less than or equal to `n`. A prime number is one that has no factors other than `1` and itself.

Examples

```
p = primes(37)

p =

     2     3     5     7    11    13    17    19    23    29    31    37
```

See Also

`factor`

Purpose

Create hardcopy output

Syntax

```
print
print filename
print -ddriver
print -dformat
print -dformat filename
print -smodelname
print ... -options
[pcmd,dev] = printopt
```

Description

`print` and `printopt` produce hardcopy output. All arguments to the `print` command are optional. You can use them in any combination or order.

`print` sends the contents of the current figure, including bitmap representations of any user interface controls, to the printer using the device and system printing command defined by `printopt`.

`print filename` directs the output to the file designated by `filename`. If `filename` does not include an extension, `print` appends an appropriate extension.

`print -ddriver` prints the figure using the specified printer *`driver`*, (such as color PostScript). If you omit `-ddriver`, print uses the default value stored in `printopt.m`. The Printer Driver table lists all supported device types.

`print -dformat` copies the figure to the system clipboard (Windows only). A valid *`format`* for this operation is either `-dmeta` (Windows Enhanced Metafile) or `-dbitmap` (Windows Bitmap).

`print -dformat filename` exports the figure to the specified file using the specified graphics *`format`*, (such as TIFF). The Graphics Format table lists all supported graphics file formats.

`print -smodelname` prints the current Simulink model *`modelname`*.

`print -options` specifies print options that modify the action of the `print` command. (For example, the `noui` option suppresses printing of user interface controls.) The Options section lists available options.

`print(...)` is the function form of `print`. It enables you to pass variables for any input arguments. This form is useful for passing filenames and handles. See Batch Processing for an example.

`[pcmd,dev] = printopt` returns strings containing the current system-dependent printing command and output device. `printopt` is an M-file used by `print` to produce the hardcopy output. You can edit the M-file `printopt.m` to set your default printer type and destination.

`pcmd` and `dev` are platform-dependent strings. `pcmd` contains the command that `print` uses to send a file to the printer. `dev` contains the printer driver or graphics format option for the `print` command. Their defaults are platform dependent.

Platform	System Printing Command	Driver or Format
UNIX	`lpr  r`	`dps2`
Windows	`COPY /B %s LPT1:`	`dwin`

Drivers

The table below shows the complete list of printer drivers supported by MATLAB. If you do not specify a driver, MATLAB uses the default setting shown in the previous table.

Some of the drivers are available from a product called Ghostscript, which is shipped with MATLAB. The last column indicates when Ghostscript is used.

Some drivers are not available on all platforms. This is noted in the first column of the table.

Printer Driver	PRINT Command Option String	GhostScript
Canon BubbleJet BJ10e	`-dbj10e`	Yes
Canon BubbleJet BJ200 color	`-dbj200`	Yes
Canon Color BubbleJet BJC-70/BJC-600/BJC-4000	`-dbjc600`	Yes
Canon Color BubbleJet BJC-800	`-dbjc800`	Yes

Printer Driver	PRINT Command Option String	GhostScript
DEC LN03	`-dln03`	Yes
Epson and compatible 9- or 24-pin dot matrix print drivers	`-depson`	Yes
Epson and compatible 9-pin with interleaved lines (triple resolution)	`-deps9high`	Yes
Epson LQ-2550 and compatible; color (not supported on HP-700)	`-depsonc`	Yes
Fujitsu 3400/2400/1200	`-depsonc`	Yes
HP DesignJet 650C color (not supported on Windows)	`-ddnj650c`	Yes
HP DeskJet 500	`-ddjet500`	Yes
HP DeskJet 500C (creates black and white output)	`-dcdjmono`	Yes
HP DeskJet 500C (with 24 bit/pixel color and high-quality Floyd-Steinberg color dithering) (not supported on Windows)	`-dcdjcolor`	Yes
HP DeskJet 500C/540C color (not supported on Windows)	`-dcdj500`	Yes
HP Deskjet 550C color (not supported on Windows)	`-dcdj550`	Yes
HP DeskJet and **DeskJet Plus**	`-ddeskjet`	Yes
HP LaserJet	`-dlaserjet`	Yes
HP LaserJet+	`-dljetplus`	Yes
HP LaserJet IIP	`-dljet2p`	Yes
HP LaserJet III	`-dljet3`	Yes
HP LaserJet 4.5L and 5P	`-dljet4`	Yes
HP LaserJet 5 and 6	`-dpxlmono`	Yes

Printer Driver	PRINT Command Option String	GhostScript
HP PaintJet color	`-dpaintjet`	Yes
HP PaintJet XL color	`-dpjxl`	Yes
HP PaintJet XL color	`-dpjetxl`	Yes
HP PaintJet XL300 color (not supported on Windows)	`-dpjxl300`	Yes
HPGL for HP 7475A and other compatible plotters. (Renderer cannot be set to Z-buffer.)	`-dhpgl`	No
IBM 9-pin Proprinter	`-dibmpro`	Yes
PostScript black and white	`-dps`	No
PostScript color	`-dpsc`	No
PostScript Level 2 black and white	`-dps2`	No
PostScript Level 2 color	`-dpsc2`	No
Windows color (Windows only)	`-dwinc`	No
Windows monochrome (Windows only)	`-dwin`	No

Note Generally, Level 2 PostScript files are smaller and are rendered more quickly when printing than Level 1 PostScript files. However, not all PostScript printers support Level 2, so determine the capabilities of your printer before using those drivers. Level 2 PostScript is the default for UNIX. You can change this default by editing the `printopt.m` file.

Graphics Format Files

To save your figure as a graphics-format file, specify a format switch and filename. To set the resolution of the output file for a built-in MATLAB format, use the `-r` switch. (For example, `-r300` sets the output resolution to 300 dots per inch.) The `-r` switch is also supported for Windows Enhanced Metafiles but is not supported for Ghostscript formats.

The table below shows the supported output formats for exporting from MATLAB and the switch settings to use. In some cases, a format is available both as a MATLAB output filter and as a Ghostscript output filter. The first column indicates this by showing “MATLAB” or “Ghostscript” in parentheses. All formats except for EMF are supported on both the PC and UNIX platforms.

Graphics Format	Bitmap or Vector	PRINT Command Option String	MATLAB or Ghostscript
BMP monochrome BMP	Bitmap	`-dbmpmono`	Ghostscript
BMP 24-bit BMP	Bitmap	`-dbmp16m`	Ghostscript
BMP 8-bit (256-color) BMP *this format uses a fixed colormap	Bitmap	`-dbmp256`	Ghostscript
BMP 24-bit	Bitmap	`-dbmp`	MATLAB
EMF	Vector	`-dmeta`	MATLAB
EPS black and white	Vector	`-deps`	MATLAB
EPS color	Vector	`-depsc`	MATLAB
EPS Level 2 black and white	Vector	`-deps2`	MATLAB
EPS Level 2 color	Vector	`-depsc2`	MATLAB
HDF 24-bit	Bitmap	`-dhdf`	MATLAB
ILL (Adobe Illustrator)	Vector	`-dill`	MATLAB
JPEG 24-bit	Bitmap	`-djpeg`	MATLAB
PBM (plain format) 1-bit	Bitmap	`-dpbm`	Ghostscript
PBM (raw format) 1-bit	Bitmap	`-dpbmraw`	Ghostscript
PCX 1-bit	Bitmap	`-dpcxmono`	Ghostscript
PCX 24-bit color PCX file format, three 8-bit planes	Bitmap	`-dpcx24b`	Ghostscript

Graphics Format	Bitmap or Vector	PRINT Command Option String	MATLAB or Ghostscript
PCX 8-bit Newer color PCX file format (256-color)	Bitmap	`-dpcx256`	Ghostscript
PCX Older color PCX file format (EGA/VGA, 16-color)	Bitmap	`-dpcx16`	Ghostscript
PCX 8-bit	Bitmap	`-dpcx`	MATLAB
PDF Color PDF file format		`-dpdf`	Ghostscript
PGM Portable Graymap (plain format)	Bitmap	`-dpgm`	Ghostscript
PGM Portable Graymap (raw format)	Bitmap	`-dpgmraw`	Ghostscript
PNG 24-bit	Bitmap	`-dpng`	MATLAB
PPM Portable Pixmap, plain format	Bitmap	`-dppm`	Ghostscript
PPM Portable Pixmap raw format	Bitmap	`-dppmraw`	Ghostscript
TIFF 24-bit	Bitmap	`-dtiff` or `-dtiffn`	MATLAB
TIFF preview for EPS Files	Bitmap	`-tiff`	

The TIFF image format is supported on all platforms by almost all word processors for importing images. JPEG is a lossy, highly compressed format that is supported on all platforms for image processing and for inclusion into HTML documents on the World Wide Web. To create these formats, MATLAB renders the figure using the Z-buffer rendering method and the resulting bitmap is then saved to the specified file.

Options

This table summarizes options that you can specify for `print`. The second column also shows which tutorial sections contain more detailed information.

The sections listed are located under Printing and Exporting Figures with MATLAB.

Option	Description
`-adobecset`	PostScript only. Use PostScript default character set encoding. See “Early PostScript 1 Printers.”
`-append`	PostScript only. Append figure to existing PostScript file. See “Settings That Are Driver Specific.”
`-cmyk`	PostScript only. Print with CMYK colors instead of RGB. See “Setting CMYK Color.”
`-ddriver`	Printing only. Printer driver to use. See Drivers table.
`-dformat`	Exporting only. Graphics format to use. See Graphics Format Files table.
`-dsetup`	Display the **Print Setup** dialog.
`-fhandle`	Handle of figure to print. Note that you cannot specify both this option and the `-s`*`windowtitle`* option. See “Which Figure Is Printed.”
`-loose`	PostScript and Ghostscript only. Use loose bounding box for PostScript. See “Producing Uncropped Figures.”
`-noui`	Suppress printing of user interface controls. See “Excluding User Interface Controls.”
`-opengl`	Render using the OpenGL algorithm. Note that you cannot specify this method in conjunction with `-zbuffer` or `-painters`. See “Selecting a Renderer.”
`-painters`	Render using the Painter’s algorithm. Note that you cannot specify this method in conjunction with `-zbuffer` or `-opengl`. See “Selecting a Renderer.”
`-Pprinter`	Specify name of printer to use. See “Selecting Printer.”
`-rnumber`	PostScript and Ghostscript only. Specify resolution in dots per inch. See “Setting the Resolution.”

Option	Description
`-swindowtitle`	Specify name of Simulink system window to print. Note that you cannot specify both this option and the `-fhandle` option. See “Which Figure Is Printed.”
`-v`	Windows only. Display the Windows **Print** dialog box. The `v` stands for “verbose mode.”
`-zbuffer`	Render using the Z-buffer algorithm. Note that you cannot specify this method in conjunction with `-opengl` or `-painters`. See “Selecting a Renderer.”

Paper Sizes

MATLAB supports a number of standard paper sizes. You can select from the following list by setting the `PaperType` property of the figure or selecting a supported paper size from the **Print** dialog box.

Property Value	Size (Width-by-Height)
`usletter`	8.5-by-11 inches
`uslegal`	11-by-14 inches
`tabloid`	11-by-17 inches
`A0`	841-by-1189 mm
`A1`	594-by-841 mm
`A2`	420-by-594 mm
`A3`	297-by-420 mm
`A4`	210-by-297 mm
`A5`	148-by-210 mm
`B0`	1029-by-1456 mm
`B1`	728-by-1028 mm
`B2`	514-by-728 mm

Property Value	Size (Width-by-Height)
B3	364-by-514 mm
B4	257-by-364 mm
B5	182-by-257 mm
arch-A	9-by-12 inches
arch-B	12-by-18 inches
arch-C	18-by-24 inches
arch-D	24-by-36 inches
arch-E	36-by-48 inches
A	8.5-by-11 inches
B	11-by-17 inches
C	17-by-22 inches
D	22-by-34 inches
E	34-by-43 inches

Printing Tips

This section includes information about specific printing issues.

Figures with Resize Functions

The `print` command produces a warning when you print a figure having a callback routine defined for the figure `ResizeFcn`. To avoid the warning, set the figure `PaperPositionMode` property to `auto` or select **Match Figure Screen Size** in the **File->Page Setup** dialog box.

Troubleshooting MS-Windows Printing

If you encounter problems such as segmentation violations, general protection faults, or application errors, or the output does not appear as you expect when using MS-Windows printer drivers, try the following:

- If your printer is PostScript compatible, print with one of the MATLAB built-in PostScript drivers. There are various PostScript device options that you can use with the `print` command: they all start with `–dps`.
- The behavior you are experiencing may occur only with certain versions of the print driver. Contact the print driver vendor for information on how to obtain and install a different driver.
- Try printing with one of the MATLAB built-in Ghostscript devices. These devices use Ghostscript to convert PostScript files into other formats, such as HP LaserJet, PCX, Canon BubbleJet, and so on.
- Copy the figure as a Windows Enhanced Metafile using the **Edit-->Copy Figure** menu item on the figure window menu or the `print –dmeta` option at the command line. You can then import the file into another application for printing.

  You can set copy options in the figure's **File-->Preferences-->Copying Options** dialog box. The Windows Enhanced Metafile clipboard format produces a better quality image than Windows Bitmap.

Printing MATLAB GUIs

You can generally obtain better results when printing a figure window that contains MATLAB `uicontrols` by setting these key properties:

- Set the figure `PaperPositionMode` property to `auto`. This ensures the printed version is the same size as the onscreen version. With `PaperPositionMode` set to `auto` MATLAB does not resize the figure to fit the current value of the `PaperPosition`. This is particularly important if you have specified a figure `ResizeFcn`, because if MATLAB resizes the figure during the print operation, the `ResizeFcn` is automatically called.

  To set `PaperPositionMode` on the current figure, use the command

  ```
  set(gcf,'PaperPositionMode','auto')
  ```

- Set the figure `InvertHardcopy` property to `off`. By default, MATLAB changes the figure background color of printed output to white, but does not change the color of uicontrols. If you have set the background color, for example, to match the gray of the GUI devices, you must set `InvertHardcopy` to `off` to preserve the color scheme.

  To set `InvertHardcopy` on the current figure, use the command

  ```
  set(gcf,'InvertHardcopy','off')
  ```

- Use a color device if you want lines and text that are in color on the screen to be written to the output file as colored objects. Black and white devices convert colored lines and text to black or white to provide the best contrast with the background and to avoid dithering.
- Use the `print` command's `–loose` option to prevent MATLAB from using a bounding box that is tightly wrapped around objects contained in the figure. This is important if you have intentionally used space between uicontrols or axes and the edge of the figure and you want to maintain this appearance in the printed output.

Notes on Printing Interpolated Shading with PostScript Drivers

MATLAB can print surface objects (such as graphs created with `surf` or `mesh`) using interpolated colors. However, only patch objects that are composed of triangular faces can be printed using interpolated shading.

Printed output is always interpolated in RGB space, not in the colormap colors. This means that if you are using indexed color and interpolated face coloring, the printed output can look different from what is displayed on screen.

PostScript files generated for interpolated shading contain the color information of the graphics object's vertices and require the printer to perform the interpolation calculations. This can take an excessive amount of time and in some cases, printers may actually time out before finishing the print job. One solution to this problem is to interpolate the data and generate a greater number of faces, which can then be flat shaded.

To ensure that the printed output matches what you see on the screen, print using the `-zbuffer` option. To obtain higher resolution (for example, to make text look better), use the `-r` option to increase the resolution. There is, however, a tradeoff between the resolution and the size of the created PostScript file, which can be quite large at higher resolutions. The default resolution of 150 dpi generally produces good results. You can reduce the size of the output file by making the figure smaller before printing it and setting the figure `PaperPositionMode` to `auto`, or by just setting the `PaperPosition` property to a smaller size.

Examples

Specifying the Figure to Print

You can print a noncurrent figure by specifying the figure's handle. If a figure has the title "Figure No. 2", its handle is 2. The syntax is

```
print -fhandle
```

This example prints the figure whose handle is 2, regardless of which figure is the current figure.

```
print -f2
```

Note You must use the `-f` option if the figure's handle is hidden (i.e., its `HandleVisibility` property is set to `off`).

This example saves the figure with the handle `-f2` to a PostScript file named `Figure2`, which can be printed later.

```
print -f2 -dps 'Figure2.ps'
```

If the figure uses noninteger handles, use the `figure` command to get its value, and then pass it in as the first argument.

```
h = figure('IntegerHandle','off')
print h -depson
```

You can also pass a figure handle as a variable to the function form of `print`. For example,

```
h = figure; plot(1:4,5:8)
print(h)
```

This example uses the function form of `print` to enable a filename to be passed in as a variable.

```
filename = 'mydata';
print('-f3', '-dpsc', filename);
```

(Because a filename is specified, the figure will be printed to a file.)

Specifying the Model to Print

To print a noncurrent Simulink model, use the `-s` option with the title of the window. For example, this command prints the Simulink window titled `f14`.

```
print -sf14
```

If the window title includes any spaces, you must call the function form rather than the command form of `print`. For example, this command saves Simulink window title `Thruster Control`.

```
print('-sThruster Control')
```

To print the current system, use

```
print -s
```

For information about issues specific to printing Simulink windows, see the Simulink documentation.

This example prints a surface plot with interpolated shading. Setting the current figure's (`gcf`) `PaperPositionMode` to `auto` enables you to resize the figure window and print it at the size you see on the screen. See Options and the previous section for information on the `–zbuffer` and `–r200` options.

```
surf(peaks)
shading interp
set(gcf,'PaperPositionMode','auto')
print –dpsc2 –zbuffer –r200
```

Batch Processing

You can use the function form of `print` to pass variables containing file names. For example, this for loop creates a series of graphs and prints each one with a different file name.

```
for k=1:length(fnames)
   surf(Z(:,:,k))
   print('-dtiff','-r200',fnames(k))
end
```

Tiff Preview

The command

```
print -depsc -tiff -r300 picture1
```

saves the current figure at 300 dpi, in a color Encapsulated PostScript file named `picture1.eps`. The `-tiff` option creates a 72 dpi TIFF preview, which many word processor applications can display on screen after you import the EPS file. This enables you to view the picture on screen within your word

processor and print the document to a PostScript printer using a resolution of 300 dpi.

See Also

`orient`, `figure`

Purpose

Display print dialog box

Syntax

```
printdlg
printdlg(fig)
printdlg('-crossplatform',fig)
printdlg('-setup',fig)
```

Description

`printdlg` prints the current figure.

`printdlg(fig)` creates a dialog box from which you can print the figure window identified by the handle `fig`. Note that uimenus do not print.

`printdlg('-crossplatform',fig)` displays the standard cross-platform MATLAB printing dialog rather than the built-in printing dialog box for Microsoft Windows computers. Insert this option before the `fig` argument.

`printdlg('-setup',fig)` forces the printing dialog to appear in a setup mode. Here one can set the default printing options without actually printing.

printpreview

Purpose

Preview figure to be printed

Syntax

```
printpreview
printpreview(f)
```

Description

`printpreview` displays a dialog box showing the figure in the currently active figure window as it will be printed. The figure is displayed with a `1/4` size thumbnail or full size image.

`printpreview(f)` displays a dialog box showing the figure having the handle `f` as it will be printed.

You can select any of the following options from the **Print Preview** dialog box.

Option Button	Description
`Print...`	Close **Print Preview** and open the **Print** dialog
`Page Setup...`	Open the **Page Setup** dialog
`Zoom In`	Display a full size image of the page
`Zoom Out`	Display a 1/4 scaled image of the page
`Close`	Close the **Print Preview** dialog

See Also

`printdlg`, `pagesetupdlg`

Purpose

Product of array elements

Syntax

```
B = prod(A)
B = prod(A,dim)
```

Description

`B = prod(A)` returns the products along different dimensions of an array.

If `A` is a vector, `prod(A)` returns the product of the elements.

If `A` is a matrix, `prod(A)` treats the columns of `A` as vectors, returning a row vector of the products of each column.

If `A` is a multidimensional array, `prod(A)` treats the values along the first non-singleton dimension as vectors, returning an array of row vectors.

`B = prod(A,dim)` takes the products along the dimension of `A` specified by scalar `dim`.

Examples

The magic square of order 3 is

```
M = magic(3)

M =
     8     1     6
     3     5     7
     4     9     2
```

The product of the elements in each column is

```
prod(M) =

    96    45    84
```

The product of the elements in each row can be obtained by:

```
prod(M,2) =

     48
    105
     72
```

See Also

`cumprod`, `diff`, `sum`

profile

Purpose

Profile the execution time for a function

Graphical Interface

As an alternative to the `profile` function, select **Desktop -> Profiler** from the desktop.

Syntax

```
profile on
profile on -detail level
profile on -history
profile off
profile resume
profile clear
profile viewer
s = profile('status')
stats = profile('info')
```

Description

The `profile` function helps you debug and optimize M-files by tracking their execution time. For each function in the M-file, `profile` records information about execution time, number of calls, parent functions, child functions, code line hit count, and code line execution time. Some people use `profile` simply to see the child functions; see also `depfun` for that purpose. To open the Profiler graphical user interface, use the `profile viewer` syntax.

`profile on` starts the Profiler, clearing previously recorded profile statistics.

`profile on -detail level` starts the Profiler, clearing previously recorded profile statistics, and specifying the set of functions you want to profile. Use the following text strings as the value of the `-detail` option, *`level`*.

Value for level	Gathers Information About
`'builtin'`	M-functions, M-subfunctions, and MEX-functions, plus built-in functions, such as `eig`
`'mmex'`	M-functions, M-subfunctions, and MEX-functions. This is the default value.

`profile on -history` starts the Profiler, clearing previously recorded profile statistics, and recording the exact sequence of function calls. The `profile`

function records up to 10,000 function entry and exit events. For more than 10,000 events, `profile` continues to record other profile statistics, but not the sequence of calls. By default, the `history` option is not enabled.

`profile off` stops the Profiler.

`profile resume` restarts the Profiler without clearing previously recorded statistics.

`profile clear` clears the statistics recorded by `profile`.

`profile viewer` stops the Profiler and displays the results in the Profiler window.

`S = profile('status')` returns a structure containing information about the current status of the Profiler. The table lists the fields in the order they appear in the structure.

Field	Values
`ProfilerStatus`	`'on'` or `'off'`
`DetailLevel`	`'mmex'` or `'builtin'`
`HistoryTracking`	`'on'` or `'off'`

`stats = profile('info')` stops the Profiler and displays a structure containing the results. Use this function to access the data generated by `profile`. The table lists the fields in the order they appear in the structure.

Field	Description
`FunctionTable`	Structure array containing statistics about each functions called
`FunctionHistory`	Array containing function call history
`ClockPrecision`	Precision of `profile`'s time measurement

Field	Description
`Name`	Name of the profiler
`ClockSpeed`	Estimated clock speed of the CPU

The `FunctionTable` field is an array of structures, where each structure contains information about one of the functions or subfunctions called during execution. The following table lists these fields in the order they appear in the structure.

Field	Description
`FunctionName`	Function name, includes subfunction references
`FileName`	Filename is a fully qualified path
`Type`	M-functions, MEX-functions, and many other types of functions including M-subfunctions, nested functions, and anonymous functions
`NumCalls`	Number of times this function was called
`TotalTime`	Total time spent in this function and its child functions
`TotalRecursiveTime`	No longer used. Ignore value.
`Children`	`FunctionTable` indices to child functions
`Parents`	`FunctionTable` indices to parent functions

Field	Description
`ExecutedLines`	Array containing line-by-line details for the function being profiled. Column 1: Number of the line that executed. If a line was not executed, it does not appear in this matrix. Column 2: Number of times that line was executed Column 3: Total time spent on that line. Note: The sum of Column 3 does not necessarily add up to the function's `TotalTime`.
`IsRecursive`	Boolean value: `True` if recursive, otherwise `False`
`AcceleratorMessages`	No longer used

Examples

This example profiles the MATLAB `magic` command and then displays the results in the Profiler window. The example then retrieves the profile data on which the HTML display is based and uses the `profsave` command to save the profile data in HTML form.

```
profile on
plot(magic(35))
profile viewer
p = profile('info');
profsave(p,'profile_results')
```

Another way to save profile data is to store it in a MAT-file. This example stores the profile data in a MAT-file, clears the profile data from memory, and then loads the profile data from the MAT-file. This example also shows a way to bring the reloaded profile data into the Profiler graphical interface as live profile data; not as a static HTML page.

```
p = profile('info');
save myprofiledata p
clear p
load myprofiledata
profview(0,p)
```

This example illustrates an effective way to view the results of profiling when the `history` option is enabled. The history data describes the sequence of functions entered and exited during execution. The `profile` command returns history data in the `FunctionHistory` field of the structure it returns. The history data is a 2-by-n array. The first row contains Boolean values where `1` means entrance into a function and `0` means exit from a function. The second row identifies the function being entered or exited by its index in the `FunctionTable` field. This example reads the history data and displays it in the MATLAB Command Window.

```
profile on -history
plot(magic(4));
p = profile('info');

for n = 1:size(p.FunctionHistory,2)
    if p.FunctionHistory(1,n)==0
        str = 'entering function: ';
    else
        str = ' exiting function: ';
    end
    disp([str p.FunctionTable(p.FunctionHistory(2,n)).FunctionName]);
end
```

See Also

`depdir`, `depfun`, `mlint`, `profsave`

See Profiling for Improving Performance

Purpose

Save profile report in HTML format

Syntax

```
profsave
profsave(profinfo)
profsave(profinfo,dirname)
```

Description

`profsave` executes the `profile('info')` function and saves the results in HTML format. `profsave` creates a separate HTML file for each function listed in the `FunctionTable` field of the structure returned by `profile`. By default, `profsave` stores the HTML files in a subdirectory of the current directory named `profile_results`.

`profsave(profinfo)` saves the profiling results, `profinfo`, in HTML format. `profinfo` is a structure of profiling information returned by the `profile('info')` function.

`profsave(profinfo,dirname)` saves the profiling results, `profinfo`, in HTML format. `profsave` creates a separate HTML file for each function listed in the `FunctionTable` field of `profinfo` and stores them in the directory specified by `dirname`.

Examples

Run `profile` and save the results.

```
profile on
plot(magic(5))
profile off
profsave(profile('info'),'myprofile_results')
```

See Also

`profile`

Profiling for Improving Performance

propedit

Purpose

Starts the Property Editor

Syntax

```
propedit
propedit(handle_list)
propedit(handle_list,'v6')
```

Description

`propedit` starts the Property Editor, a graphical user interface to the properties of graphics objects. There must be a current figure to call propedit without an object handle.

`propedit(handle_list)` edits the properties for the object (or objects) in `handle_list`.

`propedit(handle_list,'v6')` displays the MATLAB Version 6 Property Editor.

Starting the Property Editor enables plot editing mode for the figure.

Note The Version 6 Property Editor may not work with all objects.

See Also

`inspect`, `plotedit`, `propertyeditor`

Purpose

Show or hide property editor

Syntax

```
propertyeditor('on')
propertyeditor('off')
propertyeditor('toggle'), propertyeditor
propertyeditor(figure_handle,...)
```

Description

`propertyeditor('on')` displays the property editor on the current figure.

`propertyeditor('off')` hides the property editor on the current figure.

`propertyeditor('toggle')` or `propertyeditor` toggles the visibility of the property editor on the current figure.

`propertyeditor(figure_handle,...)` displays or hides the property editor on the figure specified by `figure_handle`.

See Also

`plotbrowser`, `figurepalette`

psi

Purpose

Psi (polygamma) function

Syntax

```
Y = psi(X)
Y = psi(k,X)
Y = psi(k0:k1,X)
```

Description

`Y = psi(X)` evaluates the ψ function for each element of array `X`. `X` must be real and nonnegative. The ψ function, also known as the digamma function, is the logarithmic derivative of the gamma function

$$\begin{aligned}\psi(x) &= \text{digamma}(x) \\ &= \frac{d(\log(\Gamma(x)))}{dx} \\ &= \frac{d(\Gamma(x))/dx}{\Gamma(x)}\end{aligned}$$

`Y = psi(k,X)` evaluates the `k`th derivative of ψ at the elements of `X`. `psi(0,X)` is the digamma function, `psi(1,X)` is the trigamma function, `psi(2,X)` is the tetragamma function, etc.

`Y = psi(k0:k1,X)` evaluates derivatives of order `k0` through `k1` at `X`. `Y(k,j)` is the `(k-1+k0)`th derivative of ψ, evaluated at `X(j)`.

Examples

Example 1. Use the `psi` function to calculate Euler's constant, γ.

```
format long
-psi(1)
ans =
   0.57721566490153

-psi(0,1)
ans =
   0.57721566490153
```

Example 2. The trigamma function of 2, `psi(1,2)`, is the same as $(\pi^2/6) - 1$.

```
format long
psi(1,2)
ans =
   0.64493406684823
```

```
pi^2/6 - 1
ans =
   0.64493406684823
```

Example 3. This code produces the first page of Table 6.1 in Abramowitz and Stegun [1].

```
x = (1:.005:1.250)';
[x gamma(x) gammaln(x) psi(0:1,x)' x-1]
```

Example 4. This code produces a portion of Table 6.2 in [1].

```
psi(2:3,1:.01:2)'
```

See Also

`gamma`, `gammainc`, `gammaln`

References

[1] Abramowitz, M. and I. A. Stegun, *Handbook of Mathematical Functions*, Dover Publlications, 1965, Sections 6.3 and 6.4.

publish

Purpose

Run M-file containing cells, and save results to file of specified type

Graphical Interface

As an alternative to the `publish` function, use the **File -> Publish To** menu items in the Editor/Debugger.

Syntax

```
publish('script')
publish('script', 'format')
publish('script', 'options')
```

Description

`publish('script')` runs the file named `script` and publishes the code, comments, and results to an HTML output file. The output file is named `script.html` and is stored, along with other supporting output files, in an `html` subdirectory in `script`'s directory.

`publish('script', 'format')` runs the file named `script` and publishes the code, comments, and results to an output file using the specified `format`. Allowable values for `format` are `html` (the default), `xml`, `tex` for LaTeX, `doc` for Microsoft Word documents, and `ppt` for Microsoft PowerPoint documents. The output file is named `script.format` and is stored, along with other supporting output files, in an `html` subdirectory in `script`'s directory.

`publish('script', 'options')` provides a structure of options that may contain any of the following fields (first choice listed is the default):

Field	Values
`format`	`'html' | 'doc' | 'ppt' | 'xml' | 'rpt' | 'latex'`
`stylesheet`	`''` | an XSL filename (ignored unless format is HTML or XML)
`outputDir`	`''` (an html subfolder below the file) | `full path`
`imageFormat`	`'png'` | any supported by `PRINT` or `IMWRITE`, depending on `figureSnapMethod`
`figureSnapMethod`	`'print' | 'getframe'`

Field	Values
useNewFigure	true | false
maxHeight	[] | positive integer (pixels)
maxWidth	[] | positive integer (pixels)
showCode	true | false
evalCode	true | false
stopOnError	true | false
createThumbnail	true | false

Examples

To publish the file d:/mymfiles/sine_wave.m to HTML, run

```
publish('d:/mymfiles/sine_wave.m', 'html')
```

MATLAB runs the file and saves the code, comments, and results to d:/mymfiles/html/sine_wave.html. Open that file in a browser to view the published document.

See Also

notebook

Publishing to HTML, XML, LaTeX, Word and PowerPoint Using Cells

pwd

Purpose

Display current directory

Graphical Interface

As an alternative to the `pwd` function, use the current directory field in the MATLAB desktop toolbar.

Syntax

```
pwd
s = pwd
```

Description

`pwd` displays the current working directory.

`s = pwd` returns the current directory to the variable `s`.

See Also

`cd`, `dir`, `fileparts`, `mfilename`, `path`, `what`

Purpose

Quasi-Minimal Residual method

Syntax

```
x = qmr(A,b)
qmr(A,b,tol)
qmr(A,b,tol,maxit)
qmr(A,b,tol,maxit,M)
qmr(A,b,tol,maxit,M1,M2)
qmr(A,b,tol,maxit,M1,M2,x0)
qmr(afun,b,tol,maxit,m1fun,m2fun,x0,p1,p2,...)
[x,flag] = qmr(A,b,...)
[x,flag,relres] = qmr(A,b,...)
[x,flag,relres,iter] = qmr(A,b,...)
[x,flag,relres,iter,resvec] = qmr(A,b,...)
```

Description

`x = qmr(A,b)` attempts to solve the system of linear equations `A*x=b` for `x`. The `n`-by-`n` coefficient matrix `A` must be square and should be large and sparse. The column vector `b` must have length `n`. `A` can be a function `afun` such that `afun(x)` returns `A*x` and `afun(x,'transp')` returns `A'*x`.

If `qmr` converges, a message to that effect is displayed. If `qmr` fails to converge after the maximum number of iterations or halts for any reason, a warning message is printed displaying the relative residual `norm(b-A*x)/norm(b)` and the iteration number at which the method stopped or failed.

`qmr(A,b,tol)` specifies the tolerance of the method. If `tol` is `[]`, then `qmr` uses the default, `1e-6`.

`qmr(A,b,tol,maxit)` specifies the maximum number of iterations. If `maxit` is `[]`, then `qmr` uses the default, `min(n,20)`.

`qmr(A,b,tol,maxit,M)` and `qmr(A,b,tol,maxit,M1,M2)` use preconditioners `M` or `M = M1*M2` and effectively solve the system `inv(M)*A*x = inv(M)*b` for `x`. If `M` is `[]` then `qmr` applies no preconditioner. `M` can be a function `mfun` such that `mfun(x)` returns `M\x` and `mfun(x,'transp')` returns `M'\x`.

`qmr(A,b,tol,maxit,M1,M2,x0)` specifies the initial guess. If `x0` is `[]`, then `qmr` uses the default, an all zero vector.

`qmr(afun,b,tol,maxit,m1fun,m2fun,x0,p1,p2,...)` passes parameters `p1,p2,...` to functions `afun(x,p1,p2,...)` and `afun(x,p1,p2,...,'transp')` and similarly to the preconditioner functions `m1fun` and `m2fun`.

`[x,flag] = qmr(A,b,...)` also returns a convergence flag.

Flag	Convergence
0	`qmr` converged to the desired tolerance `tol` within `maxit` iterations.
1	`qmr` iterated `maxit` times but did not converge.
2	Preconditioner `M` was ill-conditioned.
3	The method stagnated. (Two consecutive iterates were the same.)
4	One of the scalar quantities calculated during `qmr` became too small or too large to continue computing.

Whenever `flag` is not `0`, the solution `x` returned is that with minimal norm residual computed over all the iterations. No messages are displayed if the `flag` output is specified.

`[x,flag,relres] = qmr(A,b,...)` also returns the relative residual `norm(b-A*x)/norm(b)`. If `flag` is `0`, `relres <= tol`.

`[x,flag,relres,iter] = qmr(A,b,...)` also returns the iteration number at which `x` was computed, where `0 <= iter <= maxit`.

`[x,flag,relres,iter,resvec] = qmr(A,b,...)` also returns a vector of the residual norms at each iteration, including `norm(b-A*x0)`.

Examples

Example 1.

```
n = 100;
on = ones(n,1);
A = spdiags([-2*on 4*on -on],-1:1,n,n);
b = sum(A,2);
```

```
tol = 1e-8; maxit = 15;
M1 = spdiags([on/(-2) on],-1:0,n,n);
M2 = spdiags([4*on -on],0:1,n,n);
x = qmr(A,b,tol,maxit,M1,M2,[]);
```

Alternatively, use this matrix-vector product function

```
function y = afun(x,n,transp_flag)
if (nargin > 2) & strcmp(transp_flag,'transp')
   y = 4 * x;
   y(1:n-1) = y(1:n-1) - 2 * x(2:n);
   y(2:n) = y(2:n) - x(1:n-1);
else
   y = 4 * x;
   y(2:n) = y(2:n) - 2 * x(1:n-1);
   y(1:n-1) = y(1:n-1) - x(2:n);
end
```

as input to `qmr`

```
x1 = qmr(@afun,b,tol,maxit,M1,M2,[],n);
```

Example 2.

```
load west0479;
A = west0479;
b = sum(A,2);
[x,flag] = qmr(A,b)
```

`flag` is `1` because `qmr` does not converge to the default tolerance `1e-6` within the default 20 iterations.

```
[L1,U1] = luinc(A,1e-5);
[x1,flag1] = qmr(A,b,1e-6,20,L1,U1)
```

`flag1` is `2` because the upper triangular `U1` has a zero on its diagonal, and `qmr` fails in the first iteration when it tries to solve a system such as `U1*y = r` for `y` using backslash.

```
[L2,U2] = luinc(A,1e-6);
[x2,flag2,relres2,iter2,resvec2] = qmr(A,b,1e-15,10,L2,U2)
```

`flag2` is `0` because `qmr` converges to the tolerance of `1.6571e-016` (the value of `relres2`) at the eighth iteration (the value of `iter2`) when preconditioned by

the incomplete LU factorization with a drop tolerance of `1e-6`. `resvec2(1) = norm(b)` and `resvec2(9) = norm(b-A*x2)`. You can follow the progress of `qmr` by plotting the relative residuals at each iteration starting from the initial estimate (iterate number `0`).

```
semilogy(0:iter2,resvec2/norm(b),'-o')
xlabel('iteration number')
ylabel('relative residual')
```



See Also

`bicg`, `bicgstab`, `cgs`, `gmres`, `lsqr`, `luinc`, `minres`, `pcg`, `symmlq`

`@` (function handle), `\` (backslash)

References

[1] Barrett, R., M. Berry, T. F. Chan, et al., *Templates for the Solution of Linear Systems: Building Blocks for Iterative Methods*, SIAM, Philadelphia, 1994.

[2] Freund, Roland W. and Nöel M. Nachtigal, "QMR: A quasi-minimal residual method for non-Hermitian linear systems", *SIAM Journal: Numer. Math.* 60, 1991, pp. 315-339.

Purpose

Orthogonal-triangular decomposition

Syntax

```
[Q,R] = qr(A)        (full and sparse matrices)
[Q,R] = qr(A,0)      (full and sparse matrices)
[Q,R,E] = qr(A)      (full matrices)
[Q,R,E] = qr(A,0)    (full matrices)
X = qr(A)            (full matrices)
R = qr(A)            (sparse matrices)
[C,R] = qr(A,B)      (sparse matrices)
R = qr(A,0)          (sparse matrices)
[C,R] = qr(A,B,0)    (sparse matrices)
```

Description

The `qr` function performs the orthogonal-triangular decomposition of a matrix. This factorization is useful for both square and rectangular matrices. It expresses the matrix as the product of a real orthonormal or complex unitary matrix and an upper triangular matrix.

`[Q,R] = qr(A)` produces an upper triangular matrix `R` of the same dimension as `A` and a unitary matrix `Q` so that `A = Q*R`. For sparse matrices, `Q` is often nearly full. If `[m n] = size(A)`, then `Q` is `m`-by-`m` and `R` is `m`-by-`n`.

`[Q,R] = qr(A,0)` produces an "economy-size" decomposition. If `[m n] = size(A)`, and `m > n`, then `qr` computes only the first `n` columns of of `Q` and `R` is `n`-by-`n`. If `m <= n`, it is the same as `[Q,R] = qr(A)`.

`[Q,R,E] = qr(A)` for full matrix `A`, produces a permutation matrix `E`, an upper triangular matrix `R` with decreasing diagonal elements, and a unitary matrix `Q` so that `A*E = Q*R`. The column permutation `E` is chosen so that `abs(diag(R))` is decreasing.

`[Q,R,E] = qr(A,0)` for full matrix `A`, produces an "economy-size" decomposition in which `E` is a permutation vector, so that `A(:,E) = Q*R`. The column permutation `E` is chosen so that `abs(diag(R))` is decreasing.

`X = qr(A)` for full matrix `A`, returns the output of the LAPACK subroutine `DGEQRF` or `ZGEQRF`. `triu(qr(A))` is `R`.

`R = qr(A)` for sparse matrix `A`, produces only an upper triangular matrix, `R`. The matrix `R` provides a Cholesky factorization for the matrix associated with the normal equations,

```
R'*R = A'*A
```

This approach avoids the loss of numerical information inherent in the computation of `A'*A`. It may be preferred to `[Q,R] = qr(A)` since `Q` is always nearly full.

`[C,R] = qr(A,B)` for sparse matrix `A`, applies the orthogonal transformations to `B`, producing `C = Q'*B` without computing `Q`. `B` and `A` must have the same number of rows.

`R = qr(A,0)` and `[C,R] = qr(A,B,0)` for sparse matrix `A`, produce "economy-size" results.

For sparse matrices, the Q-less QR factorization allows the solution of sparse least squares problems

$$\text{minimize} \|Ax - b\|$$

with two steps

```
[C,R] = qr(A,b)
x = R\c
```

If `A` is sparse but not square, MATLAB uses the two steps above for the linear equation solving backslash operator, i.e., `x = A\b`.

Examples

Example 1. Start with

```
A =  [ 1     2     3
       4     5     6
       7     8     9
      10    11    12 ]
```

This is a rank-deficient matrix; the middle column is the average of the other two columns. The rank deficiency is revealed by the factorization:

```
[Q,R] = qr(A)

Q =
```

```
    -0.0776    -0.8331     0.5444     0.0605
    -0.3105    -0.4512    -0.7709     0.3251
    -0.5433    -0.0694    -0.0913    -0.8317
    -0.7762     0.3124     0.3178     0.4461

R =

   -12.8841   -14.5916   -16.2992
         0    -1.0413    -2.0826
         0          0     0.0000
         0          0          0
```

The triangular structure of `R` gives it zeros below the diagonal; the zero on the diagonal in `R(3,3)` implies that `R`, and consequently `A`, does not have full rank.

Example 2. This examples uses matrix `A` from the first example. The QR factorization is used to solve linear systems with more equations than unknowns. For example, let

```
b = [1;3;5;7]
```

The linear system $Ax = b$ represents four equations in only three unknowns. The best solution in a least squares sense is computed by

```
x = A\b
```

which produces

```
Warning: Rank deficient, rank = 2, tol = 1.4594E-014
x =
    0.5000
         0
    0.1667
```

The quantity `tol` is a tolerance used to decide if a diagonal element of `R` is negligible. If `[Q,R,E] = qr(A)`, then

```
tol = max(size(A))*eps*abs(R(1,1))
```

The solution `x` was computed using the factorization and the two steps

```
y = Q'*b;
x = R\y
```

The computed solution can be checked by forming Ax. This equals b to within roundoff error, which indicates that even though the simultaneous equations $Ax = b$ are overdetermined and rank deficient, they happen to be consistent. There are infinitely many solution vectors x; the QR factorization has found just one of them.

Algorithm

The qr function uses LAPACK routines to compute the QR decomposition:

Syntax	Real	Complex
`R = qr(A)` `R = qr(A,0)`	DGEQRF	ZGEQRF
`[Q,R] = qr(A)` `[Q,R] = qr(A,0)`	DGEQRF, DORGQR	ZGEQRF, ZUNGQR
`[Q,R,e] = qr(A)` `[Q,R,e] = qr(A,0)`	DGEQP3, DORGQR	ZGEQPF, ZUNGQR

See Also

lu, null, orth, qrdelete, qrinsert, qrupdate

The arithmetic operators \ and /

References

[1] Anderson, E., Z. Bai, C. Bischof, S. Blackford, J. Demmel, J. Dongarra, J. Du Croz, A. Greenbaum, S. Hammarling, A. McKenney, and D. Sorensen, *LAPACK User's Guide* (http://www.netlib.org/lapack/lug/lapack_lug.html), Third Edition, SIAM, Philadelphia, 1999.

Purpose

Delete column or row from QR factorization

Syntax

```
[Q1,R1] = qrdelete(Q,R,j)
[Q1,R1] = qrdelete(Q,R,j,'col')
[Q1,R1] = qrdelete(Q,R,j,'row')
```

Description

`[Q1,R1] = qrdelete(Q,R,j)` returns the QR factorization of the matrix `A1`, where `A1` is `A` with the column `A(:,j)` removed and `[Q,R] = qr(A)` is the QR factorization of `A`.

`[Q1,R1] = qrdelete(Q,R,j,'col')` is the same as `qrdelete(Q,R,j)`.

`[Q1,R1] = qrdelete(Q,R,j,'row')` returns the QR factorization of the matrix `A1`, where `A1` is `A` with the row `A(j,:)` removed and `[Q,R] = qr(A)` is the QR factorization of `A`.

Examples

```
A = magic(5);
[Q,R] = qr(A);
j = 3;
[Q1,R1] = qrdelete(Q,R,j,'row');

Q1 =
    0.5274   -0.5197   -0.6697   -0.0578
    0.7135    0.6911    0.0158    0.1142
    0.3102   -0.1982    0.4675   -0.8037
    0.3413   -0.4616    0.5768    0.5811

R1 =
   32.2335   26.0908   19.9482   21.4063   23.3297
         0  -19.7045  -10.9891    0.4318   -1.4873
         0         0   22.7444    5.8357   -3.1977
         0         0         0  -14.5784    3.7796
```

returns a valid QR factorization, although possibly different from

```
A2 = A;
A2(j,:) = [];
[Q2,R2] = qr(A2)
```

```
Q2 =
   -0.5274    0.5197    0.6697   -0.0578
   -0.7135   -0.6911   -0.0158    0.1142
   -0.3102    0.1982   -0.4675   -0.8037
   -0.3413    0.4616   -0.5768    0.5811

R2 =
  -32.2335  -26.0908  -19.9482  -21.4063  -23.3297
         0   19.7045   10.9891   -0.4318    1.4873
         0         0  -22.7444   -5.8357    3.1977
         0         0         0  -14.5784    3.7796
```

Algorithm

The `qrdelete` function uses a series of Givens rotations to zero out the appropriate elements of the factorization.

See Also

`planerot`, `qr`, `qrinsert`

Purpose

Insert column or row into QR factorization

Syntax

```
[Q1,R1] = qrinsert(Q,R,j,x)
[Q1,R1] = qrinsert(Q,R,j,x,'col')
[Q1,R1] = qrinsert(Q,R,j,x,'row')
```

Description

`[Q1,R1] = qrinsert(Q,R,j,x)` returns the QR factorization of the matrix `A1`, where `A1` is `A = Q*R` with the column `x` inserted before `A(:,j)`. If `A` has `n` columns and `j = n+1`, then `x` is inserted after the last column of `A`.

`[Q1,R1] = qrinsert(Q,R,j,x,'col')` is the same as `qrinsert(Q,R,j,x)`.

`[Q1,R1] = qrinsert(Q,R,j,x,'row')` returns the QR factorization of the matrix `A1`, where `A1` is `A = Q*R` with an extra row, `x`, inserted before `A(j,:)`.

Examples

```
A = magic(5);
[Q,R] = qr(A);
j = 3;
x = 1:5;
[Q1,R1] = qrinsert(Q,R,j,x,'row')

Q1 =
    0.5231    0.5039   -0.6750    0.1205    0.0411    0.0225
    0.7078   -0.6966    0.0190   -0.0788    0.0833   -0.0150
    0.0308    0.0592    0.0656    0.1169    0.1527   -0.9769
    0.1231    0.1363    0.3542    0.6222    0.6398    0.2104
    0.3077    0.1902    0.4100    0.4161   -0.7264   -0.0150
    0.3385    0.4500    0.4961   -0.6366    0.1761    0.0225

R1 =
   32.4962   26.6801   21.4795   23.8182   26.0031
         0   19.9292   12.4403    2.1340    4.3271
         0         0   24.4514   11.8132    3.9931
         0         0         0   20.2382   10.3392
         0         0         0         0   16.1948
         0         0         0         0         0
```

returns a valid QR factorization, although possibly different from

```
A2 = [A(1:j-1,:); x; A(j:end,:)];
[Q2,R2] = qr(A2)

Q2 =
   -0.5231    0.5039    0.6750   -0.1205    0.0411    0.0225
   -0.7078   -0.6966   -0.0190    0.0788    0.0833   -0.0150
   -0.0308    0.0592   -0.0656   -0.1169    0.1527   -0.9769
   -0.1231    0.1363   -0.3542   -0.6222    0.6398    0.2104
   -0.3077    0.1902   -0.4100   -0.4161   -0.7264   -0.0150
   -0.3385    0.4500   -0.4961    0.6366    0.1761    0.0225

R2 =
  -32.4962  -26.6801  -21.4795  -23.8182  -26.0031
         0   19.9292   12.4403    2.1340    4.3271
         0         0  -24.4514  -11.8132   -3.9931
         0         0         0  -20.2382  -10.3392
         0         0         0         0   16.1948
         0         0         0         0         0
```

Algorithm

The `qrinsert` function inserts the values of `x` into the `j`th column (row) of `R`. It then uses a series of Givens rotations to zero out the nonzero elements of `R` on and below the diagonal in the `j`th column (row).

See Also

`planerot`, `qr`, `qrdelete`

Description

Rank 1 update to QR factorization

Syntax

```
[Q1,R1] = qrupdate(Q,R,u,v)
```

Description

`[Q1,R1] = qrupdate(Q,R,u,v)` when `[Q,R] = qr(A)` is the original QR factorization of `A`, returns the QR factorization of `A + u*v'`, where `u` and `v` are column vectors of appropriate lengths.

Remarks

`qrupdate` works only for full matrices.

Examples

The matrix

```
mu = sqrt(eps)

mu =

   1.4901e-08

A = [ones(1,4); mu*eye(4)];
```

is a well-known example in least squares that indicates the dangers of forming `A'*A`. Instead, we work with the QR factorization – orthonormal Q and upper triangular R.

```
[Q,R] = qr(A);
```

As we expect, `R` is upper triangular.

```
R =

   -1.0000   -1.0000   -1.0000   -1.0000
         0    0.0000    0.0000    0.0000
         0         0    0.0000    0.0000
         0         0         0    0.0000
         0         0         0         0
```

In this case, the upper triangular entries of `R`, excluding the first row, are on the order of `sqrt(eps)`.

Consider the update vectors

```
u = [-1 0 0 0 0]'; v = ones(4,1);
```

Instead of computing the rather trivial QR factorization of this rank one update to A from scratch with

```
[QT,RT] = qr(A + u*v')

QT =

     0     0     0     0     1
    -1     0     0     0     0
     0    -1     0     0     0
     0     0    -1     0     0
     0     0     0    -1     0

RT =

  1.0e-007 *

   -0.1490         0         0         0
         0   -0.1490         0         0
         0         0   -0.1490         0
         0         0         0   -0.1490
         0         0         0         0
```

we may use qrupdate.

```
[Q1,R1] = qrupdate(Q,R,u,v)

Q1 =

   -0.0000   -0.0000   -0.0000   -0.0000    1.0000
    1.0000   -0.0000   -0.0000   -0.0000    0.0000
    0.0000    1.0000   -0.0000   -0.0000    0.0000
    0.0000    0.0000    1.0000   -0.0000    0.0000
   -0.0000   -0.0000   -0.0000    1.0000    0.0000

R1 =

   1.0e-007 *
    0.1490    0.0000    0.0000    0.0000
         0    0.1490    0.0000    0.0000
         0         0    0.1490    0.0000
```

```
     0          0          0     0.1490
     0          0          0          0
```

Note that both factorizations are correct, even though they are different.

Algorithm

`qrupdate` uses the algorithm in section 12.5.1 of the third edition of *Matrix Computations* by Golub and van Loan. `qrupdate` is useful since, if we take `N = max(m,n)`, then computing the new QR factorization from scratch is roughly an $O(N^3)$ algorithm, while simply updating the existing factors in this way is an $O(N^2)$ algorithm.

References

[1] Golub, Gene H. and Charles Van Loan, *Matrix Computations*, Third Edition, Johns Hopkins University Press, Baltimore, 1996

See Also

`cholupdate`, `qr`

quad, quad8

Purpose

Numerically evaluate integral, adaptive Simpson quadrature

Note The `quad8` function, which implemented a higher order method, is obsolete. The `quadl` function is its recommended replacement.

Syntax

```
q = quad(fun,a,b)
q = quad(fun,a,b,tol)
q = quad(fun,a,b,tol,trace)
[q,fcnt] = quadl(fun,a,b,...)
```

Description

Quadrature is a numerical method used to find the area under the graph of a function, that is, to compute a definite integral.

$$q = \int_a^b f(x)\,dx$$

`q = quad(fun,a,b)` tries to approximate the integral of function `fun` from `a` to `b` to within an error of `1e-6` using recursive adaptive Simpson quadrature. `fun` is a function handle for either an M-file function or an anonymous function. The function `y = fun(x)` should accept a vector argument `x` and return a vector result `y`, the integrand evaluated at each element of `x`.

Parameterizing Functions Called by Function Functions, in the online MATLAB documentation, explains how to provide addition parameters to the function `fun`, if necessary.

`q = quad(fun,a,b,tol)` uses an absolute error tolerance tol instead of the default which is `1.0e-6`. Larger values of `tol` result in fewer function evaluations and faster computation, but less accurate results. In MATLAB version 5.3 and earlier, the `quad` function used a less reliable algorithm and a default relative tolerance of `1.0e-3`.

`q = quad(fun,a,b,tol,trace)` with non-zero `trace` shows the values of `[fcnt a b-a Q]` during the recursion.

`[q,fcnt] = quad(...)` returns the number of function evaluations.

The function quadl may be more efficient with high accuracies and smooth integrands.

Examples

Pass M-file function handle @myfun to quad:

```
Q = quad(@myfun,0,2);
```

where the M-file myfun.m is

```
function y = myfun(x)
y = 1./(x.^3-2*x-5);
```

Pass anonymous function handle F to quad:

```
F = @(x)1./(x.^3-2*x-5);
Q = quad(F,0,2);
```

Algorithm

quad implements a low order method using an adaptive recursive Simpson's rule.

Diagnostics

quad may issue one of the following warnings:

'Minimum step size reached' indicates that the recursive interval subdivision has produced a subinterval whose length is on the order of roundoff error in the length of the original interval. A nonintegrable singularity is possible.

'Maximum function count exceeded' indicates that the integrand has been evaluated more than 10,000 times. A nonintegrable singularity is likely.

'Infinite or Not-a-Number function value encountered' indicates a floating point overflow or division by zero during the evaluation of the integrand in the interior of the interval.

See Also

dblquad, quadl, triplequad, @ (function handle), anonymous functions

References

[1] Gander, W. and W. Gautschi, "Adaptive Quadrature – Revisited", BIT, Vol. 40, 2000, pp. 84-101. This document is also available at http://www.inf.ethz.ch/personal/gander.

quadl

Purpose

Numerically evaluate integral, adaptive Lobatto quadrature

Syntax

```
q = quadl(fun,a,b)
q = quadl(fun,a,b,tol)
q = quadl(fun,a,b,tol,trace)
[q,fcnt] = quadl(fun,a,b,...)
```

Description

`q = quadl(fun,a,b)` approximates the integral of function `fun` from `a` to `b`, to within an error of 10^{-6} using recursive adaptive Lobatto quadrature. `fun` is a function handle for either an M-file function or an anonymous function. `fun` accepts a vector `x` and returns a vector `y`, the function `fun` evaluated at each element of `x`.

Parameterizing Functions Called by Function Functions, in the online MATLAB documentation, explains how to provide addition parameters to the function `fun`, if necessary.

`q = quadl(fun,a,b,tol)` uses an absolute error tolerance of `tol` instead of the default, which is `1.0e-6`. Larger values of `tol` result in fewer function evaluations and faster computation, but less accurate results.

`quadl(fun,a,b,tol,trace)` with non-zero `trace` shows the values of `[fcnt a b-a q]` during the recursion.

`[q,fcnt] = quadl(...)` returns the number of function evaluations.

Use array operators `.*`, `./` and `.^` in the definition of `fun` so that it can be evaluated with a vector argument.

The function `quad` may be more efficient with low accuracies or nonsmooth integrands.

Examples

Pass M-file function handle `@myfun` to `quadl`:

```
Q = quadl(@myfun,0,2);
```

where the M-file `myfun.m` is

```
function y = myfun(x)
y = 1./(x.^3-2*x-5);
```

Pass anonymous function handle `F` to `quadl`:

```
F = @(x) 1./(x.^3-2*x-5);
Q = quadl(F,0,2);
```

Algorithm

`quadl` implements a high order method using an adaptive Gauss/Lobatto qudrature rule.

Diagnostics

`quadl` may issue one of the following warnings:

`'Minimum step size reached'` indicates that the recursive interval subdivision has produced a subinterval whose length is on the order of roundoff error in the length of the original interval. A nonintegrable singularity is possible.

`'Maximum function count exceeded'` indicates that the integrand has been evaluated more than 10,000 times. A nonintegrable singularity is likely.

`'Infinite or Not-a-Number function value encountered'` indicates a floating point overflow or division by zero during the evaluation of the integrand in the interior of the interval.

See Also

`dblquad`, `quad`, `triplequad`, `@` (function handle), anonymous functions

References

[1] Gander, W. and W. Gautschi, “Adaptive Quadrature – Revisited”, BIT, Vol. 40, 2000, pp. 84-101. This document is also available at `http://www.inf.ethz.ch/personal/gander`.

quadv

Purpose

Vectorized quadrature

Syntax

```
Q = quadv(fun,A,B)
Q = quadv(fun,A,B,tol)
Q = quadv(fun,A,B,tol,trace)
[Q,fcnt] = quadv(...)
```

Description

`Q = quadv(fun,A,B)` approximates the integral of the complex array-valued function `fun` from `A` to `B` to within an error of `1.e-6` using recursive adaptive Simpson quadrature. The function `y = fun(x)` should accept a scalar argument `x` and return an array result `Y`, whose components are the integrands evaluated at `x`.

Parameterizing Functions Called by Function Functions, in the online MATLAB documentation, explains how to provide addition parameters to the function `fun`, if necessary.

`Q = quadv(fun,A,B,tol)` uses the absolute error tolerance `TOL` for all the integrals instead of the default, which is 1.e-6.

`Q = quadv(fun,A,B,tol,trace)` with non-zero `trace` shows the values of `[fcnt a b-a Q(1)]` during the recursion.

`[Q,fcnt] = quadv(...)` returns the number of function evaluations.

The same tolerance is used for all components, so the results obtained with `quadv` are usually not the same as those obtained with `quad` on the individual components.

Example

```
fun = @(x,n) (1./((1:n)+x));
Q = quadv(fun,0,1,[],[],10)
```

The resulting array `Q` has elements `Q(k) = log((k+1)./(k))`.

```
Q =

  Columns 1 through 8

    0.6931    0.4055    0.2877    0.2231    0.1823    0.1542
0.1335    0.1178

  Columns 9 through 10
```

```
                0.1054      0.0953
```

See Also

quad, dblquad, triplequad

questdlg

Purpose

Create and display question dialog box

Syntax

```
button = questdlg('qstring')
button = questdlg('qstring','title')
button = questdlg('qstring','title','default')
button = questdlg('qstring','title','str1','str2','default')
button = questdlg('qstring','title','str1','str2','str3','default')
```

Description

`button = questdlg('qstring')` displays a modal dialog presenting the question `'qstring'`. The dialog has three default buttons, **Yes**, **No**, and **Cancel**. If the user presses one of these three buttons, `button` is set to the name of the button pressed. If the user presses the close button on the dialog, `button` is set to the empty string. If the user presses the **Return** key, button is set to `'Yes'`. `'qstring'` is a cell array or a string that automatically wraps to fit within the dialog box.

`button = questdlg('qstring','title')` displays a question dialog with '*`title`*' displayed in the dialog's title bar.

`button = questdlg('qstring','title','default')` specifies which push button is the default in the event that the **Return** key is pressed. '*`default`*' must be `'Yes'`, `'No'`, or `'Cancel'`.

`button = questdlg('qstring','title','str1','str2','default')` creates a question dialog box with two push buttons labeled `'str1'` and `'str2'`. `'default'` specifies the default button selection and must be `'str1'` or `'str2'`.

`button = questdlg('qstring','title','str1','str2','str3','default')` creates a question dialog box with three push buttons labeled `'str1'`, `'str2'`, and `'str3'`. `'default'` specifies the default button selection and must be `'str1'`, `'str2'`, or `'str3'`.

In all cases where `'default'` is specified, if`'default'` is not set to one of the button names, pressing the **Return** key displays a warning and the dialog remains open.

See Also

`inputdlg`, `textwrap`

Purpose

Terminate MATLAB

Graphical Interface

As an alternative to the `quit` function, use the close box or select **Exit MATLAB** from the **File** menu in the MATLAB desktop.

Syntax

```
quit
quit cancel
quit force
```

Description

`quit` terminates MATLAB after running `finish.m`, if `finish.m` exists. The workspace is not automatically saved by `quit`. To save the workspace or perform other actions when quitting, create a `finish.m` file to perform those actions. For example, you can display a dialog box to confirm quitting using a `finish.m` file—see the following examples for details. If an error occurs while `finish.m` is running, `quit` is canceled so that you can correct your `finish.m` file without losing your workspace.

`quit cancel` is for use in `finish.m` and cancels quitting. It has no effect anywhere else.

`quit force` bypasses `finish.m` and terminates MATLAB. Use this to override `finish.m`, for example, if an errant `finish.m` will not let you quit.

Remarks

When using Handle Graphics in `finish.m`, use `uiwait`, `waitfor`, or `drawnow` so that figures are visible. See the reference pages for these functions for more information.

Examples

Two sample `finish.m` files are included with MATLAB. Use them to help you create your own `finish.m`, or rename one of the files to `finish.m` to use it.

- `finishsav.m`—Saves the workspace to a MAT-file when MATLAB quits.
- `finishdlg.m`—Displays a dialog allowing you to cancel quitting; it uses `quit cancel` and contains the following code:

```
button = questdlg('Ready to quit?', ...
                            'Exit Dialog','Yes','No','No');
switch button
            case 'Yes',
              disp('Exiting MATLAB');
              %Save variables to matlab.mat
              save
            case 'No',
              quit cancel;
end
```

See Also

`finish`, `save`, `startup`

quiver

Purpose

Quiver or velocity plot

Syntax

```
quiver(x,y,u,v)
quiver(u,v)
quiver(...,scale)
quiver(...,LineSpec)
quiver(...,LineSpec,'filled')
quiver(axes_handle,...)
h = quiver(...)
hlines = quiver('v6',...)
```

Description

A quiver plot displays velocity vectors as arrows with components `(u,v)` at the points `(x,y)`.

For example, the first vector is defined by components `u(1),v(1)` and is displayed at the point `x(1),y(1)`.

`quiver(x,y,u,v)` plots vectors as arrows at the coordinates specified in each corresponding pair of elements in `x` and `y`. The matrices `x`, `y`, `u`, and `v` must all

be the same size and contain corresponding position and velocity components. However, x and y can also be vectors, as explained in the next section.

Expanding x and y Coordinates

MATLAB expands x and y if they are not matrices. This expansion is equivalent to calling meshgrid to generate matrices from vectors:

```
[x,y] = meshgrid(x,y);
quiver(x,y,u,v)
```

In this case, the following must be true:

`length(x) = n` and `length(y) = m`, where `[m,n] = size(u) = size(v)`.

The vector x corresponds to the columns of u and v, and vector y corresponds to the rows of u and v.

`quiver(u,v)` draws vectors specified by u and v at equally spaced points in the *x-y* plane.

`quiver(...,scale)` automatically scales the arrows to fit within the grid and then stretches them by the factor `scale`. `scale = 2` doubles their relative length and `scale = 0.5` halves the length. Use `scale = 0` to plot the velocity vectors without automatic scaling.

`quiver(...,LineSpec)` specifies line style, marker symbol, and color using any valid `LineSpec`. `quiver` draws the markers at the origin of the vectors.

`quiver(...,LineSpec,'filled')` fills markers specified by `LineSpec`.

`quiver(axes_handles,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = quiver(...)` returns the handle to the quivergroup object.

Backward Compatible Version

`hlines = quiver('v6',...)` returns the handles of line objects instead of quivergroup objects for compatibility with MATLAB 6.5 and earlier.

Examples

Showing the Gradient with Quiver Plots

Plot the gradient field of the function $z = xe^{(-x^2-y^2)}$:

```
[X,Y] = meshgrid(-2:.2:2);
Z = X.*exp(-X.^2 - Y.^2);
[DX,DY] = gradient(Z,.2,.2);
contour(X,Y,Z)
hold on
quiver(X,Y,DX,DY)
colormap hsv
hold off
```



See Also

`contour`, `LineSpec`, `plot`, `quiver3`

"Direction and Velocity Plots" for related functions

Two-Dimensional Quiver Plots for more examples

See "Quivergroup Properties" for property descriptions

Purpose

Three-dimensional velocity plot

Syntax

```
quiver3(x,y,z,u,v,w)
quiver3(z,u,v,w)
quiver3(...,scale)
quiver3(...,LineSpec)
quiver3(...,LineSpec,'filled')
quiver3(axes_handle,...)
h = quiver3(...)
```

Description

A three-dimensional quiver plot displays vectors with components (u,v,w) at the points (x,y,z).

`quiver3(x,y,z,u,v,w)` plots vectors with components (u,v,w) at the points (x,y,z). The matrices `x,y,z,u,v,w` must all be the same size and contain the corresponding position and vector components.

`quiver3(z,u,v,w)` plots the vectors at the equally spaced surface points specified by matrix `z`. `quiver3` automatically scales the vectors based on the distance between them to prevent them from overlapping.

`quiver3(...,scale)` automatically scales the vectors to prevent them from overlapping, then multiplies them by `scale`. `scale = 2` doubles their relative length and `scale = 0.5` halves them. Use `scale = 0` to plot the vectors without the automatic scaling.

`quiver3(...,LineSpec)` specifies line type and color using any valid `LineSpec`.

`quiver3(...,LineSpec,'filled')` fills markers specified by `LineSpec`.

`quiver3(axes_handles,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = quiver3(...)` returns a vector of line handles.

Examples

Plot the surface normals of the function $z = xe^{(-x^2-y^2)}$.

```
[X,Y] = meshgrid(-2:0.25:2,-1:0.2:1);
Z = X.* exp(-X.^2 - Y.^2);
```

```
[U,V,W] = surfnorm(X,Y,Z);
quiver3(X,Y,Z,U,V,W,0.5);
hold on
surf(X,Y,Z);
colormap hsv
view(-35,45)
axis ([-2 2 -1 1 -.6 .6])
hold off
```



See Also `axis`, `contour`, `LineSpec`, `plot`, `plot3`, `quiver`, `surfnorm`, `view`

"Direction and Velocity Plots" for related functions

Three-Dimensional Quiver Plots for more examples

Modifying Properties

You can set and query graphics object properties using the `set` and `get` commands or the Property Editor (`propertyeditor`).

Note that you cannot define default properties for areaseries objects.

See Plot Objects for more information on quivergroup objects.

Quivergroup Property Descriptions

This section provides a description of properties. Curly braces { } enclose default values.

`AutoScale` `{on} | off`

Autoscale arrow length. Based on average spacing in the *x* and *y* directions, `AutoScale` scales the arrow length to fit within the grid-defined coordinate data and keeps the arrows from overlapping. After autoscaling, quiver applies the `AutoScaleFactor` to the arrow length.

`AutoScaleFactor` scalar (default = 0.9)

User-specified scale factor. When `AutoScale` is on, the `quiver` function applies this user-specified autoscale factor to the arrow length. A value of `2` doubles the length of the arrows; `0.5` halves the length.

`BeingDeleted` `on | {off}` Read Only

This object is being deleted. The `BeingDeleted` property provides a mechanism that you can use to determine if objects are in the process of being deleted. MATLAB sets the `BeingDeleted` property to `on` when the object's delete function callback is called (see the `DeleteFcn` property). It remains set to `on` while the delete function executes, after which the object no longer exists.

For example, an object's delete function might call other functions that act on a number of different objects. These functions might not need to perform actions on objects that are going to be deleted, and therefore can check the object's `BeingDeleted` property before acting.

`BusyAction` `cancel | {queue}`

Callback routine interruption. The `BusyAction` property enables you to control how MATLAB handles events that potentially interrupt executing callbacks. If there is a callback function executing, callbacks invoked subsequently always attempt to interrupt it.

If the `Interruptible` property of the object whose callback is executing is set to `on` (the default), then interruption occurs at the next point where the event

queue is processed. If the `Interruptible` property is `off`, the `BusyAction` property (of the object owning the executing callback) determines how MATLAB handles the event. The choices are

- `cancel` — Discard the event that attempted to execute a second callback routine.
- `queue` — Queue the event that attempted to execute a second callback routine until the current callback finishes.

`ButtonDownFcn` string or function handle

Button press callback function. A callback that executes whenever you press a mouse button while the pointer is over the quivergroup object.

This property can be

- A string that is a valid MATLAB expression
- The name of an M-file
- A function handle

The expression executes in the MATLAB workspace.

See Function Handle Callbacks for information on how to use function handles to define the callbacks.

`Children` array of graphics object handles

Children of the quivergroup object. An array containing the handles of all line objects parented to the quivergroup object (whether visible or not).

Note that if a child object's `HandleVisibility` property is set to `callback` or `off`, its handle does not show up in the quiver `Children` property unless you set the Root `ShowHiddenHandles` property to `on`:

```
set(0,'ShowHiddenHandles','on')
```

`Clipping` `{on} | off`

Clipping mode. MATLAB clips quiver plots to the axes plot box by default. If you set `Clipping` to `off`, arrows might be displayed outside the axes plot box.

`Color` `ColorSpec`

Color of arrows. A three-element RGB vector or one of the MATLAB predefined names, specifying the arrow color. See the `ColorSpec` reference page for more

information on specifying color. For example, the following statement shows the arrow color set to blue.

```
h = quiver(u,v,'Color','b');
```

CreateFcn string or function handle

Callback routine executed during object creation. This property defines a callback that executes when MATLAB creates a quivergroup object. You must specify the callback during the creation of the object. For example,

```
quiver(u,v,'CreateFcn',@CallbackFcn)
```

where `@CallbackFcn` is a function handle that references the callback function.

MATLAB executes this routine after setting all other quivergroup properties. Setting this property on an existing quivergroup object has no effect.

The handle of the object whose `CreateFcn` is being executed is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

DeleteFcn string or function handle

Callback executed during object deletion. A callback that executes when the quivergroup object is deleted (e.g., this might happen when you issue a `delete` command on the quivergroup object, its parent axes, or the figure containing it). MATLAB executes the callback before destroying the object's properties so that the callback routine can query these values.

The handle of the object whose `DeleteFcn` is being executed is accessible only through the Root `CallbackObject` property, which can be queried using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

See the `BeingDeleted` property for related information.

DisplayName string

Label used by plot legends. The legend and the plot browser use this text for labels for any quivergroup objects appearing in these legends.

EraseMode {normal} | none | xor | background

Erase mode. This property controls the technique MATLAB uses to draw and erase quiver child objects (the lines used to construct the arrows). Alternative erase modes are useful for creating animated sequences, where control of the way individual objects are redrawn is necessary to improve performance and obtain the desired effect.

- `normal` — Redraw the affected region of the display, performing the three-dimensional analysis necessary to ensure that all objects are rendered correctly. This mode produces the most accurate picture, but is the slowest. The other modes are faster but do not perform a complete redraw and are therefore less accurate.
- `none` — Do not erase objects when they are moved or destroyed. While the objects are still visible on the screen after erasing with `EraseMode none`, you cannot print these objects because MATLAB stores no information about their former locations.
- `xor`— Draw and erase the object by performing an exclusive OR (XOR) with each pixel index of the screen behind it. Erasing the object does not damage the color of the objects behind it. However, the color of the erased object depends on the color of the screen behind it and it is correctly colored only when it is over the axes background color (or the figure background color if the axes `Color` property is set to `none`). That is, it isn't erased correctly if there are objects behind it.
- `background` — Erase the graphics objects by redrawing them in the axes background color, (or the figure background color if the axes `Color` property is set to `none`). This damages other graphics objects that are behind the erased object, but the erased object is always properly colored.

Printing with Nonnormal Erase Modes

MATLAB always prints figures as if the `EraseMode` of all objects is `normal`. This means graphics objects created with `EraseMode` set to `none`, `xor`, or `background` can look different on screen than on paper. On screen, MATLAB might mathematically combine layers of colors (e.g., performing an XOR operation on a pixel color and the pixel behind it) and ignore three-dimensional sorting to obtain greater rendering speed. However, these techniques are not applied to the printed output.

Set the axes background color with the axes `Color` property. Set the figure background color with the figure `Color` property.

You can use the MATLAB `getframe` command or other screen capture applications to create an image of a figure containing nonnormal mode objects.

`HandleVisibility` `{on} | callback | off`

Control access to object's handle by command-line users and GUIs. This property determines when an object's handle is visible in its parent's list of children. `HandleVisibility` is useful for preventing command-line users from accidentally accessing the quivergroup object.

- `on` — Handles are always visible when `HandleVisibility` is `on`.
- `callback` — Setting `HandleVisibility` to `callback` causes handles to be visible from within callback routines or functions invoked by callback routines, but not from within functions invoked from the command line. This provides a means to protect GUIs from command-line users, while allowing callback routines to have access to object handles.
- `off` — Setting `HandleVisibility` to `off` makes handles invisible at all times. This might be necessary when a callback invokes a function that might potentially damage the GUI (such as evaluating a user-typed string) and so temporarily hides its own handles during the execution of that function.

Functions Affected by Handle Visibility

When a handle is not visible in its parent's list of children, it cannot be returned by functions that obtain handles by searching the object hierarchy or querying handle properties. This includes `get`, `findobj`, `gca`, `gcf`, `gco`, `newplot`, `cla`, `clf`, and `close`.

Properties Affected by Handle Visibility

When a handle's visibility is restricted using `callback` or `off`, the object's handle does not appear in its parent's `Children` property, figures do not appear in the root's `CurrentFigure` property, objects do not appear in the root's `CallbackObject` property or in the figure's `CurrentObject` property, and axes do not appear in their parent's `CurrentAxes` property.

Overriding Handle Visibility

You can set the root `ShowHiddenHandles` property to `on` to make all handles visible regardless of their `HandleVisibility` settings (this does not affect the values of the `HandleVisibility` properties). See also `findall`.

Handle Validity

Handles that are hidden are still valid. If you know an object's handle, you can `set` and `get` its properties and pass it to any function that operates on handles.

`HitTest` `{on} | off`

Selectable by mouse click. `HitTest` determines whether the quivergroup object can become the current object (as returned by the `gco` command and the figure `CurrentObject` property) as a result of a mouse click on the line objects that compose the quiver plot. If `HitTest` is `off`, clicking the quivergroup object selects the object below it (which is usually the axes containing it).

`HitTestArea` `on | {off}`

Select quivergroup object on arrows or extent of graph. This property enables you to select quivergroup objects in two ways:

- Select by clicking quiver arrows (default).
- Select by clicking anywhere in the extent of the quiver plot.

When `HitTestArea` is `off`, you must click the quiver lines (excluding the base line) to select the quivergroup object. When `HitTestArea` is `on`, you can select the quivergroup object by clicking anywhere within the extent of the graph (i.e., anywhere within a rectangle that encloses all the arrows).

`Interruptible` `{on} | off`

Callback routine interruption mode. The `Interruptible` property controls whether a quivergroup object callback can be interrupted by subsequently invoked callbacks.

Only callbacks defined for the `ButtonDownFcn` property are affected by the `Interruptible` property. MATLAB checks for events that can interrupt a callback only when it encounters a `drawnow`, `figure`, `getframe`, or `pause` command in the routine. See the `BusyAction` property for related information.

Setting `Interruptible` to `on` allows any graphics object's callback to interrupt callback routines originating from a quiver property. Note that MATLAB does

not save the state of variables or the display (e.g., the handle returned by the `gca` or `gcf` command) when an interruption occurs.

`LineStyle` `{-} | -- | : | -. | none`

Line style. This property specifies the line style used for the quiver arrows. Available line styles are shown in the following table.

Symbol	Line Style
`-`	Solid line (default)
`--`	Dashed line
`:`	Dotted line
`-.`	Dash-dot line
`none`	No line

You can use `LineStyle none` when you want to place a marker at each point but do not want the points connected with a line (see the `Marker` property).

`LineWidth` scalar

Width of the quiver arrows. Specify this value in points (1 point = $^1/_{72}$ inch). The default `LineWidth` is 0.5 points.

`Marker` character (see table)

Marker symbol. The `Marker` property specifies the type of markers that are displayed at the *x*- and *y*-coordinates. You can set values for the `Marker` property independently from the `LineStyle` property. Supported markers include those shown in the following table.

Marker Specifier	Description
`+`	Plus sign
`o`	Circle
`*`	Asterisk
`.`	Point

Marker Specifier	Description
x	Cross
s	Square
d	Diamond
^	Upward-pointing triangle
v	Downward-pointing triangle
>	Right-pointing triangle
<	Left-pointing triangle
p	Five-pointed star (pentagram)
h	Six-pointed star (hexagram)
none	No marker (default)

`MarkerEdgeColor` `ColorSpec | none | {auto}`

Marker edge color. The color of the marker or the edge color for filled markers (circle, square, diamond, pentagram, hexagram, and the four triangles). `ColorSpec` defines the color to use. `none` specifies no color, which makes nonfilled markers invisible. `auto` sets `MarkerEdgeColor` to the same color as the quiver `Color` property.

`MarkerFaceColor` `ColorSpec | {none} | auto`

Marker face color. The fill color for markers that are closed shapes (circle, square, diamond, pentagram, hexagram, and the four triangles). `ColorSpec` defines the color to use. `none` makes the interior of the marker transparent, allowing the background to show through. `auto` sets the fill color to the axes color, or to the figure color, if the axes `Color` property is set to `none` (which is the factory default for axes).

`MarkerSize` size in points

Marker size. A scalar specifying the size of the marker in points. The default value for `MarkerSize` is 6 points (1 point = 1/72 inch). Note that MATLAB draws the point marker (specified by the `'.'` symbol) at one-third the specified size.

MaxHeadSize scalar (default = 0.2

Maximum size of arrowhead. A value determining the maximum size of the arrowhead relative to the length of the arrow.

Parent axes handle

Parent of quivergroup object. This property contains the handle of the quivergroup object's parent object. The parent of a quivergroup object is the axes, hggroup, or hgtransform object that contains it.

See Objects That Can Contain Other Objects for more information on parenting graphics objects.

Selected `on | {off}`

Is object selected? When you set this property to `on`, MATLAB displays selection handles at the corners and midpoints if the `SelectionHighlight` property is also `on` (the default). You can, for example, define the `ButtonDownFcn` callback to set this property to `on`, thereby indicating that the quivergroup object is selected.

SelectionHighlight `{on} | off`

Objects are highlighted when selected. When the `Selected` property is `on`, MATLAB indicates the selected state by drawing selection handles on the arrows. When `SelectionHighlight` is `off`, MATLAB does not draw the handles.

ShowArrowHead `{on} | off`

Display arrowheads on vectors. When this property is `on`, MATLAB draws arrowheads on the vectors displayed by `quiver`. When you set this property to off, `quiver` draws the vectors as lines without arrowheads.

Tag string

User-specified object label. The `Tag` property provides a means to identify graphics objects with a user-specified label. This is particularly useful when you are constructing interactive graphics programs that would otherwise need to define object handles as global variables or pass them as arguments between callbacks.

For example, you might create a quivergroup object and set the `Tag` property:

```
t = quiver(u,v,'Tag','quiver1')
```

When you want to access the quivergroup object, you can use `findobj` to find the object's handle. The following statement changes the `Color` property of the object whose `Tag` is `quiver1`.

```
set(findobj('Tag','quiver1'),'Color','red')
```

`Type` string (read only)

Type of graphics object. This property contains a string that identifies the class of the graphics object. For stem objects, `Type` is `'hggroup'`. This statement finds all the hggroup objects in the current axes.

```
t = findobj(gca,'Type','hggroup');
```

`UIContextMenu` handle of a uicontextmenu object

Associate a context menu with the quivergroup object. Assign this property the handle of a uicontextmenu object created in the quivergroup object's parent figure. Use the `uicontextmenu` function to create the context menu. MATLAB displays the context menu whenever you right-click over the extent of the quivergroup object.

`UserData` array

User-specified data. This property can be any data you want to associate with the quivergroup object (including cell arrays and structures). The quivergroup object does not set values for this property, but you can access it using the `set` and `get` functions.

`Visible` `{on} | off`

Visibility of quivergroup object and its children. By default, stem object visibility is `on`. This means all children of the quivergroup object are visible unless the child object's `Visible` property is set to `off`. Setting a quivergroup object's `Visible` property to `off` also makes its children invisible.

`UData` matrix

One dimension of 2-D or 3-D vector components. `UData`, `VData`, and `WData`, together specify the components of the vectors displayed as arrows in the quiver graph. For example, the first vector is defined by components `UData(1)`,`VData(1)`,`WData(1)`.

UDataSource string (MATLAB variable)

Link UData to MATLAB variable. Set this property to a MATLAB variable that, by default, is evaluated in the base workspace to generate the UData.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change UData.

You can use the refreshdata function to force an update of the object's data. refreshdata also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call refreshdata.

See the refreshdata reference page for more information.

Note If you change one data source property to return data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

VData matrix

One dimension of 2-D or 3-D vector components. UData, VData and WData (for 3-D) together specify the components of the vectors displayed as arrows in the quiver graph. For example, the first vector is defined by components UData(1),VData(1),WData(1).

VDataSource string (MATLAB variable)

Link VData to MATLAB variable. Set this property to a MATLAB variable that, by default, is evaluated in the base workspace to generate the VData.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change VData.

You can use the refreshdata function to force an update of the object's data. refreshdata also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call refreshdata.

See the refreshdata reference page for more information.

Note If you change one data source property to return data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

`WData` matrix

One dimension of 2-D or 3-D vector components. `UData`, `VData` and `WData` (for 3-D) together specify the components of the vectors displayed as arrows in the quiver graph. For example, the first vector is defined by components `UData(1)`,`VData(1)`,`WData(1)`.

`WDataSource` string (MATLAB variable)

Link `WData` to MATLAB variable. Set this property to a MATLAB variable that, by default, is evaluated in the base workspace to generate the `WData`.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change `WData`.

You can use the `refreshdata` function to force an update of the object's data. `refreshdata` also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call `refreshdata`.

See the `refreshdata` reference page for more information.

Note If you change one data source property to return data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

`XData` vector or matrix

X-axis coordinates of arrows. The `quiver` function draws an individual arrow at each *x*-axis location in the `XData` array. `XData` can be either a matrix equal in size to all other data properties or for 2-D, a vector equal in length to the number of columns in `UData` or `VData`. That is, `length(XData) == size(UData,2)`.

If you do not specify XData (i.e., the input argument X), the quiver function uses the indices of UData to create the quiver graph. See the XDataMode property for related information.

XDataMode {auto} | manual

Use automatic or user-specified x-axis values. If you specify XData (by setting the XData property or specifying the input argument X), the quiver function sets this property to manual.

If you set XDataMode to auto after having specified XData, the quiver function resets the *x* tick-mark labels to the indices of the U, V, and W data, overwriting any previous values.

XDataSource string (MATLAB variable)

Link XData to MATLAB variable. Set this property to a MATLAB variable that, by default, is evaluated in the base workspace to generate the XData.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change XData.

You can use the refreshdata function to force an update of the object's data. refreshdata also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call refreshdata.

See the refreshdata reference page for more information.

Note If you change one data source property to return data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

YData vector or matrix

Y-axis coordinates of arrows. The quiver function draws an individual arrow at each *y*-axis location in the YData array. YData can be either a matrix equal in size to all other data properties or for 2-D, a vector equal in length to the number of rows in UData or VData. That is, length(YData) == size(UData,1).

If you do not specify YData (i.e., the input argument Y), the quiver function uses the indices of VData to create the quiver graph. See the YDataMode property for related information.

The input argument y in the quiver function calling syntax assigns values to YData.

YDataMode {auto} | manual

Use automatic or user-specified y-axis values. If you specify YData (by setting the YData property or specifying the input argument Y), MATLAB sets this property to manual.

If you set YDataMode to auto after having specified YData, MATLAB resets the *y* tick-mark labels to the indices of the U, V, and W data, overwriting any previous values.

YDataSource string (MATLAB variable)

Link YData to MATLAB variable. Set this property to a MATLAB variable that, by default, is evaluated in the base workspace to generate the YData.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change YData.

You can use the refreshdata function to force an update of the object's data. refreshdata also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call refreshdata.

See the refreshdata reference page for more information.

Note If you change one data source property to a variable that contains data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

ZData vector or matrix

Z-axis coordinates of arrows. The quiver function draws an individual arrow at each *z*-axis location in the ZData array. ZData must be a matrix equal in size to XData and YData.

The input argument `z` in the `quiver3` function calling syntax assigns values to `ZData`.

Purpose

QZ factorization for generalized eigenvalues

Syntax

```
[AA,BB,Q,Z,] = qz(A,B)
[AA,BB,Q,Z,V,W] = qz(A,B)
qz(A,B,flag)
```

Description

The qz function gives access to intermediate results in the computation of generalized eigenvalues.

`[AA,BB,Q,Z] = qz(A,B)` for square matrices `A` and `B`, produces upper quasitriangular matrices `AA` and `BB`, and unitary matrices `Q` and `Z` such that `Q*A*Z = AA`, and `Q*B*Z = BB`. For complex matrices, `AA` and `BB` are triangular.

`[AA,BB,Q,Z,V,W] = qz(A,B)` also produces matrices `V` and `W` whose columns are generalized eigenvectors.

`qz(A,B,flag)` for real matrices `A` and `B`, produces one of two decompositions depending on the value of `flag`:

`'complex'`	Produces a possibly complex decomposition with a triangular `AA`. For compatibility with earlier versions, `'complex'` is the default.
`'real'`	Produces a real decomposition with a quasitriangular `AA`, containing 1-by-1 and 2-by-2 blocks on its diagonal.

If `AA` is triangular, the diagonal elements of `AA` and `BB`, $\alpha = \mathrm{diag}(AA)$ and $\beta = \mathrm{diag}(BB)$, are the generalized eigenvalues that satisfy

$$A*V*\beta = B*V*\alpha$$
$$\beta*W'*A = \alpha*W'*B$$

The eigenvalues produced by

$$\lambda = \mathrm{eig}(A, B)$$

are the ratios of the αs and βs.

$\lambda = \alpha./\beta$

If `AA` is triangular, the diagonal elements of `AA` and `BB`,

2rand

Purpose

Uniformly distributed random numbers and arrays

Syntax

```
Y = rand(n)
Y = rand(m,n)
Y = rand([m n])
Y = rand(m,n,p,...)
Y = rand([m n p...])
Y = rand(size(A))
rand
s = rand('state')
```

Description

The `rand` function generates arrays of random numbers whose elements are uniformly distributed in the interval `(0,1)`.

`Y = rand(n)` returns an `n`-by-`n` matrix of random entries. An error message appears if `n` is not a scalar.

`Y = rand(m,n)` or `Y = rand([m n])` returns an `m`-by-`n` matrix of random entries.

`Y = rand(m,n,p,...)` or `Y = rand([m n p...])` generates random arrays.

`Y = rand(size(A))` returns an array of random entries that is the same size as `A`.

`rand`, by itself, returns a scalar whose value changes each time it's referenced.

`s = rand('state')` returns a 35-element vector containing the current state of the uniform generator. To change the state of the generator:

`rand('state',s)`	Resets the state to `s`.
`rand('state',0)`	Resets the generator to its initial state.
`rand('state',j)`	For integer `j`, resets the generator to its `j`-th state.
`rand('state',sum(100*clock))`	Resets it to a different state each time.

Examples

Example 1. `R = rand(3,4)` may produce

```
R =
   0.2190    0.6793    0.5194    0.0535
   0.0470    0.9347    0.8310    0.5297
   0.6789    0.3835    0.0346    0.6711
```

This code makes a random choice between two equally probable alternatives.

```
if rand < .5
   'heads'
else
   'tails'
end
```

Example 2. Generate a uniform distribution of random numbers on a specified interval `[a,b]`. To do this, multiply the output of `rand` by `(b-a)` then add a. For example, to generate a 5-by-5 array of uniformly distributed random numbers on the interval `[10,50]`

```
a = 10; b = 50;
x = a + (b-a) * rand(5)
x =

   18.1106   10.6110   26.7460   43.5247   30.1125
   17.9489   39.8714   43.8489   10.7856   38.3789
   34.1517   27.8039   31.0061   37.2511   27.1557
   20.8875   47.2726   18.1059   25.1792   22.1847
   17.9526   28.6398   36.8855   43.2718   17.5861
```

See Also

`randn`, `randperm`, `sprand`, `sprandn`

Purpose

Normally distributed random numbers and arrays

Syntax

```
Y = randn(n)
Y = randn(m,n)
Y = randn([m n])
Y = randn(m,n,p,...)
Y = randn([m n p...])
Y = randn(size(A))
randn
s = randn('state')
```

Description

The `randn` function generates arrays of random numbers whose elements are normally distributed with mean 0, variance $\sigma^2 = 1$, and standard deviation $\sigma = 1$.

`Y = randn(n)` returns an `n`-by-`n` matrix of random entries. An error message appears if `n` is not a scalar.

`Y = randn(m,n)` or `Y = randn([m n])` returns an `m`-by-`n` matrix of random entries.

`Y = randn(m,n,p,...)` or `Y = randn([m n p...])` generates random arrays.

`Y = randn(size(A))` returns an array of random entries that is the same size as `A`.

`randn`, by itself, returns a scalar whose value changes each time it's referenced.

`s = randn('state')` returns a 2-element vector containing the current state of the normal generator. To change the state of the generator:

`randn('state',s)`	Resets the state to `s`.
`randn('state',0)`	Resets the generator to its initial state.
`randn('state',j)`	For integer `j`, resets the generator to its `j`th state.
`randn('state',sum(100*clock))`	Resets it to a different state each time.

Examples

Example 1. `R = randn(3,4)` may produce

```
R =
    1.1650    0.3516    0.0591    0.8717
    0.6268   -0.6965    1.7971   -1.4462
    0.0751    1.6961    0.2641   -0.7012
```

For a histogram of the `randn` distribution, see `hist`.

Example 2. Generate a random distribution with a specific mean and variance σ^2. To do this, multiply the output of `randn` by the standard deviation σ, and then add the desired mean. For example, to generate a 5-by-5 array of random numbers with a mean of .6 that are distributed with a variance of 0.1

```
x = .6 + sqrt(0.1) * randn(5)
x =

    0.8713    0.4735    0.8114    0.0927    0.7672
    0.9966    0.8182    0.9766    0.6814    0.6694
    0.0960    0.8579    0.2197    0.2659    0.3085
    0.1443    0.8251    0.5937    1.0475   -0.0864
    0.7806    1.0080    0.5504    0.3454    0.5813
```

See Also

`rand`, `randperm`, `sprand`, `sprandn`

Purpose

Random permutation

Syntax

```
p = randperm(n)
```

Description

`p = randperm(n)` returns a random permutation of the integers `1:n`.

Remarks

The `randperm` function calls `rand` and therefore changes `rand`'s state.

Examples

`randperm(6)` might be the vector

```
   [3   2   6   4   1   5]
```

or it might be some other permutation of `1:6`.

See Also

`permute`

rank

Purpose

Rank of a matrix

Syntax

```
k = rank(A)
k = rank(A,tol)
```

Description

The `rank` function provides an estimate of the number of linearly independent rows or columns of a full matrix.

`k = rank(A)` returns the number of singular values of `A` that are larger than the default tolerance, `max(size(A))*norm(A)*eps`.

`k = rank(A,tol)` returns the number of singular values of `A` that are larger than `tol`.

Remark

Use `sprank` to determine the structural rank of a sparse matrix.

Algorithm

There are a number of ways to compute the rank of a matrix. MATLAB uses the method based on the singular value decomposition, or SVD. The SVD algorithm is the most time consuming, but also the most reliable.

The `rank` algorithm is

```
s = svd(A);
tol = max(size(A))*s(1)*eps;
r = sum(s > tol);
```

See Also

`sprank`

References

[1] Anderson, E., Z. Bai, C. Bischof, S. Blackford, J. Demmel, J. Dongarra, J. Du Croz, A. Greenbaum, S. Hammarling, A. McKenney, and D. Sorensen, *LAPACK User's Guide* (`http://www.netlib.org/lapack/lug/lapack_lug.html`), Third Edition, SIAM, Philadelphia, 1999.

Purpose

Rational fraction approximation

Syntax

```
[N,D] = rat(X)
[N,D] = rat(X,tol)
rat(...)
S = rats(X,strlen)
S = rats(X)
```

Description

Even though all floating-point numbers are rational numbers, it is sometimes desirable to approximate them by simple rational numbers, which are fractions whose numerator and denominator are small integers. The `rat` function attempts to do this. Rational approximations are generated by truncating continued fraction expansions. The `rats` function calls `rat`, and returns strings.

`[N,D] = rat(X)` returns arrays `N` and `D` so that `N./D` approximates `X` to within the default tolerance, `1.e-6*norm(X(:),1)`.

`[N,D] = rat(X,tol)` returns `N./D` approximating `X` to within `tol`.

`rat(X)`, with no output arguments, simply displays the continued fraction.

`S = rats(X,strlen)` returns a string containing simple rational approximations to the elements of `X`. Asterisks are used for elements that cannot be printed in the allotted space, but are not negligible compared to the other elements in `X`. `strlen` is the length of each string element returned by the `rats` function. The default is `strlen = 13`, which allows 6 elements in 78 spaces.

`S = rats(X)` returns the same results as those printed by MATLAB with `format rat`.

Examples

Ordinarily, the statement

```
s = 1 - 1/2 + 1/3 - 1/4 + 1/5 - 1/6 + 1/7
```

produces

```
s =
   0.7595
```

However, with

```
format rat
```

or with

```
rats(s)
```

the printed result is

```
s =
   319/420
```

This is a simple rational number. Its denominator is 420, the least common multiple of the denominators of the terms involved in the original expression. Even though the quantity `s` is stored internally as a binary floating-point number, the desired rational form can be reconstructed.

To see how the rational approximation is generated, the statement `rat(s)`

produces

```
1 + 1/(-4 + 1/(-6 + 1/(-3 + 1/(-5))))
```

And the statement

```
[n,d] = rat(s)
```

produces

```
n = 319, d = 420
```

The mathematical quantity π is certainly not a rational number, but the MATLAB quantity `pi` that approximates it is a rational number. `pi` is the ratio of a large integer and 2^{52}:

```
14148475504056880/4503599627370496
```

However, this is not a simple rational number. The value printed for `pi` with `format rat`, or with `rats(pi)`, is

```
355/113
```

This approximation was known in Euclid's time. Its decimal representation is

```
3.14159292035398
```

and so it agrees with `pi` to seven significant figures. The statement

```
rat(pi)
```

produces

```
3 + 1/(7 + 1/(16))
```

This shows how the `355/113` was obtained. The less accurate, but more familiar approximation `22/7` is obtained from the first two terms of this continued fraction.

Algorithm

The `rat(X)` function approximates each element of `X` by a continued fraction of the form

$$\frac{n}{d} = d_1 + \frac{1}{d_2 + \frac{1}{\left(d_3 + \ldots + \frac{1}{d_k}\right)}}$$

The d s are obtained by repeatedly picking off the integer part and then taking the reciprocal of the fractional part. The accuracy of the approximation increases exponentially with the number of terms and is worst when `X = sqrt(2)`. For `x = sqrt(2)`, the error with `k` terms is about `2.68*(.173)^k`, so each additional term increases the accuracy by less than one decimal digit. It takes 21 terms to get full floating-point accuracy.

See Also

`format`

rbbox

Purpose

Create rubberband box for area selection

Syntax

```
rbbox
rbbox(initialRect)
rbbox(initialRect,fixedPoint)
rbbox(initialRect,fixedPoint,stepSize)
finalRect = rbbox(...)
```

Description

`rbbox` initializes and tracks a rubberband box in the current figure. It sets the initial rectangular size of the box to 0, anchors the box at the figure's `CurrentPoint`, and begins tracking from this point.

`rbbox(initialRect)` specifies the initial location and size of the rubberband box as `[x y width height]`, where `x` and `y` define the lower left corner, and `width` and `height` define the size. `initialRect` is in the units specified by the current figure's `Units` property, and measured from the lower left corner of the figure window. The corner of the box closest to the pointer position follows the pointer until `rbbox` receives a button-up event.

`rbbox(initialRect,fixedPoint)` specifies the corner of the box that remains fixed. All arguments are in the units specified by the current figure's `Units` property, and measured from the lower left corner of the figure window. `fixedPoint` is a two-element vector, `[x y]`. The tracking point is the corner diametrically opposite the anchored corner defined by `fixedPoint`.

`rbbox(initialRect,fixedPoint,stepSize)` specifies how frequently the rubberband box is updated. When the tracking point exceeds `stepSize` figure units, `rbbox` redraws the rubberband box. The default stepsize is `1`.

`finalRect = rbbox(...)` returns a four-element vector, `[x y width height]`, where `x` and `y` are the *x* and *y* components of the lower left corner of the box, and `width` and `height` are the dimensions of the box.

Remarks

`rbbox` is useful for defining and resizing a rectangular region:

- For box definition, `initialRect` is `[x y 0 0]`, where `(x,y)` is the figure's `CurrentPoint`.
- For box resizing, `initialRect` defines the rectangular region that you resize (e.g., a legend). `fixedPoint` is the corner diametrically opposite the tracking point.

`rbbox` returns immediately if a button is not currently pressed. Therefore, you use `rbbox` with `waitforbuttonpress` so that the mouse button is down when `rbbox` is called. `rbbox` returns when you release the mouse button.

Examples

Assuming the current view is `view(2)`, use the current axes' `CurrentPoint` property to determine the extent of the rectangle in dataspace units:

```
k = waitforbuttonpress;

point1 = get(gca,'CurrentPoint');    % button down detected
finalRect = rbbox;                   % return figure units
point2 = get(gca,'CurrentPoint');    % button up detected

point1 = point1(1,1:2);              % extract x and y
point2 = point2(1,1:2);

p1 = min(point1,point2);             % calculate locations
offset = abs(point1-point2);         % and dimensions

x = [p1(1) p1(1)+offset(1) p1(1)+offset(1) p1(1) p1(1)];
y = [p1(2) p1(2) p1(2)+offset(2) p1(2)+offset(2) p1(2)];

hold on
axis manual
plot(x,y)                            % redraw in dataspace units
```

See Also

`axis`, `dragrect`, `waitforbuttonpress`

"View Control" for related functions

rcond

Purpose

Matrix reciprocal condition number estimate

Syntax

```
c = rcond(A)
```

Description

`c = rcond(A)` returns an estimate for the reciprocal of the condition of `A` in 1-norm using the LAPACK condition estimator. If `A` is well conditioned, `rcond(A)` is near 1.0. If `A` is badly conditioned, `rcond(A)` is near 0.0. Compared to `cond`, `rcond` is a more efficient, but less reliable, method of estimating the condition of a matrix.

Algorithm

`rcond` uses LAPACK routines to compute the estimate of the reciprocal condition number:

Matrix	Routine
Real	`DLANGE`, `DGETRF`, `DGECON`
Complex	`ZLANGE`, `ZGETRF`, `ZGECON`

See Also

`cond`, `condest`, `norm`, `normest`, `rank`, `svd`

References

[1] Anderson, E., Z. Bai, C. Bischof, S. Blackford, J. Demmel, J. Dongarra, J. Du Croz, A. Greenbaum, S. Hammarling, A. McKenney, and D. Sorensen, *LAPACK User's Guide* (`http://www.netlib.org/lapack/lug/lapack_lug.html`), Third Edition, SIAM, Philadelphia, 1999.

Purpose

Real part of complex number

Syntax

```
X = real(Z)
```

Description

`X = real(Z)` returns the real part of the elements of the complex array `Z`.

Examples

`real(2+3*i)` is 2.

See Also

`abs`, `angle`, `conj`, `i`, `j`, `imag`

reallog

Purpose

Natural logarithm for nonnegative real arrays

Syntax

```
Y = reallog(X)
```

Description

`Y = reallog(X)` returns the natural logarithm of each element in array `X`. Array `X` must contain only nonnegative real numbers. The size of `Y` is the same as the size of `X`.

Examples

```
M = magic(4)

M =
    16     2     3    13
     5    11    10     8
     9     7     6    12
     4    14    15     1

reallog(M)

ans =
    2.7726    0.6931    1.0986    2.5649
    1.6094    2.3979    2.3026    2.0794
    2.1972    1.9459    1.7918    2.4849
    1.3863    2.6391    2.7081         0
```

See Also

`log`, `realpow`, `realsqrt`

Purpose

Largest positive floating-point number

Syntax

```
n = realmax
```

Description

`n = realmax` returns the largest floating-point number representable on your computer. Anything larger overflows.

`realmax('double')` is the same as `realmax` with no arguments.

`realmax('single')` is the largest single precision floating point number representable on your computer. Anything larger overflows to `single(Inf)`.

Examples

`realmax` is one bit less than 2^{1024} or about `1.7977e+308`.

Algorithm

The `realmax` function is equivalent to `pow2(2-eps,maxexp)`, where `maxexp` is the largest possible floating-point exponent.

Execute `type realmax` to see `maxexp` for various computers.

See Also

`eps`, `realmin`, `intmax`

realmin

Purpose

Smallest positive floating-point number

Syntax

```
n = realmin
```

Description

`n = realmin` returns the smallest positive normalized floating-point number on your computer. Anything smaller underflows or is an IEEE “denormal.”

`REALMIN('double')` is the same as `REALMIN` with no arguments.

`REALMIN('single')` is the smallest positive normalized single precision floating point number on your computer.

Examples

`realmin` is `2^(-1022)` or about `2.2251e-308`.

Algorithm

The `realmin` function is equivalent to `pow2(1,minexp)` where `minexp` is the smallest possible floating-point exponent.

Execute `type realmin` to see `minexp` for various computers.

See Also

`eps`, `realmax`, `intmin`

Purpose

Array power for real-only output

Syntax

```
Z = realpow(X,Y)
```

Description

`Z = realpow(X,Y)` raises each element of array `X` to the power of its corresponding element in array `Y`. Arrays `X` and `Y` must be the same size. The range of `realpow` is the set of all real numbers, i.e., all elements of the output array `Z` must be real.

Examples

```
X = -2*ones(3,3)

X =
     -2     -2     -2
     -2     -2     -2
     -2     -2     -2

Y = pascal(3)

ans =
      1      1      1
      1      2      3
      1      3      6

realpow(X,Y)

ans =
     -2     -2     -2
     -2      4     -8
     -2     -8     64
```

See Also

`reallog`, `realsqrt`, `.^` (array power operator)

realsqrt

Purpose

Square root for nonnegative real arrays

Syntax

```
Y = realsqrt(X)
```

Description

`Y = realsqrt(X)` returns the square root of each element of array `X`. Array `X` must contain only nonnegative real numbers. The size of `Y` is the same as the size of `X`.

Examples

```
M = magic(4)

M =
    16     2     3    13
     5    11    10     8
     9     7     6    12
     4    14    15     1

realsqrt(M)

ans =
    4.0000    1.4142    1.7321    3.6056
    2.2361    3.3166    3.1623    2.8284
    3.0000    2.6458    2.4495    3.4641
    2.0000    3.7417    3.8730    1.0000
```

See Also

`reallog`, `realpow`, `sqrt`, `sqrtm`

Purpose

Create a 2-D rectangle object

Syntax

```
rectangle
rectangle('Position',[x,y,w,h])
rectangle(...,'Curvature',[x,y])
h = rectangle(...)
```

Description

`rectangle` draws a rectangle with `Position` `[0,0,1,1]` and `Curvature` `[0,0]` (i.e., no curvature).

`rectangle('Position',[x,y,w,h])` draws the rectangle from the point `x`,`y` and having a width of `w` and a height of `h`. Specify values in axes data units.

Note that, to display a rectangle in the specified proportions, you need to set the axes data aspect ratio so that one unit is of equal length along both the x and y axes. You can do this with the command `axis equal` or `daspect([1,1,1])`.

`rectangle(...,'Curvature',[x,y])` specifies the curvature of the rectangle sides, enabling it to vary from a rectangle to an ellipse. The horizontal curvature `x` is the fraction of width of the rectangle that is curved along the top and bottom edges. The vertical curvature `y` is the fraction of the height of the rectangle that is curved along the left and right edges.

The values of `x` and `y` can range from `0` (no curvature) to `1` (maximum curvature). A value of `[0,0]` creates a rectangle with square sides. A value of `[1,1]` creates an ellipse. If you specify only one value for `Curvature`, then the same length (in axes data units) is curved along both horizontal and vertical sides. The amount of curvature is determined by the shorter dimension.

`h = rectangle(...)` returns the handle of the rectangle object created.

Remarks

Rectangle objects are 2-D and can be drawn in an axes only if the view is `[0 90]` (i.e., `view(2)`). Rectangles are children of axes and are defined in coordinates of the axes data.

Examples

This example sets the data aspect ratio to `[1,1,1]` so that the rectangle is displayed in the specified proportions (`daspect`). Note that the horizontal and

vertical curvature can be different. Also, note the effects of using a single value for `Curvature`.

```
rectangle('Position',[0.59,0.35,3.75,1.37],...
          'Curvature',[0.8,0.4],...
         'LineWidth',2,'LineStyle','--')
daspect([1,1,1])
```



Specifying a single value of `[0.4]` for `Curvature` produces



A `Curvature` of `[1]` produces a rectangle with the shortest side completely round:



This example creates an ellipse and colors the face red.

```
rectangle('Position',[1,2,5,10],'Curvature',[1,1],...
          'FaceColor','r')
daspect([1,1,1])
xlim([0,7])
ylim([1,13])
```



See Also

`line`, `patch`, rectangle properties

"Object Creation Functions" for related functions

See the `annotation` function for information about the rectangle annotation object.

Object Hierarchy



Setting Default Properties

You can set default rectangle properties on the axes, figure, and root levels:

```
set(0,'DefaultRectangleProperty',PropertyValue...)
set(gcf,'DefaultRectangleProperty',PropertyValue...)
set(gca,'DefaultRectangleProperty',PropertyValue...)
```

where *Property* is the name of the rectangle property whose default value you want to set and PropertyValue is the value you are specifying. Use set and get to access the surface properties.

Property List

The following table lists all rectangle properties and provides a brief description of each. The property name links take you to an expanded description of the properties.

Property Name	Property Description	Property Value
Defining the Rectangle Object		
Curvature	Degree of horizontal and vertical curvature	Value: two-element vector with values between 0 and 1 Default: [0,0]
EraseMode	Method of drawing and erasing the rectangle (useful for animation)	Values: normal, none, xor, background Default: normal
EdgeColor	Color of rectangle edges	Value: ColorSpec or none Default: ColorSpec [0,0,0]
FaceColor	Color of rectangle interior	Value: ColorSpec or none Default: none
LineStyle	Line style of edges	Values: –, ––, :, –., none Default: –
LineWidth	Width of edge lines in points	Value: scalar Default: 0.5 points
Position	Location and width and height of rectangle	Value: [x,y,width,height] Default: [0,0,1,1]

Property Name	Property Description	Property Value
General Information About Rectangle Objects		
`Children`	Rectangle objects have no children.	
`Parent`	The parent of a rectangle object is an axes, hggroup, or hgtransform object.	Value: object handle
`Selected`	Indicates if the rectangle is in a selected state	Values: `on`, `off` Default: `off`
`Tag`	User-specified label	Value: any string Default: `''` (empty string)
`Type`	The type of graphics object (read only)	Value: the string `'rectangle'`
`UserData`	User-specified data	Value: any matrix Default: `[]` (empty matrix)
Properties Related to Callback Routine Execution		
`BeingDeleted`	Query to see if object is being deleted.	Values: `on | off` Read only
`BusyAction`	Specifies how to handle callback routine interruption	Values: `cancel`, `queue` Default: `queue`
`ButtonDownFcn`	Defines a callback routine that executes when a mouse button is pressed on over the rectangle	Value: string or function handle Default: `''` (empty string)
`CreateFcn`	Defines a callback routine that executes when a rectangle is created	Value: string or function handle Default: `''` (empty string)
`DeleteFcn`	Defines a callback routine that executes when the rectangle is deleted (via `close` or `delete`)	Value: string or function handle Default: `''` (empty string)

Property Name	Property Description	Property Value
`Interruptible`	Determines if callback routine can be interrupted	Values: `on`, `off` Default: `on` (can be interrupted)
`UIContextMenu`	Associates a context menu with the rectangle	Value: handle of a Uicontextmenu
Controlling Access to Objects		
`HandleVisibility`	Determines if and when the rectangle's handle is visible to other functions	Values: `on`, `callback`, `off` Default: `on`
`HitTest`	Determines if the rectangle can become the current object (see the Figure `CurrentObject` property)	Values: `on`, `off` Default: `on`
Controlling the Appearance		
`Clipping`	Clipping to axes rectangle	Values: `on`, `off` Default: `on`
`SelectionHighlight`	Highlights rectangle when selected (`Selected` property is set to `on`)	Values: `on`, `off` Default: `on`
`Visible`	Makes the rectangle visible or invisible	Values: `on`, `off` Default: `on`

Rectangle properties

Modifying Properties

You can set and query graphics object properties in two ways:

- The Property Editor is an interactive tool that enables you to see and change object property values.
- The `set` and `get` commands enable you to set and query the values of properties.

To change the default values of properties, see Setting Default Property Values.

See Core Objects for general information about this type of object.

Rectangle Property Descriptions

This section lists property names along with the type of values each accepts. Curly braces { } enclose default values.

`BeingDeleted` `on | {off} read only`

This object is being deleted. The `BeingDeleted` property provides a mechanism that you can use to determine if objects are in the process of being deleted. MATLAB sets the `BeingDeleted` property to `on` when the object's delete function callback is called (see the `DeleteFcn` property). It remains set to `on` while the delete function executes, after which the object no longer exists.

For example, an object's delete function might call other functions that act on a number of different objects. These functions may not need to perform actions on objects that are going to be deleted, and therefore, can check the object's `BeingDeleted` property before acting.

`BusyAction` `cancel | {queue}`

Callback routine interruption. The `BusyAction` property enables you to control how MATLAB handles events that potentially interrupt executing callback routines. If there is a callback routine executing, callback routines invoked subsequently always attempt to interrupt it. If the `Interruptible` property of the object whose callback is executing is set to `on` (the default), then interruption occurs at the next point where the event queue is processed. If the `Interruptible` property is `off`, the `BusyAction` property (of the object owning the executing callback) determines how MATLAB handles the event. The choices are

- `cancel` — Discard the event that attempted to execute a second callback routine.
- `queue` — Queue the event that attempted to execute a second callback routine until the current callback finishes.

`ButtonDownFcn` string or function handle

Button press callback routine. A callback routine that executes whenever you press a mouse button while the pointer is over the rectangle object. Define this routine as a string that is a valid MATLAB expression or the name of an M-file. The expression executes in the MATLAB workspace.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

`Children` vector of handles

The empty matrix; rectangle objects have no children.

`Clipping` `{on} | off`

Clipping mode. MATLAB clips rectangles to the axes plot box by default. If you set `Clipping` to `off`, rectangles are displayed outside the axes plot box. This can occur if you create a rectangle, set `hold` to `on`, freeze axis scaling (`axis` set to `manual`), and then create a larger rectangle.

`CreateFcn` string or function handle

Callback routine executed during object creation. This property defines a callback routine that executes when MATLAB creates a rectangle object. You must define this property as a default value for rectangles or in a call to the `rectangle` function to create a new rectangle object. For example, the statement

```
set(0,'DefaultRectangleCreateFcn',...
      'set(gca,''DataAspectRatio'',[1,1,1])')
```

defines a default value on the root level that sets the axes `DataAspectRatio` whenever you create a rectangle object. MATLAB executes this routine after setting all rectangle properties. Setting this property on an existing rectangle object has no effect.

The handle of the object whose `CreateFcn` is being executed is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

`Curvature` one- or two-element vector `[x,y]`

Amount of horizontal and vertical curvature. This property specifies the curvature of the rectangle sides, which enables the shape of the rectangle to vary from rectangular to ellipsoidal. The horizontal curvature `x` is the fraction of width of the rectangle that is curved along the top and bottom edges. The vertical curvature `y` is the fraction of the height of the rectangle that is curved along the left and right edges.

The values of `x` and `y` can range from `0` (no curvature) to `1` (maximum curvature). A value of `[0,0]` creates a rectangle with square sides. A value of `[1,1]` creates an ellipse. If you specify only one value for `Curvature`, then the same length (in axes data units) is curved along both horizontal and vertical sides. The amount of curvature is determined by the shorter dimension.

`DeleteFcn` string or function handle

Delete rectangle callback routine. A callback routine that executes when you delete the rectangle object (e.g., when you issue a `delete` command or clear the axes or figure). MATLAB executes the routine before deleting the object's properties so these values are available to the callback routine.

The handle of the object whose `DeleteFcn` is being executed is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

`EdgeColor` `{ColorSpec} | none`

Color of the rectangle edges. This property specifies the color of the rectangle edges as a color or specifies that no edges be drawn.

`EraseMode` `{normal} | none | xor | background`

Erase mode. This property controls the technique MATLAB uses to draw and erase rectangle objects. Alternative erase modes are useful for creating animated sequences, where control of the way individual objects are redrawn is necessary to improve performance and obtain the desired effect.

- `normal` (the default) — Redraw the affected region of the display, performing the three-dimensional analysis necessary to ensure that all objects are

rendered correctly. This mode produces the most accurate picture, but is the slowest. The other modes are faster, but do not perform a complete redraw and are therefore less accurate.

- `none` — Do not erase the rectangle when it is moved or destroyed. While the object is still visible on the screen after erasing with `EraseMode` `none`, you cannot print it because MATLAB stores no information about its former location.
- `xor` — Draw and erase the rectangle by performing an exclusive OR (XOR) with the color of the screen beneath it. This mode does not damage the color of the objects beneath the rectangle. However, the rectangle's color depends on the color of whatever is beneath it on the display.
- `background` — Erase the rectangle by drawing it in the axes background `Color`, or the figure background `Color` if the axes `Color` is set to `none`. This damages objects that are behind the erased rectangle, but rectangles are always properly colored.

Printing with Nonnormal Erase Modes.

MATLAB always prints figures as if the `EraseMode` of all objects is `normal`. This means graphics objects created with `EraseMode` set to `none`, `xor`, or `background` can look different on screen than on paper. On screen, MATLAB can mathematically combine layers of colors (e.g., performing an XOR of a pixel color with that of the pixel behind it) and ignore three-dimensional sorting to obtain greater rendering speed. However, these techniques are not applied to the printed output.

You can use the MATLAB `getframe` command or other screen capture application to create an image of a figure containing nonnormal mode objects.

`FaceColor` `ColorSpec | {none}`

Color of rectangle face. This property specifies the color of the rectangle face, which is not colored by default.

`HandleVisibility` `{on} | callback | off`

Control access to object's handle by command-line users and GUIs. This property determines when an object's handle is visible in its parent's list of children. `HandleVisibility` is useful for preventing command-line users from accidentally drawing into or deleting a figure that contains only user interface devices (such as a dialog box).

Handles are always visible when HandleVisibility is on.

Setting HandleVisibility to callback causes handles to be visible from within callback routines or functions invoked by callback routines, but not from within functions invoked from the command line. This provides a means to protect GUIs from command-line users, while allowing callback routines to have complete access to object handles.

Setting HandleVisibility to off makes handles invisible at all times. This may be necessary when a callback routine invokes a function that might potentially damage the GUI (such as evaluating a user-typed string), and so temporarily hides its own handles during the execution of that function.

When a handle is not visible in its parent's list of children, it cannot be returned by functions that obtain handles by searching the object hierarchy or querying handle properties. This includes get, findobj, gca, gcf, gco, newplot, cla, clf, and close.

When a handle's visibility is restricted using callback or off, the object's handle does not appear in its parent's Children property, figures do not appear in the root's CurrentFigure property, objects do not appear in the root's CallbackObject property or in the figure's CurrentObject property, and axes do not appear in their parent's CurrentAxes property.

You can set the Root ShowHiddenHandles property to on to make all handles visible regardless of their HandleVisibility settings (this does not affect the values of the HandleVisibility properties).

Handles that are hidden are still valid. If you know an object's handle, you can set and get its properties and pass it to any function that operates on handles.

HitTest {on} | off

Selectable by mouse click. HitTest determines if the rectangle can become the current object (as returned by the gco command and the figure CurrentObject property) as a result of a mouse click on the rectangle. If HitTest is off, clicking the rectangle selects the object below it (which may be the axes containing it).

Interruptible {on} | off

Callback routine interruption mode. The Interruptible property controls whether a rectangle callback routine can be interrupted by subsequently

invoked callback routines. Only callback routines defined for the `ButtonDownFcn` are affected by the `Interruptible` property. MATLAB checks for events that can interrupt a callback routine only when it encounters a `drawnow`, `figure`, `getframe`, or `pause` command in the routine.

`LineStyle` `{-} | -- | : | -. | none`

Line style of rectangle edge. This property specifies the line style of the edges. The available line styles are

Symbol	Line Style
-	Solid line (default)
--	Dashed line
:	Dotted line
-.	Dash-dot line
none	No line

`LineWidth` scalar

The width of the rectangle edge line. Specify this value in points (1 point = $^1/_{72}$ inch). The default `LineWidth` is 0.5 points.

`Parent` handle of axes, hggroup, or hgtransform

Parent of rectangle object. This property contains the handle of the rectangle object's parent. The parent of a rectangle object is the axes, hggroup, or hgtransform object that contains it.

See Objects That Can Contain Other Objects for more information on parenting graphics objects.

`Position` four-element vector `[x,y,width,height]`

Location and size of rectangle. This property specifies the location and size of the rectangle in the data units of the axes. The point defined by `x`, `y` specifies one corner of the rectangle, and `width` and `height` define the size in units along the *x*-and *y*-axes respectively.

Selected on | off

Is object selected? When this property is on MATLAB displays selection handles if the SelectionHighlight property is also on. You can, for example, define the ButtonDownFcn to set this property, allowing users to select the object with the mouse.

SelectionHighlight {on} | off

Objects are highlighted when selected. When the Selected property is on, MATLAB indicates the selected state by drawing handles at each vertex. When SelectionHighlight is off, MATLAB does not draw the handles.

Tag string

User-specified object label. The Tag property provides a means to identify graphics objects with a user-specified label. This is particularly useful when you are constructing interactive graphics programs that would otherwise need to define object handles as global variables or pass them as arguments between callback routines. You can define Tag as any string.

Type string (read only)

Class of graphics object. For rectangle objects, Type is always the string 'rectangle'.

UIContextMenu handle of a uicontextmenu object

Associate a context menu with the rectangle. Assign this property the handle of a uicontextmenu object created in the same figure as the rectangle. Use the uicontextmenu function to create the context menu. MATLAB displays the context menu whenever you right-click over the rectangle.

UserData matrix

User-specified data. Any data you want to associate with the rectangle object. MATLAB does not use this data, but you can access it using the set and get commands.

Visible {on} | off

Rectangle visibility. By default, all rectangles are visible. When set to off, the rectangle is not visible, but still exists, and you can get and set its properties.

Purpose

Rectangle intersection area.

Syntax

```
area = rectint(A,B)
```

Description

`area = rectint(A,B)` returns the area of intersection of the rectangles specified by position vectors `A` and `B`.

If `A` and `B` each specify one rectangle, the output `area` is a scalar.

`A` and `B` can also be matrices, where each row is a position vector. `area` is then a matrix giving the intersection of all rectangles specified by `A` with all the rectangles specified by `B`. That is, if `A` is `n`-by-`4` and `B` is `m`-by-`4`, then `area` is an `n`-by-`m` matrix where `area(i,j)` is the intersection area of the rectangles specified by the `i`th row of `A` and the `j`th row of `B`.

Note A position vector is a four-element vector `[x,y,width,height]`, where the point defined by `x` and `y` specifies one corner of the rectangle, and `width` and `height` define the size in units along the x and y axes respectively.

See Also

`polyarea`

recycle

Purpose

Set option to move deleted files to recycle folder

Syntax

```
S = recycle
S = recycle state
S = recycle('state')
```

Description

`S = recycle` returns a character array `S` that shows the current state of the MATLAB file recycling option. This state can be either `on` or `off`. When file recycling is `on`, MATLAB moves all files that you delete with the `delete` function to either the recycle bin (on the PC or Macintosh) or a temporary folder (on UNIX). When file recycling is `off`, any files you delete are actually removed from the system.

The default recycle state is `off`. You can turn recycling on for all of your MATLAB sessions using the Preferences dialog box (Select **File** -> **Preferences** -> **General**). Under the heading **Default behavior of the delete function** select **Move files to the Recycle Bin**.

`S = recycle state` sets the MATLAB recycle option to the given `state`, either `on` or `off`. Return value `S` shows the previous recycle state.

`S = recycle('state')` is the function format for this command.

Remarks

To set the recycle state for all MATLAB sessions, use the **Preferences** dialog box. Open the **Preferences** dialog and select **General**. To enable or disable recycling, click **Move files to the recycle bin** or **Delete files permanently**. See "General Preferences for MATLAB" in the Desktop Tools and Development Environment documentation for more information.

Examples

Start from a state where file recycling has been turned off. Check the current recycle state:

```
recycle
ans =
   off
```

Turn file recycling on. Delete a file and verify that it has been transferred to the recycle bin or temporary folder:

```
recycle on;
delete myfile.txt
```

See Also delete, dir, ls, fileparts, mkdir, rmdir

reducepatch

Purpose

Reduce the number of patch faces

Syntax

```
reducepatch(p,r)
nfv = reducepatch(p,r)
nfv = reducepatch(fv,r)
reducepatch(...,'fast')
reducepatch(...,'verbose')
nfv = reducepatch(f,v,r)
[nf,nv] = reducepatch(...)
```

Description

`reducepatch(p,r)` reduces the number of faces of the patch identified by handle `p`, while attempting to preserve the overall shape of the original object. MATLAB interprets the reduction factor `r` in one of two ways depending on its value:

- If `r` is less than 1, `r` is interpreted as a fraction of the original number of faces. For example, if you specify `r` as 0.2, then the number of faces is reduced to 20% of the number in the original patch.
- If `r` is greater than or equal to 1, then `r` is the target number of faces. For example, if you specify `r` as 400, then the number of faces is reduced until there are 400 faces remaining.

`nfv = reducepatch(p,r)` returns the reduced set of faces and vertices but does not set the `Faces` and `Vertices` properties of patch `p`. The struct `nfv` contains the faces and vertices after reduction.

`nfv = reducepatch(fv,r)` performs the reduction on the faces and vertices in the struct `fv`.

`nfv = reducepatch(p)` or `nfv = reducepatch(fv)` uses a reduction value of `0.5`.

`reducepatch(...,'fast')` assumes the vertices are unique and does not compute shared vertices.

`reducepatch(...,'verbose')` prints progress messages to the command window as the computation progresses.

`nfv = reducepatch(f,v,r)` performs the reduction on the faces in `f` and the vertices in `v`.

`[nf,nv] = reducepatch(...)` returns the faces and vertices in the arrays `nf` and `nv`.

Remarks

If the patch contains nonshared vertices, MATLAB computes shared vertices before reducing the number of faces. If the faces of the patch are not triangles, MATLAB triangulates the faces before reduction. The faces returned are always defined as triangles.

The number of output triangles may not be exactly the number specified with the reduction factor argument (`r`), particularly if the faces of the original patch are not triangles.

Examples

This example illustrates the effect of reducing the number of faces to only 15% of the original value.

```
[x,y,z,v] = flow;
p = patch(isosurface(x,y,z,v,-3));
set(p,'facecolor','w','EdgeColor','b');
daspect([1,1,1])
view(3)
figure;
h = axes;
p2 = copyobj(p,h);
reducepatch(p2,0.15)
daspect([1,1,1])
view(3)
```


Before Reduction
3
2
1
0
−1
−2
−3
4
2
0
−2
−4
0
2
4
6
8
10



See Also

`isosurface`, `isocaps`, `isonormals`, `smooth3`, `subvolume`, `reducevolume`

"Volume Visualization" for related functions

Vector Field Displayed with Cone Plots for another example

reducevolume

Purpose

Reduce the number of elements in a volume data set

Syntax

```
[nx,ny,nz,nv] = reducevolume(X,Y,Z,V,[Rx,Ry,Rz])
[nx,ny,nz,nv] = reducevolume(V,[Rx,Ry,Rz])
nv = reducevolume(...)
```

Description

`[nx,ny,nz,nv] = reducevolume(X,Y,Z,V,[Rx,Ry,Rz])` reduces the number of elements in the volume by retaining every Rx^{th} element in the x direction, every Ry^{th} element in the y direction, and every Rz^{th} element in the z direction. If a scalar `R` is used to indicate the amount or reduction instead of a three-element vector, MATLAB assumes the reduction to be `[R R R]`.

The arrays `X`, `Y`, and `Z` define the coordinates for the volume `V`. The reduced volume is returned in `nv`, and the coordinates of the reduced volume are returned in `nx`, `ny`, and `nz`.

`[nx,ny,nz,nv] = reducevolume(V,[Rx,Ry,Rz])` assumes the arrays `X`, `Y`, and `Z` are defined as `[X,Y,Z] = meshgrid(1:n,1:m,1:p)` where `[m,n,p] = size(V)`.

`nv = reducevolume(...)` returns only the reduced volume.

Examples

This example uses a data set that is a collection of MRI slices of a human skull. This data is processed in a variety of ways:

- The 4-D array is squeezed (`squeeze`) into three dimensions and then reduced (`reducevolume`) so that what remains is every fourth element in the x and y directions and every element in the z direction.
- The reduced data is smoothed (`smooth3`).
- The outline of the skull is an isosurface generated as a patch (`p1`) whose vertex normals are recalculated to improve the appearance when lighting is applied (`patch`, `isosurface`, `isonormals`).
- A second patch (`p2`) with an interpolated face color draws the end caps (`FaceColor`, `isocaps`).
- The view of the object is set (`view`, `axis`, `daspect`).

- A 100-element grayscale colormap provides coloring for the end caps (`colormap`).
- Adding a light to the right of the camera illuminates the object (`camlight`, `lighting`).

```
load mri
D = squeeze(D);
[x,y,z,D] = reducevolume(D,[4,4,1]);
D = smooth3(D);
p1 = patch(isosurface(x,y,z,D, 5,'verbose'),...
    'FaceColor','red','EdgeColor','none');
isonormals(x,y,z,D,p1);

p2 = patch(isocaps(x,y,z,D, 5),...
    'FaceColor','interp','EdgeColor','none');
view(3); axis tight; daspect([1,1,.4])
colormap(gray(100))
camlight; lighting gouraud
```



See Also

`isosurface`, `isocaps`, `isonormals`, `smooth3`, `subvolume`, `reducepatch`

"Volume Visualization" for related functions

refresh

Purpose

Redraw current figure

Syntax

```
refresh
refresh(h)
```

Description

`refresh` erases and redraws the current figure.

`refresh(h)` redraws the figure identified by `h`.

See Also

"Figure Windows" for related functions

Purpose

Refresh data in graph when data source is specified

Syntax

```
refreshdata
refreshdata(figure_handle)
refreshdata(object_handles)
refreshdata(object_handles,'workspace')
```

Description

`refreshdata` evaluates any data source properties (`XDataSource`, `YDataSource`, or `ZDataSource`) on all objects in graphs in the current figure. If the specified data source has changed, MATLAB updates the graph to reflect this change.

Note that the variable assigned to the data source property must be in the base workspace.

`refreshdata(figure_handle)` refreshes the data of the objects in the specified figure.

`refreshdata(object_handles)` refreshes the data of the objects specified in `objects_handles` or the children of those objects. Therefore, `object_handles` can contain figure, axes, or plot object handles.

`refreshdata(object_handles,'workspace')` enables you to specify whether the data source properties are evaluated in the base workspace or the workspace of the function in which `refreshdata` was called. *`workspace`* is a string that can be:

- `base` — evaluate the data source properties in the base workspace.
- `caller` — evaluate the data source properties in the workspace of the function that called refreshdata.

Examples

This example creates a contour plot and changes its data source. The call to `refreshdata` causes the graph to update.

```
z = peaks(5);
[c h] = contour(z,'ZDataSource','z');
drawnow
pause(3) % Wait 3 seconds and the graph will update
z = peaks(20);
refreshdata(h)
```

See Also The `[X,Y,Z]DataSource` properties of plot objects.

Purpose

Match regular expression

Syntax

Each of these syntaxes apply to both `regexp` and `regexpi`. The `regexp` function is case sensitive in matching regular expressions to a string, and `regexpi` is case insensitive:

```
regexp('str', 'expr')
[start end extents match tokens names] = regexp('str', 'expr')
[v1 v2 ...] = regexp('str', 'expr', 'q1', 'q2', ...)
[v1 v2 ...] = regexp('str', 'expr', 'q1', 'q2', ..., 'once')
regexp 'str' 'expr' 'q1' 'q2' ... 'once'
```

Description

The following descriptions apply to both `regexp` and `regexpi`:

`regexp('str', 'expr')` returns a row vector containing the starting index of each substring of `str` that matches the regular expression string `expr`. If no matches are found, `regexp` returns an empty array. The `str` and `expr` arguments can also be cell arrays of strings. See the guidelines listed below under “Multiple Strings and Expressions”.

`[start end extents match tokens names] = regexp('str', 'expr')` returns up to six values, one for each output variable you specify, and in the default order (as shown in the table below).

`[v1 v2 ...] = regexp('str', 'expr', q1, q2, ...)` returns up to six values, one for each output variable you specify, and ordered according to the order of the qualifier arguments, `q1`, `q2`, etc.

Return Values for Regular Expressions

Default Order	Description	Qualifier
1	Row vector containing the starting index of each substring of `str` that matches `expr`	**`start`**
2	Row vector containing the ending index of each substring of `str` that matches `expr`	**`end`**
3	Cell array containing the starting and ending indices of each substring of `str` that matches a token in `expr`	**`tokenExtents`**

Return Values for Regular Expressions

Default Order	Description	Qualifier
4	Cell array containing the text of each substring of `str` that matches `expr`	**`match`**
5	Cell array containing the text of each token captured by `regexp`.	**`tokens`**
6	Structure array containing the name and text of each *named* token captured by `regexp`. If there are no named tokens in `expr`, `regexp` returns a structure array with no fields. Field names of the returned structure are set to the token names, and field values are the text of those tokens. Named tokens are generated by the expression `(?<tokenname>)`.	**`names`**

`[v1 v2 ...] = regexp('str', 'expr', 'q1', 'q2', ..., '`**`once`**`')` returns just the first match found. The keyword **`once`** must come last in the argument list. Output and qualifier arguments are not required.

`regexp 'str' 'expr' 'q1' 'q2' ... '`**`once`**`'` is the command syntax for this function. Only the `'str'` and `'expr'` arguments are required.

Remarks

Multiple Strings and Expressions

Either the `str` or `expr` argument, or both, can be a cell array of strings, according to the following guidelines:

- If `str` is a cell array of strings, then each of the `regexp` outputs is a cell array having the same dimensions as `str`.
- If `str` is a single string but `expr` is a cell array of strings, then each of the `regexp` outputs is a cell array having the same dimensions as `expr`.
- If both `str` and `expr` are cell arrays of strings, these two cell arrays must contain the same number of elements.

See “Regular Expressions” in the MATLAB documentation for a listing of all regular expression elements supported by MATLAB.

`regexp` does not support international character sets.

Examples

Example 1

Return a row vector of indices that match words that start with `c`, end with `t`, and contain one or more vowels between them. Make the matches insensitive to letter case (by using `regexpi`):

```
str = 'bat cat can car COAT court cut ct CAT-scan';
regexpi(str, 'c[aeiou]+t')
ans =
     5    17    28    35
```

Example 2

Return a cell array of row vectors of indices that match capital letters and white spaces in the cell array of strings `str`:

```
str = {'Madrid, Spain' 'Romeo and Juliet' 'MATLAB is great'};
s1 = regexp(str, '[A-Z]');
s2 = regexp(str, '\s');
```

Capital letters, `'[A-Z]'`, were found at these `str` indices:

```
s1{:}
ans =
     1     9
ans =
     1    11
ans =
     1     2     3     4     5     6
```

Space characters, `'\s'`, were found at these `str` indices:

```
s2{:}
ans =
     8
ans =
     6    10
ans =
     7    10
```

Example 3

Return the text and the starting and ending indices of words containing the letter x:

```
str = 'regexp helps you relax';
[m s e] = regexp(str, '\w*x\w*', 'match', 'start', 'end')
m =
    'regexp'    'relax'
s =
     1    18
e =
     6    22
```

Example 4

Search a string for opening and closing HTML tags. Use the expression `<(\w+)` to find the opening tag (e.g., `'<tagname'`) and to create a token for it. Use the expression `</\1>` to find another occurrence of the same token, but formatted as a closing tag (e.g., `'</tagname>'`):

```
str = 'if <code>A</code> == x<sup>2</sup>, <em>disp(x)</em>';
expr = '<(\w+).*?>.*?</\1>';

[tok mat] = regexp(str, expr, 'tokens', 'match');

tok{:}
ans =
    'code'
ans =
    'sup'
ans =
    'em'

mat{:}
ans =
    <code>A</code>
ans =
    <sup>2</sup>
ans =
    <em>disp(x)</em>
```

See “Tokens” in the MATLAB Programming documentation for information on using tokens.

Example 5

Enter a string containing two names, the first and last names being in a different order:

```
str = sprintf('John Davis\nRogers, James')
str =
    John Davis
    Rogers, James
```

Create an expression that generates first and last name tokens, assigning the names `first` and `last` to the tokens. Call `regexp` to get the text and names of each token found:

```
expr = ...
   '(?<first>\w+)\s+(?<last>\w+)|(?<last>\w+),\s+(?<first>\w+)';

[tokens names] = regexp(str, expr, 'tokens', 'names');
```

Examine the `tokens` cell array that was returned. The first and last name tokens appear in the order in which they were generated: first name–last name, then last name–first name:

```
tokens{:}
ans =
    'John'    'Davis'
ans =
    'Rogers'    'James'
```

Now examine the `names` structure that was returned. First and last names appear in a more usable order:

```
names(:,1)
ans =
    first: 'John'
     last: 'Davis'
```

```
names(:,2)
ans =
    first: 'James'
     last: 'Rogers'
```

See Also

regexprep, strfind, findstr, strmatch, strcmp, strcmpi, strncmp, strncmpi

Purpose

Replace string using regular expression

Syntax

```
s = regexprep('str', 'expr', 'repstr')
s = regexprep('str', 'expr', 'repstr', optionlist)
```

Description

`s = regexprep('str', 'expr', 'repstr')` replaces all occurrences of the regular expression `expr` in string `str` with the string `repstr`. The new string is returned in `s`. If no matches are found, return string `s` is the same as input string `str`.

If `str` is a cell array of strings, then the `regexprep` return value `s` is always a cell array of strings having the same dimensions as `str`.

If `expr` is a cell array of strings and `repstr` is a single string, `regexprep` uses the same replacement string on each expression in `expr`. If both `expr` and `repstr` are cell arrays of strings, then `expr` and `repstr` must contain the same number of elements, and `regexprep` pairs each `repstr` element with its matching element in `expr`.

You can capture parts of the input string as tokens and then reuse them in the replacement string. Specify the parts of the string to capture using the `(...)` operator. Specify the tokens to use in the replacement string using the operators `$1`, `$2`, `$N` to reference the first, second, and `N`th tokens captured. (See the section on "Tokens" and the example "Using Tokens in a Replacement String" in the External Interfaces documentation for information on using tokens.)

`s = regexprep('str', 'expr', 'repstr' optionlist)` By default, `regexprep` replaces all matches and is case sensitive. You can use one or more

of the following options with `regexprep`. Separate each option in *`optionlist`* with a comma.

Option	Description
`'ignorecase'`	Ignore the case of characters when matching `expr` to `str`.
`'preservecase'`	Ignore case when matching (as with `'ignorecase'`), but override the case of `replace` characters with the case of corresponding characters in `str` when replacing.
`'once'`	Replace only the first occurrence of `expr` in `str`.
`N`	Replace only the `N`th occurrence of `expr` in `str`.

Remarks

See "Regular Expressions" in the MATLAB documentation for a listing of all regular expression metacharacters supported by MATLAB.

`regexprep` does not support international character sets.

Examples

Example 1

Perform a case-sensitive replacement on words starting with `m` and ending with `y`:

```
str = 'My flowers may bloom in May';
pat = 'm(\w*)y';
regexprep(str, pat, 'April')
ans =
   My flowers April bloom in May
```

Replace all words starting with `m` and ending with `y`, regardless of case, but maintain the original case in the replacement strings:

```
regexprep(str, pat, 'April', 'preservecase')
ans =
   April flowers april bloom in April
```

Example 2

Replace all variations of the words `'walk up'` using the letters following `walk` as a token. In the replacement string

```
str = 'I walk up, they walked up, we are walking up.';
pat = 'walk(\w*) up';
regexprep(str, pat, 'ascend$1')
ans =
   I ascend, they ascended, we are ascending.
```

Example 3

This example operates on a cell array of strings. It searches for consecutive matching letters (e.g., `'oo'`) and uses a common replacement value (`'--'`) for all matches. The function returns a cell array of strings having the same dimensions as the input cell array:

```
str = {                                  ...
'Whose woods these are I think I know.' ; ...
'His house is in the village though;'   ; ...
'He will not see me stopping here'      ; ...
'To watch his woods fill up with snow.'};


a = regexprep(str, '(.)\1', '--', 'ignorecase')
a =
    'Whose w--ds these are I think I know.'
    'His house is in the vi--age though;'
    'He wi-- not s-- me sto--ing here'
    'To watch his w--ds fi-- up with snow.'
```

See Also

`regexp`, `regexpi`, `strfind`, `findstr`, `strmatch`, `strcmp`, `strcmpi`, `strncmp`, `strncmpi`

rehash

Purpose

Refresh function and file system path caches

Syntax

```
rehash
rehash path
rehash toolbox
rehash pathreset
rehash toolboxreset
rehash toolboxcache
```

Description

`rehash` with no arguments updates the MATLAB list of known files and classes for directories on the search path that are not in `$matlabroot/toolbox`. It compares the timestamps for loaded functions (functions that have been called but not cleared in the current session) against their timestamps on disk. It clears loaded functions if the files on disk are newer. All of this normally happens each time MATLAB displays the Command Window prompt. Therefore, use `rehash` with no arguments only when you run an M-file that updates another M-file, and the calling file needs to reuse the updated version before it has finished running.

`rehash path` performs the same updates as `rehash`, but uses a different technique for detecting the files and directories that require updates. If you receive a warning during MATLAB startup notifying you that MATLAB could not tell if a directory has changed and you encounter problems with MATLAB using the most current versions of your M-files, run `rehash path`.

`rehash toolbox` updates all directories in `$matlabroot/toolbox`. Run this when you add or remove files in `$matlabroot/toolbox` during a session by some means other than MATLAB tools, like the Editor.

`rehash pathreset` performs the same updates as `rehash path`, and also ensures the known files and classes list follows precedence rules for shadowed functions.

`rehash toolboxreset` performs the same updates as `rehash toolbox`, and also ensures the known files and classes list follows precedence rules for shadowed functions.

`rehash` **`toolboxcache`** performs the same updates as `rehash` **`toolbox`**, and also updates the cache file. This is the equivalent of clicking the **Update Toolbox Path Cache** button in General Preferences.

See Also

`addpath`, `clear`, `path`, `rmpath`

Toolbox Path Caching

rem

Purpose

Remainder after division

Syntax

```
R = rem(X,Y)
```

Description

`R = rem(X,Y)` if `Y ~= 0`, returns `X - n.*Y` where `n = fix(X./Y)`. If `Y` is not an integer and the quotient `X./Y` is within roundoff error of an integer, then `n` is that integer. By convention, `rem(X,0)` is `NaN`. The inputs `X` and `Y` must be real arrays of the same size, or real scalars.

Remarks

So long as operands `X` and `Y` are of the same sign, the statement `rem(X,Y)` returns the same result as does `mod(X,Y)`. However, for positive `X` and `Y`,

```
rem(-X,Y) = mod(-X,Y)-Y
```

The `rem` function returns a result that is between 0 and `sign(X)*abs(Y)`. If `Y` is zero, `rem` returns `NaN`.

See Also

`mod`

Purpose

Rename file on FTP server

Syntax

```
rename(f,'oldname','newname')
```

Description

`rename(f,'oldname','newname')` changes the name of the file `oldname` to `newname` in the current directory of the FTP server `f`, where `f` was created using `ftp`.

Examples

Connect to server `testsite`, view the contents, and change the name of `testfile.m` to `showresults.m`.

```
test=ftp('ftp.testsite.com');
dir(test)
.               ..       testfile.m
rename(test,'testfile.m','showresults.m')
dir(test)
.               ..       showresults.m
```

See Also

`dir (ftp)`, `delete (ftp)`, `ftp`, `mget (ftp)`, `mput (ftp)`

repmat

Purpose

Replicate and tile an array

Syntax

```
B = repmat(A,m,n)
B = repmat(A,[m n])
B = repmat(A,[m n p...])
repmat(A,m,n)
```

Description

`B = repmat(A,m,n)` creates a large matrix `B` consisting of an `m`-by-`n` tiling of copies of `A`. The statement `repmat(A,n)` creates an `n`-by-`n` tiling.

`B = repmat(A,[m n])` accomplishes the same result as `repmat(A,m,n)`.

`B = repmat(A,[m n p...])` produces a multidimensional (`m`-by-`n`-by-`p`-by-...) array composed of copies of `A`. `A` may be multidimensional.

`repmat(A,m,n)` when `A` is a scalar, produces an `m`-by-`n` matrix filled with `A`'s value. This can be much faster than `a*ones(m,n)` when `m` or `n` is large.

Examples

In this example, `repmat` replicates 12 copies of the second-order identity matrix, resulting in a "checkerboard" pattern.

```
B = repmat(eye(2),3,4)

B =
     1     0     1     0     1     0     1     0
     0     1     0     1     0     1     0     1
     1     0     1     0     1     0     1     0
     0     1     0     1     0     1     0     1
     1     0     1     0     1     0     1     0
     0     1     0     1     0     1     0     1
```

The statement `N = repmat(NaN,[2 3])` creates a 2-by-3 matrix of `NaN`s.

Purpose

Reset graphics object properties to their defaults

Syntax

```
reset(h)
```

Description

`reset(h)` resets all properties having factory defaults on the object identified by `h`. To see the list of factory defaults, use the statement

```
get(0,'factory')
```

If `h` is a figure, MATLAB does not reset `Position`, `Units`, `PaperPosition`, and `PaperUnits`. If `h` is an axes, MATLAB does not reset `Position` and `Units`.

Examples

`reset(gca)` resets the properties of the current axes.

`reset(gcf)` resets the properties of the current figure.

See Also

`cla`, `clf`, `gca`, `gcf`, `hold`

"Object Manipulation" for related functions

reshape

Purpose

Reshape array

Syntax

```
B = reshape(A,m,n)
B = reshape(A,m,n,p,...)
B = reshape(A,[m n p ...])
B = reshape(A,...,[],...)
B = reshape(A,siz)
```

Description

`B = reshape(A,m,n)` returns the `m`-by-`n` matrix `B` whose elements are taken column-wise from `A`. An error results if `A` does not have `m*n` elements.

`B = reshape(A,m,n,p,...)` or `B = reshape(A,[m n p ...])` returns an n-dimensional array with the same elements as `A` but reshaped to have the size `m`-by-`n`-by-`p`-by-... . The product of the specified dimensions, `m*n*p*...`, must be the same as `prod(size(A))`.

`B = reshape(A,...,[],...)` calculates the length of the dimension represented by the placeholder `[]`, such that the product of the dimensions equals `prod(size(A))`. The value of `prod(size(A))` must be evenly divisible by the product of the specified dimensions. You can use only one occurence of `[]`.

`B = reshape(A,siz)` returns an n-dimensional array with the same elements as `A`, but reshaped to `siz`, a vector representing the dimensions of the reshaped array. The quantity `prod(siz)` must be the same as `prod(size(A))`.

Examples

Reshape a 3-by-4 matrix into a 2-by-6 matrix.

```
A =
    1    4    7    10
    2    5    8    11
    3    6    9    12

B = reshape(A,2,6)

B =
    1    3    5    7    9   11
    2    4    6    8   10   12
B = reshape(A,2,[])
```

```
B =
     1     3     5     7     9    11
     2     4     6     8    10    12
```

See Also

`shiftdim`, `squeeze`

The colon operator `:`

residue

Purpose

Convert between partial fraction expansion and polynomial coefficients

Syntax

```
[r,p,k] = residue(b,a)
[b,a] = residue(r,p,k)
```

Description

The `residue` function converts a quotient of polynomials to pole-residue representation, and back again.

`[r,p,k] = residue(b,a)` finds the residues, poles, and direct term of a partial fraction expansion of the ratio of two polynomials, $b(s)$ and $a(s)$, of the form

$$\frac{b(s)}{a(s)} = \frac{b_1 s^m + b_2 s^{m-1} + b_3 s^{m-2} + \ldots + b_{m+1}}{a_1 s^n + a_2 s^{n-1} + a_3 s^{n-2} + \ldots + a_{n+1}}$$

where b_j and a_j are the `j`th elements of the input vectors `b` and `a`.

`[b,a] = residue(r,p,k)` converts the partial fraction expansion back to the polynomials with coefficients in `b` and `a`.

Definition

If there are no multiple roots, then

$$\frac{b(s)}{a(s)} = \frac{r_1}{s-p_1} + \frac{r_2}{s-p_2} + \ldots + \frac{r_n}{s-p_n} + k(s)$$

The number of poles `n` is

```
n = length(a)-1 = length(r) = length(p)
```

The direct term coefficient vector is empty if `length(b) < length(a)`; otherwise

```
length(k) = length(b)-length(a)+1
```

If `p(j) = ... = p(j+m-1)` is a pole of multiplicity `m`, then the expansion includes terms of the form

$$\frac{r_j}{s-p_j} + \frac{r_{j+1}}{(s-p_j)^2} + \ldots + \frac{r_{j+m-1}}{(s-p_j)^m}$$

Arguments

`b,a`	Vectors that specify the coefficients of the polynomials in descending powers of s
`r`	Column vector of residues
`p`	Column vector of poles
`k`	Row vector of direct terms

Algorithm

It first obtains the poles with `roots`. Next, if the fraction is nonproper, the direct term `k` is found using `deconv`, which performs polynomial long division. Finally, the residues are determined by evaluating the polynomial with individual roots removed. For repeated roots, `resi2` computes the residues at the repeated root locations.

Limitations

Numerically, the partial fraction expansion of a ratio of polynomials represents an ill-posed problem. If the denominator polynomial, $a(s)$, is near a polynomial with multiple roots, then small changes in the data, including roundoff errors, can make arbitrarily large changes in the resulting poles and residues. Problem formulations making use of state-space or zero-pole representations are preferable.

Examples

If the ratio of two polynomials is expressed as

$$\frac{b(s)}{a(s)} = \frac{5s^3 + 3s^2 - 2s + 7}{-4s^3 + 8s + 3}$$

then

```
b = [ 5 3 -2 7]
a = [-4 0 8 3]
```

and you can calculate the partial fraction expansion as

```
[r, p, k] = residue(b,a)

r =
   -1.4167
   -0.6653
    1.3320
```

```
p =
    1.5737
   -1.1644
   -0.4093

k =
   -1.2500
```

Now, convert the partial fraction expansion back to polynomial coefficients.

```
[b,a] = residue(r,p,k)

b =
   -1.2500   -0.7500    0.5000   -1.7500

a =
    1.0000   -0.0000   -2.0000   -0.7500
```

The result can be expressed as

$$\frac{b(s)}{a(s)} = \frac{-1.25s^3 - 0.75s^2 + 0.50s - 1.75}{s^3 - 2.00s - 0.75}$$

Note that the result is normalized for the leading coefficient in the denominator.

See Also

`deconv`, `poly`, `roots`

References

[1] Oppenheim, A.V. and R.W. Schafer, *Digital Signal Processing*, Prentice-Hall, 1975, p. 56.

Purpose

Restore the default search path

Syntax

```
restoredefaultpath
restoredefaultpath; matlabrc
```

Description

`restoredefaultpath` sets the search path to include only installed products from the MathWorks. Run `restoredefaultpath` if you are having problems with the search path. If `restoredefaultpath` seems to correct the problem, run `savepath`. Start MATLAB again to be sure the problem does not reappear.

`restoredefaultpath; matlabrc` sets the search path to include only installed products from the MathWorks and corrects path problems encountered during startup. Run `restoredefaultpath; matlabrc` if you are having problems with the search path and `restoredefaultpath` by itself does not correct the problem. After the problem seems to be resolved, run `savepath`. Start MATLAB again to be sure the problem does not reappear.

See Also

`addpath`, `path`, `pathdef`, `rmpath`, `savepath`

Search Path in the MATLAB User Guide

rethrow

Purpose

Reissue error

Syntax

```
rethrow(err)
```

Description

`rethrow(err)` reissues the error specified by `err`. The currently running M-file terminates and control returns to the keyboard (or to any enclosing `catch` block). The `err` argument must be a MATLAB structure containing the following character array fields.

Fieldname	Description
`message`	Text of the error message
`identifier`	Message identifier of the error message

See "Message Identifiers" in the MATLAB documentation for more information on the syntax and usage of message identifiers.

A convenient way to get a valid `err` structure for the last error issued is by using the `lasterror` function.

Examples

`rethrow` is usually used in conjunction with `try-catch` statements to reissue an error from a `catch` block after performing `catch`-related operations. For example,

```
try
   do_something
catch
   do_cleanup
   rethrow(lasterror)
end
```

See Also

`error`, `lasterror`, `lasterr`, `try`, `catch`, `dbstop`

Purpose

Return to the invoking function

Syntax

```
return
```

Description

`return` causes a normal return to the invoking function or to the keyboard. It also terminates keyboard mode.

Examples

If the determinant function were an M-file, it might use a `return` statement in handling the special case of an empty matrix, as follows:

```
function d = det(A)
%DET det(A) is the determinant of A.
if isempty(A)
    d = 1;
    return
else
    ...
end
```

See Also

`break`, `continue`, `disp`, `end`, `error`, `for`, `if`, `keyboard`, `switch`, `while`

rgb2hsv

Purpose

Convert RGB colormap to HSV colormap

Syntax

```
cmap = rgb2hsv(M)
```

Description

`cmap = rgb2hsv(M)` converts an RGB colormap `M` to an HSV colormap `cmap`. Both colormaps are *m*-by-3 matrices. The elements of both colormaps are in the range 0 to 1.

The columns of the input matrix `M` represent intensities of red, green, and blue, respectively. The columns of the output matrix `cmap` represent hue, saturation, and value, respectively.

`hsv_image = rgb2hsv(rgb_image)` converts the RGB image to the equivalent HSV image. RGB is an m-by-n-by-3 image array whose three planes contain the red, green, and blue components for the image. HSV is returned as an m-by-n-by-3 image array whose three planes contain the hue, saturation, and value components for the image.

See Also

`brighten`, `colormap`, `hsv2rgb`, `rgbplot`

"Color Operations" for related functions

Purpose

Plot colormap

Syntax

```
rgbplot(cmap)
```

Description

`rgbplot(cmap)` plots the three columns of `cmap`, where `cmap` is an *m*-by-3 colormap matrix. `rgbplot` draws the first column in red, the second in green, and the third in blue.

Examples

Plot the RGB values of the `copper` colormap.

```
rgbplot(copper)
```



See Also

`colormap`

"Color Operations" for related functions

ribbon

Purpose

Ribbon plot

Syntax

```
ribbon(Y)
ribbon(X,Y)
ribbon(X,Y,width)
ribbon(axes_handle,...)
h = ribbon(...)
```

Description

`ribbon(Y)` plots the columns of `Y` as separate three-dimensional ribbons using `X = 1:size(Y,1)`.

`ribbon(X,Y)` plots `X` versus the columns of `Y` as three-dimensional strips. `X` and `Y` are vectors of the same size or matrices of the same size. Additionally, `X` can be a row or a column vector, and `Y` a matrix with `length(X)` rows.

`ribbon(X,Y,width)` specifies the width of the ribbons. The default is `0.75`.

`ribbon(axes_handle,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = ribbon(...)` returns a vector of handles to surface graphics objects. `ribbon` returns one handle per strip.

Examples

Create a ribbon plot of the `peaks` function.

```
[x,y] = meshgrid(-3:.5:3,-3:.1:3);
z = peaks(x,y);
ribbon(y,z)
colormap hsv
```



See Also

`plot`, `plot3`, `surface`, `waterfall`

"Polygons and Surfaces" for related functions

rmappdata

Purpose

Remove application-defined data

Syntax

```
rmappdata(h,name)
```

Description

`rmappdata(h,name)` removes the application-defined data `name` from the object specified by handle `h`.

See Also

`getappdata`, `isappdata`, `setappdata`

Purpose

Remove directory

Graphical Interface

As an alternative to the `rmdir` function, use the delete feature in the Current Directory browser.

Syntax

```
rmdir('dirname')
rmdir('dirname','s')
[status,message,messageid] = rmdir('dirname','s')
```

Description

`rmdir('dirname')` removes the directory `dirname` from the current directory. If the directory is not empty, you must use the **s** argument. If `dirname` is not in the current directory, specify the relative path to the current directory or the full path for `dirname`.

`rmdir('dirname','s')` removes the directory `dirname` and its contents from the current directory. This removes all subdirectories and files in the current directory regardless of their write permissions.

`[status, message, messageid] = rmdir('dirname','s')` removes the directory `dirname` and its contents from the current directory, returning the status, a message, and the MATLAB error message ID (see `error` and `lasterr`). Here, `status` is `1` for success and is `0` for error, and `message`, `messageid`, and the **s** input argument are optional.

Examples

Remove Empty Directory

To remove `myfiles` from the current directory, where `myfiles` is empty, type

```
rmdir('myfiles')
```

If the current directory is `matlabr13/work`, and `myfiles` is in `d:/matlabr13/work/project/`, use the relative path to `myfiles`

```
rmdir('project/myfiles')
```

or the full path to `myfiles`

```
rmdir('d:/matlabr13/work/project/myfiles')
```

Remove Directory and All Contents

To remove `myfiles`, its subdirectories, and all files in the directories, assuming `myfiles` is in the current directory, type

```
rmdir('myfiles','s')
```

Remove Directory and Return Results

To remove `myfiles` from the current directory, type

```
[stat, mess, id]=rmdir('myfiles')
```

MATLAB returns

```
stat =
     0

mess =

The directory is not empty.

id =

MATLAB:RMDIR:OSError
```

indicating the directory `myfiles` is not empty.

To remove `myfiles` and its contents, run

```
[stat, mess]=rmdir('myfiles','s')
```

and MATLAB returns

```
stat =

     1

mess =

     ''
```

indicating `myfiles` and its contents were removed.

See Also

cd, copyfile, delete, dir, error, fileattrib, filebrowser, lasterr, mkdir, movefile

rmdir (ftp)

Purpose

Remove directory on FTP server

Syntax

```
rmdir(f,'dirname')
```

Description

`rmdir(f,'dirname')` removes the directory `dirname` from the current directory of the FTP server `f`, where `f` was created using `ftp`.

Examples

Connect to server `testsite`, view the contents of `testdir`, and remove the directory `newdir` from the directory `testdir`.

```
test=ftp('ftp.testsite.com');
cd(test,'testdir');
dir(test)
.               ..       newdir
dir(test,'newdir')
.               ..
rmdir(test,'newdir');
dir(test,'testdir')
.               ..
```

See Also

`cd (ftp)`, `delete (ftp)`, `dir (ftp)`, `ftp`, `mkdir (ftp)`

Purpose

Remove structure fields

Syntax

```
s = rmfield(s,'field')
s = rmfield(s,FIELDS)
```

Description

`s = rmfield(s,'field')` removes the specified field from the structure array `s`.

`s = rmfield(s,FIELDS)` removes more than one field at a time when `FIELDS` is a character array of field names or cell array of strings.

See Also

`fieldnames`, `setfield`, `getfield`, `isfield`, `orderfields`, dynamic field names

rmpath

Purpose

Remove directories from MATLAB search path

Graphical Interface

As an alternative to the `rmpath` function, use the **Set Path** dialog box. To open it, select **Set Path** from the **File** menu in the MATLAB desktop.

Syntax

```
rmpath('directory')
rmpath directory
```

Description

`rmpath('directory')` removes the specified directory from the current MATLAB search path. Use the full pathname for `directory`.

`rmpath directory` is the unquoted form of the syntax.

Examples

Remove `/usr/local/matlab/mytools` from the search path.

```
rmpath /usr/local/matlab/mytools
```

See Also

`addpath`, `cd`, `dir`, `genpath`, `matlabroot`, `partialpath`, `path`, `pathdef`, `pathsep`, `pathtool`, `rehash`, `restoredefaultpath`, `savepath`, `what`

Search Path

Purpose

Root object properties

Description

The root is a graphics object that corresponds to the computer screen. There is only one root object and it has no parent. The children of the root object are figures.

The root object exists when you start MATLAB; you never have to create it and you cannot destroy it. Use `set` and `get` to access the root properties.

See Also

`diary`, `echo`, `figure`, `format`, `gcf`, `get`, `set`

Object Hierarchy



Root Properties

Modifying Properties

You can set and query graphics object properties in two ways:

- The Property Editor is an interactive tool that enables you to see and change object property values.
- The `set` and `get` commands enable you to set and query the values of properties.

To change the default values of properties, see Setting Default Property Values.

Root Properties

This section lists property names along with the type of values each accepts. Curly braces { } enclose default values.

`BusyAction` `cancel | {queue}`

Not used by the root object.

`ButtonDownFcn` string

Not used by the root object.

`CallbackObject` handle (read only)

Handle of current callback's object. This property contains the handle of the object whose callback routine is currently executing. If no callback routines are executing, this property contains the empty matrix [ ]. See also the `gco` command.

`CaptureMatrix` (obsolete)

This property has been superseded by the `getframe` command.

`CaptureRect` (obsolete)

This property has been superseded by the `getframe` command.

`Children` vector of handles

Handles of child objects. A vector containing the handles of all nonhidden figure objects (see `HandleVisibility` for more information). You can change the order of the handles and thereby change the stacking order of the figures on the display.

`Clipping` `{on} | off`

Clipping has no effect on the root object.

CommandWindowSize [columns rows]

Current size of command window. This property contains the size of the MATLAB command window in a two-element vector. The first element is the number of columns wide and the second element is the number of rows tall.

CreateFcn

The root does not use this property.

CurrentFigure figure handle

Handle of the current figure window, which is the one most recently created, clicked in, or made current with the statement

```
figure(h)
```

which restacks the figure to the top of the screen, or

```
set(0,'CurrentFigure',h)
```

which does not restack the figures. In these statements, `h` is the handle of an existing figure. If there are no figure objects,

```
get(0,'CurrentFigure')
```

returns the empty matrix. Note, however, that `gcf` always returns a figure handle, and creates one if there are no figure objects.

DeleteFcn string

This property is not used, because you cannot delete the root object.

Diary `on | {off}`

Diary file mode. When this property is `on`, MATLAB maintains a file (whose name is specified by the `DiaryFile` property) that saves a copy of all keyboard input and most of the resulting output. See also the `diary` command.

DiaryFile string

Diary filename. The name of the diary file. The default name is `diary`.

Echo `on | {off}`

Script echoing mode. When `Echo` is `on`, MATLAB displays each line of a script file as it executes. See also the `echo` command.

ErrorMessage string

Text of last error message. This property contains the last error message issued by MATLAB.

FixedWidthFontName `font name`

Fixed-width font to use for axes, text, and uicontrols whose `FontName` *is set to* `FixedWidth`. MATLAB uses the font name specified for this property as the value for axes, text, and uicontrol `FontName` properties when their `FontName` property is set to `FixedWidth`. Specifying the font name with this property eliminates the need to hardcode font names in MATLAB applications and thereby enables these applications to run without modification in locales where non-ASCII character sets are required. In these cases, MATLAB attempts to set the value of `FixedWidthFontName` to the correct value for a given locale.

MATLAB application developers should not change this property, but should create axes, text, and uicontrols with `FontName` properties set to `FixedWidth` when they want to use a fixed-width font for these objects.

MATLAB end users can set this property if they do not want to use the preselected value. In locales where Latin-based characters are used, Courier is the default.

Format `short | {shortE} | long | longE | bank | hex | + | rat`

Output format mode. This property sets the format used to display numbers. See also the `format` command.

- `short` — Fixed-point format with 5 digits
- `shortE` — Floating-point format with 5 digits
- `shortG` — Fixed- or floating-point format displaying as many significant figures as possible with 5 digits
- `long` — Scaled fixed-point format with 15 digits
- `longE` — Floating-point format with 15 digits
- `longG` — Fixed- or floating-point format displaying as many significant figures as possible with 15 digits
- `bank` — Fixed-format of dollars and cents
- `hex` — Hexadecimal format

- + — Displays + and – symbols
- rat — Approximation by ratio of small integers

FormatSpacing compact | {loose}

Output format spacing (see also format command).

- compact — Suppress extra line feeds for more compact display.
- loose — Display extra line feeds for a more readable display.

HandleVisibility {on} | callback | off

This property is not useful on the root object.

HitTest {on} | off

This property is not useful on the root object.

Interruptible {on} | off

This property is not useful on the root object.

Language string

System environment setting.

MonitorPosition [x y width height;x y width height]

Width and height of primary and secondary monitors, in pixels. This property contains the width and height of each monitor connnected to your computer. The x and y values for the primary monitor are 0, 0 and the width and height of the monitor are specified in pixels.

The secondary monitor position is specified as

```
x = primary monitor width + 1
y = primary monitor height + 1
```

Querying the value of the figure MonitorPosition on a multiheaded system returnes the position for each monitor on a separate line.

```
v = get(0,'MonitorPosition')
v =
    x y width height % Primary monitor
    x y width height % Secondary monitor
```

Note that MATLAB sets the value of the ScreenSize property to the combined size of the monitors.

Parent handle

Handle of parent object. This property always contains the empty matrix, because the root object has no parent.

PointerLocation `[x,y]`

Current location of pointer. A vector containing the *x*- and *y*-coordinates of the pointer position, measured from the lower left corner of the screen. You can move the pointer by changing the values of this property. The `Units` property determines the units of this measurement.

This property always contains the instantaneous pointer location, even if the pointer is not in a MATLAB window. A callback routine querying the `PointerLocation` can get a different value than the location of the pointer when the callback was triggered. This difference results from delays in callback execution caused by competition for system resources.

PointerWindow handle (read only)

Handle of window containing the pointer. MATLAB sets this property to the handle of the figure window containing the pointer. If the pointer is not in a MATLAB window, the value of this property is 0. A callback routine querying the `PointerWindow` can get the wrong window handle if you move the pointer to another window before the callback executes. This error results from delays in callback execution caused by competition for system resources.

RecursionLimit integer

Number of nested M-file calls. This property sets a limit to the number of nested calls to M-files MATLAB will make before stopping (or potentially running out of memory). By default the value is set to a large value. Setting this property to a smaller value (something like 150, for example) should prevent MATLAB from running out of memory and will instead cause MATLAB to issue an error when the limit is reached.

ScreenDepth bits per pixel

Screen depth. The depth of the display bitmap (i.e., the number of bits per pixel). The maximum number of simultaneously displayed colors on the current graphics device is 2 raised to this power.

`ScreenDepth` supersedes the `BlackAndWhite` property. To override automatic hardware checking, set this property to `1`. This value causes MATLAB to assume the display is monochrome. This is useful if MATLAB is running on

color hardware but is being displayed on a monochrome terminal. Such a situation can cause MATLAB to determine erroneously that the display is color.

`ScreenSize` four-element rectangle vector (read only)

Screen size. A four-element vector,

```
[left,bottom,width,height]
```

that defines the display size. `left` and `bottom` are `0` for all `Units` except `pixels`, in which case `left` and `bottom` are `1`. `width` and `height` are the screen dimensions in units specified by the `Units` property.

`Selected` `on | off`

This property has no effect on the root level.

`SelectionHighlight` `{on} | off`

This property has no effect on the root level.

`ShowHiddenHandles` `on | {off}`

Show or hide handles marked as hidden. When set to `on`, this property disables handle hiding and exposes all object handles regardless of the setting of an object's `HandleVisibility` property. When set to `off`, all objects so marked remain hidden within the graphics hierarchy.

`Tag` string

User-specified object label. The `Tag` property provides a means to identify graphics objects with a user-specified label. While it is not necessary to identify the root object with a tag (since its handle is always `0`), you can use this property to store any string value that you can later retrieve using `set`.

`Type` string (read only)

Class of graphics object. For the root object, `Type` is always `'root'`.

`UIContextMenu` handle

This property has no effect on the root level.

`Units` `{pixels} | normalized | inches | centimeters | points | characters`

Unit of measurement. This property specifies the units MATLAB uses to interpret size and location data. All units are measured from the lower left

corner of the screen. Normalized units map the lower left corner of the screen to (0,0) and the upper right corner to (1.0,1.0). `inches`, `centimeters`, and `points` are absolute units (one point equals 1/72 of an inch). Characters are units defined by characters from the default system font; the width of one unit is the width of the letter x, the height of one character is the distance between the baselines of two lines of text.

This property affects the `PointerLocation` and `ScreenSize` properties. If you change the value of `Units`, it is good practice to return it to its default value after completing your operation, so as not to affect other functions that assume `Units` is set to the default value.

`UserData` matrix

User-specified data. This property can be any data you want to associate with the root object. MATLAB does not use this property, but you can access it using the `set` and `get` functions.

`Visible` `{on} | off`

Object visibility. This property has no effect on the root object.

Purpose

Polynomial roots

Syntax

```
r = roots(c)
```

Description

`r = roots(c)` returns a column vector whose elements are the roots of the polynomial `c`.

Row vector `c` contains the coefficients of a polynomial, ordered in descending powers. If `c` has `n+1` components, the polynomial it represents is $c_1 s^n + \ldots + c_n s + c_{n+1}$.

Remarks

Note the relationship of this function to `p = poly(r)`, which returns a row vector whose elements are the coefficients of the polynomial. For vectors, `roots` and `poly` are inverse functions of each other, up to ordering, scaling, and roundoff error.

Examples

The polynomial $s^3 - 6s^2 - 72s - 27$ is represented in MATLAB as

```
p = [1 -6 -72 -27]
```

The roots of this polynomial are returned in a column vector by

```
r = roots(p)

r =
    12.1229
    -5.7345
    -0.3884
```

Algorithm

The algorithm simply involves computing the eigenvalues of the companion matrix:

```
A = diag(ones(n-1,1),-1);
A(1,:) = -c(2:n+1)./c(1);
eig(A)
```

It is possible to prove that the results produced are the exact eigenvalues of a matrix within roundoff error of the companion matrix `A`, but this does not mean that they are the exact roots of a polynomial with coefficients within roundoff error of those in `c`.

See Also `fzero`, `poly`, `residue`

Purpose

Angle histogram

Syntax

```
rose(theta)
rose(theta,x)
rose(theta,nbins)
rose(axes_handles,...)
h = rose(...)
[tout,rout] = rose(...)
```

Description

`rose` creates an angle histogram, which is a polar plot showing the distribution of values grouped according to their numeric range. Each group is shown as one bin.

`rose(theta)` plots an angle histogram showing the distribution of `theta` in 20 angle bins or less. The vector `theta`, expressed in radians, determines the angle of each bin from the origin. The length of each bin reflects the number of elements in `theta` that fall within a group, which ranges from 0 to the greatest number of elements deposited in any one bin.

`rose(theta,x)` uses the vector `x` to specify the number and the locations of bins. `length(x)` is the number of bins and the values of `x` specify the center angle of each bin. For example, if `x` is a five-element vector, `rose` distributes the elements of `theta` in five bins centered at the specified `x` values.

`rose(theta,nbins)` plots `nbins` equally spaced bins in the range `[0, 2*pi]`. The default is `20`.

`rose(axes_handle,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = rose(...)` returns the handles of the line objects used to create the graph.

`[tout,rout] = rose(...)` returns the vectors `tout` and `rout` so `polar(tout,rout)` generates the histogram for the data. This syntax does not generate a plot.

Example

Create a rose plot showing the distribution of 50 random numbers.

```
theta = 2*pi*rand(1,50);
rose(theta)
```



See Also

`compass`, `feather`, `hist`, `line`, `polar`

"Histograms" for related functions

Histograms in Polar Coordinates for another example

Purpose

Classic symmetric eigenvalue test problem

Syntax

```
A = rosser
```

Description

`A = rosser` returns the Rosser matrix. This matrix was a challenge for many matrix eigenvalue algorithms. But LAPACK's `DSYEV` routine used in MATLAB has no trouble with it. The matrix is 8-by-8 with integer elements. It has:

- A double eigenvalue
- Three nearly equal eigenvalues
- Dominant eigenvalues of opposite sign
- A zero eigenvalue
- A small, nonzero eigenvalue

Examples

```
rosser

ans =

   611   196  -192   407    -8   -52   -49    29
   196   899   113  -192   -71   -43    -8   -44
  -192   113   899   196    61    49     8    52
   407  -192   196   611     8    44    59   -23
    -8   -71    61     8   411  -599   208   208
   -52   -43    49    44  -599   411   208   208
   -49    -8     8    59   208   208    99  -911
    29   -44    52   -23   208   208  -911    99
```

rot90

Purpose

Rotate matrix 90°

Syntax

```
B = rot90(A)
B = rot90(A,k)
```

Description

`B = rot90(A)` rotates matrix `A` counterclockwise by 90 degrees.

`B = rot90(A,k)` rotates matrix `A` counterclockwise by `k*90` degrees, where `k` is an integer.

Examples

The matrix

```
X =
     1     2     3
     4     5     6
     7     8     9
```

rotated by 90 degrees is

```
Y = rot90(X)
Y =
     3     6     9
     2     5     8
     1     4     7
```

See Also

`flipdim`, `fliplr`, `flipud`

Purpose

Rotate object about a specified direction

Syntax

```
rotate(h,direction,alpha)
rotate(...,origin)
```

Description

The `rotate` function rotates a graphics object in three-dimensional space, according to the right-hand rule.

`rotate(h,direction,alpha)` rotates the graphics object `h` by `alpha` degrees. `direction` is a two- or three-element vector that describes the axis of rotation in conjunction with the origin.

`rotate(...,origin)` specifies the origin of the axis of rotation as a three-element vector. The default origin is the center of the plot box.

Remarks

The graphics object you want rotated must be a child of the same axes. The object's data is modified by the rotation transformation. This is in contrast to `view` and `rotate3d`, which only modify the viewpoint.

The axis of rotation is defined by an origin and a point *P* relative to the origin. *P* is expressed as the spherical coordinates `[theta phi]` or as Cartesian coordinates.



The two-element form for `direction` specifies the axis direction using the spherical coordinates `[theta phi]`. `theta` is the angle in the *x*-*y* plane counterclockwise from the positive *x*-axis. `phi` is the elevation of the direction vector from the *x*-*y* plane.



The three-element form for `direction` specifies the axis direction using Cartesian coordinates. The direction vector is the vector from the origin to (X,Y,Z).

Examples

Rotate a graphics object 180° about the *x*-axis.

```
h = surf(peaks(20));
rotate(h,[1 0 0],180)
```

Rotate a surface graphics object 45° about its center in the *z* direction.

```
h = surf(peaks(20));
zdir = [0 0 1];
center = [10 10 0];
rotate(h,zdir,45,center)
```

Remarks

`rotate` changes the `Xdata`, `Ydata`, and `Zdata` properties of the appropriate graphics object.

See Also

`rotate3d`, `sph2cart`, `view`

The axes `CameraPosition`, `CameraTarget`, `CameraUpVector`, `CameraViewAngle`

"Object Manipulation" for related functions

Purpose

Rotate 3-D view using mouse

Syntax

```
rotate3d on
rotate3d off
rotate3d
rotate3d(figure_handle,...)
rotate3d(axes_handle,...)
```

Description

`rotate3d on` enables mouse-base rotation on all axes within the current figure.

`rotate3d off` disables interactive axes rotation in the current figure.

`rotate3d` toggles interactive axes rotation in the current figure.

`rotate3d(figure_handle,...)` enables rotation within the specified figure instead of the current figure.

`rotate3d(axes_handle,...)` enables rotation only in the specified axes.

Using rotate3d

When enabled, `rotate3d` provides continuous rotation of axes and the objects it contains through mouse movement. A numeric readout appears in the lower left corner of the figure during rotation, showing the current azimuth and elevation of the axes. Releasing the mouse button removes the animated box and the readout.

You can also enable 3-D rotation from the figure **Tools** menu or the figure toolbar.

See Also

`camorbit`, `rotate`, `view`

Object Manipulation for related functions

round

Purpose

Round to nearest integer

Syntax

```
Y = round(X)
```

Description

`Y = round(X)` rounds the elements of `X` to the nearest integers. For complex `X`, the imaginary and real parts are rounded independently.

Examples

```
a = [-1.9, -0.2, 3.4, 5.6, 7.0, 2.4+3.6i]

a =
  Columns 1 through 4
  -1.9000           -0.2000            3.4000            5.6000
  Columns 5 through 6
   7.0000             2.4000 + 3.6000i

round(a)

ans =
  Columns 1 through 4
  -2.0000                 0            3.0000            6.0000
  Columns 5 through 6
   7.0000             2.0000 + 4.0000i
```

See Also

`ceil`, `fix`, `floor`

Purpose

Reduced row echelon form

Syntax

```
R = rref(A)
[R,jb] = rref(A)
[R,jb] = rref(A,tol)
```

Description

`R = rref(A)` produces the reduced row echelon form of `A` using Gauss Jordan elimination with partial pivoting. A default tolerance of (`max(size(A))*eps *norm(A,inf)`) tests for negligible column elements.

`[R,jb] = rref(A)` also returns a vector `jb` such that:

- `r = length(jb)` is this algorithm's idea of the rank of `A`.
- `x(jb)` are the pivot variables in a linear system `Ax = b`.
- `A(:,jb)` is a basis for the range of `A`.
- `R(1:r,jb)` is the `r`-by-`r` identity matrix.

`[R,jb] = rref(A,tol)` uses the given tolerance in the rank tests.

Roundoff errors may cause this algorithm to compute a different value for the rank than `rank`, `orth` and `null`.

Note The demo `rrefmovie(A)` enables you to sequence through the iterations of the algorithm.

Examples

Use `rref` on a rank-deficient magic square:

```
A = magic(4), R = rref(A)

A =
   16    2    3   13
    5   11   10    8
    9    7    6   12
    4   14   15    1
```

```
R =
     1     0     0     1
     0     1     0     3
     0     0     1    -3
     0     0     0     0
```

See Also inv, lu, rank

Purpose

Convert real Schur form to complex Schur form

Syntax

```
[U,T] = rsf2csf(U,T)
```

Description

The *complex Schur form* of a matrix is upper triangular with the eigenvalues of the matrix on the diagonal. The *real Schur form* has the real eigenvalues on the diagonal and the complex eigenvalues in 2-by-2 blocks on the diagonal.

`[U,T] = rsf2csf(U,T)` converts the real Schur form to the complex form.

Arguments `U` and `T` represent the unitary and Schur forms of a matrix `A`, respectively, that satisfy the relationships: `A = U*T*U'` and `U'*U = eye(size(A))`. See `schur` for details.

Examples

Given matrix `A`,

```
 1     1     1     3
 1     2     1     1
 1     1     3     1
-2     1     1     4
```

with the eigenvalues

```
4.8121    1.9202 + 1.4742i    1.9202 + 1.4742i    1.3474
```

Generating the Schur form of `A` and converting to the complex Schur form

```
[u,t] = schur(A);
[U,T] = rsf2csf(u,t)
```

yields a triangular matrix `T` whose diagonal (underlined here for readability) consists of the eigenvalues of `A`.

```
U =

-0.4916       -0.2756 - 0.4411i    0.2133 + 0.5699i   -0.3428
-0.4980       -0.1012 + 0.2163i   -0.1046 + 0.2093i    0.8001
-0.6751        0.1842 + 0.3860i   -0.1867 - 0.3808i   -0.4260
-0.2337        0.2635 - 0.6481i    0.3134 - 0.5448i    0.2466
```

```
T =

    4.8121         -0.9697 + 1.0778i   -0.5212 + 2.0051i   -1.0067
         0          1.9202 + 1.4742i    2.3355              0.1117 + 1.6547i
         0               0              1.9202 - 1.4742i    0.8002 + 0.2310i
         0               0                   0              1.3474
```

See Also

schur

2save

Purpose

Save workspace variables on disk

Graphical Interface

As an alternative to the `save` function, select **Save Workspace As** from the **File** menu in the MATLAB desktop, or use the Workspace browser.

Syntax

```
save
save('filename')
save('filename', 'var1', 'var2', ...)
save('filename', '-struct', 's')
save('filename', '-struct', 's', 'f1', 'f2', ...)
save('-regexp', expr1, expr2, ...)
save('..., 'format')
save filename var1 var2 ...
```

Description

`save` by itself stores all workspace variables in a binary format in the current directory in a file named `matlab.mat`. Retrieve the data with `load`. MAT-files are double-precision, binary, MATLAB format files. They can be created on one machine and later read by MATLAB on another machine with a different floating-point format, retaining as much accuracy and range as the different formats allow. They can also be manipulated by other programs external to MATLAB.

`save('filename')` stores all workspace variables in the current directory in `filename.mat`. To save to another directory, use the full pathname for the `filename`. If `filename` is the special string `stdio`, the `save` command sends the data as standard output.

`save('filename', 'var1', 'var2', ...)` saves only the specified workspace variables in `filename.mat`. Use the `*` wildcard to save only those variables that match the specified pattern. For example, `save('A*')` saves all variables that start with `A`.

`save('filename', '-struct', 's')` saves all fields of the scalar structure `s` as individual variables within the file `filename`.

`save('filename', '-struct', 's', 'f1', 'f2', ...)` saves as individual variables only those structure fields specified (`s.f1`, `s.f2`, `...`).

`save('-regexp', expr1, expr2, ...)` saves those variables that match any of the regular expressions `expr1`, `expr2`, etc.

`save(..., 'format')` enables you to make use of other data formats available with the `save` function. See the following table.

Format	How Data Is Stored
`-append`	The specified existing MAT-file, appended to the end. See Remarks, below.
`-ascii`	8-digit ASCII format
`-ascii -double`	16-digit ASCII format
`-ascii -tabs`	Delimits with tabs
`-ascii -double -tabs`	16-digit ASCII format, tab delimited
`-mat`	Binary MAT-file form (default)
`-v4`	A format that MATLAB Version 4 can open
`-v6`	A format that MATLAB Version 6 and earlier can open

`save filename var1 var2 ...` is the command form of the syntax.

Remarks

By default, MATLAB compresses the data it saves to MAT-files. MATLAB also uses Unicode character encoding when saving character data. Specify the `-v6` option if you want to disable both of these features for a particular `save` operation. If you save data to a MAT-file that you intend to load using MATLAB Version 6 or earlier, then you must specify the `-v6` option when saving.

To override the compression and Unicode setting for all of your MATLAB sessions, use the **Preferences** dialog box. Open the **Preferences** dialog and select **General** and then **MAT-Files**. To disable data compression and Unicode encoding, click **Ensure backward compatibility (-v6)**. To turn these features back on, click **Use default features (Unicode and compression)**. See "General Preferences for MATLAB" in the Desktop Tools and Development Environment documentation for more information.

For information on any of the following topics related to saving to MAT-files, see “Exporting Data to MAT-Files” in the “MATLAB Programming” documentation:

- Appending variables to an existing MAT-file
- Compressing data in the MAT-file
- Saving in ASCII format
- Saving in MATLAB Version 4 format
- Saving with Unicode character encoding
- Data storage requirements
- Saving from external programs

Examples

Example 1

Save all variables from the workspace in binary MAT-file `test.mat`:

```
save test.mat
```

Example 2

Save variables `p` and `q` in binary MAT-file `test.mat`:

```
savefile = 'test.mat';
p = rand(1, 10);
q = ones(10);
save(savefile, 'p', 'q')
```

Example 3

Save the variables `vol` and `temp` in ASCII format to a file named `june10`:

```
save('d:\mymfiles\june10','vol','temp','-ASCII')
```

Example 4

Save the fields of structure `s1` as individual variables rather than as an entire structure.

```
s1.a = 12.7;  s1.b = {'abc', [4 5; 6 7]};  s1.c = 'Hello!';
save newstruct.mat -struct s1;
clear
```

Check what was saved to `newstruct.mat`:

```
whos -file newstruct.mat
  Name      Size                    Bytes  Class

  a         1x1                         8  double array
  b         1x2                       158  cell array
  c         1x6                        12  char array

Grand total is 16 elements using 178 bytes
```

Read only the `b` field into the MATLAB workspace.

```
str = load('newstruct.mat', 'b')
str =
    b: {'abc'  [2x2 double]}
```

Example 5

Using regular expressions, save in MAT-file `mydata.mat` those variables with names that begin with `Mon`, `Tue`, or `Wed`:

```
save('mydata', '-regexp', '^Mon|^Tue|^Wed');
```

Here is another way of doing the same thing. In this case, there are three separate expression arguments:

```
save('mydata', '-regexp', '^Mon', '^Tue', '^Wed');
```

Example 6

Save a 3000-by-3000 matrix uncompressed to file `c1.mat`, and compressed to file `c2.mat`. The compressed file uses about one quarter the disk space required to store the uncompressed data:

```
x = ones(3000);
y = uint32(rand(3000) * 100);

save c1 x y
save c2 x y -compress

d1 = dir('c1.mat');
d2 = dir('c2.mat');

d1.bytes
```

```
ans =
    45000240          % Size of the uncompressed data
d2.bytes
ans =
    11985634          % Size of the compressed data

d2.bytes/d1.bytes
ans =
    0.2663            % Ratio of compressed to uncompressed
```

Example 7

This example is similar to the last one, except that it saves one variable uncompressed, and then a second variable compressed to the same MAT-file. It then loads this data back into the MATLAB workspace:

```
x = ones(3000);
y = uint32(rand(3000) * 100);

save c1 x;
save c1 y -compress -append;

d = dir('c1.mat');
d.bytes
ans =
    20952950

clear
load c1
whos
  Name      Size                    Bytes  Class

  x      3000x3000              72000000  double array
  y      3000x3000              36000000  uint32 array

Grand total is 18000000 elements using 108000000 bytes
```

See Also

load, clear, diary, fprintf, fwrite, who, workspace

Purpose

Save figure or model using specified format

Syntax

```
saveas(h,'filename.ext')
saveas(h,'filename','format')
```

Description

`saveas(h,'filename.ext')` saves the figure or model with the handle `h` to the file `filename.ext`. The format of the file is determined by the extension, `ext`. Allowable values for `ext` are listed in this table.

ext Values	Format
`ai`	Adobe Illustrator '88
`bmp`	Windows bitmap
`emf`	Enhanced metafile
`eps`	EPS Level 1
`fig`	MATLAB figure (invalid for Simulink models)
`jpg`	JPEG image (invalid for Simulink models)
`m`	MATLAB M-file (invalid for Simulink models)
`pbm`	Portable bitmap
`pcx`	Paintbrush 24-bit
`pgm`	Portable Graymap
`png`	Portable Network Graphics
`ppm`	Portable Pixmap
`tif`	TIFF image, compressed

`saveas(h,'filename','format')` saves the figure or model with the handle `h` to the file called `filename` using the specified `format`. The filename can have an extension, but the extension is not used to define the file format. If no extension is specified, the standard extension corresponding to the specified format is automatically appended to the filename.

Allowable values for `format` are the extensions in the table above and the device types supported by `print`. The `print` device types include the formats listed in the table of extensions above as well as additional file formats. Use an extension from the table above or from the list of device types supported by `print`. When using the `print` device type to specify `format` for `saveas`, do not use the prefixed `-d`.

Remarks

You can use `open` to open files saved using `saveas` with an `m` or `fig` extension. Other formats are not supported by `open`. The **Save As** dialog box you access from the figure window's **File** menu uses `saveas`, limiting the file extensions to `m` and `fig`. The **Export** dialog box you access from the figure window's **File** menu uses `saveas` with the `format` argument.

Examples

Example 1 – Specify File Extension

Save the current figure that you annotated using the Plot Editor to a file named `pred_prey` using the MATLAB `fig` format. This allows you to open the file `pred_prey.fig` at a later time and continue editing it with the Plot Editor.

```
saveas(gcf,'pred_prey.fig')
```

Example 2 – Specify File Format but No Extension

Save the current figure, using Adobe Illustrator format, to the file `logo`. Use the `ai` extension from the above table to specify the format. The file created is `logo.ai`.

```
saveas(gcf,'logo', 'ai')
```

This is the same as using the Adobe Illustrator format from the print devices table, which is `-dill`; use `doc print` or `help print` to see the table for print device types. The file created is `logo.ai`. MATLAB automatically appends the `ai` extension for an Illustrator format file because no extension was specified.

```
saveas(gcf,'logo', 'ill')
```

Example 3 – Specify File Format and Extension

Save the current figure to the file `star.eps` using the Level 2 Color PostScript format. If you use `doc print` or `help print`, you can see from the table for print device types that the device type for this format is `-dpsc2`. The file created is `star.eps`.

```
saveas(gcf,'star.eps', 'psc2')
```

In another example, save the current model to the file `trans.tiff` using the TIFF format with no compression. From the table for print device types, you can see that the device type for this format is `-dtiffn`. The file created is `trans.tiff`.

```
saveas(gcf,'trans.tiff', 'tiffn')
```

See Also

`open`, `print`

"Printing" for related functions

Purpose

Save an object to a MAT-file

Syntax

```
B = saveobj(A)
```

Description

`B = saveobj(A)` is called by the MATLAB `save` function when object `A` is saved to a MAT-file. This call executes the `saveobj` method for the object's class, if such a method exists. The return value `B` is subsequently used by `save` to populate the MAT-file.

When you issue a `save` command on an object, MATLAB looks for a method called `saveobj` in the class directory. You can overload this method to modify the object before the save operation. For example, you could define a `saveobj` method that saves related data along with the object.

Remarks

`saveobj` can be overloaded only for user objects. `save` will not call `saveobj` for a built-in datatype, such as `double`, even if `@double/saveobj` exists.

`saveobj` will be separately invoked for each object to be saved.

A child object does not inherit the `saveobj` method of its parent class. To implement `saveobj` for any class, including a class that inherits from a parent, you must define a `saveobj` method within that class directory.

Examples

The following example shows a `saveobj` method written for the `portfolio` class. The method determines if a `portfolio` object has already been assigned an account number from a previous `save` operation. If not, `saveobj` calls `getAccountNumber` to obtain the number and assigns it to the `account_number` field. The contents of `b` is saved to the MAT-file.

```
function b = saveobj(a)
if isempty(a.account_number)
    a.account_number = getAccountNumber(a);
end
b = a;
```

See Also

`save`, `load`, `loadobj`

savepath

Purpose

Save current MATLAB search path to `pathdef.m` file

Graphical Interface

As an alternative to the `savepath` function, use the **Set Path** dialog box. To open it, select **Set Path** from the **File** menu in the MATLAB desktop.

Syntax

```
savepath
savepath newfile
```

Description

`savepath` saves the current MATLAB search path to `pathdef.m`. It returns

`0`	If the file was saved successfully
`1`	If the save failed

`savepath newfile` saves the current MATLAB search path to `newfile`, where `newfile` is in the current directory or is a relative or absolute path.

Examples

The statement

```
savepath myfiles/pathdef.m
```

saves the current search path to the file `pathdef.m`, which is located in the `myfiles` directory in the MATLAB current directory.

Consider using `savepath` in your MATLAB `finish.m` file to save the path when you exit MATLAB.

See Also

`addpath`, `cd`, `dir`, `finish`, `genpath`, `matlabroot`, `partialpath`, `pathdef`, `pathsep`, `pathtool`, `rehash`, `restoredefaultpath`, `rmpath`, `savepath`, `startup`, `what`

Search Path

Purpose

2-D scatter/bubble graph

Syntax

```
scatter(X,Y,S,C)
scatter(X,Y)
scatter(X,Y,S)
scatter(...,markertype)
scatter(...,'filled')
scatter(...,'PropertyName',propertyvalue)
scatter(axes_handle,...)
h = scatter(...)
hlines = scatter('v6',...)
```

Description

`scatter(X,Y,S,C)` displays colored circles at the locations specified by the vectors `X` and `Y` (which must be the same size).

`S` determines the area of each marker (specified in points^2). `S` can be a vector the same length as `X` and `Y` or a scalar. If `S` is a scalar, MATLAB draws all the markers the same size.

`C` determines the colors of each marker. When `C` is a vector the same length as `X` and `Y`, the values in `C` are linearly mapped to the colors in the current colormap. When `C` is a `length(X)`-by-3 matrix, it specifies the colors of the markers as RGB values. `C` can also be a color string (see `ColorSpec` for a list of color string specifiers).

`scatter(X,Y)` draws the markers in the default size and color.

`scatter(X,Y,S)` draws the markers at the specified sizes (`S`) with a single color. This type of graph is also known as a bubble plot.

`scatter(...,markertype)` uses the marker type specified instead of `'o'` (see `LineSpec` for a list of marker specifiers).

`scatter(...,'filled')` fills the markers.

`scatter(...,'PropertyName',propertyvalue)` creates the scatter graph, applying the specified property settings. See scattergroup properties for a description of properties.

`scatter(axes_handles,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = scatter(...)` returns the handle of the scattergroup object created.

Backward Compatible Version

`hpatch = scatter('v6',...)` returns the handles to the patch objects created by `scatter` (see Patch Properties for a list of properties you can specify using the object handles and `set`).

See Plot Objects and Backward Compatibility for more information.

Examples

```
load seamount
scatter(x,y,5,z)
```



See Also

`scatter3`, `plot3`

“Scatter/Bubble Plots” for related functions

See Triangulation and Interpolation of Scatter Data for related information.

See “Scattergroup Properties” for property descriptions

Purpose

3-D scatter plot

Syntax

```
scatter3(X,Y,Z,S,C)
scatter3(X,Y,Z)
scatter3(X,Y,Z,S)
scatter3(...,markertype)
scatter3(...,'filled')
h = scatter3(...,)
hpatch = scatter3('v6',...)
```

Description

`scatter3(X,Y,Z,S,C)` displays colored circles at the locations specified by the vectors `X`, `Y`, and `Z` (which must all be the same size).

`S` determines the size of each marker (specified in points). `S` can be a vector the same length as `X`, `Y`, and `Z` or a scalar. If `S` is a scalar, MATLAB draws all the markers the same size.

`C` determines the colors of each marker. When `C` is a vector the same length as `X`, `Y`, and `Z`, the values in `C` are linearly mapped to the colors in the current colormap. When `C` is a `length(X)`-by-3 matrix, it specifies the colors of the markers as RGB values. `C` can also be a color string (see `ColorSpec` for a list of color string specifiers).

`scatter3(X,Y,Z)` draws the markers in the default size and color.

`scatter3(X,Y,Z,S)` draws the markers at the specified sizes (`S`) with a single color.

`scatter3(...,markertype)` uses the marker type specified instead of `'o'` (see `LineSpec` for a list of marker specifiers).

`scatter3(...,'filled')` fills the markers.

`h = scatter3(...)` returns handles to the scattergroup objects created by `scatter3`. See "Scattergroup Properties" for property descriptions.

Backward Compatible Version

`hpatch = scatter3('v6',...)` returns the handles to the patch objects created by `scatter3` (see Patch for a list of properties you can specify using the object handles and `set`).

Remarks

Use `plot3` for single color, single marker size 3-D scatter plots.

Examples

```
[x,y,z] = sphere(16);
X = [x(:)*.5 x(:)*.75 x(:)];
Y = [y(:)*.5 y(:)*.75 y(:)];
Z = [z(:)*.5 z(:)*.75 z(:)];
S = repmat([1 .75 .5]*10,prod(size(x)),1);
C = repmat([1 2 3],prod(size(x)),1);
scatter3(X(:),Y(:),Z(:),S(:),C(:),'filled'), view(-60,60)
```



See Also

`scatter`, `plot3`

See “Scattergroup Properties” for property descriptions

“Scatter/Bubble Plots” for related functions

Modifying Properties

You can set and query graphics object properties using the `set` and `get` commands or the Property Editor (`propertyeditor`).

Note that you cannot define default property values for scattergroup objects.

See Plot Objects for information on scattergroup objects.

Scattergroup Property Descriptions

This section provides a description of properties. Curly braces { } enclose default values.

`BeingDeleted` `on | {off}` Read Only

This object is being deleted. The `BeingDeleted` property provides a mechanism that you can use to determine whether objects are in the process of being deleted. MATLAB sets the `BeingDeleted` property to `on` when the object's delete function callback is called (see the `DeleteFcn` property). It remains set to `on` while the delete function executes, after which the object no longer exists.

For example, an object's delete function might call other functions that act on a number of different objects. These functions might not need to perform actions on objects if the objects are going to be deleted, and therefore can check the object's `BeingDeleted` property before acting.

`BusyAction` `cancel | {queue}`

Callback routine interruption. The `BusyAction` property enables you to control how MATLAB handles events that potentially interrupt executing callbacks. If there is a callback function executing, callbacks invoked subsequently always attempt to interrupt it.

If the `Interruptible` property of the object whose callback is executing is set to `on` (the default), then interruption occurs at the next point where the event queue is processed. If the `Interruptible` property is `off`, the `BusyAction` property (of the object owning the executing callback) determines how MATLAB handles the event. The choices are

- `cancel` — Discard the event that attempted to execute a second callback routine.
- `queue` — Queue the event that attempted to execute a second callback routine until the current callback finishes.

ButtonDownFcn string or function handle

Button press callback function. A callback that executes whenever you press a mouse button while the pointer is over the scattergroup object.

This property can be

- A string that is a valid MATLAB expression
- The name of an M-file
- A function handle

The expression executes in the MATLAB workspace.

See Function Handle Callbacks for information on how to use function handles to define the callbacks.

CData vector, m-by-3 matrix, `ColorSpec`

Color of markers. When `CData` is a vector the same length as `XData` and `YData`, the values in `CData` are linearly mapped to the colors in the current colormap. When `CData` is a `length(XData)`-by-3 matrix, it specifies the colors of the markers as RGB values. `CData` can also be a color string (see `ColorSpec` for a list of color string specifiers).

CDataSource string (MATLAB variable)

Link YData to MATLAB variable. Set this property to a MATLAB variable that, by default, is evaluated in the base workspace to generate the `CData`.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change `CData`.

You can use the `refreshdata` function to force an update of the object's data. `refreshdata` also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call `refreshdata`.

See the `refreshdata` reference page for more information.

Note If you change one data source property to a variable that contains data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

Children array of graphics object handles

Children of the scattergroup object. An array containing the handle of a patch object parented to the scattergroup object (whether visible or not).

Note that if a child object's `HandleVisibility` property is set to `callback` or `off`, its handle does not show up in the stem `Children` property unless you set the Root `ShowHiddenHandles` property to `on`:

```
set(0,'ShowHiddenHandles','on')
```

Clipping {on} | off

Clipping mode. MATLAB clips scatter plots to the axes plot box by default. If you set `Clipping` to `off`, lines might be displayed outside the axes plot box.

CreateFcn string or function handle

Callback routine executed during object creation. This property defines a callback that executes when MATLAB creates a scattergroup object. You must specify the callback during the creation of the object. For example,

```
scatter(x,y,'CreateFcn',@CallbackFcn)
```

where `@CallbackFcn` is a function handle that references the callback function.

MATLAB executes this routine after setting all other scattergroup properties. Setting this property on an existing scattergroup object has no effect.

The handle of the object whose `CreateFcn` is being executed is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

DeleteFcn string or function handle

Callback executed during object deletion. A callback that executes when the scattergroup object is deleted (e.g., this might happen when you issue a `delete` command on the scattergroup object, its parent axes, or the figure containing it). MATLAB executes the callback before destroying the object's properties so the callback routine can query these values.

The handle of the object whose `DeleteFcn` is being executed is accessible only through the root `CallbackObject` property, which can be queried using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

See the `BeingDeleted` property for related information.

`DisplayName` string

Label used by plot legends. The legend and the plot browser use this text for labels for any scattergroup objects appearing in these legends.

`EraseMode` `{normal} | none | xor | background`

Erase mode. This property controls the technique MATLAB uses to draw and erase scatter child objects (the patch used to construct the scatter graph). Alternative erase modes are useful for creating animated sequences, where control of the way individual objects are redrawn is necessary to improve performance and obtain the desired effect.

- `normal` — Redraw the affected region of the display, performing the three-dimensional analysis necessary to ensure that all objects are rendered correctly. This mode produces the most accurate picture, but is the slowest. The other modes are faster, but do not perform a complete redraw and are therefore less accurate.
- `none` — Do not erase objects when they are moved or destroyed. While the objects are still visible on the screen after erasing with `EraseMode` `none`, you cannot print these objects because MATLAB stores no information about their former locations.
- `xor`— Draw and erase the object by performing an exclusive OR (XOR) with each pixel index of the screen behind it. Erasing the object does not damage the color of the objects behind it. However, the color of the erased object depends on the color of the screen behind it and it is correctly colored only when it is over the axes background color (or the figure background color if the axes `Color` property is set to `none`). That is, it isn't erased correctly if there are objects behind it.
- `background` — Erase the graphics objects by redrawing them in the axes background color, (or the figure background color if the axes `Color` property is set to `none`). This damages other graphics objects that are behind the erased object, but the erased object is always properly colored.

Printing with Nonnormal Erase Modes

MATLAB always prints figures as if the `EraseMode` of all objects is `normal`. This means graphics objects created with `EraseMode` set to `none`, `xor`, or `background` can look different on screen than on paper. On screen, MATLAB can mathematically combine layers of colors (e.g., performing an XOR operation on a pixel color with that of the pixel behind it) and ignore three-dimensional sorting to obtain greater rendering speed. However, these techniques are not applied to the printed output.

Set the axes background color with the axes `Color` property. Set the figure background color with the figure `Color` property.

You can use the MATLAB `getframe` command or other screen capture applications to create an image of a figure containing nonnormal mode objects.

`HandleVisibility` `{on} | callback | off`

Control access to object's handle by command-line users and GUIs. This property determines when an object's handle is visible in its parent's list of children. `HandleVisibility` is useful for preventing command-line users from accidentally accessing the scattergroup object.

- `on` — Handles are always visible when `HandleVisibility` is `on`.
- `callback` — Setting `HandleVisibility` to `callback` causes handles to be visible from within callback routines or functions invoked by callback routines, but not from within functions invoked from the command line. This provides a means to protect GUIs from command-line users, while allowing callback routines to have access to object handles.
- `off` — Setting `HandleVisibility` to `off` makes handles invisible at all times. This might be necessary when a callback invokes a function that might potentially damage the GUI (such as evaluating a user-typed string) and so temporarily hides its own handles during the execution of that function.

Functions Affected by Handle Visibility

When a handle is not visible in its parent's list of children, it cannot be returned by functions that obtain handles by searching the object hierarchy or querying handle properties. This includes `get`, `findobj`, `gca`, `gcf`, `gco`, `newplot`, `cla`, `clf`, and `close`.

Properties Affected by Handle Visibility

When a handle's visibility is restricted using `callback` or `off`, the object's handle does not appear in its parent's `Children` property, figures do not appear in the root's `CurrentFigure` property, objects do not appear in the root's `CallbackObject` property or in the figure's `CurrentObject` property, and axes do not appear in their parent's `CurrentAxes` property.

Overriding Handle Visibility

You can set the root `ShowHiddenHandles` property to `on` to make all handles visible regardless of their `HandleVisibility` settings (this does not affect the values of the `HandleVisibility` properties). See also `findall`.

Handle Validity

Handles that are hidden are still valid. If you know an object's handle, you can set and get its properties and pass it to any function that operates on handles.

`HitTest` `{on} | off`

Selectable by mouse click. `HitTest` determines whether the scattergroup object can become the current object (as returned by the `gco` command and the figure `CurrentObject` property) as a result of a mouse click on the line objects that compose the stem plot. If `HitTest` is `off`, clicking the stemseries object selects the object below it (which is usually the axes containing it).

`HitTestArea` `on | {off}`

Select scattergroup object on markers or area of scatter graph. This property enables you to select scattergroup objects in two ways:

- Select by clicking on scatter markers (default).
- Select by clicking anywhere in the extent of the scatter graph.

When `HitTestArea` is `off`, you must click the scatter markers to select the scattergroup object. When `HitTestArea` is `on`, you can select the scattergroup object by clicking anywhere within the extent of the scatter graph (i.e., anywhere within a rectangle that encloses all the scatter markers).

`Interruptible` `{on} | off`

Callback routine interruption mode. The `Interruptible` property controls whether a scattergroup object callback can be interrupted by callbacks invoked subsequently.

Only callbacks defined for the `ButtonDownFcn` property are affected by the `Interruptible` property. MATLAB checks for events that can interrupt a callback only when it encounters a `drawnow`, `figure`, `getframe`, or `pause` command in the routine. See the `BusyAction` property for related information.

Setting `Interruptible` to `on` allows any graphics object's callback to interrupt callback routines originating from a stem property. Note that MATLAB does not save the state of variables or the display (e.g., the handle returned by the `gca` or `gcf` command) when an interruption occurs.

`LineWidth` width in points (default: 0.5 points)

Width of line that draws the edge of markers. You can set the thickness of the lines used to draw the markers to a value in points.

`Marker` character (see table)

Marker symbol. The `Marker` property specifies the type of markers that are displayed on the scatter graph. The following table shows supported markers.

Marker Specifier	Description
`+`	Plus sign
`o`	Circle
`*`	Asterisk
`.`	Point
`x`	Cross
`s`	Square
`d`	Diamond
`^`	Upward-pointing triangle
`v`	Downward-pointing triangle
`>`	Right-pointing triangle
`<`	Left-pointing triangle
`p`	Five-pointed star (pentagram)

Marker Specifier	Description
h	Six-pointed star (hexagram)
none	No marker (default)

MarkerEdgeColor ColorSpec | none | {auto}

Marker edge color. The color of the marker or the edge color for filled markers (circle, square, diamond, pentagram, hexagram, and the four triangles). ColorSpec defines the color to use. none specifies no color, which makes nonfilled markers invisible. auto uses the CData property to determine the MarkerEdgeColor.

MarkerFaceColor ColorSpec | {none} | auto

Marker face color. The fill color for markers that are closed shapes (circle, square, diamond, pentagram, hexagram, and the four triangles). ColorSpec defines the color to use. none makes the interior of the marker transparent, allowing the background to show through. auto sets the fill color to the axes color, or the figure color if the axes Color property is set to none (which is the factory default for axes objects).

Parent handle of axes, hggroup, or hgtransform

Parent of scattergroup object. This property contains the handle of the scattergroup object's parent. The parent of a scattergroup object is the axes that contains it. You can reparent scattergroup objects to other axes, hggroup, or hgtransform objects.

See Objects That Can Contain Other Objects for more information on parenting graphics objects.

Selected on | {off}

Is object selected. When you set this property to on, MATLAB displays selection handles at the corners and midpoints if the SelectionHighlight property is also on (the default). You can, for example, define the ButtonDownFcn callback to set this property to on, thereby indicating that the scattergroup object is selected.

SelectionHighlight {on} | off

Objects are highlighted when selected. When the Selected property is on, MATLAB indicates the selected state by drawing selection handles on the scatter markers. When SelectionHighlight is off, MATLAB does not draw the handles.

SizeData square points

Size of markers in square points. This property specifies the area of the marker in the scatter graph in units of points. Since there are 72 points to one inch, to specify a marker that has an area of one square inch you would use a value of 72^2.

Tag string

User-specified object label. The Tag property provides a means to identify graphics objects with a user-specified label. This is particularly useful when you are constructing interactive graphics programs that would otherwise need to define object handles as global variables or pass them as arguments between callbacks.

For example, you might create a stemseries object and set the Tag property:

```
t = scatter(x,y,'Tag','scatter1')
```

When you want to access the scattergroup object, you can use findobj to find the scattergroup object's handle. The following statement changes the MarkerFaceColor property of the object whose Tag is scatter1.

```
set(findobj('Tag','scatter1'),'MarkerFaceColor','red')
```

Type string (read only)

Type of graphics object. This property contains a string that identifies the class of the graphics object. For stemseries objects, Type is 'hggroup'. The following statement finds all the hggroup objects in the current axes.

```
t = findobj(gca,'Type','hggroup');
```

UIContextMenu handle of a uicontextmenu object

Associate a context menu with the scattergroup object. Assign this property the handle of a uicontextmenu object created in the scattergroup object's parent figure. Use the uicontextmenu function to create the context menu. MATLAB

displays the context menu whenever you right-click over the scattergroup object.

`UserData` array

User-specified data. This property can be any data you want to associate with the scattergroup object (including cell arrays and structures). The scattergroup object does not set values for this property, but you can access it using the `set` and `get` functions.

`Visible` `{on} | off`

Visibility of scattergroup object and its children. By default, scattergroup object visibility is `on`. This means all children of the scattergroup object are visible unless the child object's `Visible` property is set to `off`. Setting a scattergroup object's `Visible` property to `off` also makes its children invisible.

`XData` `array`

X-coordinates of scatter markers. The scatter function draws individual markers at each *x*-axis location in the `XData` array. The input argument `x` in the `scatter` function calling syntax assigns values to `XData`.

`XDataSource` string (MATLAB variable)

Link XData to MATLAB variable. Set this property to a MATLAB variable that, by default, is evaluated in the base workspace to generate the `XData`.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change `XData`.

You can use the `refreshdata` function to force an update of the object's data. `refreshdata` also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call `refreshdata`.

See the `refreshdata` reference page for more information.

Note If you change one data source property to a variable that contains data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

YData scalar, vector, or matrix

Y-coordinates of scatter markers. The scatter function draws individual markers at each *y*-axis location in the `YData` array.

The input argument `y` in the `scatter` function calling syntax assigns values to `YData`.

YDataSource string (MATLAB variable)

Links YData to MATLAB variable. Set this property to a MATLAB variable that, by default, is evaluated in the base workspace to generate the `YData`.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change `YData`.

You can use the `refreshdata` function to force an update of the object's data. `refreshdata` also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call `refreshdata`.

See the `refreshdata` reference page for more information.

Note If you change one data source property to a variable that contains data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

ZData vector of coordinates

Z-coordinates. A vector of *z*-coordinates defining the scattergroup object. `XData` and `YData` must be the same length.

ZDataSource string (MATLAB variable)

Link `ZData` to MATLAB variable. Set this property to a MATLAB variable that, by default, is evaluated in the base workspace to generate the `ZData`.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change `ZData`.

You can use the `refreshdata` function to force an update of the object's data. `refreshdata` also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call `refreshdata`.

See the `refreshdata` reference page for more information.

Note If you change one data source property to a variable that contains data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

Purpose

Schur decomposition

Syntax

```
T = schur(A)
T = schur(A,flag)
[U,T] = schur(A,...)
```

Description

The `schur` command computes the Schur form of a matrix.

`T = schur(A)` returns the Schur matrix `T`.

`T = schur(A,flag)` for real matrix A, returns a Schur matrix `T` in one of two forms depending on the value of `flag`:

`'complex'`	`T` is triangular and is complex if `A` has complex eigenvalues.
`'real'`	`T` has the real eigenvalues on the diagonal and the complex eigenvalues in 2-by-2 blocks on the diagonal. `'real'` is the default.

If `A` is complex, `schur` returns the complex Schur form in matrix `T`. The complex Schur form is upper triangular with the eigenvalues of `A` on the diagonal.

The function `rsf2csf` converts the real Schur form to the complex Schur form.

`[U,T] = schur(A,...)` also returns a unitary matrix `U` so that `A = U*T*U'` and `U'*U = eye(size(A))`.

Examples

`H` is a 3-by-3 eigenvalue test matrix:

```
H = [ -149    -50   -154
       537    180    546
       -27     -9    -25 ]
```

Its Schur form is

```
schur(H)

ans =
     1.0000   -7.1119 -815.8706
          0    2.0000  -55.0236
          0         0    3.0000
```

The eigenvalues, which in this case are 1, 2, and 3, are on the diagonal. The fact that the off-diagonal elements are so large indicates that this matrix has poorly conditioned eigenvalues; small changes in the matrix elements produce relatively large changes in its eigenvalues.

Algorithm

`schur` uses LAPACK routines to compute the Schur form of a matrix:

Matrix A	Routine
Real symmetric	`DSYTRD`, `DSTEQR` `DSYTRD`, `DORGTR`, `DSTEQR` (with output `U`)
Real nonsymmetric	`DGEHRD`, `DHSEQR` `DGEHRD`, `DORGHR`, `DHSEQR` (with output `U`)
Complex Hermitian	`ZHETRD`, `ZSTEQR` `ZHETRD`, `ZUNGTR`, `ZSTEQR` (with output `U`)
Non-Hermitian	`ZGEHRD`, `ZHSEQR` `ZGEHRD`, `ZUNGHR`, `ZHSEQR` (with output `U`)

See Also

`eig`, `hess`, `qz`, `rsf2csf`

References

[1] Anderson, E., Z. Bai, C. Bischof, S. Blackford, J. Demmel, J. Dongarra, J. Du Croz, A. Greenbaum, S. Hammarling, A. McKenney, and D. Sorensen, *LAPACK User's Guide* (`http://www.netlib.org/lapack/lug/lapack_lug.html`), Third Edition, SIAM, Philadelphia, 1999.

Purpose

Script M-files

Description

A script file is an external file that contains a sequence of MATLAB statements. By typing the filename, you can obtain subsequent MATLAB input from the file. Script files have a filename extension of `.m` and are often called M-files.

Scripts are the simplest kind of M-file. They are useful for automating blocks of MATLAB commands, such as computations you have to perform repeatedly from the command line. Scripts can operate on existing data in the workspace, or they can create new data on which to operate. Although scripts do not return output arguments, any variables that they create remain in the workspace, so you can use them in further computations. In addition, scripts can produce graphical output using commands like `plot`.

Scripts can contain any series of MATLAB statements. They require no declarations or begin/end delimiters.

Like any M-file, scripts can contain comments. Any text following a percent sign (`%`) on a given line is comment text. Comments can appear on lines by themselves, or you can append them to the end of any executable line.

See Also

`echo`, `function`, `type`

Purpose

Secant of an argument in radians

Syntax

```
Y = sec(X)
```

Description

The `sec` function operates element-wise on arrays. The function's domains and ranges include complex values. All angles are in radians.

`Y = sec(X)` returns an array the same size as `X` containing the secant of the elements of `X`.

Examples

Graph the secant over the domains $-\pi/2 < x < \pi/2$ and $\pi/2 < x < 3\pi/2$.

```
x1 = -pi/2+0.01:0.01:pi/2-0.01;
x2 = pi/2+0.01:0.01:(3*pi/2)-0.01;
plot(x1,sec(x1),x2,sec(x2)), grid on
```



The expression `sec(pi/2)` does not evaluate as infinite but as the reciprocal of the floating-point accuracy `eps`, because `pi` is a floating-point approximation to the exact value of π .

Definition

The secant can be defined as

$$\sec(z) = \frac{1}{\cos(z)}$$

Algorithm

`sec` uses FDLIBM, which was developed at SunSoft, a Sun Microsystems, Inc. business, by Kwok C. Ng, and others. For information about FDLIBM, see `http://www.netlib.org`.

See Also

`asec`, `asech`, `eps`, `pi`, `secd`, `sech`

secd

Purpose

Secant of an argument in degrees

Syntax

```
Y = secd(X)
```

Description

`Y = secd(X)` is the secant of the elements of `X`, expressed in degrees. For odd integers `n`, `secd(n*90)` is infinite, whereas `sec(n*pi/2)` is large but finite, reflecting the accuracy of the floating point value of `pi`.

See Also

`asecd`, `sec`

Purpose

Hyperbolic secant

Syntax

```
Y = sech(X)
```

Description

The `sech` function operates element-wise on arrays. The function's domains and ranges include complex values. All angles are in radians.

`Y = sech(X)` returns an array the same size as `X` containing the hyperbolic secant of the elements of `X`.

Examples

Graph the hyperbolic secant over the domain $-2\pi \le x \le 2\pi$.

```
x = -2*pi:0.01:2*pi;
plot(x,sech(x)), grid on
```



Algorithm

`sech` uses this algorithm.

$$\operatorname{sech}(z) = \frac{1}{\cosh(z)}$$

Definition

The secant can be defined as

$$\operatorname{sech}(z) = \frac{1}{\cosh(z)}$$

Algorithm

sec uses FDLIBM, which was developed at SunSoft, a Sun Microsystems, Inc. business, by Kwok C. Ng, and others. For information about FDLIBM, see http://www.netlib.org.

See Also

asec, asech, sec

Purpose

Select, move, resize, or copy axes and uicontrol graphics objects

Syntax

```
A = selectmoveresize;
set(h,'ButtonDownFcn','selectmoveresize')
```

Description

`selectmoveresize` is useful as the callback routine for axes and uicontrol button down functions. When executed, it selects the object and allows you to move, resize, and copy it.

For example, this statement sets the `ButtonDownFcn` of the current axes to `selectmoveresize`:

```
set(gca,'ButtonDownFcn','selectmoveresize')
```

`A = selectmoveresize` returns a structure array containing

- `A.Type`: a string containing the action type, which can be `Select`, `Move`, `Resize`, or `Copy`
- `A.Handles`: a list of the selected handles, or, for a `Copy`, an m-by-2 matrix containing the original handles in the first column and the new handles in the second column

See Also

The `ButtonDownFcn` of axes and uicontrol graphics objects

"Object Manipulation" for related functions

semilogx, semilogy

Purpose

Semilogarithmic plots

Syntax

```
semilogx(Y)
semilogx(X1,Y1,...)
semilogx(X1,Y1,LineSpec,...)
semilogx(...,'PropertyName',PropertyValue,...)
h = semilogx(...)
hlines = semilogx('v6',...)
semilogy(...)
h = semilogy(...)
hlines = semilogx('v6',...)
```

Description

`semilogx` and `semilogy` plot data as logarithmic scales for the *x*- and *y*-axis, respectively, logarithmic.

`semilogx(Y)` creates a plot using a base 10 logarithmic scale for the *x*-axis and a linear scale for the *y*-axis. It plots the columns of `Y` versus their index if `Y` contains real numbers. `semilogx(Y)` is equivalent to `semilogx(real(Y), imag(Y))` if `Y` contains complex numbers. `semilogx` ignores the imaginary component in all other uses of this function.

`semilogx(X1,Y1,...)` plots all `Xn` versus `Yn` pairs. If only `Xn` or `Yn` is a matrix, `semilogx` plots the vector argument versus the rows or columns of the matrix, depending on whether the vector's row or column dimension matches the matrix.

`semilogx(X1,Y1,LineSpec,...)` plots all lines defined by the `Xn,Yn,LineSpec` triples. `LineSpec` determines line style, marker symbol, and color of the plotted lines.

`semilogx(...,'PropertyName',PropertyValue,...)` sets property values for all lineseries graphics objects created by `semilogx`.

`semilogy(...)` creates a plot using a base 10 logarithmic scale for the *y*-axis and a linear scale for the *x*-axis.

`h = semilogx(...)` and `h = semilogy(...)` return a vector of handles to lineseries graphics objects, one handle per line.

Backward Compatible Version

`hlines = semilogx('v6',...)` and `hlines = semilogy('v6',...)` return the handles to line objects instead of lineseries objects.

Remarks

If you do not specify a color when plotting more than one line, `semilogx` and `semilogy` automatically cycle through the colors and line styles in the order specified by the current axes `ColorOrder` and `LineStyleOrder` properties.

You can mix `Xn,Yn` pairs with `Xn,Yn,LineSpec` triples; for example,

```
semilogx(X1,Y1,X2,Y2,LineSpec,X3,Y3)
```

Examples

Create a simple `semilogy` plot.

```
x = 0:.1:10;
semilogy(x,10.^x)
```



See Also

`line`, `LineSpec`, `loglog`, `plot`
"Basic Plots and Graphs" for related functions

sendmail

Purpose

Send e-mail message to list of e-mail addresses

Syntax

```
sendmail('recipients','subject')
sendmail('recipients','subject','message','attachments')
```

Description

`sendmail('recipients','subject')` sends e-mail to `recipients` with the specified `subject`. For `recipients`, use a string for a single address, or a cell array of strings for multiple addresses.

`sendmail('recipients','subject','message','attachments')` sends `message` to `recipients` with the specified `subject`. For `recipients`, use a string for a single address, or a cell array of strings for multiple addresses. For `message`, use a string or cell array. When `message` is a string, the text automatically wraps at 75 characters. When `message` is a cell array, it does not wrap but rather each cell is a new line. To force text to start on a new line in strings or cells, use `10`, as shown in the "Example of sendmail with New Lines Specified" on page 2-1937. Specify `attachments` as a cell array of files to send along with `message`.

To use `sendmail`, you must set the preferences for your e-mail server (Internet SMTP server) and your e-mail address must be set. MATLAB tries to read the SMTP mail server from your system registry, but if it cannot, it results in an error. In this event, identify the outgoing mail server for your electronic mail application, which is usually listed in the application's preferences, or, consult your e-mail system administrator. Then provide the information to MATLAB using

```
setpref('Internet','SMTP_Server','myserver.myhost.com');
```

If you cannot easily determine your e-mail server, try using `mail`, as in

```
setpref('Internet','SMTP_Server','mail');
```

which might work because `mail` is often a default for mail systems.

Similarly, if MATLAB cannot determine your e-mail address and produces an error, specify your e-mail address using

```
setpref('Internet','E_mail','myaddress@example.com');
```

Note The `sendmail` function does not support email servers that require authentication.

Examples

Example of sendmail with Two Attachments

```
sendmail('user@otherdomain.com','Test subject','Test message',
{'directory/attach1.html','attach2.doc'});
```

Example of sendmail with New Lines Specified

This mail message forces the message to start new lines after each `10`.

```
sendmail('user@otherdomain.com','New subject', ...
['Line1 of message' 10 'Line2 of message' 10 ...
 'Line3 of message' 10 'Line4 of message']);
```

The resulting message is

```
Line1 of message
Line2 of message
Line3 of message
Line4 of message
```

Purpose

Set object properties

Syntax

```
set(H,'PropertyName',PropertyValue,...)
set(H,a)
set(H,pn,pv...)
set(H,pn,<m-by-n cell array>)
a= set(h)
a= set(O,'FactoryObjectTypePropertyName')
a= set(h,'Default')
a= set(h,'DefaultObjectTypePropertyName')
<cell array> = set(h,'PropertyName')
```

Description

`set(H,'PropertyName',PropertyValue,...)` sets the named properties to the specified values on the object(s) identified by `H`. `H` can be a vector of handles, in which case `set` sets the properties' values for all the objects.

`set(H,a)` sets the named properties to the specified values on the object(s) identified by `H`. `a` is a structure array whose field names are the object property names and whose field values are the values of the corresponding properties.

`set(H,pn,pv,...)` sets the named properties specified in the cell array `pn` to the corresponding value in the cell array `pv` for all objects identified in `H`.

`set(H,pn,<m-by-n cell array>)` sets `n` property values on each of `m` graphics objects, where `m = length(H)` and `n` is equal to the number of property names contained in the cell array `pn`. This allows you to set a given group of properties to different values on each object.

`a = set(h)` returns the user-settable properties and possible values for the object identified by `h`. `a` is a structure array whose field names are the object's property names and whose field values are the possible values of the corresponding properties. If you do not specify an output argument, MATLAB displays the information on the screen. `h` must be scalar.

`a = set(O,'FactoryObjectTypePropertyName')` returns the possible values of the named property for the specified object type, if the values are strings. The argument `FactoryObjectTypePropertyName` is the word `Factory` concatenated with the object type (e.g., `axes`) and the property name (e.g., `CameraPosition`).

`a = set(h,'Default')` returns the names of properties having default values set on the object identified by `h`. `set` also returns the possible values if they are strings. `h` must be scalar.

`a = set(h,'Default`*`ObjectTypePropertyName`*`')` returns the possible values of the named property for the specified object type, if the values are strings. The argument `Default`*`ObjectTypePropertyName`* is the word `Default` concatenated with the object type (e.g., `axes`) and the property name (e.g., `CameraPosition`). For example, `DefaultAxesCameraPosition`. `h` must be scalar.

`pv = set(h,'`*`PropertyName`*`')` returns the possible values for the named property. If the possible values are strings, `set` returns each in a cell of the cell array `pv`. For other properties, `set` returns an empty cell array. If you do not specify an output argument, MATLAB displays the information on the screen. `h` must be scalar.

Remarks

You can use any combination of property name/property value pairs, structure arrays, and cell arrays in one call to `set`.

Examples

Set the `Color` property of the current axes to blue.

```
set(gca,'Color','b')
```

Change all the lines in a plot to black.

```
plot(peaks)
set(findobj('Type','line'),'Color','k')
```

You can define a group of properties in a structure to better organize your code. For example, these statements define a structure called `active`, which contains a set of property definitions used for the uicontrol objects in a particular figure. When this figure becomes the current figure, MATLAB changes colors and enables the controls.

```
active.BackgroundColor = [.7 .7 .7];
active.Enable = 'on';
active.ForegroundColor = [0 0 0];

if gcf == control_fig_handle
   set(findobj(control_fig_handle,'Type','uicontrol'),active)
end
```

You can use cell arrays to set properties to different values on each object. For example, these statements define a cell array to set three properties,

```
PropName(1) = {'BackgroundColor'};
PropName(2) = {'Enable'};
PropName(3) = {'ForegroundColor'};
```

These statements define a cell array containing three values for each of three objects (i.e., a 3-by-3 cell array).

```
PropVal(1,1) = {[.5 .5 .5]};
PropVal(1,2) = {'off'};
PropVal(1,3) = {[.9 .9 .9]};

PropVal(2,1) = {[1 0 0]};
PropVal(2,2) = {'on'};
PropVal(2,3) = {[1 1 1]};

PropVal(3,1) = {[.7 .7 .7]};
PropVal(3,2) = {'on'};
PropVal(3,3) = {[0 0 0]};
```

Now pass the arguments to `set`,

```
set(H,PropName,PropVal)
```

where `length(H) = 3` and each element is the handle to a uicontrol.

Setting Different Values for the Same Property on Multiple Objects

Suppose you want to set the value of the `Tag` property on five line objects, each to a different value. Note how the value cell array needs to be transposed to have the proper shape.

```
h = plot(rand(5));
set(h,{'Tag'},{'line1','line2','line3','line4','line5'}')
```

See Also

`findobj`, `gca`, `gcf`, `gco`, `gcbo`, `get`

"Finding and Identifying Graphics Objects" for related functions

Purpose

Configure or display timer object properties

Syntax

```
set(obj)
prop_struct = set(obj)
set(obj,'PropertyName')
prop_cell = set(obj,'PropertyName')
set(obj,'PropertyName',PropertyValue,...)
set(obj,S)
set(obj,PN,PV)
```

Description

`set(obj)` displays property names and their possible values for all configurable properties of timer object `obj`. `obj` must be a single timer object.

`prop_struct = set(obj)` returns the property names and their possible values for all configurable properties of timer object `obj`. `obj` must be a single timer object. The return value, `prop_struct`, is a structure whose field names are the property names of `obj`, and whose values are cell arrays of possible property values or empty cell arrays if the property does not have a finite set of possible string values.

`set(obj,'PropertyName')` displays the possible values for the specified property, *`PropertyName`*, of timer object `obj`. `obj` must be a single timer object.

`prop_cell=set(obj,'PropertyName')` returns the possible values for the specified property, *`PropertyName`*, of timer object `obj`. `obj` must be a single timer object. The returned array, `prop_cell`, is a cell array of possible value strings or an empty cell array if the property does not have a finite set of possible string values.

`set(obj,'PropertyName',PropertyValue,...)` configures the property, *`PropertyName`*, to the specified value, `PropertyValue`, for timer object `obj`. You can specify multiple property name/property value pairs in a single statement. `obj` can be a single timer object or a vector of timer objects, in which case `set` configures the property values for all the timer objects specified.

`set(obj,S)` configures the properties of `obj`, with the values specified in `S`, where `S` is a structure whose field names are object property names.

`set(obj,PN,PV)` configures the properties specified in the cell array of strings, `PN`, to the corresponding values in the cell array `PV`, for the timer object `obj`. `PN` must be a vector. If `obj` is an array of timer objects, `PV` can be an M-by-N cell array, where M is equal to the length of timer object array and N is equal to the length of `PN`. In this case, each timer object is updated with a different set of values for the list of property names contained in `PN`.

Note When specifying parameter/value pairs, you can use any mixture of strings, structures, and cell arrays in the same call to `set`.

Examples

Create a timer object.

```
t = timer;
```

Display all configurable properties and their possible values.

```
set(t)
    BusyMode: [ {drop} | queue | error ]
    ErrorFcn: string -or- function handle -or- cell array
   ExecutionMode: [ {singleShot} | fixedSpacing | fixedDelay | fixedRate ]
    Name
    ObjectVisibility: [ {on} | off ]
    Period
    StartDelay
    StartFcn: string -or- function handle -or- cell array
    StopFcn: string -or- function handle -or- cell array
    Tag
    TasksToExecute
    TimerFcn: string -or- function handle -or- cell array
    UserData
```

View the possible values of the `ExecutionMode` property.

```
set(t, 'ExecutionMode')
[ {singleShot} | fixedSpacing | fixedDelay | fixedRate ]
```

Set the value of a specific timer object property.

```
set(t, 'ExecutionMode', 'FixedRate')
```

Set the values of several properties of the timer object.

```
set(t, 'TimerFcn', 'callbk', 'Period', 10)
```

Use a cell array to specify the names of the properties you want to set and another cell array to specify the values of these properties.

```
set(t, {'StartDelay', 'Period'}, {30, 30})
```

See Also

`timer`, `get`

setappdata

Purpose

Set application-defined data

Syntax

```
setappdata(h,name,value)
```

Description

`setappdata(h,name,value)` sets application-defined data for the object with handle `h`. The application-defined data, which is created if it does not already exist, is assigned a `name` and a `value`. `value` can be any type of data.

See Also

`getappdata`, `isappdata`, `rmappdata`

Purpose

Return the set difference of two vectors

Syntax

```
c = setdiff(A, B)
c = setdiff(A, B, 'rows')
[c, i] = setdiff(...)
```

Description

`c = setdiff(A, B)` returns the values in `A` that are not in `B`. The resulting vector is sorted in ascending order. In set theory terms, `c = A - B`. `A` and `B` can be cell arrays of strings.

`c = setdiff(A, B, 'rows')`, when `A` and `B` are matrices with the same number of columns, returns the rows from `A` that are not in `B`.

`[c,i] = setdiff(...)` also returns an index vector `index` such that `c = a(i)` or `c = a(i,:)`.

Examples

```
A = magic(5);
B = magic(4);
[c, i] = setdiff(A(:), B(:));
c' =    17    18    19    20    21    22    23    24    25
i' =     1    10    14    18    19    23     2     6    15
```

See Also

`intersect`, `ismember`, `issorted`, `setxor`, `union`, `unique`

Purpose

Return the set difference of two vectors

Syntax

```
c = setdiff(A, B)
c = setdiff(A, B, 'rows')
[c, i] = setdiff(...)
```

Description

`c = setdiff(A, B)` returns the values in `A` that are not in `B`. The resulting vector is sorted in ascending order. In set theory terms, `c = A - B`. `A` and `B` can be cell arrays of strings.

`c = setdiff(A, B, 'rows')`, when `A` and `B` are matrices with the same number of columns, returns the rows from `A` that are not in `B`.

`[c,i] = setdiff(...)` also returns an index vector `index` such that `c = a(i)` or `c = a(i,:)`.

Examples

```
A = magic(5);
B = magic(4);
[c, i] = setdiff(A(:), B(:));
c' =    17    18    19    20    21    22    23    24    25
i' =     1    10    14    18    19    23     2     6    15
```

See Also

`intersect`, `ismember`, `issorted`, `setxor`, `union`, `unique`

setfield

Purpose

Set field of structure array

Syntax

```
s = setfield(s, 'field', v)
s = setfield(s, {i,j}, 'field', {k} ,v)
```

Description

`s = setfield(s, 'field', v)`, where `s` is a 1-by-1 structure, sets the contents of the specified field to the value `v`. This is equivalent to the syntax `s.field = v`.

`s = setfield(s, {i,j}, 'field', {k}, v)` sets the contents of the specified field to the value `v`. This is equivalent to the syntax `s(i,j).field(k) = v`. All subscripts must be passed as cell arrays — that is, they must be enclosed in curly braces (similar to`{i,j}` and `{k}` above). Pass field references as strings.

Remarks

In many cases, you can use dynamic field names in place of the `getfield` and `setfield` functions. Dynamic field names express structure fields as variable expressions that MATLAB evaluates at run-time. See Technical Note 32236 for information about using dynamic field names versus the `getfield` and `setfield` functions.

Examples

Given the structure

```
mystr(1,1).name = 'alice';
mystr(1,1).ID = 0;
mystr(2,1).name = 'gertrude';
mystr(2,1).ID = 1;
```

You can change the `name` field of `mystr(2,1)` using

```
mystr = setfield(mystr, {2,1}, 'name', 'ted');
mystr(2,1).name

ans =

ted
```

The following example sets fields of a structure using `setfield` with variable and quoted field names and additional subscripting arguments.

```
class = 5;   student = 'John_Doe';
```

```
grades_Doe = [85, 89, 76, 93, 85, 91, 68, 84, 95, 73];
grades = [];

grades = setfield(grades, {class}, student, 'Math', ...
   {10, 21:30}, grades_Doe);
```

You can check the outcome using the standard structure syntax.

```
grades(class).John_Doe.Math(10, 21:30)

ans =

    85    89    76    93    85    91    68    84    95    73
```

See Also

`getfield`, `fieldnames`, `isfield`, `orderfields`, `rmfield`, dynamic field names

setstr

Purpose Set string flag

Description This MATLAB 4 function has been renamed `char` in MATLAB 5.

Purpose

Set exclusive OR of two vectors

Syntax

```
c = setxor(A, B)
c = setxor(A, B, 'rows')
[c, ia, ib] = setxor(...)
```

Description

`c = setxor(A, B)` returns the values that are not in the intersection of `A` and `B`. The resulting vector is sorted. `A` and `B` can be cell arrays of strings.

`c = setxor(A, B, 'rows')`, when `A` and `B` are matrices with the same number of columns, returns the rows that are not in the intersection of `A` and `B`.

`[c, ia, ib] = setxor(...)` also returns index vectors `ia` and `ib` such that `c` is a sorted combination of the elements `c = a(ia)` and `c = b(ib)` or, for row combinations, `c = a(ia,:)` and `c = b(ib,:)`.

Examples

```
a = [-1 0 1 Inf -Inf NaN];
b = [-2 pi 0 Inf];
c = setxor(a, b)

c =
      -Inf   -2.0000   -1.0000    1.0000    3.1416       NaN
```

See Also

`intersect`, `ismember`, `issorted`, `setdiff`, `union`, `unique`

shading

Purpose

Set color shading properties

Syntax

```
shading flat
shading faceted
shading interp
```

Description

The `shading` function controls the color shading of surface and patch graphics objects.

`shading flat` each mesh line segment and face has a constant color determined by the color value at the endpoint of the segment or the corner of the face that has the smallest index or indices.

`shading faceted` flat shading with superimposed black mesh lines. This is the default shading mode.

`shading interp` varies the color in each line segment and face by interpolating the colormap index or true color value across the line or face.

Examples

Compare a flat, faceted, and interpolated-shaded sphere.

```
subplot(3,1,1)
sphere(16)
axis square
shading flat
title('Flat Shading')

subplot(3,1,2)
sphere(16)
axis square
shading faceted
title('Faceted Shading')

subplot(3,1,3)
sphere(16)
axis square
shading interp
title('Interpolated Shading')
```



Algorithm

`shading` sets the `EdgeColor` and `FaceColor` properties of all surface and patch graphics objects in the current axes. `shading` sets the appropriate values, depending on whether the surface or patch objects represent meshes or solid surfaces.

See Also

`fill`, `fill3`, `hidden`, `mesh`, `patch`, `pcolor`, `surf`

The `EdgeColor` and `FaceColor` properties for surface and patch graphics objects

"Color Operations" for related functions

Purpose

Shift dimensions

Syntax

```
B = shiftdim(X,n)
[B,nshifts] = shiftdim(X)
```

Description

`B = shiftdim(X,n)` shifts the dimensions of `X` by `n`. When `n` is positive, `shiftdim` shifts the dimensions to the left and wraps the `n` leading dimensions to the end. When `n` is negative, `shiftdim` shifts the dimensions to the right and pads with singletons.

`[B,nshifts] = shiftdim(X)` returns the array `B` with the same number of elements as `X` but with any leading singleton dimensions removed. A singleton dimension is any dimension for which `size(A,dim) = 1`. `nshifts` is the number of dimensions that are removed.

If `X` is a scalar, `shiftdim` has no effect.

Examples

The `shiftdim` command is handy for creating functions that, like `sum` or `diff`, work along the first nonsingleton dimension.

```
a = rand(1,1,3,1,2);
[b,n]  = shiftdim(a); % b is 3-by-1-by-2 and n is 2.
c = shiftdim(b,-n);   % c == a.
d = shiftdim(a,3);    % d is 1-by-2-by-1-by-1-by-3.
```

See Also

`circshift`, `reshape`, `squeeze`

showplottool

Purpose

Show or hide one of the figure plot tools

Syntax

```
showplottool('tool')
showplottool('on','tool')
showplottool('off','tool')
showplottool('toggle','tool')
showplottool(figure_handle,...)
```

Description

`showplottool('tool')` shows the specified plot tool on the current figure. *`tool`* can be one of the following strings:

- `figurepalette`
- `plotbrowser`
- `propertyeditor`

`showplottool('on','tool')` shows the specified plot tool on the current figure.

`showplottool('off','tool')` hides the specified plot tool on the current figure.

`showplottool('toggle','tool')` toggles the visibility of the specified plot tool on the current figure.

`showplottool(figure_handle,...)` operates on the specified figure instead of the current figure.

See Also

`getplottool`, `plottools`

Purpose

Reduce the size of patch faces

Syntax

```
shrinkfaces(p,sf)
nfv = shrinkfaces(p,sf)
nfv = shrinkfaces(fv,sf)
shrinkfaces(p), shrinkfaces(fv)
nfv = shrinkfaces(f,v,sf)
[nf,nv] = shrinkfaces(...)
```

Description

`shrinkfaces(p,sf)` shrinks the area of the faces in patch `p` to shrink factor `sf`. A shrink factor of 0.6 shrinks each face to 60% of its original area. If the patch contains shared vertices, MATLAB creates nonshared vertices before performing the face-area reduction.

`nfv = shrinkfaces(p,sf)` returns the face and vertex data in the struct `nfv`, but does not set the `Faces` and `Vertices` properties of patch `p`.

`nfv = shrinkfaces(fv,sf)` uses the face and vertex data from the struct `fv`.

`shrinkfaces(p)` and `shrinkfaces(fv)` (without specifying a shrink factor) assume a shrink factor of 0.3.

`nfv = shrinkfaces(f,v,sf)` uses the face and vertex data from the arrays `f` and `v`.

`[nf,nv] = shrinkfaces(...)` returns the face and vertex data in two separate arrays instead of a struct.

Examples

This example uses the flow data set, which represents the speed profile of a submerged jet within an infinite tank (type `help flow` for more information). Two isosurfaces provide a before and after view of the effects of shrinking the face size.

- First `reducevolume` samples the flow data at every other point and then `isosurface` generates the faces and vertices data.
- The `patch` command accepts the face/vertex struct and draws the first (`p1`) isosurface.
- Use the `daspect`, `view`, and `axis` commands to set up the view and then add a `title`.

- The `shrinkfaces` command modifies the face/vertex data and passes it directly to `patch`.

```
[x,y,z,v] = flow;
[x,y,z,v] = reducevolume(x,y,z,v,2);
fv = isosurface(x,y,z,v,-3);
p1 = patch(fv);
set(p1,'FaceColor','red','EdgeColor',[.5,.5,.5]);
daspect([1 1 1]); view(3); axis tight
title('Original')

figure
p2 = patch(shrinkfaces(fv,.3));
set(p2,'FaceColor','red','EdgeColor',[.5,.5,.5]);
daspect([1 1 1]); view(3); axis tight
title('After Shrinking')
```





See Also

`isosurface`, `patch`, `reducevolume`, `daspect`, `view`, `axis`

"Volume Visualization" for related functions

sign

Purpose

Signum function

Syntax

```
Y = sign(X)
```

Description

`Y = sign(X)` returns an array `Y` the same size as `X`, where each element of `Y` is:

- `1` if the corresponding element of `X` is greater than zero
- `0` if the corresponding element of `X` equals zero
- `-1` if the corresponding element of `X` is less than zero

For nonzero complex `X`, `sign(X) = X./abs(X)`.

See Also

`abs`, `conj`, `imag`, `real`

Purpose

Sine of an argument in radians

Syntax

```
Y = sin(X)
```

Description

The `sin` function operates element-wise on arrays. The function's domains and ranges include complex values. All angles are in radians.

`Y = sin(X)` returns the circular sine of the elements of `X`.

Examples

Graph the sine function over the domain $-\pi \le x \le \pi$.

```
x = -pi:0.01:pi;
plot(x,sin(x)), grid on
```



The expression `sin(pi)` is not exactly zero, but rather a value the size of the floating-point accuracy `eps`, because `pi` is only a floating-point approximation to the exact value of π.

Definition

The sine can be defined as

$$\sin(x+iy) = \sin(x)\cosh(y) + i\cos(x)\sinh(y)$$

$$\sin(z) = \frac{e^{iz} - e^{-iz}}{2i}$$

Algorithm

`sin` uses FDLIBM, which was developed at SunSoft, a Sun Microsystems, Inc. business, by Kwok C. Ng, and others. For information about FDLIBM, see `http://www.netlib.org`.

See Also

`asin`, `asinh`, `sind`, `sinh`

Purpose

Sine of an argument in degrees

Syntax

```
Y = sind(X)
```

Description

`Y = sind(X)` is the sine of the elements of `X`, expressed in degrees. For integers `n`, `sind(n*180)` is exactly zero, whereas `sin(n*pi)` reflects the accuracy of the floating point value of `pi`.

See Also

`asind`, `sin`

single

Purpose

Convert to single-precision

Syntax

```
B = single(A)
```

Description

`B = single(A)` converts the matrix `A` to single precision, returning that value in `B`. `A` can be any numeric object (such as a `double`). If `A` is already single precision, `single` has no effect. Single-precision quantities require less storage than double-precision quantities, but have less precision and a smaller range.

The `single` class is primarily meant to be used to store single-precision values. Hence most operations that manipulate arrays without changing their elements are defined. Examples are `reshape`, `size`, the relational operators, subscripted assignment, and subscripted reference.

You can define your own methods for the `single` class by placing the appropriately named method in an `@single` directory within a directory on your path.

Examples

```
a = magic(4);
b = single(a);

whos
  Name      Size         Bytes  Class

  a         4x4            128  double array
  b         4x4             64  single array
```

See Also

`double`

Purpose

Hyperbolic sine of an argument in radians

Syntax

```
Y = sinh(X)
```

Description

The `sinh` function operates element-wise on arrays. The function's domains and ranges include complex values. All angles are in radians.

`Y = sinh(X)` returns the hyperbolic sine of the elements of `X`.

Examples

Graph the hyperbolic sine function over the domain $-5 \le x \le 5$.

```
x = -5:0.01:5;
plot(x,sinh(x)), grid on
```



Definition

The hyperbolic sine can be defined as

$$\sinh(z) = \frac{e^z - e^{-z}}{2}$$

Algorithm

`sinh` uses FDLIBM, which was developed at SunSoft, a Sun Microsystems, Inc. business, by Kwok C. Ng, and others. For information about FDLIBM, see `http://www.netlib.org`.

See Also

`asin`, `asinh`, `sin`

size

Purpose

Array dimensions

Syntax

```
d = size(X)
[m,n] = size(X)
m = size(X,dim)
[d1,d2,d3,...,dn] = size(X)
```

Description

`d = size(X)` returns the sizes of each dimension of array `X` in a vector `d` with `ndims(X)` elements.

`[m,n] = size(X)` returns the size of matrix `X` in separate variables `m` and `n`.

`m = size(X,dim)` returns the size of the dimension of `X` specified by scalar `dim`.

`[d1,d2,d3,...,dn] = size(X)` returns the sizes of the first `n` dimensions of array `X` in separate variables.

If the number of output arguments `n` does not equal `ndims(X)`, then for:

`n > ndims(X)`	`size` returns ones in the "extra" variables, i.e., outputs `ndims(X)+1` through `n`.
`n < ndims(X)`	`dn` contains the product of the sizes of the remaining dimensions of `X`, i.e., dimensions `n+1` through `ndims(X)`.

Note For a Java array, `size` returns the length of the Java array as the number of rows. The number of columns is always 1. For a Java array of arrays, the result describes only the top level array.

Examples

Example 1. The size of the second dimension of `rand(2,3,4)` is 3.

```
m = size(rand(2,3,4),2)

m =
     3
```

Here the size is output as a single vector.

```
d = size(rand(2,3,4))

d =
     2     3     4
```

Here the size of each dimension is assigned to a separate variable.

```
[m,n,p] = size(rand(2,3,4))
m =
     2

n =
     3

p =
     4
```

Example 2. If `X = ones(3,4,5)`, then

```
[d1,d2,d3] = size(X)

d1 =       d2 =       d3 =
     3          4          5
```

But when the number of output variables is less than `ndims(X)`:

```
[d1,d2] = size(X)

d1 =       d2 =
     3          20
```

The “extra” dimensions are collapsed into a single product.

If `n > ndims(X)`, the “extra” variables all represent singleton dimensions:

```
[d1,d2,d3,d4,d5,d6] = size(X)

d1 =       d2 =       d3 =
     3          4          5

d4 =       d5 =       d6 =
     1          1          1
```

See Also exist, length, numel, whos

Purpose

Volumetric slice plot

Syntax

```
slice(V,sx,sy,sz)
slice(X,Y,Z,V,sx,sy,sz)
slice(V,XI,YI,ZI)
slice(X,Y,Z,V,XI,YI,ZI)
slice(...,'method')
slice(axes_handle,...)
h = slice(...)
```

Description

`slice` displays orthogonal slice planes through volumetric data.

`slice(V,sx,sy,sz)` draws slices along the *x*, *y*, *z* directions in the volume `V` at the points in the vectors `sx`, `sy`, and `sz`. `V` is an *m*-by-*n*-by-*p* volume array containing data values at the default location `X = 1:n`, `Y = 1:m`, `Z = 1:p`. Each element in the vectors `sx`, `sy`, and `sz` defines a slice plane in the *x*-, *y*-, or *z*-axis direction.

`slice(X,Y,Z,V,sx,sy,sz)` draws slices of the volume `V`. `X`, `Y`, and `Z` are three-dimensional arrays specifying the coordinates for `V`. `X`, `Y`, and `Z` must be monotonic and orthogonally spaced (as if produced by the function `meshgrid`). The color at each point is determined by 3-D interpolation into the volume `V`.

`slice(V,XI,YI,ZI)` draws data in the volume `V` for the slices defined by `XI`, `YI`, and `ZI`. `XI`, `YI`, and `ZI` are matrices that define a surface, and the volume is evaluated at the surface points. `XI`, `YI`, and `ZI` must all be the same size.

`slice(X,Y,Z,V,XI,YI,ZI)` draws slices through the volume `V` along the surface defined by the arrays `XI`, `YI`, `ZI`.

`slice(...,'method')` specifies the interpolation method. `'method'` is `'linear'`, `'cubic'`, or `'nearest'`.

- `linear` specifies trilinear interpolation (the default).
- `cubic` specifies tricubic interpolation.
- `nearest` specifies nearest-neighbor interpolation.

`slice(axes_handles,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = slice(...)` returns a vector of handles to surface graphics objects.

Remarks

The color drawn at each point is determined by interpolation into the volume `V`.

Examples

Visualize the function

$$v = xe^{(-x^2-y^2-z^2)}$$

over the range –2 ≤x ≤2, –2 ≤y ≤2, 2 ≤z ≤2:

```
[x,y,z] = meshgrid(–2:.2:2,–2:.25:2,–2:.16:2);
v = x.*exp(–x.^2–y.^2–z.^2);
xslice = [–1.2,.8,2]; yslice = 2; zslice = [–2,0];
slice(x,y,z,v,xslice,yslice,zslice)
colormap hsv
```



Slicing At Arbitrary Angles

You can also create slices that are oriented in arbitrary planes. To do this,

- Create a slice surface in the domain of the volume (`surf`, `linspace`).
- Orient this surface with respect to the axes (`rotate`).
- Get the `XData`, `YData`, and `ZData` of the surface (`get`).
- Use this data to draw the slice plane within the volume.

For example, these statements slice the volume in the first example with a rotated plane. Placing these commands within a for loop "passes" the plane through the volume along the *z*-axis.

```
for i = -2:.5:2
   hsp = surf(linspace(-2,2,20),linspace(-2,2,20),zeros(20)+i);
   rotate(hsp,[1,-1,1],30)
   xd = get(hsp,'XData');
   yd = get(hsp,'YData');
   zd = get(hsp,'ZData');
   delete(hsp)
   slice(x,y,z,v,[-2,2],2,-2) % Draw some volume boundaries
   hold on
   slice(x,y,z,v,xd,yd,zd)
   hold off
   axis tight
   view(-5,10)
   drawnow
end
```

The following picture illustrates three positions of the same slice surface as it passes through the volume.



Slicing with a Nonplanar Surface

You can slice the volume with any surface. This example probes the volume created in the previous example by passing a spherical slice surface through the volume.

```
[xsp,ysp,zsp] = sphere;
slice(x,y,z,v,[-2,2],2,-2)  % Draw some volume boundaries

for i = -3:.2:3
   hsp = surface(xsp+i,ysp,zsp);
   rotate(hsp,[1 0 0],90)
   xd = get(hsp,'XData');
   yd = get(hsp,'YData');
   zd = get(hsp,'ZData');
   delete(hsp)
   hold on
   hslicer = slice(x,y,z,v,xd,yd,zd);
   axis tight
```

```
    xlim([-3,3])
    view(-10,35)
    drawnow
    delete(hslicer)
    hold off
end
```

The following picture illustrates three positions of the spherical slice surface as it passes through the volume.



See Also

`interp3`, `meshgrid`

"Volume Visualization" for related functions

Exploring Volumes with Slice Planes for more examples

smooth3

Purpose

Smooth 3-D data

Syntax

```
W = smooth3(V)
W = smooth3(V,'filter')
W = smooth3(V,'filter',size)
W = smooth3(V,'filter',size,sd)
```

Description

`W = smooth3(V)` smoothes the input data `V` and returns the smoothed data in `W`.

`W = smooth3(V,'filter')` *`filter`* determines the convolution kernel and can be the strings

- `'gaussian'`
- `'box'` (default)

`W = smooth3(V,'filter',size)` sets the size of the convolution kernel (default is `[3 3 3]`). If `size` is scalar, then `size` is interpreted as [`size`, `size`, `size`].

`W = smooth3(V,'filter',size,sd)` sets an attribute of the convolution kernel. When *`filter`* is `gaussian`, `sd` is the standard deviation (default is .65).

Examples

This example smoothes some random 3-D data and then creates an isosurface with end caps.

```
rand('seed',0)
data = rand(10,10,10);
data = smooth3(data,'box',5);
p1 = patch(isosurface(data,.5), ...
   'FaceColor','blue','EdgeColor','none');
p2 = patch(isocaps(data,.5), ...
    'FaceColor','interp','EdgeColor','none');
isonormals(data,p1)
view(3); axis vis3d tight
camlight; lighting phong
```



See Also

`isocaps`, `isonormals`, `isosurface`, `patch`

"Volume Visualization" for related functions

See Displaying an Isosurface for another example.

sort

Purpose

Sort array elements in ascending or descending order

Syntax

```
B = sort(A)
B = sort(A,dim)
B = sort(...,mode)
[B,IX] = sort(...)
```

Description

`B = sort(A)` sorts the elements along different dimensions of an array, and arranges those elements in ascending order.

If A is a ...	sort(A) ...
Vector	Sorts the elements of `A`.
Matrix	Sorts each column of `A`.
Multidimensional array	Sorts `A` along the first non-singleton dimension, and returns an array of sorted vectors.
Cell array of strings	Sorts the strings in ASCII dictionary order.

Integer, real, logical, and character arrays are permitted. In addition, any of the numeric types can be complex. For elements of A with identical values, the order of these elements is preserved in the sorted list. When `A` is complex, the elements are sorted by magnitude, i.e., `abs(A)`, and where magnitudes are equal, further sorted by phase angle, i.e., `angle(A)`, on the interval $[-\pi, \pi]$. If `A` includes any `NaN` elements, `sort` places these at the high end.

`B = sort(A,dim)` sorts the elements along the dimension of `A` specified by a scalar `dim`. If `dim` is a vector, `sort` works iteratively on the specified dimensions. Thus, `sort(A,[1 2])` is equivalent to `sort(sort(A,2),1)`.

`B = sort(...,mode)` sorts the elements in the specified direction, depending on the value of `mode`.

`'ascend'`	Ascending order (default)
`'descend'`	Descending order

`[B,IX] = sort(A,...)` also returns an array of indices `IX`, where `size(IX) == size(A)`. If `A` is a vector, `B = A(IX)`. If `A` is an `m`-by-`n` matrix, then each column of `IX` is a permutation vector of the corresponding column of `A`, such that

```
for j = 1:n
    B(:,j) = A(IX(:,j),j);
end
```

If `A` has repeated elements of equal value, the returned indices preserve the original ordering.

Examples

Example 1. This example sorts a matrix `A` in each dimension, and then sorts it a third time, requesting an array of indices for the sorted result.

```
A = [ 3 7 5
      0 4 2 ];

sort(A,1)

ans =
     0     4     2
     3     7     5

sort(A,2)

ans =
     3     5     7
     0     2     4

[B,IX] = sort(A,2)

B =
     3     5     7
     0     2     4

IX =
     1     3     2
     1     3     2
```

Example 2. This example sorts each column of a matrix in descending order.

```
A = [ 3  7  5
      6  8  3
      0  4  2 ];

sort(A,1,'descend')

ans =
     6   8   5
     3   7   3
     0   4   2
```

This is equivalent to

```
sort(A,'descend')

ans =
     6   8   5
     3   7   3
     0   4   2
```

See Also

`max`, `mean`, `median`, `min`, `sortrows`

Purpose

Sort rows in ascending order

Syntax

```
B = sortrows(A)
B = sortrows(A,column)
[B,index] = sortrows(A)
```

Description

`B = sortrows(A)` sorts the rows of `A` as a group in ascending order. Argument `A` must be either a matrix or a column vector.

For strings, this is the familiar dictionary sort. When `A` is complex, the elements are sorted by magnitude, and, where magnitudes are equal, further sorted by phase angle on the interval $[-\pi, \pi]$.

`B = sortrows(A,column)` sorts the matrix based on the columns specified in the vector `column`. For example, `sortrows(A,[2 3])` sorts the rows of `A` by the second column, and where these are equal, further sorts by the third column.

`[B,index] = sortrows(A)` also returns an index vector `index`.

If `A` is a column vector, then `B = A(index)`.

If `A` is an `m`-by-`n` matrix, then `B = A(index,:)`.

Examples

Given the 5-by-5 string matrix,

```
A = ['one  ';'two  ';'three';'four ';'five '];
```

The commands `B = sortrows(A)` and `C = sortrows(A,1)` yield

```
B =         C =
    five        four
    four        five
    one         one
    three       two
    two         three
```

See Also

`sort`

sound

Purpose

Convert vector into sound

Syntax

```
sound(y,Fs)
sound(y)
sound(y,Fs,bits)
```

Description

`sound(y,Fs)` sends the signal in vector `y` (with sample frequency `Fs`) to the speaker on PC and most UNIX platforms. Values in `y` are assumed to be in the range $-1.0 \le y \le 1.0$. Values outside that range are clipped. Stereo sound is played on platforms that support it when `y` is an `n`-by-2 matrix.

Note The playback duration that results from setting `Fs` depends on the sound card you have installed. Most sound cards support sample frequencies of approximately 5-10 kHz to 44.1 kHz. Sample frequencies outside this range can produce unexpected results.

`sound(y)` plays the sound at the default sample rate or 8192 Hz.

`sound(y,Fs,bits)` plays the sound using `bits` number of bits/sample, if possible. Most platforms support `bits = 8` or `bits = 16`.

Remarks

MATLAB supports all Windows-compatible sound devices.

See Also

`auread`, `auwrite`, `soundsc`, `wavread`, `wavwrite`

Purpose

Scale data and play as sound

Syntax

```
soundsc(y,Fs)
soundsc(y)
soundsc(y,Fs,bits)
soundsc(y,...,slim)
```

Description

`soundsc(y,Fs)` sends the signal in vector `y` (with sample frequency `Fs`) to the speaker on PC and most UNIX platforms. The signal `y` is scaled to the range $-1.0 \le y \le 1.0$ before it is played, resulting in a sound that is played as loud as possible without clipping.

Note The playback duration that results from setting `Fs` depends on the sound card you have installed. Most sound cards support sample frequencies of approximately 5-10 kHz to 44.1 kHz. Sample frequencies outside this range can produce unexpected results.

`soundsc(y)` plays the sound at the default sample rate or 8192 Hz.

`soundsc(y,Fs,bits)` plays the sound using `bits` number of bits/sample if possible. Most platforms support `bits = 8` or `bits = 16`.

`soundsc(y,...,slim)`, where `slim = [slow shigh]`, maps the values in `y` between `slow` and `shigh` to the full sound range. The default value is `slim = [min(y) max(y)]`.

Remarks

MATLAB supports all Windows-compatible sound devices.

See Also

`auread`, `auwrite`, `sound`, `wavread`, `wavwrite`

spalloc

Purpose

Allocate space for sparse matrix

Syntax

```
S = spalloc(m,n,nzmax)
```

Description

`S = spalloc(m,n,nzmax)` creates an all zero sparse matrix `S` of size `m`-by-`n` with room to hold `nzmax` nonzeros. The matrix can then be generated column by column without requiring repeated storage allocation as the number of nonzeros grows.

`spalloc(m,n,nzmax)` is shorthand for

```
sparse([],[],[],m,n,nzmax)
```

Examples

To generate efficiently a sparse matrix that has an average of at most three nonzero elements per column

```
S = spalloc(n,n,3*n);
for j = 1:n
    S(:,j) = [zeros(n-3,1)' round(rand(3,1))'];
end
```

Purpose

Create sparse matrix

Syntax

```
S = sparse(A)
S = sparse(i,j,s,m,n,nzmax)
S = sparse(i,j,s,m,n)
S = sparse(i,j,s)
S = sparse(m,n)
```

Description

The `sparse` function generates matrices in the MATLAB sparse storage organization.

`S = sparse(A)` converts a full matrix to sparse form by squeezing out any zero elements. If `S` is already sparse, `sparse(S)` returns `S`.

`S = sparse(i,j,s,m,n,nzmax)` uses vectors `i`, `j`, and `s` to generate an `m`-by-`n` sparse matrix such that `S(i(k),j(k)) = s(k)`, with space allocated for `nzmax` nonzeros. Vectors `i`, `j`, and `s` are all the same length. Any elements of `s` that are zero are ignored, along with the corresponding values of `i` and `j`. Any elements of `s` that have duplicate values of `i` and `j` are added together.

Note If any value in `i` or `j` is larger than the maximum integer size, `2^31-1`, then the sparse matrix cannot be constructed.

To simplify this six-argument call, you can pass scalars for the argument `s` and one of the arguments `i` or `j`—in which case they are expanded so that `i`, `j`, and `s` all have the same length.

`S = sparse(i,j,s,m,n)` uses `nzmax = length(s)`.

`S = sparse(i,j,s)` uses `m = max(i)` and `n = max(j)`. The maxima are computed before any zeros in `s` are removed, so one of the rows of `[i j s]` might be `[m n 0]`.

`S = sparse(m,n)` abbreviates `sparse([],[],[],m,n,0)`. This generates the ultimate sparse matrix, an `m`-by-`n` all zero matrix.

Remarks

All of the MATLAB built-in arithmetic, logical, and indexing operations can be applied to sparse matrices, or to mixtures of sparse and full matrices. Operations on sparse matrices return sparse matrices and operations on full matrices return full matrices.

In most cases, operations on mixtures of sparse and full matrices return full matrices. The exceptions include situations where the result of a mixed operation is structurally sparse, for example, `A.*S` is at least as sparse as `S`.

Note If you divide a sparse matrix `S` by `0`, for each entry of `S` that is `0`, the corresponding entry of `S/0` is also `0`. This differs from the usual MATLAB arithmetic rule that `0/0 = NaN`, which applies to nonsparse matrices.

Examples

`S = sparse(1:n,1:n,1)` generates a sparse representation of the `n`-by-`n` identity matrix. The same `S` results from `S = sparse(eye(n,n))`, but this would also temporarily generate a full `n`-by-`n` matrix with most of its elements equal to zero.

`B = sparse(10000,10000,pi)` is probably not very useful, but is legal and works; it sets up a `10000`-by-`10000` matrix with only one nonzero element. Don't try `full(B)`; it requires 800 megabytes of storage.

This dissects and then reassembles a sparse matrix:

```
[i,j,s] = find(S);
[m,n] = size(S);
S = sparse(i,j,s,m,n);
```

So does this, if the last row and column have nonzero entries:

```
[i,j,s] = find(S);
S = sparse(i,j,s);
```

See Also

`diag`, `find`, `full`, `nnz`, `nonzeros`, `nzmax`, `spones`, `sprandn`, `sprandsym`, `spy`

The `sparfun` directory

Purpose

Form least squares augmented system

Syntax

```
S = spaugment(A,c)
```

Description

`S = spaugment(A,c)` creates the sparse, square, symmetric indefinite matrix `S = [c*I A; A' 0]`. The matrix `S` is related to the least squares problem

```
min norm(b - A*x)
```

by

```
r = b - A*x
S * [r/c; x] = [b; 0]
```

The optimum value of the residual scaling factor `c`, involves `min(svd(A))` and `norm(r)`, which are usually too expensive to compute.

`S = spaugment(A)` without a specified value of `c`, uses `max(max(abs(A)))/1000`.

Note In previous versions of MATLAB, the augmented matrix was used by sparse linear equation solvers, `\` and /, for nonsquare problems. Now, MATLAB performs a least squares solve using the `qr` factorization of `A` instead.

See Also

`spparms`

spconvert

Purpose

Import matrix from sparse matrix external format

Syntax

```
S = spconvert(D)
```

Description

`spconvert` is used to create sparse matrices from a simple sparse format easily produced by non-MATLAB sparse programs. `spconvert` is the second step in the process:

1. Load an ASCII data file containing `[i,j,v]` or `[i,j,re,im]` as rows into a MATLAB variable.
2. Convert that variable into a MATLAB sparse matrix.

`S = spconvert(D)` converts a matrix `D` with rows containing `[i,j,s]` or `[i,j,r,s]` to the corresponding sparse matrix. `D` must have an `nnz` or `nnz+1` row and three or four columns. Three elements per row generate a real matrix and four elements per row generate a complex matrix. A row of the form `[m n 0]` or `[m n 0 0]` anywhere in `D` can be used to specify `size(S)`. If `D` is already sparse, no conversion is done, so `spconvert` can be used after `D` is loaded from either a MAT-file or an ASCII file.

Examples

Suppose the ASCII file `uphill.dat` contains

```
1     1     1.000000000000000
1     2     0.500000000000000
2     2     0.333333333333333
1     3     0.333333333333333
2     3     0.250000000000000
3     3     0.200000000000000
1     4     0.250000000000000
2     4     0.200000000000000
3     4     0.166666666666667
4     4     0.142857142857143
4     4     0.000000000000000
```

Then the statements

```
load uphill.dat
H = spconvert(uphill)
```

```
H =
   (1,1)        1.0000
   (1,2)        0.5000
   (2,2)        0.3333
   (1,3)        0.3333
   (2,3)        0.2500
   (3,3)        0.2000
   (1,4)        0.2500
   (2,4)        0.2000
   (3,4)        0.1667
   (4,4)        0.1429
```

recreate `sparse(triu(hilb(4)))`, possibly with roundoff errors. In this case, the last line of the input file is not necessary because the earlier lines already specify that the matrix is at least 4-by-4.

spdiags

Purpose

Extract and create sparse band and diagonal matrices

Syntax

```
[B,d] = spdiags(A)
B = spdiags(A,d)
A = spdiags(B,d,A)
A = spdiags(B,d,m,n)
```

Description

The `spdiags` function generalizes the function `diag`. Four different operations, distinguished by the number of input arguments, are possible:

`[B,d] = spdiags(A)` extracts all nonzero diagonals from the `m`-by-`n` matrix `A`. `B` is a `min(m,n)`-by-`p` matrix whose columns are the `p` nonzero diagonals of `A`. `d` is a vector of length `p` whose integer components specify the diagonals in `A`.

`B = spdiags(A,d)` extracts the diagonals specified by `d`.

`A = spdiags(B,d,A)` replaces the diagonals specified by `d` with the columns of `B`. The output is sparse.

`A = spdiags(B,d,m,n)` creates an `m`-by-`n` sparse matrix by taking the columns of `B` and placing them along the diagonals specified by `d`.

Note If a column of `B` is longer than the diagonal it's replacing, `spdiags` takes elements of super-diagonals from the lower part of the column of `B`, and elements of sub-diagonals from the upper part of the column of `B`.

Arguments

The `spdiags` function deals with three matrices, in various combinations, as both input and output.

`A` An `m`-by-`n` matrix, usually (but not necessarily) sparse, with its nonzero or specified elements located on `p` diagonals.

`B` A `min(m,n)`-by-`p` matrix, usually (but not necessarily) full, whose columns are the diagonals of `A`.

`d` A vector of length `p` whose integer components specify the diagonals in `A`.

Roughly, A, B, and d are related by

```
for k = 1:p
    B(:,k) = diag(A,d(k))
end
```

Some elements of B, corresponding to positions outside of A, are not defined by these loops. They are not referenced when B is input and are set to zero when B is output.

Examples

Example 1. This example generates a sparse tridiagonal representation of the classic second difference operator on n points.

```
e = ones(n,1);
A = spdiags([e -2*e e], -1:1, n, n)
```

Turn it into Wilkinson's test matrix (see `gallery`):

```
A = spdiags(abs(-(n-1)/2:(n-1)/2)',0,A)
```

Finally, recover the three diagonals:

```
B = spdiags(A)
```

Example 2. The second example is not square.

```
A = [11    0   13    0
      0   22    0   24
      0    0   33    0
     41    0    0   44
      0   52    0    0
      0    0   63    0
      0    0    0   74]
```

Here `m = 7`, `n = 4`, and `p = 3`.

The statement `[B,d] = spdiags(A)` produces `d = [-3 0 2]'` and

```
B = [41   11    0
     52   22    0
     63   33   13
     74   44   24]
```

Conversely, with the above `B` and `d`, the expression `spdiags(B,d,7,4)` reproduces the original `A`.

Example 3. This example shows how `spdiags` creates the diagonals when the columns of `B` are longer than the diagonals they are replacing.

```
B = repmat((1:6)',[1 7])

B =

     1     1     1     1     1     1     1
     2     2     2     2     2     2     2
     3     3     3     3     3     3     3
     4     4     4     4     4     4     4
     5     5     5     5     5     5     5
     6     6     6     6     6     6     6

d = [-4 -2 -1 0 3 4 5];
A = spdiags(B,d,6,6);
full(A)

ans =

   1   0   0   4   5   6
   1   2   0   0   5   6
   1   2   3   0   0   6
   0   2   3   4   0   0
   1   0   3   4   5   0
   0   2   0   4   5   6
```

See Also

`diag`

Purpose

Sparse identity matrix

Syntax

```
S = speye(m,n)
S = speye(n)
```

Description

`S = speye(m,n)` forms an `m`-by-`n` sparse matrix with `1`s on the main diagonal.

`S = speye(n)` abbreviates `speye(n,n)`.

Examples

`I = speye(1000)` forms the sparse representation of the 1000-by-1000 identity matrix, which requires only about 16 kilobytes of storage. This is the same final result as `I = sparse(eye(1000,1000))`, but the latter requires eight megabytes for temporary storage for the full representation.

See Also

`spalloc`, `spones`, `spdiags`, `sprand`, `sprandn`

spfun

Purpose

Apply function to nonzero sparse matrix elements

Syntax

```
f = spfun(fun,S)
```

Description

The `spfun` function selectively applies a function to only the *nonzero* elements of a sparse matrix `S`, preserving the sparsity pattern of the original matrix (except for underflow or if `fun` returns zero for some nonzero elements of `S`).

`f = spfun(fun,S)` evaluates `fun(S)` on the nonzero elements of `S`. You can specify `fun` as a function handle for an M-file or anonymous function.

Remarks

Functions that operate element-by-element, like those in the `elfun` directory, are the most appropriate functions to use with `spfun`.

Examples

Given the 4-by-4 sparse diagonal matrix

```
S = spdiags([1:4]',0,4,4)

S =
   (1,1)        1
   (2,2)        2
   (3,3)        3
   (4,4)        4
```

Because `fun` returns nonzero values for all nonzero element of `S`, `f = spfun(@exp,S)` has the same sparsity pattern as `S`.

```
f =
   (1,1)        2.7183
   (2,2)        7.3891
   (3,3)       20.0855
   (4,4)       54.5982
```

whereas `exp(S)` has `1`s where `S` has `0`s.

```
full(exp(S))

ans =
    2.7183    1.0000    1.0000    1.0000
    1.0000    7.3891    1.0000    1.0000
```

```
    1.0000    1.0000   20.0855    1.0000
    1.0000    1.0000    1.0000   54.5982
```

See Also function handle (@), anonymous functions

sph2cart

Purpose

Transform spherical coordinates to Cartesian

Syntax

```
[x,y,z] = sph2cart(THETA,PHI,R)
```

Description

`[x,y,z] = sph2cart(THETA,PHI,R)` transforms the corresponding elements of spherical coordinate arrays to Cartesian, or *xyz*, coordinates. `THETA`, `PHI`, and `R` must all be the same size. `THETA` and `PHI` are angular displacements in radians from the positive *x*-axis and from the *x-y* plane, respectively.

Algorithm

The mapping from spherical coordinates to three-dimensional Cartesian coordinates is




```
x = r .* cos(phi) .* cos(theta)
y = r .* cos(phi) .* sin(theta)
      z = r .* sin(phi)
```

See Also

`cart2pol`, `cart2sph`, `pol2cart`

Purpose

Generate sphere

Syntax

```
sphere
sphere(n)
[X,Y,Z] = sphere(...)
```

Description

The `sphere` function generates the *x*-, *y*-, and *z*-coordinates of a unit sphere for use with `surf` and `mesh`.

`sphere` generates a sphere consisting of 20-by-20 faces.

`sphere(n)` draws a `surf` plot of an `n`-by-`n` sphere in the current figure.

`[X,Y,Z] = sphere(n)` returns the coordinates of a sphere in three matrices that are `(n+1)`-by-`(n+1)` in size. You draw the sphere with `surf(X,Y,Z)` or `mesh(X,Y,Z)`.

Examples

Generate and plot a sphere.

```
sphere
axis equal
```



See Also

`cylinder`, `axis equal`

"Polygons and Surfaces" for related functions

Purpose

Spin colormap

Syntax

```
spinmap
spinmap(t)
spinmap(t,inc)
spinmap('inf')
```

Description

The `spinmap` function shifts the colormap RGB values by some incremental value. For example, if the increment equals 1, color 1 becomes color 2, color 2 becomes color 3, etc.

`spinmap` cyclically rotates the colormap for approximately five seconds using an incremental value of 2.

`spinmap(t)` rotates the colormap for approximately `10*t` seconds. The amount of time specified by `t` depends on your hardware configuration (e.g., if you are running MATLAB over a network).

`spinmap(t,inc)` rotates the colormap for approximately `10*t` seconds and specifies an increment `inc` by which the colormap shifts. When `inc` is 1, the rotation appears smoother than the default (i.e., 2). Increments greater than 2 are less smooth than the default. A negative increment (e.g., –2) rotates the colormap in a negative direction.

`spinmap('inf')` rotates the colormap for an infinite amount of time. To break the loop, press **Ctrl-C**.

See Also

`colormap`, `colormapeditor`

"Color Operations" for related functions

spline

Purpose

Cubic spline data interpolation

Syntax

```
pp = spline(x,Y)
yy = spline(x,Y,xx)
```

Description

`pp = spline(x,Y)` returns the piecewise polynomial form of the cubic spline interpolant for later use with `ppval` and the spline utility `unmkpp`. `x` must be a vector.

If `Y` is a vector, `Y(j)` is taken as the value to be matched at `x(j)`, hence `Y` must have the same length as `x`, except in the case described in "Exceptions" (1). The not-a-knot end conditions are used.

If `Y` is a matrix or an `N`-dimensional array, `Y(:,...,:,j)` is taken as the value to be matched at `x(j)`, hence the last dimension of `Y` must equal `length(x)`, except in the case described in "Exceptions" (2).

`yy = spline(x,Y,xx)` is the same as `yy = ppval(spline(x,Y),xx)`, thus providing, in `yy`, the values of the interpolant at `xx`. For information regarding the size of `yy`, see `ppval`.

Exceptions

1. If `Y` is a vector that contains two more values than `x` has entries, the first and last value in `Y` are used as the endslopes for the cubic spline. If `Y` is a vector, this means
   - `f(x) = Y(2:end-1)`
   - `df(min(x)) = Y(1)`
   - `df(max(x)) = Y(end)`
2. If `Y` is a matrix or an `N`-dimensional array with `size(Y,N)` equal to `length(x)+2`, the following hold:
   - `f(x(j))` matches the value `Y(:,...,:,j+1)` for `j=1:length(x)`
   - `Df(min(x))` matches `Y(:,:,...:,1)`
   - `Df(max(x))` matches `Y(:,:,...:,end)`

Note You can also perform spline interpolation using the `interp1` function with the command `interp1(x,y,xx,'spline')`. Note that while `spline`

performs interpolation on rows of an input matrix, `interp1` performs interpolation on columns of an input matrix.

Examples

Example 1. This generates a sine curve, then samples the spline over a finer mesh.

```
x = 0:10;
y = sin(x);
xx = 0:.25:10;
yy = spline(x,y,xx);
plot(x,y,'o',xx,yy)
```



Example 2. This illustrates the use of clamped or complete spline interpolation where end slopes are prescribed. Zero slopes at the ends of an interpolant to the values of a certain distribution are enforced.

```
x = -4:4;
y = [0 .15 1.12 2.36 2.36 1.46 .49 .06 0];
cs = spline(x,[0 y 0]);
xx = linspace(-4,4,101);
```

```
plot(x,y,'o',xx,ppval(cs,xx),'-');
```



Example 3. The two vectors

```
t = 1900:10:1990;
p = [ 75.995  91.972  105.711  123.203  131.669 ...
      150.697 179.323  203.212  226.505  249.633 ];
```

represent the census years from 1900 to 1990 and the corresponding United States population in millions of people. The expression

```
spline(t,p,2000)
```

uses the cubic spline to extrapolate and predict the population in the year 2000. The result is

```
ans =
    270.6060
```

Example 4. The statements

```
x = pi*[0:.5:2];
y = [0  1  0 -1  0  1  0;
```

```
     1  0  1  0 -1  0  1];
pp = spline(x,y);
yy = ppval(pp, linspace(0,2*pi,101));
plot(yy(1,:),yy(2,:),'-b',y(1,2:5),y(2,2:5),'or'), axis equal
```

generate the plot of a circle, with the five data points `y(:,2),...,y(:,6)` marked with o's. Note that this `y` contains two more values (i.e., two more columns) than does `x`, hence `y(:,1)` and `y(:,end)` are used as endslopes.



Example 5. The following code generates sine and cosine curves, then samples the splines over a finer mesh.

```
x = 0:.25:1;
Y = [sin(x); cos(x)];
xx = 0:.1:1;
YY = spline(x,Y,xx);
plot(x,Y(1,:),'o',xx,YY(1,:),'-'); hold on;
plot(x,Y(2,:),'o',xx,YY(2,:),':'); hold off;
```



Algorithm

A tridiagonal linear system (with, possibly, several right sides) is being solved for the information needed to describe the coefficients of the various cubic polynomials which make up the interpolating spline. `spline` uses the functions `ppval`, `mkpp`, and `unmkpp`. These routines form a small suite of functions for working with piecewise polynomials. For access to more advanced features, see the M-file help for these functions and the Spline Toolbox.

See Also

`interp1`, `ppval`, `mkpp`, `unmkpp`

References

[1] de Boor, C., *A Practical Guide to Splines*, Springer-Verlag, 1978.

Purpose

Replace nonzero sparse matrix elements with ones

Syntax

```
R = spones(S)
```

Description

`R = spones(S)` generates a matrix `R` with the same sparsity structure as `S`, but with 1's in the nonzero positions.

Examples

`c = sum(spones(S))` is the number of nonzeros in each column.

`r = sum(spones(S'))'` is the number of nonzeros in each row.

`sum(c)` and `sum(r)` are equal, and are equal to `nnz(S)`.

See Also

`nnz`, `spalloc`, `spfun`

spparms

Purpose

Set parameters for sparse matrix routines

Syntax

```
spparms('key',value)
spparms
values = spparms
[keys,values] = spparms
spparms(values)
value = spparms('key')
spparms('default')
spparms('tight')
```

Description

`spparms('key',value)` sets one or more of the *tunable* parameters used in the sparse routines, particularly the minimum degree orderings, `colmmd` and `symmmd`, and the approximate minimum degree ordering, `colamd`. In ordinary use, you should never need to deal with this function.

The meanings of the `key` parameters are

`'spumoni'` Sparse Monitor flag:

- `0` Produces no diagnostic output, the default
- `1` Produces information about choice of algorithm based on matrix structure, and about storage allocation
- `2` Also produces very detailed information about the sparse matrix algorithms

`'thr_rel'`, `'thr_abs'` Minimum degree threshold is `thr_rel*mindegree + thr_abs`.

`'exact_d'` Nonzero to use exact degrees in minimum degree. Zero to use approximate degrees.

`'supernd'` If positive, minimum degree amalgamates the supernodes every `supernd` stages.

`'rreduce'` If positive, minimum degree does row reduction every `rreduce` stages.

`'wh_frac'` Rows with `density > wh_frac` are ignored in `colmmd`.

`'autommd'`	Nonzero to use minimum degree (MMD) orderings with QR-based \ and /.
`'autoamd'`	Nonzero to use `colamd` ordering with the UMFPACK LU-based \ and /.
`'piv_tol'`	Pivot tolerance used by the UMFPACK LU-based \ and /.
`'bandden'`	Band density used by LAPACK-based \ and / for banded matrices. Band density is defined as (# nonzeros in the band)/(# nonzeros in a full band). If `bandden = 1.0`, never use band solver. If `bandden = 0.0`, always use band solver. Default is `0.5`.

Note Cholesky-based \ and / on symmetric positive definite matrices use `symmmd`.
LU-based \ and / (UMFPACK) on square matrices use a modified `colamd`.
QR-based \ and / on rectangular matrices use `colmmd`.

`spparms`, by itself, prints a description of the current settings.

`values = spparms` returns a vector whose components give the current settings.

`[keys,values] = spparms` returns that vector, and also returns a character matrix whose rows are the keywords for the parameters.

`spparms(values)`, with no output argument, sets all the parameters to the values specified by the argument vector.

`value = spparms('key')` returns the current setting of one parameter.

`spparms('default')` sets all the parameters to their default settings.

`spparms('tight')` sets the minimum degree ordering parameters to their *tight* settings, which can lead to orderings with less fill-in, but which make the ordering functions themselves use more execution time.

The key parameters for `default` and `tight` settings are

	Keyword	Default	Tight
values(1)	'spumoni'	0.0	
values(2)	'thr_rel'	1.1	1.0
values(3)	'thr_abs'	1.0	0.0
values(4)	'exact_d'	0.0	1.0
values(5)	'supernd'	3.0	1.0
values(6)	'rreduce'	3.0	1.0
values(7)	'wh_frac'	0.5	0.5
values(8)	'autommd'	1.0	
values(9)	'autoamd'	1.0	
values(10)	'piv_tol'	0.1	
values(11)	'bandden'	0.5	
values(12)	'umfpack'	1.0	

Notes

Sparse `A\b` on symmetric positive definite `A` uses `symmmd` and Cholesky-based solver. `symmmd` uses the parameter `'autoamd'`to turn the preordering on or off.

Sparse `A\b` on general square `A` uses UMFPACK and its modified `colamd` reordering. `colamd` does not used the parameters above, other than `'autoamd'` which turns the preordering on or off, and `'piv_tol'` which controls the pivot tolerance. UMFPACK also responds to `'spumoni'`, as do the majority of the built-in sparse matrix functions.

See Also

`\`, `chol`, `colamd`, `colmmd`, `symmmd`

References

[1] Gilbert, John R., Cleve Moler, and Robert Schreiber, “Sparse Matrices in MATLAB: Design and Implementation,” *SIAM Journal on Matrix Analysis and Applications*, Vol. 13, 1992, pp. 333-356.

[2] Davis, T. A., *UMFPACK Version 4.0 User Guide* (`http://www.cise.ufl.edu/research/sparse/umfpack/v4.0/UserGuide.pdf`), Dept. of Computer and Information Science and Engineering, Univ. of Florida, Gainesville, FL, 2002.

sprand

Purpose

Sparse uniformly distributed random matrix

Syntax

```
R = sprand(S)
R = sprand(m,n,density)
R = sprand(m,n,density,rc)
```

Description

`R = sprand(S)` has the same sparsity structure as `S`, but uniformly distributed random entries.

`R = sprand(m,n,density)` is a random, `m`-by-`n`, sparse matrix with approximately `density*m*n` uniformly distributed nonzero entries `(0 <= density <= 1)`.

`R = sprand(m,n,density,rc)` also has reciprocal condition number approximately equal to `rc`. `R` is constructed from a sum of matrices of rank one.

If `rc` is a vector of length `lr`, where `lr <= min(m,n)`, then `R` has `rc` as its first `lr` singular values, all others are zero. In this case, `R` is generated by random plane rotations applied to a diagonal matrix with the given singular values. It has a great deal of topological and algebraic structure.

See Also

`sprandn`, `sprandsym`

Purpose

Sparse normally distributed random matrix

Syntax

```
R = sprandn(S)
R = sprandn(m,n,density)
R = sprandn(m,n,density,rc)
```

Description

`R = sprandn(S)` has the same sparsity structure as `S`, but normally distributed random entries with mean `0` and variance `1`.

`R = sprandn(m,n,density)` is a random, `m`-by-`n`, sparse matrix with approximately `density*m*n` normally distributed nonzero entries `(0 <= density <= 1)`.

`R = sprandn(m,n,density,rc)` also has reciprocal condition number approximately equal to `rc`. `R` is constructed from a sum of matrices of rank one.

If `rc` is a vector of length `lr`, where `lr <= min(m,n)`, then `R` has `rc` as its first `lr` singular values, all others are zero. In this case, `R` is generated by random plane rotations applied to a diagonal matrix with the given singular values. It has a great deal of topological and algebraic structure.

See Also

`sprand`, `sprandsym`

sprandsym

Purpose

Sparse symmetric random matrix

Syntax

```
R = sprandsym(S)
R = sprandsym(n,density)
R = sprandsym(n,density,rc)
R = sprandsym(n,density,rc,kind)
```

Description

`R = sprandsym(S)` returns a symmetric random matrix whose lower triangle and diagonal have the same structure as `S`. Its elements are normally distributed, with mean `0` and variance `1`.

`R = sprandsym(n,density)` returns a symmetric random, `n`-by-`n`, sparse matrix with approximately `density*n*n` nonzeros; each entry is the sum of one or more normally distributed random samples, and `(0 <= density <= 1)`.

`R = sprandsym(n,density,rc)` returns a matrix with a reciprocal condition number equal to `rc`. The distribution of entries is nonuniform; it is roughly symmetric about 0; all are in $[-1, 1]$.

If `rc` is a vector of length `n`, then `R` has eigenvalues `rc`. Thus, if `rc` is a positive (nonnegative) vector then `R` is a positive definite matrix. In either case, `R` is generated by random Jacobi rotations applied to a diagonal matrix with the given eigenvalues or condition number. It has a great deal of topological and algebraic structure.

`R = sprandsym(n,density,rc,kind)` returns a positive definite matrix. Argument `kind` can be:

- `1` to generate `R` by random Jacobi rotation of a positive definite diagonal matrix. `R` has the desired condition number exactly.
- `2` to generate an `R` that is a shifted sum of outer products. `R` has the desired condition number only approximately, but has less structure.
- `3` to generate an `R` that has the same structure as the matrix `S` and approximate condition number `1/rc`. `density` is ignored.

See Also

`sprand`, `sprandn`

Purpose

Structural rank

Syntax

```
r = sprank(A)
```

Description

`r = sprank(A)` is the structural rank of the sparse matrix `A`. Also known as maximum traversal, maximum assignment, and size of a maximum matching in the bipartite graph of `A`.

Always `sprank(A) >= rank(full(A))`, and in exact arithmetic `sprank(A) == rank(full(sprandn(A)))` with probability one.

Examples

```
A = [1    0    2    0
     2    0    4    0 ];

A = sparse(A);

sprank(A)

ans =
     2

rank(full(A))

ans =
     1
```

See Also

`dmperm`

sprintf

Purpose

Write formatted data to a string

Syntax

```
[s, errmsg] = sprintf(format, A, ...)
```

Description

`[s, errmsg] = sprintf(format, A, ...)` formats the data in matrix `A` (and in any additional matrix arguments) under control of the specified `format` string and returns it in the MATLAB string variable `s`. The `sprintf` function returns an error message string `errmsg` if an error occurred. `errmsg` is an empty matrix if no error occurred.

`sprintf` is the same as `fprintf` except that it returns the data in a MATLAB string variable rather than writing it to a file.

Format String

The `format` argument is a string containing C language conversion specifications. A conversion specification controls the notation, alignment, significant digits, field width, and other aspects of output format. The format string can contain escape characters to represent nonprinting characters such as newline characters and tabs.

Conversion specifications begin with the `%` character and contain these optional and required elements:

- Flags (optional)
- Width and precision fields (optional)
- A subtype specifier (optional)
- Conversion character (required)

You specify these elements in the following order:

Flags

You can control the alignment of the output using any of these optional flags.

Character	Description	Example
A minus sign (`-`)	Left-justifies the converted argument in its field	`% 5.2d`
A plus sign (`+`)	Always prints a sign character (+ or –)	`%+5.2d`
Zero (`0`)	Pad with zeros rather than spaces.	`%05.2d`

Field Width and Precision Specifications

You can control the width and precision of the output by including these options in the format string.

Character	Description	Example
Field width	A digit string specifying the minimum number of digits to be printed.	`%6f`
Precision	A digit string including a period (.) specifying the number of digits to be printed to the right of the decimal point	`%6.2f`

Conversion Characters

Conversion characters specify the notation of the output.

Specifier	Description
`%c`	Single character
`%d`	Decimal notation (signed)
`%e`	Exponential notation (using a lowercase `e` as in `3.1415e+00`)
`%E`	Exponential notation (using an uppercase `E` as in `3.1415E+00`)

Specifier	Description
%f	Fixed-point notation
%g	The more compact of %e or %f, as defined in [2]. Insignificant zeros do not print.
%G	Same as %g, but using an uppercase E
%o	Octal notation (unsigned)
%s	String of characters
%u	Decimal notation (unsigned)
%x	Hexadecimal notation (using lowercase letters a–f)
%X	Hexadecimal notation (using uppercase letters A–F)

The following tables describe the nonalphanumeric characters found in format specification strings.

Escape Characters

This table lists the escape character sequences you use to specify non-printing characters in a format specification.

Character	Description
\b	Backspace
\f	Form feed
\n	New line
\r	Carriage return
\t	Horizontal tab
\\	Backslash

Character	Description
\" or " (two single quotes)	Single quotation mark
%%	Percent character

Remarks

The `sprintf` function behaves like its ANSI C language namesake with these exceptions and extensions.

- If you use `sprintf` to convert a MATLAB double into an integer, and the double contains a value that cannot be represented as an integer (for example, it contains a fraction), MATLAB ignores the specified conversion and outputs the value in exponential format. To successfully perform this conversion, use the `fix`, `floor`, `ceil`, or `round` functions to change the value in the double into a value that can be represented as an integer before passing it to `sprintf`.
- The following nonstandard subtype specifiers are supported for the conversion characters `%o`, `%u`, `%x`, and `%X`.

`b`	The underlying C data type is a double rather than an unsigned integer. For example, to print a double-precision value in hexadecimal, use a format like `'%bx'`.
`t`	The underlying C data type is a float rather than an unsigned integer.

  For example, to print a double value in hexadecimal use the format `'%bx'`.
- The `sprintf` function is vectorized for nonscalar arguments. The function recycles the format string through the elements of `A` (columnwise) until all the elements are used up. The function then continues in a similar manner through any additional matrix arguments.
- If `%s` is used to print part of a nonscalar double argument, the following behavior occurs:
  a. Successive values are printed as long as they are integers and in the range of a valid character. The first invalid character terminates the

printing for this %s specifier and is used for a later specifier. For example, pi terminates the string below and is printed using %f format.

```
Str = [65 66 67 pi];
sprintf('%s %f', Str)
ans =
ABC 3.141593
```

b If the first value to print is not a valid character, then just that value is printed for this %s specifier using an e conversion as a warning to the user. For example, pi is formatted by %s below in exponential notation, and 65, though representing a valid character, is formatted as fixed-point (%f).

```
Str = [pi 65 66 67];
sprintf('%s %f %s', Str)
ans =
3.141593e+000 65.000000 BC
```

c One exception is zero, which is a valid character. If zero is found first, %s prints nothing and the value is skipped. If zero is found after at least one valid character, it terminates the printing for this %s specifier and is used for a later specifier.

- sprintf prints negative zero and exponents differently on some platforms, as shown in the following tables.

Negative Zero Printed with %e, %E, %f, %g, or %G

	Display of Negative Zero		
Platform	**%e or %E**	**%f**	**%g or %G**
PC	0.000000e+000	0.000000	0
Others	-0.000000e+00	-0.000000	-0

Exponents Printed with %e, %E, %g, or %G

Platform	Minimum Digits in Exponent	Example
PC	3	1.23e+004
UNIX	2	1.23e+04

You can resolve this difference in exponents by postprocessing the results of `sprintf`. For example, to make the PC output look like that of UNIX, use

```
a = sprintf('%e', 12345.678);
if ispc, a = strrep(a, 'e+0', 'e+');   end
```

Examples

Command	Result
`sprintf('%0.5g',(1+sqrt(5))/2)`	`1.618`
`sprintf('%0.5g',1/eps)`	`4.5036e+15`
`sprintf('%15.5f',1/eps)`	`4503599627370496.00000`
`sprintf('%d',round(pi))`	`3`
`sprintf('%s','hello')`	`hello`
`sprintf('The array is %dx%d.',2,3)`	`The array is 2x3`
`sprintf('\n')`	Line termination character on all platforms

See Also

`int2str`, `num2str`, `sscanf`

References

[1] Kernighan, B.W., and D.M. Ritchie, *The C Programming Language*, Second Edition, Prentice-Hall, Inc., 1988.

[2] ANSI specification X3.159-1989: “Programming Language C,” ANSI, 1430 Broadway, New York, NY 10018.

spy

Purpose

Visualize sparsity pattern

Syntax

```
spy(S)
spy(S,markersize)
spy(S,'LineSpec')
spy(S,'LineSpec',markersize)
```

Description

`spy(S)` plots the sparsity pattern of any matrix `S`.

`spy(S,markersize)`, where `markersize` is an integer, plots the sparsity pattern using markers of the specified point size.

`spy(S,'LineSpec')`, where `LineSpec` is a string, uses the specified plot marker type and color.

`spy(S,'LineSpec',markersize)` uses the specified type, color, and size for the plot markers.

`S` is usually a sparse matrix, but full matrices are acceptable, in which case the locations of the nonzero elements are plotted.

Note `spy` replaces `format +`, which takes much more space to display essentially the same information.

Examples

This example plots the 60-by-60 sparse adjacency matrix of the connectivity graph of the Buckminster Fuller geodesic dome. This matrix also represents the soccer ball and the carbon-60 molecule.

```
B = bucky;
spy(B)
```



See Also `find`, `gplot`, `LineSpec`, `symamd`, `symmmd`, `symrcm`

sqrt

Purpose

Square root

Syntax

```
B = sqrt(X)
```

Description

`B = sqrt(X)` returns the square root of each element of the array `X`. For the elements of `X` that are negative or complex, `sqrt(X)` produces complex results.

Remarks

See `sqrtm` for the matrix square root.

Examples

```
sqrt((-2:2)')
ans =
      0 + 1.4142i
      0 + 1.0000i
      0
 1.0000
 1.4142
```

See Also

`sqrtm`

Purpose

Matrix square root

Syntax

```
X = sqrtm(A)
[X,resnorm] = sqrtm(A)
[X,alpha,condest] = sqrtm(A)
```

Description

`X = sqrtm(A)` is the principal square root of the matrix `A`, i.e. `X*X = A`.

`X` is the unique square root for which every eigenvalue has nonnegative real part. If `A` has any eigenvalues with negative real parts then a complex result is produced. If `A` is singular then `A` may not have a square root. A warning is printed if exact singularity is detected.

`[X, resnorm] = sqrtm(A)` does not print any warning, and returns the residual, `norm(A-X^2,'fro')/norm(A,'fro')`.

`[X, alpha, condest] = sqrtm(A)` returns a stability factor `alpha` and an estimate `condest` of the matrix square root condition number of `X`. The residual `norm(A-X^2,'fro')/norm(A,'fro')` is bounded approximately by `n*alpha*eps` and the Frobenius norm relative error in `X` is bounded approximately by `n*alpha*condest*eps`, where `n = max(size(A))`.

Remarks

If `X` is real, symmetric and positive definite, or complex, Hermitian and positive definite, then so is the computed matrix square root.

Some matrices, like `X = [0 1; 0 0]`, do not have any square roots, real or complex, and `sqrtm` cannot be expected to produce one.

Examples

Example 1. A matrix representation of the fourth difference operator is

```
X =
     5    -4     1     0     0
    -4     6    -4     1     0
     1    -4     6    -4     1
     0     1    -4     6    -4
     0     0     1    -4     5
```

This matrix is symmetric and positive definite. Its unique positive definite square root, `Y = sqrtm(X)`, is a representation of the second difference operator.

```
Y =
     2    -1    -0    -0    -0
    -1     2    -1     0    -0
     0    -1     2    -1     0
    -0     0    -1     2    -1
    -0    -0    -0    -1     2
```

Example 2. The matrix

```
X =
     7    10
    15    22
```

has four square roots. Two of them are

```
Y1 =
    1.5667    1.7408
    2.6112    4.1779
```

and

```
Y2 =
     1     2
     3     4
```

The other two are `-Y1` and `-Y2`. All four can be obtained from the eigenvalues and vectors of `X`.

```
[V,D] = eig(X);
D =
    0.1386         0
         0   28.8614
```

The four square roots of the diagonal matrix `D` result from the four choices of sign in

```
S =
   –0.3723         0
         0   –5.3723
```

All four `Y`s are of the form

```
Y = V*S/V
```

The `sqrtm` function chooses the two plus signs and produces `Y1`, even though `Y2` is more natural because its entries are integers.

See Also

`expm`, `funm`, `logm`

squeeze

Purpose

Remove singleton dimensions

Syntax

```
B = squeeze(A)
```

Description

`B = squeeze(A)` returns an array `B` with the same elements as `A`, but with all singleton dimensions removed. A singleton dimension is any dimension for which `size(A,dim) = 1`.

Examples

Consider the 2-by-1-by-3 array `Y = rand(2,1,3)`. This array has a singleton column dimension — that is, there's only one column per page.

```
Y =

Y(:,:,1) =      Y(:,:,2) =
       0.5194          0.0346
       0.8310          0.0535

Y(:,:,3) =
       0.5297
       0.6711
```

The command `Z = squeeze(Y)` yields a 2-by-3 matrix:

```
Z =
    0.5194    0.0346    0.5297
    0.8310    0.0535    0.6711
```

See Also

`reshape`, `shiftdim`

Purpose

Read string under format control

Syntax

```
A = sscanf(s, format)
A = sscanf(s, format, size)
[A, count, errmsg, nextindex] = sscanf(...)
```

Description

`A = sscanf(s, format)` reads data from the MATLAB string variable `s`, converts it according to the specified `format` string, and returns it in matrix `A`. `format` is a string specifying the format of the data to be read. See "Remarks" for details. `sscanf` is the same as `fscanf` except that it reads the data from a MATLAB string variable rather than reading it from a file.

`A = sscanf(s, format, size)` reads the amount of data specified by `size` and converts it according to the specified `format` string. `size` is an argument that determines how much data is read. Valid options are

`n`	Read `n` elements into a column vector.
`inf`	Read to the end of the file, resulting in a column vector containing the same number of elements as are in the file.
`[m,n]`	Read enough elements to fill an `m`-by-`n` matrix, filling the matrix in column order. `n` can be `Inf`, but not `m`.

If the matrix `A` results from using character conversions only, and `size` is not of the form `[M,N]`, a row vector is returned.

`sscanf` differs from its C language namesakes `scanf()` and `fscanf()` in an important respect — it is *vectorized* in order to return a matrix argument. The `format` string is cycled through the file until an end-of-file is reached or the amount of data specified by `size` is read in.

`[A, count, errmsg, nextindex] = sscanf(...)` reads data from the MATLAB string variable `s`, converts it according to the specified `format` string, and returns it in matrix `A`. `count` is an optional output argument that returns the number of elements successfully read. `errmsg` is an optional output argument that returns an error message string if an error occurred or an empty matrix if an error did not occur. `nextindex` is an optional output argument specifying one more than the number of characters scanned in `s`.

Remarks

When MATLAB reads a specified file, it attempts to match the data in the file to the format string. If a match occurs, the data is written into the matrix in column order. If a partial match occurs, only the matching data is written to the matrix, and the read operation stops.

The `format` string consists of ordinary characters and/or conversion specifications. Conversion specifications indicate the type of data to be matched and involve the character `%`, optional width fields, and conversion characters, organized as shown below:

Add one or more of these characters between the `%` and the conversion character.

An asterisk (`*`)	Skip over the matched value if the value is matched but not stored in the output matrix.
A digit string	Maximum field width
A letter	The size of the receiving object; for example, `h` for short, as in `%hd` for a short integer, or `l` for long, as in `%ld` for a long integer or `%lg` for a double floating-point number

Valid conversion characters are as shown.

`%c`	Sequence of characters; number specified by field width
`%d`	Decimal numbers
`%e, %f, %g`	Floating-point numbers
`%i`	Signed integer
`%o`	Signed octal integer
`%s`	A series of non-white-space characters
`%u`	Signed decimal integer

`%x`	Signed hexadecimal integer
`[...]`	Sequence of characters (scanlist)

If `%s` is used, an element read might use several MATLAB matrix elements, each holding one character. Use `%c` to read space characters, or `%s` to skip all white space.

Mixing character and numeric conversion specifications cause the resulting matrix to be numeric and any characters read to appear as their ASCII values, one character per MATLAB matrix element.

For more information about format strings, refer to the `scanf()` and `fscanf()` routines in a C language reference manual.

Examples

Example 1

The statements

```
s = '2.7183  3.1416';
A = sscanf(s,'%f')
```

create a two-element vector containing poor approximations to `e` and `pi`.

Example 2

Create matrix `A` with both character and numeric data:

```
A = ['abc 46 6 ghi'; 'def 7 89 jkl']
A =
   abc 46 6 ghi
   def 7 89 jkl
```

Read `A` into 2-by-N matrix `B`, ignoring the character data. As stated in the Description section, `sscanf` fills matrix `B` in column order:

```
B = sscanf(A, '%*s %d %d %*s', [2, inf])
B =
   476
   869
```

If you want sscanf to return the numeric data in B in the same order as in A, you can use this technique:

```
for k = 1:2
   C(k,:) = sscanf(A(k, :)', '%*s %d %d %*s', [1, inf]);
end

C
C =
    46     6
     7    89
```

See Also eval, sprintf, textread

Purpose

Stairstep graph

Syntax

```
stairs(Y)
stairs(X,Y)
stairs(...,LineSpec)
stairs(...,'PropertyName',propertyvalue)
stairs(axes_handle,...)
h = stairs(...)
[xb,yb] = stairs(Y,...)
```

Description

Stairstep graphs are useful for drawing time-history graphs of digitally sampled data.

`stairs(Y)` draws a stairstep graph of the elements of `Y`, drawing one line per column for matrices. The axes `ColorOrder` property determines the color of the lines.

When `Y` is a vector, the *x*-axis scale ranges from `1` to `length(Y)`. When `Y` is a matrix, the *x*-axis scale ranges from `1` to the number of rows in `Y`.

`stairs(X,Y)` plots the elements in `Y` at the locations specified in `X`. The elements of `X` must be monotonic.

`X` must be the same size as `Y` or, if Y is a matrix, `X` can be a row or a column vector such that

```
length(X) = size(Y,1)
```

`stairs(...,LineSpec)` specifies a line style, marker symbol, and color for the graph (see `LineSpec` for more information).

`stairs(...,'PropertyName',propertyvalue)` creates the stairstep graph, applying the specified property settings. See Stairseries Properties for a description of properties.

`stairs(axes_handles,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = stairs(...)` returns the handles of the stairseries objects created (one per matrix column).

`[xb,yb] = stairs(Y,...)` does not draw graphs, but returns vectors `xb` and `yb` such that `plot(xb,yb)` plots the stairstep graph.

Backward Compatible Version

`hlines = stairs('v6',...)` returns the handles of line objects instead of stairseries objects for compatibility with MATLAB 6.5 and earlier.

Examples

Create a stairstep plot of a sine wave.

```
x = linspace(-2*pi,2*pi,40);
stairs(x,sin(x))
```



See Also

`bar`, `hist`, `stem`

"Discrete Data Plots" for related functions

See "Stairseries Properties" for property descriptions

Modifying Properties

You can set and query graphics object properties using the `set` and `get` commands or the Property Editor (`propertyeditor`).

Note that you cannot define default property values for stairseries objects.

See Plot Objects for information on stairseries objects.

Stairseries Property Descriptions

This section provides a description of properties. Curly braces { } enclose default values.

`BeingDeleted` `on | {off}` Read Only

This object is being deleted. The `BeingDeleted` property provides a mechanism that you can use to determine if objects are in the process of being deleted. MATLAB sets the `BeingDeleted` property to `on` when the object's delete function callback is called (see the `DeleteFcn` property). It remains set to `on` while the delete function executes, after which the object no longer exists.

For example, an object's delete function might call other functions that act on a number of different objects. These functions might not need to perform actions on objects if the objects are going to be deleted, and therefore, can check the object's `BeingDeleted` property before acting.

`BusyAction` `cancel | {queue}`

Callback routine interruption. The `BusyAction` property enables you to control how MATLAB handles events that potentially interrupt executing callbacks. If there is a callback function executing, callbacks invoked subsequently always attempt to interrupt it.

If the `Interruptible` property of the object whose callback is executing is set to `on` (the default), then interruption occurs at the next point where the event queue is processed. If the `Interruptible` property is `off`, the `BusyAction` property (of the object owning the executing callback) determines how MATLAB handles the event. The choices are

- `cancel` — Discard the event that attempted to execute a second callback routine.
- `queue` — Queue the event that attempted to execute a second callback routine until the current callback finishes.

ButtonDownFcn string or function handle

Button press callback function. A callback that executes whenever you press a mouse button while the pointer is over the stairseries object.

This property can be

- A string that is a valid MATLAB expression
- The name of an M-file
- A function handle

The expression executes in the MATLAB workspace.

See Function Handle Callbacks for information on how to use function handles to define the callbacks.

Children array of graphics object handles

Children of the stairseries object. An array containing the handles of all line objects parented to the stairseries object (whether visible or not).

Note that if a child object's `HandleVisibility` property is set to `callback` or `off`, its handle does not show up in the stairs `Children` property unless you set the Root `ShowHiddenHandles` property to `on`:

```
set(0,'ShowHiddenHandles','on')
```

Clipping `{on} | off`

Clipping mode. MATLAB clips stairs plots to the axes plot box by default. If you set `Clipping` to `off`, lines might be displayed outside the axes plot box.

Color `ColorSpec`

Color of lines. A three-element RGB vector or one of the MATLAB predefined names, specifying the line color. See the `ColorSpec` reference page for more information on specifying color.

CreateFcn string or function handle

Callback routine executed during object creation. This property defines a callback that executes when MATLAB creates a stairseries object. You must specify the callback during the creation of the object. For example,

```
stairs(1:10,'CreateFcn',@CallbackFcn)
```

where `@CallbackFcn` is a function handle that references the callback function.

MATLAB executes this routine after setting all other stairseries properties. Setting this property on an existing stairseries object has no effect.

The handle of the object whose `CreateFcn` is being executed is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

`DeleteFcn` string or function handle

Callback executed during object deletion. A callback that executes when the stairseries object is deleted (e.g., this might happen when you issue a `delete` command on the stairseries object, its parent axes, or the figure containing it). MATLAB executes the callback before destroying the object's properties so the callback routine can query these values.

The handle of the object whose `DeleteFcn` is being executed is accessible only through the Root `CallbackObject` property, which can be queried using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

See the `BeingDeleted` property for related information.

`DisplayName` string

Label used by plot legends. The legend and the plot browser use this text for labels for any stairseries objects appearing in these legends.

`EraseMode` `{normal} | none | xor | background`

Erase mode. This property controls the technique MATLAB uses to draw and erase stairs child objects. Alternative erase modes are useful for creating animated sequences, where control of the way individual objects are redrawn is necessary to improve performance and obtain the desired effect.

- `normal` — Redraw the affected region of the display, performing the three-dimensional analysis necessary to ensure that all objects are rendered correctly. This mode produces the most accurate picture, but is the slowest. The other modes are faster, but do not perform a complete redraw and are therefore less accurate.
- `none` — Do not erase objects when they are moved or destroyed. While the objects are still visible on the screen after erasing with `EraseMode` `none`, you

cannot print these objects because MATLAB stores no information about their former locations.

- `xor`— Draw and erase the object by performing an exclusive OR (XOR) with each pixel index of the screen behind it. Erasing the object does not damage the color of the objects behind it. However, the color of the erased object depends on the color of the screen behind it and it is correctly colored only when it is over the axes background color (or the figure background color if the axes `Color` property is set to `none`). That is, it isn't erased correctly if there are objects behind it.
- `background` — Erase the graphics objects by redrawing them in the axes background color, (or the figure background color if the axes `Color` property is set to `none`). This damages other graphics objects that are behind the erased object, but the erased object is always properly colored.

Printing with Nonnormal Erase Modes

MATLAB always prints figures as if the `EraseMode` of all objects is `normal`. This means graphics objects created with `EraseMode` set to `none`, `xor`, or `background` can look different on screen than on paper. On screen, MATLAB can mathematically combine layers of colors (e.g., performing an XOR operation on a pixel color with that of the pixel behind it) and ignore three-dimensional sorting to obtain greater rendering speed. However, these techniques are not applied to the printed output.

Set the axes background color with the axes `Color` property. Set the figure background color with the figure `Color` property.

You can use the MATLAB `getframe` command or other screen capture applications to create an image of a figure containing nonnormal mode objects.

`HandleVisibility` `{on} | callback | off`

Control access to object's handle by command-line users and GUIs. This property determines when an object's handle is visible in its parent's list of children. `HandleVisibility` is useful for preventing command-line users from accidentally accessing the stairseries object.

- `on` — Handles are always visible when `HandleVisibility` is `on`.
- `callback` — Setting `HandleVisibility` to `callback` causes handles to be visible from within callback routines or functions invoked by callback routines, but not from within functions invoked from the command line. This

provides a means to protect GUIs from command-line users, while allowing callback routines to have access to object handles.

- `off` — Setting `HandleVisibility` to `off` makes handles invisible at all times. This might be necessary when a callback invokes a function that might potentially damage the GUI (such as evaluating a user-typed string) and so temporarily hides its own handles during the execution of that function.

Functions Affected by Handle Visibility

When a handle is not visible in its parent's list of children, it cannot be returned by functions that obtain handles by searching the object hierarchy or querying handle properties. This includes `get`, `findobj`, `gca`, `gcf`, `gco`, `newplot`, `cla`, `clf`, and `close`.

Properties Affected by Handle Visibility

When a handle's visibility is restricted using `callback` or `off`, the object's handle does not appear in its parent's `Children` property, figures do not appear in the root's `CurrentFigure` property, objects do not appear in the root's `CallbackObject` property or in the figure's `CurrentObject` property, and axes do not appear in their parent's `CurrentAxes` property.

Overriding Handle Visibility

You can set the root `ShowHiddenHandles` property to `on` to make all handles visible regardless of their `HandleVisibility` settings (this does not affect the values of the `HandleVisibility` properties). See also `findall`.

Handle Validity

Handles that are hidden are still valid. If you know an object's handle, you can set and get its properties and pass it to any function that operates on handles.

`HitTest` `{on} | off`

Selectable by mouse click. `HitTest` determines if the stairseries object can become the current object (as returned by the `gco` command and the figure `CurrentObject` property) as a result of a mouse click on the line objects that compose the stairs plot. If `HitTest` is `off`, clicking the stairseries object selects the object below it (which is usually the axes containing it).

HitTestArea on | {off}

Select stairseries object on lines or area of extent. This property enables you to select stairseries objects in two ways:

- Select by clicking on lines (default).
- Select by clicking anywhere in the extent of the stairstep graph.

When HitTestArea is off, you must click the lines to select the stairseries object. When HitTestArea is on, you can select the stairseries object by clicking anywhere within the extent of the stairstep graph (i.e., anywhere within a rectangle that encloses all the stairstep graph).

Interruptible {on} | off

Callback routine interruption mode. The Interruptible property controls whether a stairseries object callback can be interrupted by callbacks invoked subsequently.

Only callbacks defined for the ButtonDownFcn property are affected by the Interruptible property. MATLAB checks for events that can interrupt a callback only when it encounters a drawnow, figure, getframe, or pause command in the routine. See the BusyAction property for related information.

Setting Interruptible to on allows any graphics object's callback to interrupt callback routines originating from a stairs property. Note that MATLAB does not save the state of variables or the display (e.g., the handle returned by the gca or gcf command) when an interruption occurs.

LineStyle {–} | –– | : | –. | none

Line style. This property specifies the line style used for the stairstep lines. Available line styles are shown in the table.

Symbol	Line Style
–	Solid line (default)
––	Dashed line
:	Dotted line
–.	Dash-dot line

Symbol	Line Style
none	No line

You can use `LineStyle` `none` when you want to place a marker at each point but do not want the points connected with a line (see the `Marker` property).

`LineWidth` scalar

The width of the stairs lines. Specify this value in points (1 point = $^1/_{72}$ inch). The default `LineWidth` is 0.5 points.

`Marker` character (see table)

Marker symbol. The `Marker` property specifies the type of markers that are displayed at the end of the stairs lines. You can set values for the `Marker` property independently from the `LineStyle` property. Supported markers include those shown in the following table.

Marker Specifier	Description
+	Plus sign
o	Circle
*	Asterisk
.	Point
x	Cross
s	Square
d	Diamond
^	Upward-pointing triangle
v	Downward-pointing triangle
>	Right-pointing triangle
<	Left-pointing triangle
p	Five-pointed star (pentagram)

Marker Specifier	Description
h	Six-pointed star (hexagram)
none	No marker (default)

MarkerEdgeColor ColorSpec | none | {auto}

Marker edge color. The color of the marker or the edge color for filled markers (circle, square, diamond, pentagram, hexagram, and the four triangles). ColorSpec defines the color to use. none specifies no color, which makes nonfilled markers invisible. auto sets MarkerEdgeColor to the same color as the stairs Color property.

MarkerFaceColor ColorSpec | {none} | auto

Marker face color. The fill color for markers that are closed shapes (circle, square, diamond, pentagram, hexagram, and the four triangles). ColorSpec defines the color to use. none makes the interior of the marker transparent, allowing the background to show through. auto sets the fill color to the axes color, or the figure color, if the axes Color property is set to none (which is the factory default for axes).

MarkerSize size in points

Marker size. A scalar specifying the size of the marker in points. The default value for MarkerSize is 6 points (1 point = 1/72 inch). Note that MATLAB draws the point marker (specified by the '.' symbol) at one-third the specified size.

Parent handle of axes, hggroup, or hgtransform

Parent of stairseries object. This property contains the handle of the stairseries object's parent. The parent of a stairseries object is the axes, hggroup, or hgtransform object that contains it.

See Objects That Can Contain Other Objects for more information on parenting graphics objects.

Selected on | {off}

Is object selected. When you set this property to on, MATLAB displays selection handles at the corners and midpoints if the SelectionHighlight property is also on (the default). You can, for example, define the ButtonDownFcn callback

to set this property to `on`, thereby indicating that the stairseries object is selected.

`SelectionHighlight` `{on} | off`

Objects are highlighted when selected. When the `Selected` property is `on`, MATLAB indicates the selected state by drawing selection handles on the stairseries object. When `SelectionHighlight` is `off`, MATLAB does not draw the handles.

`Tag` string

User-specified object label. The `Tag` property provides a means to identify graphics objects with a user-specified label. This is particularly useful when you are constructing interactive graphics programs that would otherwise need to define object handles as global variables or pass them as arguments between callbacks.

For example, you might create a stairseries object and set the `Tag` property:

```
t = stairs(Y,'Tag','stairs1')
```

When you want to access the stairseries object, you can use `findobj` to find the stairseries object's handle. The following statement changes the `MarkerFaceColor` property of the object whose `Tag` is `stairs1`.

```
set(findobj('Tag','stairs1'),'MarkerFaceColor','red')
```

`Type` string (read only)

Type of graphics object. This property contains a string that identifies the class of the graphics object. For stairseries objects, `Type` is `'hggroup'`. The following statement finds all the hggroup objects in the current axes.

```
t = findobj(gca,'Type','hggroup');
```

`UIContextMenu` handle of a uicontextmenu object

Associate a context menu with the stairseries object. Assign this property the handle of a uicontextmenu object created in the stairseries object's parent figure. Use the `uicontextmenu` function to create the context menu. MATLAB displays the context menu whenever you right-click over the stairseries object.

UserData array

User-specified data. This property can be any data you want to associate with the stairseries object (including cell arrays and structures). The stairseries object does not set values for this property, but you can access it using the `set` and `get` functions.

Visible `{on} | off`

Visibility of stairseries object and its children. By default, stairseries object visibility is `on`. This means all children of the stairs are visible unless the child object's `Visible` property is set to `off`. Setting a stairseries object's `Visible` property to `off` also makes its children invisible.

XData `array`

X-axis location of stairs. The `stairs` function uses `XData` to label the *x*-axis. `XData` can be either a matrix equal in size to `YData` or a vector equal in length to the number of rows in `YData`. That is, `length(XData) == size(YData,1)`. `XData` must be monotonic.

If you do not specify `XData` (i.e., the input argument `x`), the `stairs` function uses the indices of `YData` to create the stairstep graph. See the `XDataMode` property for related information.

XDataMode `{auto} | manual`

Use automatic or user-specified x-axis values. If you specify `XData` (by setting the `XData` property or specifying the input argument `x`), the `stairs` function sets this property to `manual`.

If you set `XDataMode` to `auto` after having specified `XData`, the `stairs` function resets the stairs locations and *x* tick-mark labels to the indices of the `YData`, overwriting any previous values.

XDataSource string (MATLAB variable)

Link XData to MATLAB variable. Set this property to a MATLAB variable that, by default, is evaluated in the base workspace to generate the `XData`.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change `XData`.

You can use the `refreshdata` function to force an update of the object's data. `refreshdata` also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call `refreshdata`.

See the `refreshdata` reference page for more information.

Note If you change one data source property to return data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

`YData` scalar, vector, or matrix

Stairs plot data. `YData` contains the data plotted in the stairstep graph. Each value in `YData` is represented by a marker in the stairstep graph. If `YData` is a matrix, the `stairs` function creates a line for each column in the matrix.

The input argument `y` in the `stairs` function calling syntax assigns values to `YData`.

`YDataSource` string (MATLAB variable)

Link YData to MATLAB variable. Set this property to a MATLAB variable that, by default, is evaluated in the base workspace to generate the `YData`.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change `YData`.

You can use the `refreshdata` function to force an update of the object's data. `refreshdata` also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call `refreshdata`.

See the `refreshdata` reference page for more information.

Note If you change one data source property to a variable that contains data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

---

start

Purpose

Start timer(s) running

Syntax

```
start(obj)
```

Description

`start(obj)` starts the timer running, represented by the timer object, `obj`. If `obj` is an array of timer objects, `start` starts all the timers. Use the `timer` function to create a timer object.

`start` sets the `Running` property of the timer object, `obj`, to `'on'`, initiates `TimerFcn` callbacks, and executes the `StartFcn` callback.

The timer stops running if one of the following conditions apply:

- The number of `TimerFcn` callbacks specified in `TasksToExecute` have been executed.
- The `stop(obj)` command is issued.
- An error occurred while executing a `TimerFcn` callback.

See Also

`timer`, `stop`

Purpose

Start timer(s) running at the specified time

Syntax

```
startat(obj,time)
startat(obj,S)
startat(obj,S,pivotyear)
startat(obj,Y,M,D)
startat(obj,[Y,M,D])
startat(obj,Y,M,D,H,MI,S)
startat(obj,[Y,M,D,H,MI,S])
```

Description

`startat(obj,time)` starts the timer running, represented by the timer object `obj`, at the time specified by the serial date number `time`. If `obj` is an array of timer objects, `startat` starts all the timers running at the specified time. Use the `timer` function to create the timer object.

`startat` sets the `Running` property of the timer object, `obj`, to `'on'`, initiates `TimerFcn` callbacks, and executes the `StartFcn` callback.

The serial date number, `time`, indicates the number of days that have elapsed since 1-Jan-0000 (starting at 1). See `datenum` for additional information about serial date numbers.

`startat(obj,S)` starts the timer running at the time specified by the date string `S`. The date string must use date format 0, 1, 2, 6, 13, 14, 15, 16, or 23, as defined by the `datestr` function. Date strings with two-character years are interpreted to be within the 100 years centered on the current year.

`startat(obj,S,pivotyear)` uses the specified pivot year as the starting year of the 100-year range in which a two-character year resides. The default pivot year is the current year minus 50 years.

`startat(obj,Y,M,D)`
`startat(obj,[Y,M,D])` start the timer at the year (`Y`), month (`M`), and day (`D`) specified. `Y`, `M`, and `D` must be arrays of the same size (or they can be a scalar).

`startat(obj,Y,M,D,H,MI,S)`
`startat(obj,[Y,M,D,H,MI,S])` start the timer at the year (`Y`), month (`M`), day (`D`), hour (`H`), minute (`MI`), and second (`S`) specified. `Y`, `M`, `D`, `H`, `MI`, and `S` must be arrays of the same size (or they can be a scalar). Values outside the normal range of each array are automatically carried to the next unit (for example,

month values greater than 12 are carried to years). Month values less than 1 are set to be 1; all other units can wrap and have valid negative values.

The timer stops running if one of the following conditions apply:

- The number of `TimerFcn` callbacks specified in `TasksToExecute` have been executed.
- The `stop(obj)` command is issued.
- An error occurred while executing a `TimerFcn` callback.

Examples

This example uses a timer object to execute a function at a specified time.

```
t1=timer('TimerFcn','disp(''it is 10 o''''clock'')');
startat(t1,'10:00:00');
```

This example uses a timer to display a message when an hour has elapsed.

```
t2=timer('TimerFcn','disp(''It has been an hour now.'')');
startat(t2,now+1/24);
```

See Also

`datenum`, `datestr`, `now`, `timer`, `start`, `stop`

Purpose

MATLAB startup M-file for user-defined options

Description

`startup` automatically executes the master M-file `matlabrc.m` and, if it exists, `startup.m`, when MATLAB starts. On multiuser or networked systems, `matlabrc.m` is reserved for use by the system manager. The file `matlabrc.m` invokes the file `startup.m` if it exists on the MATLAB search path.

You can create a `startup.m` file in your own MATLAB directory. The file can include physical constants, Handle Graphics defaults, engineering conversion factors, or anything else you want predefined in your workspace.

There are other ways to predefine aspects of MATLAB. See Startup Options and About Preferences in the MATLAB documentation.

Algorithm

Only `matlabrc.m` is actually invoked by MATLAB at startup. However, `matlabrc.m` contains the statements

```
if exist('startup')==2
    startup
end
```

that invoke `startup.m`. You can extend this process to create additional startup M-files, if required.

See Also

`matlabrc`, `matlabroot`, `path`, `quit`

std

Purpose

Standard deviation

Syntax

```
s = std(X)
s = std(X,flag)
s = std(X,flag,dim)
```

Definition

There are two common textbook definitions for the standard deviation `s` of a data vector `X`.

$$(1)\quad s = \left(\frac{1}{n-1} \sum_{i=1}^{n} (x_i - \bar{x})^2 \right)^{\frac{1}{2}}$$

$$(2)\quad s = \left(\frac{1}{n} \sum_{i=1}^{n} (x_i - \bar{x})^2 \right)^{\frac{1}{2}}$$

where

$$\bar{x} = \frac{1}{n} \sum_{i=1}^{n} x_i$$

and n is the number of elements in the sample. The two forms of the equation differ only in $n-1$ versus n in the divisor.

Description

`s = std(X)`, where `X` is a vector, returns the standard deviation using (1) above. If `X` is a random sample of data from a normal distribution, s^2 is the best *unbiased* estimate of its variance.

If `X` is a matrix, `std(X)` returns a row vector containing the standard deviation of the elements of each column of `X`. If `X` is a multidimensional array, `std(X)` is the standard deviation of th elements along the first nonsingleton dimension of `X`.

`s = std(X,flag)` for `flag = 0`, is the same as `std(X)`. For `flag = 1`, `std(X,1)` returns the standard deviation using (2) above, producing the second moment of the sample about its mean.

`s = std(X,flag,dim)` computes the standard deviations along the dimension of `X` specified by scalar `dim`.

Examples

For matrix `X`

```
X =
     1     5     9
     7    15    22

s = std(X,0,1)
s =
   4.2426    7.0711    9.1924

s = std(X,0,2)
s =
   4.000
   7.5056
```

See Also

`corrcoef`, `cov`, `mean`, `median`

stem

Purpose

Plot discrete sequence data

Syntax

```
stem(Y)
stem(X,Y)
stem(...,'fill')
stem(...,LineSpec)
stem(axes_handle,...)
h = stem(...)
hlines = stem('v6',...)
```

Description

A two-dimensional stem plot displays data as lines extending from a baseline along the *x*-axis. A circle (the default) or other marker whose *y*-position represents the data value terminates each stem.

`stem(Y)` plots the data sequence `Y` as stems that extend from equally spaced and automatically generated values along the *x*-axis. When `Y` is a matrix, `stem` plots all elements in a row against the same *x* value.

`stem(X,Y)` plots `X` versus the columns of `Y`. `X` and `Y` must be vectors or matrices of the same size. Additionally, `X` can be a row or a column vector and `Y` a matrix with `length(X)` rows.

`stem(...,'fill')` specifies whether to color the circle at the end of the stem.

`stem(...,LineSpec)` specifies the line style, marker symbol, and color for the stem and top marker (the baseline is not affected). See `LineSpec` for more information.

`stem(axes_handles,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = stem(...)` returns a vector of stemseries object handles in `h`, one handle per column of data in `Y`.

Backward Compatible Version

`hlines = stem('v6',...)` returns the handles of line objects instead of stemseries objects for compatibility with MATLAB 6.5 and earlier.

`hlines` contains the handles to three line graphics objects:

- `hlines(1)` — The marker symbol at the top of each stem
- `hlines(2)` — The stem line
- `hlines(3)` — The baseline handle

See Plot Objects and Backward Compatibility for more information.

Examples

Single Series of Data

This example creates a stem plot representing the cosine of 10 values linearly spaced between 0 and 2π. Note that the line style of the baseline is set by first getting its handle from the stemseries object's `BaseLine` property.

```
t = linspace(-2*pi,2*pi,10);
h = stem(t,cos(t),'fill','--');
set(get(h,'BaseLine'),'LineStyle',':')
set(h,'MarkerFaceColor','red')
```



The following diagram illustrates the parent-child relationship in the previous stem plot. Note that the stemseries object contains two line objects used to draw the stem lines and the end markers. The baseline is a separate line object.



Two Series of Data on One Graph

The following example creates a stem plot from a two-column matrix. In this case, the `stem` function creates two stemseries objects, one of each column of data. Both objects' handles are returned in the output argument `h`.

- `h(1)` is the handle to the stemseries object plotting the expression `exp(-.07*x).*cos(x)`.
- `h(2)` is the handle to the stemseries object plotting the expression `exp(.05*x).*cos(x)`.

```
x = 0:25;
y = [exp(-.07*x).*cos(x);exp(.05*x).*cos(x)]';
h = stem(x,y);
set(h(1),'MarkerFaceColor','blue')
set(h(2),'MarkerFaceColor','red','Marker','square')
```



The following diagram illustrates the parent-child relationship in the previous stem plot. Note that each column in the input matrix y results in the creation of a stemseries object, which contains two line objects (one for the stems and one for the markers). The baseline is shared by both stemseries objects.



See Also

`bar`, `plot`, `stairs`

See “Stemseries Properties” for property descriptions

Purpose

Plot three-dimensional discrete sequence data

Syntax

```
stem3(Z)
stem3(X,Y,Z)
stem3(...,'fill')
stem3(...,LineSpec)
h = stem3(...)
hlines = stem3('v6',...)
```

Description

Three-dimensional stem plots display lines extending from the *x*-*y* plane. A circle (the default) or other marker symbol whose *z*-position represents the data value terminates each stem.

`stem3(Z)` plots the data sequence `Z` as stems that extend from the *x*-*y* plane. *x* and *y* are generated automatically. When `Z` is a row vector, `stem3` plots all elements at equally spaced *x* values against the same *y* value. When `Z` is a column vector, `stem3` plots all elements at equally spaced *y* values against the same *x* value.

`stem3(X,Y,Z)` plots the data sequence `Z` at values specified by `X` and `Y`. `X`, `Y`, and `Z` must all be vectors or matrices of the same size.

`stem3(...,'fill')` specifies whether to color the interior of the circle at the end of the stem.

`stem3(...,LineSpec)` specifies the line style, marker symbol, and color for the stems. See `LineSpec` for more information.

`h = stem3(...)` returns handles to stemseries graphics objects.

Backward Compatible Version

`hlines = stem3('v6',...)` returns the handles of line objects instead of stemseries objects for compatibility with MATLAB 6.5 and earlier.

Examples

Create a three-dimensional stem plot to visualize a function of two variables.

```
X = linspace(0,1,10);
Y = X./2;
Z = sin(X) + cos(Y);
```

```
stem3(X,Y,Z,'fill')
view(-25,30)
```



See Also

`bar`, `plot`, `stairs`, `stem`

"Discrete Data Plots" for related functions

"Stemseries Properties" for descriptions of properties.

Three-Dimensional Stem Plots for more examples.

Modifying Properties

You can set and query graphics object properties using the `set` and `get` commands or with the property editor (`propertyeditor`).

Note that you cannot define default properties for stemseries objects.

See Plot Objects for information on stemseries objects.

Stemseries Property Descriptions

This section provides a description of properties. Curly braces { } enclose default values.

`BaseLine` handle of baseline

Handle of the baseline object. This property contains the handle of the line object used as the baseline. You can set the properties of this line using its handle. For example, the following statements create a stem plot, obtain the handle of the baseline from the stemseries object, and then set line properties that make the baseline a dashed, red line.

```
stem_handle = stem(randn(10,1));
baseline_handle = get(stem_handle,'BaseLine');
set(baseline_handle,'LineStyle','--','Color','red')
```

`BaseValue` *y*-axis value

Y-axis value where baseline is drawn. You can specify the value along the *y*-axis at which MATLAB draws the baseline.

`BeingDeleted` `on | {off}` Read Only

This object is being deleted. The `BeingDeleted` property provides a mechanism that you can use to determine if objects are in the process of being deleted. MATLAB sets the `BeingDeleted` property to `on` when the object's delete function callback is called (see the `DeleteFcn` property). It remains set to `on` while the delete function executes, after which the object no longer exists.

For example, an object's delete function might call other functions that act on a number of different objects. These functions might not need to perform actions on objects if the objects are going to be deleted, and therefore can check the object's `BeingDeleted` property before acting.

`BusyAction` `cancel | {queue}`

Callback routine interruption. The `BusyAction` property enables you to control how MATLAB handles events that potentially interrupt executing callbacks. If

there is a callback function executing, callbacks invoked subsequently always attempt to interrupt it.

If the `Interruptible` property of the object whose callback is executing is set to `on` (the default), then interruption occurs at the next point where the event queue is processed. If the `Interruptible` property is `off`, the `BusyAction` property (of the object owning the executing callback) determines how MATLAB handles the event. The choices are

- `cancel` — Discard the event that attempted to execute a second callback routine.
- `queue` — Queue the event that attempted to execute a second callback routine until the current callback finishes.

`ButtonDownFcn` string or function handle

Button press callback function. A callback that executes whenever you press a mouse button while the pointer is over the stemseries object.

This property can be

- A string that is a valid MATLAB expression
- The name of an M-file
- A function handle

The expression executes in the MATLAB workspace.

See Function Handle Callbacks for information on how to use function handles to define the callbacks.

`Children` array of graphics object handles

Children of the stemseries object. An array containing the handles of all line objects parented to the stemseries object (whether visible or not).

Note that if a child object's `HandleVisibility` property is set to `callback` or `off`, its handle does not show up in the stem `Children` property unless you set the Root `ShowHiddenHandles` property to `on`:

```
set(0,'ShowHiddenHandles','on')
```

Clipping {on} | off

Clipping mode. MATLAB clips stem plots to the axes plot box by default. If you set Clipping to off, lines might be displayed outside the axes plot box.

Color ColorSpec

Color of stem lines. A three-element RGB vector or one of the MATLAB predefined names, specifying the line color. See the ColorSpec reference page for more information on specifying color.

For example, the following statement would produce a stem plot with red lines.

```
h = stem(randn(10,1),'Color','r');
```

CreateFcn string or function handle

Callback routine executed during object creation. This property defines a callback that executes when MATLAB creates a stemseries object. You must specify the callback during the creation of the object. For example,

```
stem(x,y,'CreateFcn',@CallbackFcn)
```

where @*CallbackFcn* is a function handle that references the callback function.

MATLAB executes this routine after setting all other stemseries properties. Setting this property on an existing stemseries object has no effect.

The handle of the object whose CreateFcn is being executed is accessible only through the root CallbackObject property, which you can query using gcbo.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

DeleteFcn string or function handle

Callback executed during object deletion. A callback that executes when the stemseries object is deleted (e.g., this might happen when you issue a delete command on the stemseries object, its parent axes, or the figure containing it). MATLAB executes the callback before destroying the object's properties so the callback routine can query these values.

The handle of the object whose DeleteFcn is being executed is accessible only through the root CallbackObject property, which can be queried using gcbo.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

See the `BeingDeleted` property for related information.

`DisplayName` string

Label used by plot legends. The legend and the plot browser use this text for labels for any stemseries objects appearing in these legends.

`EraseMode` `{normal} | none | xor | background`

Erase mode. This property controls the technique MATLAB uses to draw and erase stem child objects (the lines used to construct the stem plot). Alternative erase modes are useful for creating animated sequences, where control of the way individual objects are redrawn is necessary to improve performance and obtain the desired effect.

- `normal` — Redraw the affected region of the display, performing the three-dimensional analysis necessary to ensure that all objects are rendered correctly. This mode produces the most accurate picture, but is the slowest. The other modes are faster, but do not perform a complete redraw and are therefore less accurate.
- `none` — Do not erase objects when they are moved or destroyed. While the objects are still visible on the screen after erasing with `EraseMode none`, you cannot print these objects because MATLAB stores no information about their former locations.
- `xor`— Draw and erase the object by performing an exclusive OR (XOR) with each pixel index of the screen behind it. Erasing the object does not damage the color of the objects behind it. However, the color of the erased object depends on the color of the screen behind it and it is correctly colored only when it is over the axes background color (or the figure background color if the axes `Color` property is set to `none`). That is, it isn't erased correctly if there are objects behind it.
- `background` — Erase the graphics objects by redrawing them in the axes background color (or the figure background color if the axes `Color` property is set to `none`). This damages other graphics objects that are behind the erased object, but the erased object is always properly colored.

Printing with Nonnormal Erase Modes

MATLAB always prints figures as if the `EraseMode` of all objects is `normal`. This means graphics objects created with `EraseMode` set to `none`, `xor`, or `background` can look different on screen than on paper. On screen, MATLAB can

mathematically combine layers of colors (e.g., performing an XOR operation on a pixel color with that of the pixel behind it) and ignore three-dimensional sorting to obtain greater rendering speed. However, these techniques are not applied to the printed output.

Set the axes background color with the axes `Color` property. Set the figure background color with the figure `Color` property.

You can use the MATLAB `getframe` command or other screen capture applications to create an image of a figure containing nonnormal mode objects.

`HandleVisibility` `{on} | callback | off`

Control access to object's handle by command-line users and GUIs. This property determines when an object's handle is visible in its parent's list of children. `HandleVisibility` is useful for preventing command-line users from accidentally accessing the stemseries object.

- `on` — Handles are always visible when `HandleVisibility` is `on`.
- `callback` — Setting `HandleVisibility` to `callback` causes handles to be visible from within callback routines or functions invoked by callback routines, but not from within functions invoked from the command line. This provides a means to protect GUIs from command-line users, while allowing callback routines to have access to object handles.
- `off` — Setting `HandleVisibility` to `off` makes handles invisible at all times. This might be necessary when a callback invokes a function that might potentially damage the GUI (such as evaluating a user-typed string) and so temporarily hides its own handles during the execution of that function.

Functions Affected by Handle Visibility

When a handle is not visible in its parent's list of children, it cannot be returned by functions that obtain handles by searching the object hierarchy or querying handle properties. This includes `get`, `findobj`, `gca`, `gcf`, `gco`, `newplot`, `cla`, `clf`, and `close`.

Properties Affected by Handle Visibility

When a handle's visibility is restricted using `callback` or `off`, the object's handle does not appear in its parent's `Children` property, figures do not appear in the root's `CurrentFigure` property, objects do not appear in the root's

CallbackObject property or in the figure's CurrentObject property, and axes do not appear in their parent's CurrentAxes property.

Overriding Handle Visibility

You can set the root ShowHiddenHandles property to on to make all handles visible regardless of their HandleVisibility settings (this does not affect the values of the HandleVisibility properties). See also findall.

Handle Validity

Handles that are hidden are still valid. If you know an object's handle, you can set and get its properties and pass it to any function that operates on handles.

HitTest {on} | off

Selectable by mouse click. HitTest determines whether the stemseries object can become the current object (as returned by the gco command and the figure CurrentObject property) as a result of a mouse click on the line objects that compose the stem plot. If HitTest is off, clicking the stemseries object selects the object below it (which is usually the axes containing it).

HitTestArea on | {off}

Select stemseries object on stem lines or area of extent. This property enables you to select stemseries objects in two ways:

- Select by clicking stem lines (default).
- Select by clicking anywhere in the extent of the stem graph.

When HitTestArea is off, you must click the stem lines (excluding the baseline) to select the stemseries object. When HitTestArea is on, you can select the stemseries object by clicking anywhere within the extent of the stem plot (i.e., anywhere within a rectangle that encloses all the stem lines).

Interruptible {on} | off

Callback routine interruption mode. The Interruptible property controls whether a stemseries object callback can be interrupted by callbacks invoked subsequently.

Only callbacks defined for the ButtonDownFcn property are affected by the Interruptible property. MATLAB checks for events that can interrupt a callback only when it encounters a drawnow, figure, getframe, or pause command in the routine. See the BusyAction property for related information.

Setting `Interruptible` to `on` allows any graphics object's callback to interrupt callback routines originating from a stem property. Note that MATLAB does not save the state of variables or the display (e.g., the handle returned by the `gca` or `gcf` command) when an interruption occurs.

`LineStyle` `{-} | -- | : | -. | none`

Line style. This property specifies the line style used for the stem lines. Available line styles are shown in the table.

Symbol	Line Style
-	Solid line (default)
--	Dashed line
:	Dotted line
-.	Dash-dot line
none	No line

You can use `LineStyle none` when you want to place a marker at each point but do not want the points connected with a line (see the `Marker` property).

`LineWidth` scalar

Width of the stem lines. Specify this value in points (1 point = $^1/_{72}$ inch). The default `LineWidth` is 0.5 points.

`Marker` character (see table)

Marker symbol. The `Marker` property specifies the type of markers that are displayed at the end of the stem lines. You can set values for the `Marker` property independently from the `LineStyle` property. Supported markers include those shown in the following table.

Marker Specifier	Description
+	Plus sign
o	Circle

Marker Specifier	Description
*	Asterisk
.	Point
x	Cross
s	Square
d	Diamond
^	Upward-pointing triangle
v	Downward-pointing triangle
>	Right-pointing triangle
<	Left-pointing triangle
p	Five-pointed star (pentagram)
h	Six-pointed star (hexagram)
none	No marker (default)

`MarkerEdgeColor` `ColorSpec | none | {auto}`

Marker edge color. The color of the marker or the edge color for filled markers (circle, square, diamond, pentagram, hexagram, and the four triangles). `ColorSpec` defines the color to use. `none` specifies no color, which makes nonfilled markers invisible. `auto` sets `MarkerEdgeColor` to the same color as the stem `Color` property.

`MarkerFaceColor` `ColorSpec | {none} | auto`

Marker face color. The fill color for markers that are closed shapes (circle, square, diamond, pentagram, hexagram, and the four triangles). `ColorSpec` defines the color to use. `none` makes the interior of the marker transparent, allowing the background to show through. `auto` sets the fill color to the axes color, or the figure color, if the axes `Color` property is set to `none` (which is the factory default for axes).

MarkerSize size in points

Marker size. A scalar specifying the size of the marker in points. The default value for `MarkerSize` is 6 points (1 point = 1/72 inch). Note that MATLAB draws the point marker (specified by the `'.'` symbol) at one-third the specified size.

Parent handle of axes, hggroup, or hgtransform

Parent of stemseries object. This property contains the handle of the stemseries object's parent. The parent of a stemseries object is the axes, hggroup, or hgtransform object that contains it.

See Objects That Can Contain Other Objects for more information on parenting graphics objects.

Selected `on | {off}`

Is object selected? When you set this property to `on`, MATLAB displays selection handles at the corners and midpoints if the `SelectionHighlight` property is also `on` (the default). You can, for example, define the `ButtonDownFcn` callback to set this property to `on`, thereby indicating that the stemseries object has been selected.

SelectionHighlight `{on} | off`

Objects are highlighted when selected. When the `Selected` property is `on`, MATLAB indicates the selected state by drawing selection handles on the stems. When `SelectionHighlight` is `off`, MATLAB does not draw the handles.

ShowBaseLine `{on} | off`

Turn baseline display on or off. This property determines whether stem plots display a baseline from which the stems are drawn. By default, the baseline is displayed.

Tag string

User-specified object label. The `Tag` property provides a means to identify graphics objects with a user-specified label. This is particularly useful when you are constructing interactive graphics programs that would otherwise need to define object handles as global variables or pass them as arguments between callbacks.

For example, you might create a stemseries object and set the `Tag` property:

```
t = stem(Y,'Tag','stem1')
```

When you want to access the stemseries object, you can use `findobj` to find the stemseries object's handle. The following statement changes the `MarkerFaceColor` property of the object whose `Tag` is `stem1`.

```
set(findobj('Tag','stem1'),'MarkerFaceColor','red')
```

`Type` string (read only)

Type of graphics object. This property contains a string that identifies the class of the graphics object. For stemseries objects, `Type` is `'hggroup'`. The following statement finds all the hggroup objects in the current axes.

```
t = findobj(gca,'Type','hggroup');
```

`UIContextMenu` handle of a uicontextmenu object

Associate a context menu with the stemseries object. Assign this property the handle of a uicontextmenu object created in the stemseries object's parent figure. Use the `uicontextmenu` function to create the context menu. MATLAB displays the context menu whenever you right-click over the stemseries object.

`UserData` array

User-specified data. This property can be any data you want to associate with the stemseries object (including cell arrays and structures). The stemseries object does not set values for this property, but you can access it using the `set` and `get` functions.

`Visible` `{on} | off`

Visibility of stemseries object and its children. By default, stemseries object visibility is `on`. This means all children of the stem are visible unless the child object's `Visible` property is set to `off`. Setting a stemseries object's `Visible` property to `off` also makes its children invisible.

`XData` `array`

X-axis location of stems. The stem function draws an individual stem at each *x*-axis location in the `XData` array. `XData` can be either a matrix equal in size to `YData` or a vector equal in length to the number of rows in `YData`. That is, `length(XData) == size(YData,1)`. `XData` does not need to be monotonically increasing.

If you do not specify `XData` (i.e., the input argument `x`), the stem function uses the indices of `YData` to create the stem plot. See the `XDataMode` property for related information.

XDataMode {auto} | manual

Use automatic or user-specified x-axis values. If you specify XData, MATLAB sets this property to manual.

If you set XDataMode to auto after having specified XData, MATLAB resets the *x*-axis ticks and *x*-tick labels to the column indices of the ZData, overwriting any previous values for XData.

XDataSource string (MATLAB variable)

Link XData to MATLAB variable. Set this property to a MATLAB variable that, by default, is evaluated in the base workspace to generate the XData.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change XData.

You can use the refreshdata function to force an update of the object's data. refreshdata also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call refreshdata.

See the refreshdata reference page for more information.

Note If you change one data source property to return data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

YData scalar, vector, or matrix

Stem plot data. YData contains the data plotted as stems. Each value in YData is represented by a marker in the stem plot. If YData is a matrix, MATLAB creates a series of stems for each column in the matrix.

The input argument y in the stem function calling syntax assigns values to YData.

YDataSource string (MATLAB variable)

Link YData to MATLAB variable. Set this property to a MATLAB variable that, by default, is evaluated in the base workspace to generate the YData.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change YData.

You can use the `refreshdata` function to force an update of the object's data. `refreshdata` also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call `refreshdata`.

See the `refreshdata` reference page for more information.

Note If you change one data source property to a variable that contains data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

`ZData` vector of coordinates

Z-coordinates. A data defining the stems for 3-D stem graphs. `XData` and `YData` (if specified) must be the same size.

`ZDataSource` string (MATLAB variable)

Link `ZData` to MATLAB variable. Set this property to a MATLAB variable that, by default, is evaluated in the base workspace to generate the `ZData`.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change `ZData`.

You can use the `refreshdata` function to force an update of the object's data. `refreshdata` also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call `refreshdata`.

See the `refreshdata` reference page for more information.

Note If you change one data source property to a variable that contains data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

Purpose

Stop timer(s)

Syntax

```
stop(obj)
```

Description

`stop(obj)` stops the timer, represented by the timer object, `obj`. If obj is an array of timer objects, the `stop` function stops them all. Use the `timer` function to create a timer object.

The `stop` function sets the `Running` property of the timer object, `obj`, to `'off'`, halts further `TimerFcn` callbacks, and executes the `StopFcn` callback.

See Also

`timer`, `start`

str2double

Purpose

Convert string to double-precision value

Syntax

```
x = str2double('str')
X = str2double(C)
```

Description

`X = str2double('str')` converts the string `str`, which should be an ASCII character representation of a real or complex scalar value, to the MATLAB double-precision representation. The string can contain digits, a comma (thousands separator), a decimal point, a leading `+` or `-` sign, an `e` preceding a power of 10 scale factor, and an `i` for a complex unit.

If `str` does not represent a valid scalar value, `str2double` returns `NaN`.

`X = str2double(C)` converts the strings in the cell array of strings `C` to double precision. The matrix `X` returned will be the same size as `C`.

Examples

Here are some valid `str2double` conversions.

```
str2double('123.45e7')
str2double('123 + 45i')
str2double('3.14159')
str2double('2.7i - 3.14')
str2double({'2.71' '3.1415'})
str2double('1,200.34')
```

See Also

`char`, `hex2num`, `num2str`, `str2num`

Purpose

Construct a function handle from a function name string

Syntax

```
fhandle = str2func('str')
```

Description

`str2func('str')` constructs a function handle `fhandle` for the function named in the string `'str'`.

You can create a function handle using either the `@function` syntax or the `str2func` command. You can also perform this operation on a cell array of strings. In this case, an array of function handles is returned.

Examples

Example 1

To convert the string, `'sin'`, into a handle for that function, type

```
fh = str2func('sin')
fh =
    @sin
```

Example 2

If you pass a function name string in a variable, the function that receives the variable can convert the function name to a function handle using `str2func`. The example below passes the variable, `funcname`, to function `makeHandle`, which then creates a function handle. Here is the function M-file:

```
function fh = makeHandle(funcname)
fh = str2func(funcname);
```

This is the code that calls `makdHandle` to construct the function handle:

```
makeHandle('sin')
ans =
    @sin
```

Example 3

In the following example, the `myminbnd` function expects to receive either a function handle or string in the first argument. If you pass a string, `myminbnd` constructs a function handle from it using `str2func`, and then uses that handle in a call to `fminbnd`:

```
function myminbnd(fhandle, lower, upper)
if ischar(fhandle)
```

```
    disp 'converting function string to function handle ...'
    fhandle = str2func(fhandle);
end
fminbnd(fhandle, lower, upper)
```

Whether you call `myminbnd` with a function handle or function name string, the function can handle the argument appropriately:

```
myminbnd('humps', 0.3, 1)
converting function string to function handle ...
ans =
    0.6370
```

See Also

`function_handle`, `func2str`, `functions`

Purpose

Form a blank padded character matrix from strings

Syntax

```
S = str2mat(T1, T2, T3, ...)
```

Description

`S = str2mat(T1, T2, T3, ...)` forms the matrix `S` containing the text strings `T1, T2, T3, ...` as rows. The function automatically pads each string with blanks in order to form a valid matrix. Each text parameter, `Ti`, can itself be a string matrix. This allows the creation of arbitrarily large string matrices. Empty strings are significant.

Note This routine will become obsolete in a future version. Use `char` instead.

Remarks

`str2mat` differs from `strvcat` in that empty strings produce blank rows in the output. In `strvcat`, empty strings are ignored.

Examples

```
x = str2mat('36842', '39751', '38453', '90307');

whos x
  Name      Size         Bytes  Class

  x         4x5             40  char array

x(2,3)

ans =

    7
```

See Also

`char`, `strvcat`

str2num

Purpose

String to number conversion

Syntax

```
x = str2num('str')
```

Description

`x = str2num('str')` converts the string `str`, which is an ASCII character representation of a numeric value, to numeric representation. The string can contain

- Digits
- A decimal point
- A leading + or - sign
- A letter `e` or `d` preceding a power of 10 scale factor
- A letter `i` or `j` indicating a complex or imaginary number.

The `str2num` function can also convert string matrices.

Examples

`str2num('3.14159e0')` is approximately π.

To convert a string matrix,

```
str2num(['1 2';'3 4'])

ans =

     1     2
     3     4
```

See Also

`num2str`, `hex2num`, `sscanf`, `sparse`, `special characters`

Purpose

String concatenation

Syntax

```
t = strcat(s1, s2, s3, ...)
```

Description

`t = strcat(s1, s2, s3, ...)` horizontally concatenates corresponding rows of the character arrays `s1`, `s2`, `s3`, etc. All input arrays must have the same number of rows (or any can be a single string). When the inputs are all character arrays, the output is also a character array.

When any of the inputs is a cell array of strings, `strcat` returns a cell array of strings formed by concatenating corresponding elements of `s1`, `s2`, etc. The inputs must all have the same size (or any can be a scalar). Any of the inputs can also be character arrays.

Trailing spaces in character array inputs are ignored and do not appear in the output. This is not true for inputs that are cell arrays of strings. Use the concatenation syntax `[s1 s2 s3 ...]` to preserve trailing spaces.

Remarks

`strcat` and matrix operation are different for strings that contain trailing spaces:

```
a = 'hello '
b = 'goodbye'
strcat(a, b)
ans =
hellogoodbye
[a b]
ans =
hello goodbye
```

Examples

Given two 1-by-2 cell arrays `a` and `b`,

```
a =                          b =
    'abcde'    'fghi'            'jkl'    'mn'
```

the command `t = strcat(a,b)` yields

```
t =
    'abcdejkl'    'fghimn'
```

Given the 1-by-1 cell array `c = { Q'}`, the command `t = strcat(a,b,c)` yields

```
t =
    'abcdejklQ'    'fghimnQ'
```

See Also

strvcat, cat, cellstr

Purpose

Compare strings

Syntax

```
k = strcmp('str1', 'str2')
TF = strcmp(S, T)
```

Description

`k = strcmp('str1', 'str2')` compares the strings `str1` and `str2` and returns logical true (`1`) if the two are identical and logical false (`0`) otherwise.

`TF = strcmp(S, T)` where either `S` or `T` is a cell array of strings, returns an array `TF` the same size as `S` and `T` containing `1` for those elements of `S` and `T` that match and `0` otherwise. `S` and `T` must be the same size (or one can be a scalar cell). Either one can also be a character array with the right number of rows.

Remarks

Note that the value returned by `strcmp` is not the same as the C language convention. In addition, the `strcmp` function is case sensitive; any leading and trailing blanks in either of the strings are explicitly included in the comparison.

`strcmp` is intended for comparison of character data. When used to compare numeric data, `strcmp` returns `0`.

Examples

```
strcmp('Yes', 'No') =
   0
strcmp('Yes', 'Yes') =
   1

A =
    'MATLAB'              'SIMULINK'
    'Toolboxes'           'The MathWorks'

B =
    'Handle Graphics'     'Real Time Workshop'
    'Toolboxes'           'The MathWorks'

C =
    'Signal Processing'     'Image Processing'
    'MATLAB'                'SIMULINK'

strcmp(A, B)
ans =
     0     0
     1     1
```

```
strcmp(A, C)
ans =
     0     0
     0     0
```

See Also

strcmpi, strncmp, strncmpi, strmatch, strfind, findstr, regexp, regexpi, regexprep

Purpose

Compare strings ignoring case

Syntax

```
strcmpi(str1, str2)
strcmpi(S, T)
```

Description

`strcmpi(str1, str2)` returns `1` if strings `str1` and `str2` are the same except for case and `0` otherwise.

`strcmpi(S, T)` when either `S` or `T` is a cell array of strings, returns an array the same size as `S` and `T` containing `1` for those elements of `S` and `T` that match except for case, and `0` otherwise. `S` and `T` must be the same size (or one can be a scalar cell). Either one can also be a character array with the right number of rows.

Remarks

`strcmpi` is intended for comparison of character data. When used to compare numeric data, `strcmpi` returns `0`.

`strcmpi` supports international character sets.

See Also

`strcmp`, `strncmpi`, `strncmp`, `strmatch`, `strfind`, `findstr`, `regexp`, `regexpi`, `regexprep`

stream2

Purpose

Compute 2-D streamline data

Syntax

```
XY = stream2(x,y,u,v,startx,starty)
XY = stream2(u,v,startx,starty)
XY = stream2(...,options)
```

Description

`XY = stream2(x,y,u,v,startx,starty)` computes streamlines from vector data `u` and `v`. The arrays `x` and `y` define the coordinates for `u` and `v` and must be monotonic and 2-D plaid (such as the data produced by `meshgrid`). `startx` and `starty` define the starting positions of the streamlines. The section "Specifying Starting Points for Stream Plots" provides more information on defining starting points.

The returned value `XY` contains a cell array of vertex arrays.

`XY = stream2(u,v,startx,starty)` assumes the arrays `x` and `y` are defined as `[x,y] = meshgrid(1:n,1:m)` where `[m,n] = size(u)`.

`XY = stream2(...,options)` specifies the options used when creating the streamlines. Define `options` as a one- or two-element vector containing the step size or the step size and the maximum number of vertices in a streamline:

```
[stepsize]
```

or

```
[stepsize, max_number_vertices]
```

If you do not specify a value, MATLAB uses the default:

- Stepsize = 0.1 (one tenth of a cell)
- Maximum number of vertices = 10000

Use the `streamline` command to plot the data returned by `stream2`.

Examples

This example draws 2-D streamlines from data representing air currents over regions of North America.

```
load wind
[sx,sy] = meshgrid(80,20:10:50);
streamline(stream2(x(:,:,5),y(:,:,5),u(:,:,5),v(:,:,5),sx,sy));
```

See Also

`coneplot`, `stream3`, `streamline`

"Volume Visualization" for related functions

Specifying Starting Points for Stream Plots for related information

stream3

Purpose

Compute 3-D streamline data

Syntax

```
XYZ = stream3(X,Y,Z,U,V,W,startx,starty,startz)
XYZ = stream3(U,V,W,startx,starty,startz)
```

Description

`XYZ = stream3(X,Y,Z,U,V,W,startx,starty,startz)` computes streamlines from vector data `U`, `V`, `W`. The arrays `X`, `Y`, `Z` define the coordinates for `U`, `V`, `W` and must be monotonic and 3-D plaid (such as the data produced by `meshgrid`). `startx`, `starty`, and `startz` define the starting positions of the streamlines. The section "Specifying Starting Points for Stream Plots" provides more information on defining starting points.

The returned value `XYZ` contains a cell array of vertex arrays.

`XYZ = stream3(U,V,W,startx,starty,startz)` assumes the arrays `X`, `Y`, and `Z` are defined as `[X,Y,Z] = meshgrid(1:N,1:M,1:P)` where `[M,N,P] = size(U)`.

`XYZ = stream3(...,options)` specifies the options used when creating the streamlines. Define `options` as a one- or two-element vector containing the step size or the step size and the maximum number of vertices in a streamline:

```
[stepsize]
```

or

```
[stepsize, max_number_vertices]
```

If you do not specify values, MATLAB uses the default:

- Stepsize = 0.1 (one tenth of a cell)
- Maximum number of vertices = 10000

Use the `streamline` command to plot the data returned by `stream3`.

Examples

This example draws 3-D streamlines from data representing air currents over regions of North America.

```
load wind
[sx sy sz] = meshgrid(80,20:10:50,0:5:15);
streamline(stream3(x,y,z,u,v,w,sx,sy,sz))
view(3)
```

See Also

`coneplot`, `stream2`, `streamline`

"Volume Visualization" for related functions

Specifying Starting Points for Stream Plots for related information

streamline

Purpose

Draw streamlines from 2-D or 3-D vector data

Syntax

```
streamline(X,Y,Z,U,V,W,startx,starty,startz)
streamline(U,V,W,startx,starty,startz)
streamline(XYZ)
streamline(X,Y,U,V,startx,starty)
streamline(U,V,startx,starty)
streamline(XY)
streamline(...,options)
streamline(axes_handle,...)
h = streamline(...)
```

Description

`streamline(X,Y,Z,U,V,W,startx,starty,startz)` draws streamlines from 3-D vector data `U`, `V`, `W`. The arrays `X`, `Y`, `Z` define the coordinates for `U`, `V`, `W` and must be monotonic and 3-D plaid (such as the data produced by `meshgrid`). `startx`, `starty`, `startz` define the starting positions of the streamlines. The section "Specifying Starting Points for Stream Plots" provides more information on defining starting points.

`streamline(U,V,W,startx,starty,startz)` assumes the arrays `X`, `Y`, and `Z` are defined as `[X,Y,Z] = meshgrid(1:N,1:M,1:P)` where `[M,N,P] = size(U)`.

`streamline(XYZ)` assumes `XYZ` is a precomputed cell array of vertex arrays (as produced by `stream3`).

`streamline(X,Y,U,V,startx,starty)` draws streamlines from 2-D vector data `U`, `V`. The arrays `X`, `Y` define the coordinates for `U`, `V` and must be monotonic and 2-D plaid (such as the data produced by `meshgrid`). `startx` and `starty` define the starting positions of the streamlines. The output argument `h` contains a vector of line handles, one handle for each streamline.

`streamline(U,V,startx,starty)` assumes the arrays `X` and `Y` are defined as `[X,Y] = meshgrid(1:N,1:M)` where `[M,N] = size(U)`.

`streamline(XY)` assumes `XY` is a precomputed cell array of vertex arrays (as produced by `stream2`).

`streamline(...,options)` specifies the options used when creating the streamlines. Define `options` as a one- or two-element vector containing the step size or the step size and the maximum number of vertices in a streamline:

```
[stepsize]
```

or

```
[stepsize, max_number_vertices]
```

If you do not specify values, MATLAB uses the default:

- Stepsize = 0.1 (one tenth of a cell)
- Maximum number of vertices = 1000

`streamline(axes_handles,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = streamline(...)` returns a vector of line handles, one handle for each streamline.

Examples

This example draws streamlines from data representing air currents over a region of North America. Loading the `wind` data set creates the variables `x`, `y`, `z`, `u`, `v`, and `w` in the MATLAB workspace.

The plane of streamlines indicates the flow of air from the west to the east (the *x*-direction) beginning at x = 80 (which is close to the minimum value of the x coordinates). The *y*- and *z*-coordinate starting points are multivalued and approximately span the range of these coordinates. `meshgrid` generates the starting positions of the streamlines.

```
load wind
[sx,sy,sz] = meshgrid(80,20:10:50,0:5:15);
h = streamline(x,y,z,u,v,w,sx,sy,sz);
set(h,'Color','red')
view(3)
```

See Also

`coneplot`, `stream2`, `stream3`, `streamparticles`

"Volume Visualization" for related functions

Specifying Starting Points for Stream Plots for related information

Stream Line Plots of Vector Data for another example

streamparticles

Purpose

Display stream particles

Syntax

```
streamparticles(vertices)
streamparticles(vertices,n)
streamparticles(...,'PropertyName',PropertyValue,...)
streamparticles(line_handle,...)
h = streamparticles(...)
```

Description

`streamparticles(vertices)` draws stream particles of a vector field. Stream particles are usually represented by markers and can show the position and velocity of a streamline. `vertices` is a cell array of 2-D or 3-D vertices (as if produced by `stream2` or `stream3`).

`streamparticles(vertices,n)` uses `n` to determine how many stream particles to draw. The `ParticleAlignment` property controls how `n` is interpreted.

- If `ParticleAlignment` is set to `off` (the default) and `n` is greater than `1`, then approximately `n` particles are drawn evenly spaced over the streamline vertices.

  If `n` is less than or equal to `1`, `n` is interpreted as a fraction of the original stream vertices; for example, if `n` is `0.2`, approximately 20% of the vertices are used.

  `n` determines the upper bound for the number of particles drawn. Note that the actual number of particles can deviate from `n` by as much as a factor of 2.

- If `ParticleAlignment` is `on`, `n` determines the number of particles on the streamline having the most vertices and sets the spacing on the other streamlines to this value. The default value is `n = 1`.

`streamparticles(...,'PropertyName',PropertyValue,...)` controls the stream particles using named properties and specified values. Any unspecified properties have default values. MATLAB ignores the case of property names.

Stream Particle Properties

`Animate` — Stream particle motion [nonnegative integer]

The number of times to animate the stream particles. The default is `0`, which does not animate. `Inf` animates until you enter **Ctrl-c**.

`FrameRate` — Animation frames per second [nonnegative integer]

This property specifies the number of frames per second for the animation. `Inf`, the default, draws the animation as fast as possible. Note that the speed of the animation might be limited by the speed of the computer. In such cases, the value of `FrameRate` cannot necessarily be achieved.

`ParticleAlignment` — Align particles with streamlines [`on` | `{off}`]

Set this property to `on` to draw particles at the beginning of each streamline. This property controls how `streamparticles` interprets the argument `n` (number of stream particles).

Stream particles are line objects. In addition to stream particle properties, you can specify any line object property, such as `Marker` and `EraseMode`. `streamparticles` sets the following line properties when called.

Line Property	Value Set by streamparticles
`EraseMode`	`xor`
`LineStyle`	`none`
`Marker`	`o`
`MarkerEdgeColor`	`none`
`MarkerFaceColor`	`red`

You can override any of these properties by specifying a property name and value as arguments to `streamparticles`. For example, this statement uses RGB values to set the `MarkerFaceColor` to medium gray:

```
streamparticles(vertices,'MarkerFaceColor',[.5 .5 .5])
```

`streamparticles(line_handle,...)` uses the line object identified by `line_handle` to draw the stream particles.

`h = streamparticles(...)` returns a vector of handles to the line objects it creates.

Examples

This example combines streamlines with stream particle animation. The `interpstreamspeed` function determines the vertices along the streamlines

where stream particles will be drawn during the animation, thereby controlling the speed of the animation. Setting the axes `DrawMode` property to `fast` provides faster rendering.

```
load wind
[sx sy sz] = meshgrid(80,20:1:55,5);
verts = stream3(x,y,z,u,v,w,sx,sy,sz);
sl = streamline(verts);
iverts = interpstreamspeed(x,y,z,u,v,w,verts,.025);
axis tight; view(30,30); daspect([1 1 .125])
camproj perspective; camva(8)
set(gca,'DrawMode','fast')
box on
streamparticles(iverts,35,'animate',10,'ParticleAlignment','on')
```

The following picture is a static view of the animation.



This example uses the streamlines in the `z = 5` plane to animate the flow along these lines with `streamparticles`.

```
load wind
daspect([1 1 1]); view(2)
[verts averts] = streamslice(x,y,z,u,v,w,[],[],[5]);
sl = streamline([verts averts]);
```

```
axis tight off;
set(sl,'Visible','off')
iverts = interpstreamspeed(x,y,z,u,v,w,verts,.05);
set(gca,'DrawMode','fast','Position',[0 0 1 1],'ZLim',[4.9 5.1])
set(gcf,'Color','black')
streamparticles(iverts, 200, ...
    'Animate',100,'FrameRate',40, ...
    'MarkerSize',10,'MarkerFaceColor','yellow')
```

See Also

`interpstreamspeed`, `stream3`, `streamline`

"Volume Visualization" for related functions

Creating Stream Particle Animations for more details

Specifying Starting Points for Stream Plots for related information

streamribbon

Purpose

Create a 3-D stream ribbon plot

Syntax

```
streamribbon(X,Y,Z,U,V,W,startx,starty,startz)
streamribbon(U,V,W,startx,starty,startz)
streamribbon(vertices,X,Y,Z,cav,speed)
streamribbon(vertices,cav,speed)
streamribbon(vertices,twistangle)
streamribbon(...,width)
streamribbon(axes_handle,...)
h = streamribbon(...)
```

Description

`streamribbon(X,Y,Z,U,V,W,startx,starty,startz)` draws stream ribbons from vector volume data `U`, `V`, `W`. The arrays `X`, `Y`, `Z` define the coordinates for `U`, `V`, `W` and must be monotonic and 3-D plaid (as if produced by `meshgrid`). `startx`, `starty`, and `startz` define the starting positions of the stream ribbons at the center of the ribbons. The section "Specifying Starting Points for Stream Plots" provides more information on defining starting points.

The twist of the ribbons is proportional to the curl of the vector field. The width of the ribbons is calculated automatically.

Generally, you should set the `DataAspectRatio` (`daspect`) before calling `streamribbon`.

`streamribbon(U,V,W,startx,starty,startz)` assumes `X`, `Y`, and `Z` are determined by the expression

```
[X,Y,Z] = meshgrid(1:n,1:m,1:p)
```

where `[m,n,p] = size(U)`.

`streamribbon(vertices,X,Y,Z,cav,speed)` assumes precomputed streamline vertices, curl angular velocity, and flow speed. `vertices` is a cell array of streamline vertices (as produced by `stream3`). `X`, `Y`, `Z`, `cav`, and `speed` are 3-D arrays.

`streamribbon(vertices,cav,speed)` assumes `X`, `Y`, and `Z` are determined by the expression

```
[X,Y,Z] = meshgrid(1:n,1:m,1:p)
```

where `[m,n,p] = size(cav)`.

`streamribbon(vertices,twistangle)` uses the cell array of vectors `twistangle` for the twist of the ribbons (in radians). The size of each corresponding element of `vertices` and `twistangle` must be equal.

`streamribbon(...,width)` sets the width of the ribbons to `width`.

`streamribbon(axes_handles,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = streamribbon(...)` returns a vector of handles (one per start point) to `surface` objects.

Examples

This example uses stream ribbons to indicate the flow in the wind data set. Inputs include the coordinates, vector field components, and starting location for the stream ribbons.

```
load wind
[sx sy sz] = meshgrid(80,20:10:50,0:5:15);
daspect([1 1 1])
streamribbon(x,y,z,u,v,w,sx,sy,sz);
%-----Define viewing and lighting
axis tight
shading interp;
view(3);
camlight; lighting gouraud
```



This example uses precalculated vertex data (`stream3`), curl average velocity (`curl`), and speed ($\sqrt{u^2+v^2+w^2}$). Using precalculated data enables you to use values other than those calculated from the single data source. In this case, the speed is reduced by a factor of 10 compared to the previous example.

```
load wind
[sx sy sz] = meshgrid(80,20:10:50,0:5:15);
daspect([1 1 1])
verts = stream3(x,y,z,u,v,w,sx,sy,sz);
cav = curl(x,y,z,u,v,w);
spd = sqrt(u.^2 + v.^2 + w.^2).*.1;
streamribbon(verts,x,y,z,cav,spd);
%-----Define viewing and lighting
axis tight
shading interp
view(3)
camlight; lighting gouraud
```



This example specifies a twist angle for the stream ribbon.

```
t = 0:.15:15;
verts = {[cos(t)' sin(t)' (t/3)']};
twistangle = {cos(t)'};
daspect([1 1 1])
streamribbon(verts,twistangle);
%-----Define viewing and lighting
axis tight
shading interp;
view(3);
camlight; lighting gouraud
```



This example combines cone plots (`coneplot`) and stream ribbon plots in one graph.

```
%-----Define 3-D arrays x, y, z, u, v, w
xmin = -7; xmax = 7;
ymin = -7; ymax = 7;
zmin = -7; zmax = 7;
x = linspace(xmin,xmax,30);
y = linspace(ymin,ymax,20);
z = linspace(zmin,zmax,20);
[x y z] = meshgrid(x,y,z);
u = y; v = -x; w = 0*x+1;
daspect([1 1 1]);
[cx cy cz] = meshgrid(linspace(xmin,xmax,30),...
   linspace(ymin,ymax,30),[-3 4]);
h = coneplot(x,y,z,u,v,w,cx,cy,cz,'quiver');
set(h,'color','k');
%-----Plot two sets of streamribbons
[sx sy sz] = meshgrid([-1 0 1],[-1 0 1],-6);
streamribbon(x,y,z,u,v,w,sx,sy,sz);
[sx sy sz] = meshgrid([1:6],[0],-6);
streamribbon(x,y,z,u,v,w,sx,sy,sz);
```

```
%-----Define viewing and lighting
shading interp
view(-30,10) ; axis off tight
camproj perspective; camva(66); camlookat;
camdolly(0,0,.5,'fixtarget')
camlight
```



See Also

`curl`, `streamtube`, `streamline`, `stream3`

"Volume Visualization" for related functions

Displaying Curl with Stream Ribbons for another example

Specifying Starting Points for Stream Plots for related information

streamslice

Purpose

Draws streamlines in slice planes

Syntax

```
streamslice(X,Y,Z,U,V,W,startx,starty,startz)
streamslice(U,V,W,startx,starty,startz)
streamslice(X,Y,U,V)
streamslice(U,V)
streamslice(...,density)
streamslice(...,'arrowmode')
streamslice(...,'method')
streamslice(axes_handle,...)
h = streamslice(...)
[vertices arrowvertices] = streamslice(...)
```

Description

`streamslice(X,Y,Z,U,V,W,startx,starty,startz)` draws well spaced streamlines (with direction arrows) from vector data `U`, `V`, `W` in axis aligned *x*-, *y*-, *z*-planes starting at the points in the vectors `startx`, `starty`, `startz`. (The section "Specifying Starting Points for Stream Plots" provides more information on defining starting points.) The arrays `X`, `Y`, `Z` define the coordinates for `U`, `V`, `W` and must be monotonic and 3-D plaid (as if produced by `meshgrid`). `U`, `V`, `W` must be m-by-n-by-p volume arrays.

You should not assume that the flow is parallel to the slice plane. For example, in a stream slice at a constant `z`, the `z` component of the vector field `W` is ignored when you are calculating the streamlines for that plane.

Stream slices are useful for determining where to start streamlines, stream tubes, and stream ribbons. It is good practice is to set the axes `DataAspectRatio` to `[1 1 1]` when using `streamslice`.

`streamslice(U,V,W,startx,starty,startz)` assumes `X`, `Y`, and `Z` are determined by the expression

```
[X,Y,Z] = meshgrid(1:n,1:m,1:p)
```

where `[m,n,p] = size(U)`.

`streamslice(X,Y,U,V)` draws well spaced streamlines (with direction arrows) from vector volume data `U`, `V`. The arrays `X`, `Y` define the coordinates for `U`, `V` and must be monotonic and 2-D plaid (as if produced by `meshgrid`).

`streamslice(U,V)` assumes `X`, `Y`, and `Z` are determined by the expression

```
[X,Y,Z] = meshgrid(1:n,1:m,1:p)
```

where `[m,n,p] = size(U)`.

`streamslice(...,density)` modifies the automatic spacing of the streamlines. `density` must be greater than `0`. The default value is `1`; higher values produce more streamlines on each plane. For example, `2` produces approximately twice as many streamlines, while `0.5` produces approximately half as many.

`streamslice(...,'arrowsmode')` determines if direction arrows are present or not. `arrowmode` can be

- `arrows` — Draw direction arrows on the streamlines (default).
- `noarrows` — Do not draw direction arrows.

`streamslice(...,'method')` specifies the interpolation method to use. `method` can be

- `linear` — Linear interpolation (default)
- `cubic` — Cubic interpolation
- `nearest` — Nearest-neighbor interpolation

See `interp3` for more information on interpolation methods.

`streamslice(axes_handles,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = streamslice(...)` returns a vector of handles to the line objects created.

`[vertices arrowvertices] = streamslice(...)` returns two cell arrays of vertices for drawing the streamlines and the arrows. You can pass these values to any of the streamline drawing functions (`streamline`, `streamribbon`, `streamtube`).

Examples

This example creates a stream slice in the `wind` data set at `z = 5`.

```
load wind
daspect([1 1 1])
```

```
streamslice(x,y,z,u,v,w,[],[],[5])
axis tight
```



This example uses `streamslice` to calculate vertex data for the streamlines and the direction arrows. This data is then used by `streamline` to plot the lines and arrows. Slice planes illustrating with color the wind speed ($\sqrt{u^2 + v^2 + w^2}$) are drawn by `slice` in the same planes.

```
load wind
daspect([1 1 1])
[verts averts] = streamslice(u,v,w,10,10,10);
streamline([verts averts])
spd = sqrt(u.^2 + v.^2 + w.^2);
hold on;
slice(spd,10,10,10);
colormap(hot)
shading interp
view(30,50); axis(volumebounds(spd));
camlight; material([.5 1 0])
```



This example superimposes contour lines on a surface and then uses `streamslice` to draw lines that indicate the gradient of the surface. `interp2` is used to find the points for the lines that lie on the surface.

```
z = peaks;
surf(z)
shading interp
hold on
[c ch] = contour3(z,20); set(ch,'edgecolor','b')
[u v] = gradient(z);
h = streamslice(-u,-v);
set(h,'color','k')
for i=1:length(h);
   zi = interp2(z,get(h(i),'xdata'),get(h(i),'ydata'));
   set(h(i),'zdata',zi);
end
view(30,50); axis tight
```



See Also

`contourslice`, `slice`, `streamline`, `volumebounds`

"Volume Visualization" for related functions

Specifying Starting Points for Stream Plots for related information

Purpose

Creates a 3-D stream tube plot

Syntax

```
streamtube(X,Y,Z,U,V,W,startx,starty,startz)
streamtube(U,V,W,startx,starty,startz)
streamtube(vertices,X,Y,Z,divergence)
streamtube(vertices,divergence)
streamtube(vertices,width)
streamtube(vertices)
streamtube(...,[scale n])
streamtube(axes_handle,...)
h = streamtube(...)
```

Description

`streamtube(X,Y,Z,U,V,W,startx,starty,startz)` draws stream tubes from vector volume data `U`, `V`, `W`. The arrays `X`, `Y`, `Z` define the coordinates for `U`, `V`, `W` and must be monotonic and 3-D plaid (as if produced by `meshgrid`). `startx`, `starty`, and `startz` define the starting positions of the streamlines at the center of the tubes. The section "Specifying Starting Points for Stream Plots" provides more information on defining starting points.

The width of the tubes is proportional to the normalized divergence of the vector field.

Generally, you should set the `DataAspectRatio` (`daspect`) before calling `streamtube`.

`streamtube(U,V,W,startx,starty,startz)` assumes `X`, `Y`, and `Z` are determined by the expression

```
[X,Y,Z] = meshgrid(1:n,1:m,1:p)
```

where `[m,n,p] = size(U)`.

`streamtube(vertices,X,Y,Z,divergence)` assumes precomputed streamline vertices and divergence. `vertices` is a cell array of streamline vertices (as produced by `stream3`). `X`, `Y`, `Z`, and `divergence` are 3-D arrays.

`streamtube(vertices,divergence)` assumes `X`, `Y`, and `Z` are determined by the expression

```
[X,Y,Z] = meshgrid(1:n,1:m,1:p)
```

where `[m,n,p] = size(divergence)`.

`streamtube(vertices,width)` specifies the width of the tubes in the cell array of vectors, `width`. The size of each corresponding element of `vertices` and `width` must be equal. `width` can also be a scalar, specifying a single value for the width of all stream tubes.

`streamtube(vertices)` selects the width automatically.

`streamtube(...,[scale n])` scales the width of the tubes by `scale`. The default is `scale = 1`. When the stream tubes are created, using start points or divergence, specifying `scale = 0` suppresses automatic scaling. `n` is the number of points along the circumference of the tube. The default is `n = 20`.

`streamtube(axes_handles,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = streamtube(...z)` returns a vector of handles (one per start point) to `surface` objects used to draw the stream tubes.

Examples

This example uses stream tubes to indicate the flow in the wind data set. Inputs include the coordinates, vector field components, and starting location for the stream tubes.

```
load wind
[sx sy sz] = meshgrid(80,20:10:50,0:5:15);
daspect([1 1 1])
streamtube(x,y,z,u,v,w,sx,sy,sz);
%-----Define viewing and lighting
view(3)
axis tight
shading interp;
camlight; lighting gouraud
```



This example uses precalculated vertex data (`stream3`) and divergence (`divergence`).

```
load wind
[sx sy sz] = meshgrid(80,20:10:50,0:5:15);
daspect([1 1 1])
verts = stream3(x,y,z,u,v,w,sx,sy,sz);
div = divergence(x,y,z,u,v,w);
streamtube(verts,x,y,z,-div);
%-----Define viewing and lighting
view(3)
axis tight
shading interp
camlight; lighting gouraud
```



See Also

`divergence`, `streamribbon`, `streamline`, `stream3`

"Volume Visualization" for related functions

Displaying Divergence with Stream Tubes for another example

Specifying Starting Points for Stream Plots for related information

Purpose

Find one string within another

Syntax

```
k = strfind(str, pattern)
k = strfind(cellstr, pattern)
```

Description

`k = strfind(str, pattern)` searches the string `str` for occurrences of a shorter string, `pattern`, and returns the starting index of each such occurrence in the double array `k`. If `pattern` is not found in `str`, or if `pattern` is longer than `str`, then `strfind` returns the empty array `[]`.

`k = strfind(cellstr, pattern)` searches each string in cell array of strings `cellstr` for occurrences of a shorter string, `pattern`, and returns the starting index of each such occurrence in cell array `k`. If `pattern` is not found in a string or if `pattern` is longer then all strings in the cell array, then `strfind` returns the empty array `[]`, for that string in the cell array.

The search performed by `strfind` is case sensitive. Any leading and trailing blanks in `pattern` or in the strings being searched are explicitly included in the comparison.

Examples

Use `strfind` to find a two-letter pattern in string `S`:

```
S = 'Find the starting indices of the pattern string';
strfind(S, 'in')
ans =
     2    15    19    45

strfind(S, 'In')
ans =
     []

strfind(S, ' ')
ans =
     5     9    18    26    29    33    41
```

Use `strfind` on a cell array of strings:

```
cstr = {'How much wood would a woodchuck chuck';
        'if a woodchuck could chuck wood?'};

idx = strfind(cstr, 'wood');
```

```
idx{:,:}
ans =
    10    23
ans =
     6    28
```

This means that `'wood'` occurs at indices 10 and 23 in the first string and at indices 6 and 28 in the second.

See Also

`findstr`, `strmatch`, `strtok`, `strcmp`, `strncmp`, `strcmpi`, `strncmpi`, `regexp`, `regexpi`, `regexprep`

Purpose

MATLAB string handling

Syntax

```
S = 'Any Characters'
S = char(X)
X = double(S)
```

Description

`S = 'Any Characters'` creates a character array, or string. The string is actually a vector whose components are the numeric codes for the characters (the first 127 codes are ASCII). The actual characters displayed depend on the character set encoding for a given font. The length of `S` is the number of characters. A quotation within the string is indicated by two quotes.

`S = [S1 S2 ...]` concatenates character arrays `S1`, `S2`, etc. into a new character array, `S`.

`S = strcat(S1, S2, ...)` concatenates `S1`, `S2`, etc., which can be character arrays or cell arrays of strings. When the inputs are all character arrays, the output is also a character array. When any of the inputs is a cell array of strings, `strcat` returns a cell array of strings.

Trailing spaces in `strcat` character array inputs are ignored and do not appear in the output. This is not true for `strcat` inputs that are cell arrays of strings. Use the `S = [S1 S2 ...]` concatenation syntax, shown above, to preserve trailing spaces.

`S = char(X)` can be used to convert an array that contains positive integers representing numeric codes into a MATLAB character array.

`X = double(S)` converts the string to its equivalent double-precision numeric codes.

A collection of strings can be created in either of the following two ways:

- As the rows of a character array via `strvcat`
- As a cell array of strings via the curly braces

You can convert between character array and cell array of strings using `char` and `cellstr`. Most string functions support both types.

`ischar(S)` tells if `S` is a string variable. `iscellstr(S)` tells if `S` is a cell array of strings.

Examples

Create a simple string that includes a single quote.

```
msg = 'You''re right!'

msg =
You're right!
```

Create the string `name` using two methods of concatenation.

```
name = ['Thomas' ' R. ' 'Lee']

name = strcat('Thomas',' R.',' Lee')
```

Create a vertical array of strings.

```
C = strvcat('Hello','Yes','No','Goodbye')

C =
Hello
Yes
No
Goodbye
```

Create a cell array of strings.

```
S = {'Hello' 'Yes' 'No' 'Goodbye'}

S =
    'Hello'    'Yes'    'No'    'Goodbye'
```

See Also

`char`, `cellstr`, `ischar`, `iscellstr`, `strvcat`, `sprintf`, `sscanf`, `input`

Purpose

Justify a character array

Syntax

```
T = strjust(S)
T = strjust(S, 'right')
T = strjust(S, 'left')
T = strjust(S, 'center')
```

Description

`T = strjust(S) or T = strjust(S, 'right')` returns a right-justified version of the character array `S`.

`T = strjust(S, 'left')` returns a left-justified version of `S`.

`T = strjust(S, 'center')` returns a center-justified version of `S`.

See Also

`deblank`

strmatch

Purpose

Find possible matches for a string

Syntax

```
x = strmatch('str', STRS)
x = strmatch('str', STRS, 'exact')
```

Description

`x = strmatch('str', STRS)` looks through the rows of the character array or cell array of strings `STRS` to find strings that begin with string `str`, returning the matching row indices. `strmatch` is fastest when `STRS` is a character array.

`x = strmatch('str', STRS, 'exact')` returns only the indices of the strings in `STRS` matching `str` exactly.

Examples

The statement

```
x = strmatch('max', strvcat('max', 'minimax', 'maximum'))
```

returns `x = [1; 3]` since rows 1 and 3 begin with `'max'`. The statement

```
x = strmatch('max', strvcat('max', 'minimax', 'maximum'),'exact')
```

returns `x = 1`, since only row 1 matches `'max'` exactly.

See Also

`strcmp`, `strcmpi`, `strncmp`, `strncmpi`, `strfind`, `findstr`, `strvcat`, `regexp`, `regexpi`, `regexprep`

Purpose

Compare the first n characters of two strings

Syntax

```
k = strncmp('str1', 'str2', n)
TF = strncmp(S, T, n)
```

Description

`k = strncmp('str1', 'str2', n)` returns logical true (`1`) if the first `n` characters of the strings `str1` and `str2` are the same, and returns logical false (`0`) otherwise. Arguments `str1` and `str2` can also be cell arrays of strings.

`TF = strncmp(S, T, N)`, where either `S` or `T` is a cell array of strings, returns an array `TF` the same size as `S` and `T` containing `1` for those elements of `S` and `T` that match (up to `n` characters), and `0` otherwise. `S` and `T` must be the same size (or one can be a scalar cell). Either one can also be a character array with the right number of rows.

Remarks

The command `strncmp` is case sensitive. Any leading and trailing blanks in either of the strings are explicitly included in the comparison.

`strncmp` is intended for comparison of character data. When used to compare numeric data, `strncmp` returns `0`.

See Also

`strncmpi`, `strcmp`, `strcmpi`, `strmatch`, `strfind`, `findstr`, `regexp`, `regexpi`, `regexprep`

strncmpi

Purpose

Compare first n characters of strings ignoring case

Syntax

```
strncmpi('str1', 'str2', n)
TF = strncmpi(S, T, n)
```

Description

`strncmpi('str1', 'str2', n)` returns 1 if the first `n` characters of the strings `str1` and `str2` are the same except for case, and 0 otherwise.

`TF = strncmpi(S, T, n)`, when either `S` or `T` is a cell array of strings, returns an array the same size as `S` and `T` containing 1 for those elements of `S` and `T` that match except for case (up to `n` characters), and 0 otherwise. `S` and `T` must be the same size (or one can be a scalar cell). Either one can also be a character array with the right number of rows.

Remarks

`strncmpi` is intended for comparison of character data. When used to compare numeric data, `strncmpi` returns 0.

`strncmpi` supports international character sets.

See Also

`strncmp`, `strcmpi`, `strcmp`, `strmatch`, `strfind`, `findstr`, `regexp`, `regexpi`, `regexprep`

Purpose

Read formatted data from a string

Syntax

```
A = strread('str')
[A, B, ...] = strread('str')
[A, B, ...] = strread('str', 'format')
[A, B, ...] = strread('str', 'format', N)
[A, B, ...] = strread('str', 'format', N, param, value, ...)
```

Description

`A = strread('str')` reads numeric data from input string `str` into a 1-by-`N` vector `A`, where `N` equals the number of whitespace-separated numbers in `str`. Use this form only with strings containing numeric data. See "Example 1" below.

`[A, B, ...] = strread('str')` reads numeric data from the string input `str` into scalar output variables `A`, `B`, and so on. The number of output variables must equal the number of whitespace-separated numbers in `str`. Use this form only with strings containing numeric data. See "Example 2" below.

`[A, B, ...] = strread('str', 'format')` reads data from `str` into variables `A`, `B`, and so on using the specified `format`. The number of output variables `A`, `B`, etc. must be equal to the number of format specifiers (e.g., `%s` or `%d`) in the `format` argument. You can read all of the data in `str` to a single output variable as long as you use only one format specifier in the command. See "Example 4" and "Example 5" below.

The table "Formats for strread" lists the valid format specifiers. More information on using formats is available under "Formats" in the Remarks section below.

`[A, B, ...] = strread('str', 'format', N)` reads data from `str` reusing the `format` string `N` times, where `N` is an integer greater than zero. If `N` is -1, `strread` reads the entire string. When `str` contains only numeric data, you can set `format` to the empty string (`''`). See "Example 3" below.

`[A, B, ...] = strread('str', 'format', N, param, value, ...)` customizes `strread` using `param`/`value` pairs, as listed in the table "Parameters and Values for strread" below. When `str` contains only numeric data, you can set `format` to the empty string (`''`). The `N` argument is optional and may be omitted entirely. See "Example 7" below.

Formats for strread

Format	Action	Output
Literals (ordinary characters)	Ignore the matching characters. For example, in a string that has `Dept` followed by a number (for department number), to skip the `Dept` and read only the number, use `'Dept'` in the `format` string.	None
`%d`	Read a signed integer value.	Double array
`%u`	Read an integer value.	Double array
`%f`	Read a floating-point value.	Double array
`%s`	Read a white-space separated string.	Cell array of strings
`%q`	Read a string, which could be in double quotes.	Cell array of strings. Does not include the double quotes.
`%c`	Read characters, including white space.	Character array
`%[...]`	Read the longest string containing characters specified in the brackets.	Cell array of strings
`%[^...]`	Read the longest nonempty string containing characters that are not specified in the brackets.	Cell array of strings
`%*...`	Ignore the characters following `*`. See Example 8 below.	No output
`%w...`	Read field width specified by `w`. The `%f` format supports `%w.pf`, where `w` is the field width and `p` is the precision.	

Parameters and Values for strread

param	value	Action
`white-space`	`\*` where `*` can be	Treats vector of characters, `*`, as white space. Default is `\b\r\n\t`.

	`b`
	`f`
	`n`
	`r`
	`t`
	`\\`
	`\''` or `''`
	`%%`
		Backspace
		Form feed
		New line
		Carriage return
		Horizontal tab
		Backslash
		Single quotation mark
		Percent sign

`delimiter`	Delimiter character	Specifies delimiter character. Default is none.
`expchars`	Exponent characters	Default is `eEdD`.
`bufsize`	Positive integer	Specifies the maximum string length, in bytes. Default is `4095`.
`commentstyle`	`matlab`	Ignores characters after `%`.
`commentstyle`	`shell`	Ignores characters after `#`.
`commentstyle`	`c`	Ignores characters between `/*` and `*/`.
`commentstyle`	`c++`	Ignores characters after `//`.

Remarks

Delimiters

If your data uses a character other than a space as a delimiter, you must use the `strread` parameter `'delimiter'` to specify the delimiter. For example, if the string `str` used a semicolon as a delimiter, you would use this command:

```
[names, types, x, y, answer] = strread(str,'%s %s %f ...
    %d %s','delimiter',';')
```

Formats

The `format` string determines the number and types of return arguments. The number of return arguments must match the number of conversion specifiers in the `format` string.

The `strread` function continues reading `str` until the entire string is read. If there are fewer format specifiers than there are entities in `str`, `strread` reapplies the format specifiers, starting over at the beginning. See Example 5 below.

The `format` string supports a subset of the conversion specifiers and conventions of the C language `fscanf` routine. White-space characters in the `format` string are ignored.

Examples

Example 1

Read numeric data into a 1-by-5 vector:

```
a = strread('0.41 8.24 3.57 6.24 9.27')
a =
    0.4100    8.2400    3.5700    6.2400    9.2700
```

Example 2

Read numeric data into separate scalar variables:

```
[a b c d e] = strread('0.41 8.24 3.57 6.24 9.27')
a =
    0.4100
b =
    8.2400
c =
    3.5700
d =
    6.2400
e =
    9.2700
```

Example 3

Read the only first three numbers in the string, also formatting as floating point:

```
a = strread('0.41 8.24 3.57 6.24 9.27', '%4.2f', 3)
```

```
a =
    0.4100
    8.2400
    3.5700
```

Example 4

Truncate the data to one decimal digit by specifying format `%3.1f`. The second specifier, `%*1d`, tells `strread` not to read in the remaining decimal digit:

```
a = strread('0.41 8.24 3.57 6.24 9.27', '%3.1f %*1d')

a =
    0.4000
    8.2000
    3.5000
    6.2000
    9.2000
```

Example 5

Read six numbers into two variables, reusing the format specifiers:

```
[a b] = strread('0.41 8.24 3.57 6.24 9.27 3.29', '%f %f')

a =
    0.4100
    3.5700
    9.2700
b =
    8.2400
    6.2400
    3.2900
```

Example 6

Read string and numeric data to two output variables. Ignore commas in the input string:

```
str = 'Section 4, Page 7, Line 26';

[name value] = strread(str, '%s %d,')
name =
    'Section'
    'Page'
    'Line'
value =
     4
     7
    26
```

Example 7

Read the string used in the last example, but this time delimiting with commas instead of spaces:

```
str = 'Section 4, Page 7, Line 26';

[a b c] = strread(str, '%s %s %s', 'delimiter', ',')
```

```
a =
    'Section 4'
b =
    'Page 7'
c =
    'Line 26'
```

Example 8

Read selected portions of the input string:

```
str = '<table border=5 width="100%" cellspacing=0>';

[border width space] = strread(str, ...
   '%*s%*s %c %*s "%4s" %*s %c', 'delimiter', '= ')
border =
     5
width =
    '100%'
space =
     0
```

Example 9

Read the string into two vectors, restricting the `Answer` values to `T` and `F`. Also note that two delimiters (comma and space) are used here:

```
str = 'Answer_1: T, Answer_2: F, Answer_3: F';

[a b] = strread(str, '%s %[TF]', 'delimiter', ', ')
a =
    'Answer_1:'
    'Answer_2:'
    'Answer_3:'
b =
    'T'
    'F'
    'F'
```

See Also

`textread`, `sscanf`

strrep

Purpose

String search and replace

Syntax

```
str = strrep(str1, str2, str3)
```

Description

`str = strrep(str1, str2, str3)` replaces all occurrences of the string `str2` within string `str1` with the string `str3`.

`strrep(str1, str2, str3)`, when any of `str1`, `str2`, or `str3` is a cell array of strings, returns a cell array the same size as `str1`, `str2`, and `str3` obtained by performing a `strrep` using corresponding elements of the inputs. The inputs must all be the same size (or any can be a scalar cell). Any one of the strings can also be a character array with the right number of rows.

Examples

```
s1 = 'This is a good example.';
str = strrep(s1, 'good', 'great')
str =
This is a great example.

A =
    'MATLAB'              'SIMULINK'
    'Toolboxes'           'The MathWorks'

B =
    'Handle Graphics'     'Real Time Workshop'
    'Toolboxes'           'The MathWorks'

C =
    'Signal Processing'     'Image Processing'
    'MATLAB'                'SIMULINK'

strrep(A, B, C)
ans =
    'MATLAB'     'SIMULINK'
    'MATLAB'     'SIMULINK'
```

See Also

`strfind`

Purpose

First token in string

Syntax

```
token = strtok('str')
token = strtok('str', delimiter)
[token, rem] = strtok(...)
```

Description

`token = strtok('str')` uses the default delimiters, the white-space characters. These include tabs (ASCII 9), carriage returns (ASCII 13), and spaces (ASCII 32). Any leading white-space characters are ignored. If `str` is a cell array of strings, `token` is a cell array of tokens.

`token = strtok('str', delimiter)` returns the first token in the text string `str`, that is, the first set of characters before a delimiter is encountered. The vector `delimiter` contains valid delimiter characters. Any leading delimiters are ignored. If `str` is a cell array of strings, `token` is a cell array of tokens.

`[token, rem] = strtok(...)` returns the remainder `rem` of the original string. The remainder consists of all characters from the first delimiter on. If `str` is a cell array of strings, `token` is a cell array of tokens, and `rem` is a character array.

Examples

Example 1

This example uses the default white-space delimiter:

```
s = '  This is a simple example.';
[token, rem] = strtok(s)
token =
   This
rem =
   is a simple example.
```

Example 2

Take a string of HTML code and break it down into segments delimited by the < and > characters. Write a `while` loop to parse the string and print each segment:

```
s = sprintf('%s%s%s', ...
'<ul class=continued><li class=continued><pre>', ...
'<a name="13474"></a>token = strtok(''str'', delimiter)', ...
'<a name="13475"></a>token = strtok(''str'')');

rem = s;

while true
   [t{k}, rem] = strtok(rem, '<>');
   if isempty(t{k}),  break;  end
   disp(sprintf('%s',t{k}))
   end
```

Here is the output:

```
ul class=continued
li class=continued
pre
a name="13474"
/a
token = strtok('str', delimiter)
a name="13475"
/a
token = strtok('str')
```

Example 3

Using `strtok` on a cell array of strings returns a cell array of strings in `token` and a character array in `rem`:

```
s = {'all in good time'; ...
     'my dog has fleas'; ...
     'leave no stone unturned'};

rem = s;

for k = 1:4
   [token, rem] = strtok(rem);
   token
   end
```

Here is the output:

```
token =
    'all'
    'my'
    'leave'
token =
    'in'
    'dog'
    'no'
token =
    'good'
    'has'
    'stone'
token =
    'time'
    'fleas'
    'unturned'
```

See Also

`findstr`, `strmatch`

strtrim

Purpose

Remove leading and trailing white-space from string

Syntax

```
S = strtrim(str)
C = strtrim(cstr)
```

Description

`S = strtrim(str)` returns a copy of string `str` with all leading and trailing white-space characters removed. A white-space character is one for which the `isspace` function returns `true`.

`C = strtrim(cstr)` returns a copy of the cell array of strings `cstr` with all leading and trailing white-space characters removed from each string in the cell array.

Examples

Remove the leading white-space characters (spaces and tabs) from `str`:

```
str = sprintf('  \t   Remove    leading white-space')
str =
        Remove    leading white-space

str = strtrim(str)
str =
Remove    leading white-space
```

Remove leading and trailing white-space from the cell array of strings:

```
cstr = {'     Trim leading white-space';
        'Trim trailing white-space     '};

cstr = strtrim(cstr)
cstr =
    'Trim leading white-space'
    'Trim trailing white-space'
```

See Also

`isspace`, `cellstr`, `deblank`

Purpose

Create structure array

Syntax

```
s = struct('field1', {}, 'field2', {}, ...)
s = struct('field1', values1, 'field2', values2, ...)
```

Description

`s = struct('field1', {}, 'field2', {}, ...)` creates an empty structure with fields `field1`, `field2`, ...

`s = struct('field1', values1, 'field2', values2, ...)` creates a structure array with the specified fields and values. The value arrays `values1`, `values2`, etc., must be cell arrays of the same size or scalar cells. Corresponding elements of the value arrays are placed into corresponding structure array elements. The size of the resulting structure is the same size as the value cell arrays or 1-by-1 if none of the values is a cell.

Remarks

The most common way to access the data in a structure is by specifying the name of the field that you want to reference. Another means of accessing structure data is to use dynamic field names. These names express the field as a variable expression that MATLAB evaluates at run-time.

Examples

The command

```
s = struct('type', {'big','little'}, 'color', {'red'}, 'x', {3 4})
```

produces a structure array s:

```
s =
1x2 struct array with fields:
    type
    color
    x
```

The value arrays have been distributed among the fields of s:

```
s(1)
ans =
     type: 'big'
    color: 'red'
        x: 3

s(2)
```

```
ans =
     type: 'little'
    color: 'red'
        x: 4
```

Similarly, the command

```
a.b = struct('z', {});
```

produces an empty structure `a.b` with field `z`.

```
a.b
ans =
      0x0 struct array with fields:
          z
```

See Also

`isstruct`, `fieldnames`, `isfield`, `orderfields`, `getfield`, `setfield`, `rmfield`, `substruct`, `deal`, `cell2struct`, `struct2cell`, dynamic field names

Purpose

Structure to cell array conversion

Syntax

```
c = struct2cell(s)
```

Description

`c = struct2cell(s)` converts the `m`-by-`n` structure `s` (with `p` fields) into a `p`-by-`m`-by-`n` cell array `c`.

If structure `s` is multidimensional, cell array `c` has size `[p size(s)]`.

Examples

The commands

```
clear s, s.category = 'tree';
s.height = 37.4; s.name = 'birch';
```

create the structure

```
s =
    category: 'tree'
      height: 37.4000
        name: 'birch'
```

Converting the structure to a cell array,

```
c = struct2cell(s)

c =
    'tree'
    [37.4000]
    'birch'
```

See Also

`cell2struct`, `cell`, `iscell`, `struct`, `isstruct`, `fieldnames`, dynamic field names

Purpose

Vertical concatenation of strings

Syntax

```
S = strvcat(t1, t2, t3, ...)
```

Description

`S = strvcat(t1, t2, t3, ...)` forms the character array `S` containing the text strings (or string matrices) `t1,t2,t3,...` as rows. Spaces are appended to each string as necessary to form a valid matrix. Empty arguments are ignored.

Remarks

If each text parameter, `ti`, is itself a character array, `strvcat` appends them vertically to create arbitrarily large string matrices.

Examples

The command `strvcat('Hello','Yes')` is the same as `['Hello';'Yes  ']`, except that `strvcat` performs the padding automatically.

```
t1 = 'first'; t2 = 'string'; t3 = 'matrix'; t4 = 'second';

S1 = strvcat(t1, t2, t3)       S2 = strvcat(t4, t2, t3)

S1 =                           S2 =

first                          second
string                         string
matrix                         matrix

S3 = strvcat(S1, S2)

S3 =
first
string
matrix
second
string
matrix
```

See Also

`cat`, `int2str`, `mat2str`, `num2str`, `strings`

Purpose

Single index from subscripts

Syntax

```
IND = sub2ind(siz,I,J)
IND = sub2ind(siz,I1,I2,...,In)
```

Description

The `sub2ind` command determines the equivalent single index corresponding to a set of subscript values.

`IND = sub2ind(siz,I,J)` returns the linear index equivalent to the row and column subscripts `I` and `J` for a matrix of size `siz`. `siz` is a 2-element vector, where `siz(1)` is the number of rows and `siz(2)` is the number of columns.

`IND = sub2ind(siz,I1,I2,...,In)` returns the linear index equivalent to the `n` subscripts `I1,I2,...,In` for an array of size `siz`. `siz` is an `n`-element vector that specifies the size of each array dimension.

Examples

Create a 3-by-4-by-2 array, `A`.

```
A = [17 24 1 8; 2 22 7 14; 4 6 13 20];
A(:,:,2) = A - 10

A(:,:,1) =

    17    24     1     8
     2    22     7    14
     4     6    13    20


A(:,:,2) =

     7    14    -9    -2
    -8    12    -3     4
    -6    -4     3    10
```

The value at row 2, column 1, page 2 of the array is -8.

```
A(2,1,2)

ans =

    -8
```

To convert `A(2,1,2)` into its equivalent single subscript, use `sub2ind`.

```
sub2ind(size(A),2,1,2)

ans =

    14
```

You can now access the same location in `A` using the single subscripting method.

```
A(14)

ans =

    -8
```

See Also

`ind2sub`, `find`, `size`

Purpose

Create and control multiple axes

Syntax

```
subplot(m,n,p)
subplot(m,n,p,'replace')
subplot(m,n,p,'align')
subplot(h)
subplot('Position',[left bottom width height])
h = subplot(...)
```

Description

`subplot` divides the current figure into rectangular panes that are numbered rowwise. Each pane contains an axes. Subsequent plots are output to the current pane.

`subplot(m,n,p)` creates an axes in the `p`th pane of a figure divided into an `m`-by-`n` matrix of rectangular panes. The new axes becomes the current axes.

If `p` is a vector, it specifies an axes having a position that covers all the subplot positions listed in `p`.

`subplot(m,n,p,'replace')` If the specified axes already exists, delete it and create a new axes.

`subplot(m,n,p,'align')` positions the individual axes so that the plot boxes align, but does not prevent the labels and ticks from overlapping.

`subplot(h)` makes the axes with handle `h` current for subsequent plotting commands.

`subplot('Position',[left bottom width height])` creates an axes at the position specified by a four-element vector. `left`, `bottom`, `width`, and `height` are in normalized coordinates in the range from 0.0 to 1.0.

`h = subplot(...)` returns the handle to the new axes.

Remarks

If a `subplot` specification causes a new axes to overlap any existing axes, then `subplot` deletes the existing axes and uicontrol objects. However, if the `subplot` specification exactly matches the position of an existing axes, then the matching axes is not deleted and it becomes the current axes.

`subplot(1,1,1)` or `clf` deletes all axes objects and returns to the default `subplot(1,1,1)` configuration.

You can omit the parentheses and specify subplot as

```
subplot mnp
```

where `m` refers to the row, `n` refers to the column, and `p` specifies the pane.

Special Case – subplot(111)

The command `subplot(111)` is not identical in behavior to `subplot(1,1,1)` and exists only for compatibility with previous releases. This syntax does not immediately create an axes, but instead sets up the figure so that the next graphics command executes a `clf reset` (deleting all figure children) and creates a new axes in the default position. This syntax does not return a handle, so it is an error to specify a return argument. (This behavior is implemented by setting the figure's `NextPlot` property to `replace`.)

Examples

To plot `income` in the top half of a figure and `outgo` in the bottom half,

```
income = [3.2 4.1 5.0 5.6];
outgo = [2.5 4.0 3.35 4.9];
subplot(2,1,1); plot(income)
subplot(2,1,2); plot(outgo)
```



The following illustration shows four subplot regions and indicates the command used to create each.



The following combinations produce asymmetrical arrangements of subplots.

```
subplot(2,2,[1 3])
subplot(2,2,2)
subplot(2,2,4)
```



You can also use the colon operator to specify multiple locations if they are in sequence.

```
subplot(2,2,1:2)
subplot(2,2,3)
subplot(2,2,4)
```



See Also `axes`, `cla`, `clf`, `figure`, `gca`

"Basic Plots and Graphs" for more information

Purpose

Overloaded method for `A(I)=B`, `A{I}=B`, and `A.field=B`

Syntax

```
A = subsasgn(A,S,B)
```

Description

`A = subsasgn(A,S,B)` is called for the syntax `A(i)=B`, `A{i}=B`, or `A.i=B` when `A` is an object. `S` is a structure array with the fields

- `type`: A string containing `'()'`, `'{}'`, or `'.'`, where `'()'` specifies integer subscripts, `'{}'` specifies cell array subscripts, and `'.'` specifies subscripted structure fields.
- `subs`: A cell array or string containing the actual subscripts.

Remarks

`subsasgn` is designed to be used by the MATLAB interpreter to handle indexed assignments to objects. Calling `subsasgn` directly as a function is not recommended. If you do use `subsasgn` in this way, it conforms to the formal MATLAB dispatching rules and can yield unexpected results.

Examples

The syntax `A(1:2,:)=B` calls `A=subsasgn(A,S,B)` where `S` is a 1-by-1 structure with `S.type='()'` and `S.subs = {1:2,':'}`. A colon used as a subscript is passed as the string `':'`.

The syntax `A{1:2}=B` calls `A=subsasgn(A,S,B)` where `S.type='{}'`.

The syntax `A.field=B` calls `subsasgn(A,S,B)` where `S.type='.'` and `S.subs='field'`.

These simple calls are combined in a straightforward way for more complicated subscripting expressions. In such cases `length(S)` is the number of subscripting levels. For instance, `A(1,2).name(3:5)=B` calls `A=subsasgn(A,S,B)` where `S` is a 3-by-1 structure array with the following values:

```
S(1).type='()'        S(2).type='.'         S(3).type='()'
S(1).subs={1,2}       S(2).subs='name'      S(3).subs={3:5}
```

See Also

`subsref`

See “Handling Subscripted Assignment” for more information about overloaded methods and `subsasgn`.

subsindex

Purpose

Overloaded method for `X(A)`

Syntax

```
ind = subsindex(A)
```

Description

`ind = subsindex(A)` is called for the syntax `'X(A)'` when `A` is an object. `subsindex` must return the value of the object as a zero-based integer index. (`ind` must contain integer values in the range `0` to `prod(size(X))-1`.) `subsindex` is called by the default `subsref` and `subsasgn` functions, and you can call it if you overload these functions.

See Also

`subsasgn`, `subsref`

Purpose

Angle between two subspaces

Syntax

```
theta = subspace(A,B)
```

Description

`theta = subspace(A,B)` finds the angle between two subspaces specified by the columns of `A` and `B`. If `A` and `B` are column vectors of unit length, this is the same as `acos(A'*B)`.

Remarks

If the angle between the two subspaces is small, the two spaces are nearly linearly dependent. In a physical experiment described by some observations `A`, and a second realization of the experiment described by `B`, `subspace(A,B)` gives a measure of the amount of new information afforded by the second experiment not associated with statistical errors of fluctuations.

Examples

Consider two subspaces of a Hadamard matrix, whose columns are orthogonal.

```
H = hadamard(8);
A = H(:,2:4);
B = H(:,5:8);
```

Note that matrices `A` and `B` are different sizes— `A` has three columns and `B` four. It is not necessary that two subspaces be the same size in order to find the angle between them. Geometrically, this is the angle between two hyperplanes embedded in a higher dimensional space.

```
theta = subspace(A,B)
theta =
    1.5708
```

That `A` and `B` are orthogonal is shown by the fact that `theta` is equal to $\pi/2$.

```
theta - pi/2
ans =
     0
```

subsref

Purpose

Overloaded method for `A(I)`, `A{I}` and `A.field`

Syntax

```
B = subsref(A,S)
```

Description

`B = subsref(A,S)` is called for the syntax `A(i)`, `A{i}`, or `A.i` when `A` is an object. `S` is a structure array with the fields

- `type`: A string containing `'()'`, `'{}'`, or `'.'`, where `'()'` specifies integer subscripts, `'{}'` specifies cell array subscripts, and `'.'` specifies subscripted structure fields.
- `subs`: A cell array or string containing the actual subscripts.

Remarks

`subsref` is designed to be used by the MATLAB interpreter to handle indexed references to objects. Calling `subsref` directly as a function is not recommended. If you do use `subsref` in this way, it conforms to the formal MATLAB dispatching rules and can yield unexpected results.

Examples

The syntax `A(1:2,:)` calls `subsref(A,S)` where `S` is a 1-by-1 structure with `S.type='()'` and `S.subs={1:2,':'}`. A colon used as a subscript is passed as the string `':'`.

The syntax `A{1:2}` calls `subsref(A,S)` where `S.type='{}'` and `S.subs={1:2}`.

The syntax `A.field` calls `subsref(A,S)` where `S.type='.'` and `S.subs='field'`.

These simple calls are combined in a straightforward way for more complicated subscripting expressions. In such cases `length(S)` is the number of subscripting levels. For instance, `A(1,2).name(3:5)` calls `subsref(A,S)` where `S` is a 3-by-1 structure array with the following values:

```
S(1).type='()'        S(2).type='.'         S(3).type='()'
S(1).subs={1,2}       S(2).subs='name'      S(3).subs={3:5}
```

See Also

`subsasgn`

See "Handling Subscripted Reference" for more information about overloaded methods and `subsref`.

Purpose

Create structure argument for subsasgn or subsref

Syntax

```
S = substruct(type1,subs1,type2,subs2,...)
```

Description

`S = substruct(type1,subs1,type2,subs2,...)` creates a structure with the fields required by an overloaded `subsref` or `subsasgn` method. Each `type` string must be one of `'.'`, `'()'`, or `'{}'`. The corresponding `subs` argument must be either a field name (for the `'.'` type) or a cell array containing the index vectors (for the `'()'` or `'{}'` types).

The output `S` is a structure array containing the fields

- `type`: one of `'.'`, `'()'`, or `'{}'`
- `subs`: subscript values (field name or cell array of index vectors)

Examples

To call `subsref` with parameters equivalent to the syntax

```
B = A(3,5).field
```

you can use

```
S = substruct('()',{3,5},'.','field');
B = subsref(A,S);
```

The structure created by `substruct` in this example contains the following:

```
S(1)

ans =

    type: '()'
    subs: {[3]  [5]}

S(2)

ans =

    type: '.'
    subs: 'field'
```

See Also

subsasgn, subsref

Purpose

Sum of array elements

Syntax

```
B = sum(A)
B = sum(A, dim)
B = sum(A, 'double')
B = sum(A, dim, 'double')
B = sum(A, 'native')
B = sum(A, dim, 'native')
```

Description

`B = sum(A)` returns sums along different dimensions of an array.

If `A` is a vector, `sum(A)` returns the sum of the elements.

If `A` is a matrix, `sum(A)` treats the columns of `A` as vectors, returning a row vector of the sums of each column.

If `A` is a multidimensional array, `sum(A)` treats the values along the first non-singleton dimension as vectors, returning an array of row vectors.

`B = sum(A,dim)` sums along the dimension of `A` specified by scalar `dim`.

`B = sum(..., 'double')` performs additions in double-precision and return an answer of type `double`, even if `A` has data type `single` or an integer data type. This is the default for integer data types.

`B = sum(..., 'native')` performs additions in the native data type of `A` and return an answer of the same data type. This is the default for `single` and `double`.

Remarks

`sum(diag(X))` is the `trace` of `X`.

Examples

The magic square of order 3 is

```
M = magic(3)
M =
     8    1    6
     3    5    7
     4    9    2
```

This is called a magic square because the sums of the elements in each column are the same.

```
sum(M) =
     15    15    15
```

as are the sums of the elements in each row, obtained by transposing:

```
sum(M') =
     15    15    15
```

Nondouble Data Type Support

This section describes the support of sum for data types other than `double`.

Data Type `single`

You can apply `sum` to an array of type `single` and MATLAB returns an answer of type `single`. For example,

```
sum(single([2 5 8]})

ans =

     15

class(ans)

ans =

single
```

Integer Data Types

When you apply `sum` to any of the following integer data types, MATLAB returns an answer of type double:

- `int8` and `uint8`
- `int16` and `uint16`
- `int32` and `uint32`

For example,

```
sum(single([2 5 8]});
class(ans)

ans =
```

```
single
```

If you want MATLAB to perform additions on an integer data type in the same integer type as the input, use the syntax

```
sum(int8([2 5 8], 'native');
class(ans)

ans =

int8
```

See Also

`cumsum`, `diff`, `prod`, `trac`

Purpose

Extract subset of volume data set

Syntax

```
[Nx,Ny,Nz,Nv] = subvolume(X,Y,Z,V,limits)
[Nx,Ny,Nz,Nv] = subvolume(V,limits)
Nv = subvolume(...)
```

Description

`[Nx,Ny,Nz,Nv] = subvolume(X,Y,Z,V,limits)` extracts a subset of the volume data set `V` using the specified axis-aligned `limits`. `limits = [xmin,xmax,ymin, ymax,zmin,zmax]` (Any `NaN`s in the limits indicate that the volume should not be cropped along that axis.)

The arrays `X`, `Y`, and `Z` define the coordinates for the volume `V`. The subvolume is returned in `NV` and the coordinates of the subvolume are given in `NX`, `NY`, and `NZ`.

`[Nx,Ny,Nz,Nv] = subvolume(V,limits)` assumes the arrays `X`, `Y`, and `Z` are defined as

```
[X,Y,Z] = meshgrid(1:N,1:M,1:P)
```

where `[M,N,P] = size(V)`.

`Nv = subvolume(...)` returns only the subvolume.

Examples

This example uses a data set that is a collection of MRI slices of a human skull. The data is processed in a variety of ways:

- The 4-D array is squeezed (`squeeze`) into three dimensions and then a subset of the data is extracted (`subvolume`).
- The outline of the skull is an isosurface generated as a patch (`p1`) whose vertex normals are recalculated to improve the appearance when lighting is applied (`patch`, `isosurface`, `isonormals`).
- A second patch (`p2`) with interpolated face color draws the end caps (`FaceColor`, `isocaps`).
- The view of the object is set (`view`, `axis`, `daspect`).
- A 100-element grayscale colormap provides coloring for the end caps (`colormap`).

Adding lights to the right and left of the camera illuminates the object (`camlight`, `lighting`).

```
load mri
D = squeeze(D);
[x,y,z,D] = subvolume(D,[60,80,nan,80,nan,nan]);
p1 = patch(isosurface(x,y,z,D, 5),...
     'FaceColor','red','EdgeColor','none');
isonormals(x,y,z,D,p1);
p2 = patch(isocaps(x,y,z,D, 5),...
     'FaceColor','interp','EdgeColor','none');
view(3); axis tight; daspect([1,1,.4])
colormap(gray(100))
camlight right; camlight left; lighting gouraud
```



See Also `isocaps`, `isonormals`, `isosurface`, `reducepatch`, `reducevolume`, `smooth3`

"Volume Visualization" for related functions

Purpose

Superior class relationship

Syntax

```
superiorto('class1','class2',...)
```

Description

The `superiorto` function establishes a hierarchy that determines the order in which MATLAB calls object methods.

`superiorto('class1','class2',...)` invoked within a class constructor method (say `myclass.m`) indicates that `myclass`'s method should be invoked if a function is called with an object of class `myclass` and one or more objects of class `class1`, `class2`, and so on.

Remarks

Suppose `A` is of class `'class_a'`, `B` is of class `'class_b'` and `C` is of class `'class_c'`. Also suppose the constructor `class_c.m` contains the statement `superiorto('class_a')`. Then `e = fun(a,c)` or `e = fun(c,a)` invokes `class_c/fun`.

If a function is called with two objects having an unspecified relationship, the two objects are considered to have equal precedence, and the leftmost object's method is called. So `fun(b,c)` calls `class_b/fun`, while `fun(c,b)` calls `class_c/fun`.

See Also

`inferiorto`

support

Purpose

Open MathWorks Technical Support Web page

Syntax

```
support
```

Description

`support` opens The MathWorks Technical Support Web page, `http://www.mathworks.com/support`, in the MATLAB Web browser.

This Web page contains resources including

- A Search Engine, including an option for solutions to common problems
- Information about installation and licensing
- A patch archive for bug fixes you can download
- Other useful resources

See Also

`doc`, `web`

Purpose

3-D shaded surface plot

Syntax

```
surf(Z)
surf(X,Y,Z)
surf(X,Y,Z,C)
surf(...,'PropertyName',PropertyValue)
surf(axes_handle,...)
surfc(...)
h = surf(...)
h = surfc(...)
hsurface = surf('v6',...), hsurface = surfc('v6',...)
```

Description

Use `surf` and `surfc` to view mathematical functions over a rectangular region. `surf` and `surfc` create colored parametric surfaces specified by `X`, `Y`, and `Z`, with color specified by `Z` or `C`.

`surf(Z)` creates a a three-dimensional shaded surface from the *z* components in matrix `Z`, using `x = 1:n` and `y = 1:m`, where `[m,n] = size(Z)`. The height, `Z`, is a single-valued function defined over a geometrically rectangular grid. `Z` specifies the color data as well as surface height, so color is proportional to surface height.

`surf(X,Y,Z)` creates a shaded surface using `Z` for the color data as well as surface height. `X` and `Y` are vectors or matrices defining the `x` and `y` components of a surface. If `X` and `Y` are vectors, `length(X) = n` and `length(Y) = m`, where `[m,n] = size(Z)`. In this case, the vertices of the surface faces are $(X(j), Y(i), Z(i,j))$ triples.

`surf(X,Y,Z,C)` creates a shaded surface, with color defined by `C`. MATLAB performs a linear transformation on this data to obtain colors from the current colormap.

`surf(...,'PropertyName',PropertyValue)` specifies surface properties along with the data.

`surf(axes_handles,...)` and `surfc(axes_handles,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`surfc(...)` draws a contour plot beneath the surface.

`h = surf(...)` and `h = surfc(...)` return a handle to a surfaceplot graphics object.

Backward Compatible Version

`hsurface = surf('v6',...)` and `hsurface = surfc('v6',...)` returns the handles of surface objects instead of surfaceplot objects for compatibility with MATLAB 6.5 and earlier.

Algorithm

Abstractly, a parametric surface is parametrized by two independent variables, `i` and `j`, which vary continuously over a rectangle; for example, $1 \le i \le m$ and $1 \le j \le n$. The three functions `x(i,j)`, `y(i,j)`, and `z(i,j)` specify the surface. When `i` and `j` are integer values, they define a rectangular grid with integer grid points. The functions `x(i,j)`, `y(i,j)`, and `z(i,j)` become three `m`-by-`n` matrices, `X`, `Y`, and `Z`. Surface color is a fourth function, `c(i,j)`, denoted by matrix `C`.

Each point in the rectangular grid can be thought of as connected to its four nearest neighbors.

```
          i 1,j
            |
  i,j 1   i,j   i,j+1
            |
          i+1,j
```

This underlying rectangular grid induces four-sided patches on the surface. To express this another way, `[X(:) Y(:) Z(:)]` returns a list of triples specifying points in 3-space. Each interior point is connected to the four neighbors inherited from the matrix indexing. Points on the edge of the surface have three neighbors; the four points at the corners of the grid have only two neighbors. This defines a mesh of quadrilaterals or a *quad-mesh*.

Surface color can be specified in two different ways: at the vertices or at the centers of each patch. In this general setting, the surface need not be a single-valued function of `x` and `y`. Moreover, the four-sided surface patches need not be planar. For example, you can have surfaces defined in polar, cylindrical, and spherical coordinate systems.

The `shading` function sets the shading. If the shading is `interp`, `C` must be the same size as `X`, `Y`, and `Z`; it specifies the colors at the vertices. The color within

a surface patch is a bilinear function of the local coordinates. If the shading is `faceted` (the default) or `flat`, `C(i,j)` specifies the constant color in the surface patch:

```
   (i,j)       (i,j+1)
     |   C(i,j)  |
  (i+1,j)     (i+1,j+1)
```

In this case, `C` can be the same size as `X`, `Y`, and `Z` and its last row and column are ignored. Alternatively, its row and column dimensions can be one less than those of `X`, `Y`, and `Z`.

The `surf` and `surfc` functions specify the viewpoint using `view(3)`.

The range of `X`, `Y`, and `Z` or the current setting of the axes `XLimMode`, `YLimMode`, and `ZLimMode` properties (also set by the `axis` function) determines the axis labels.

The range of `C` or the current setting of the axes `CLim` and `ClimMode` properties (also set by the `caxis` function) determines the color scaling. The scaled color values are used as indices into the current colormap.

Examples

Display a surfaceplot and contour plot of the `peaks` surface.

```
[X,Y,Z] = peaks(30);
surfc(X,Y,Z)
colormap hsv
axis([-3 3 -3 3 -10 5])
```



Color a sphere with the pattern of +1s and -1s in a Hadamard matrix.

```
k = 5;
n = 2^k 1;
[x,y,z] = sphere(n);
c = hadamard(2^k);
surf(x,y,z,c);
colormap([1  1  0; 0  1  1])
axis equal
```



See Also

`axis`, `caxis`, `colormap`, `contour`, `delaunay`, `mesh`, `pcolor`, `shading`, `trisurf`, `view`

Properties for surfaceplot graphics objects

“Creating Surfaces and Meshes” for related functions

Representing a Matrix as a Surface for more examples

Coloring Mesh and Surface Plots for information about how to control the coloring of surfaces

surf2patch

Purpose

Convert surface data to patch data

Syntax

```
fvc = surf2patch(h)
fvc = surf2patch(Z)
fvc = surf2patch(Z,C)
fvc = surf2patch(X,Y,Z)
fvc = surf2patch(X,Y,Z,C)
fvc = surf2patch(...,'triangles')
[f,v,c] = surf2patch(...)
```

Description

`fvc = surf2patch(h)` converts the geometry and color data from the `surface` object identified by the handle `h` into patch format and returns the face, vertex, and color data in the struct `fvc`. You can pass this struct directly to the `patch` command.

`fvc = surf2patch(Z)` calculates the patch data from the surface's `ZData` matrix `Z`.

`fvc = surf2patch(Z,C)` calculates the patch data from the surface's `ZData` and `CData` matrices `Z` and `C`.

`fvc = surf2patch(X,Y,Z)` calculates the patch data from the surface's `XData`, `YData`, and `ZData` matrices `X`, `Y`, and `Z`.

`fvc = surf2patch(X,Y,Z,C)` calculates the patch data from the surface's `XData`, `YData`, `ZData`, and `CData` matrices `X`, `Y`, `Z`, and `C`.

`fvc = surf2patch(...,'triangles')` creates triangular faces instead of the quadrilaterals that compose surfaces.

`[f,v,c] = surf2patch(...)` returns the face, vertex, and color data in the three arrays `f`, `v`, and `c` instead of a struct.

Examples

The first example uses the `sphere` command to generate the `XData`, `YData`, and `ZData` of a surface, which is then converted to a patch. Note that the `ZData` (`z`) is passed to `surf2patch` as both the third and fourth arguments — the third argument is the `ZData` and the fourth argument is taken as the `CData`. This is because the `patch` command does not automatically use the *z*-coordinate data for the color data, as does the `surface` command.

Also, because patch is a low-level command, you must set the view to 3-D and shading to faceted to produce the same results produced by the surf command.

```
[x y z] = sphere;
patch(surf2patch(x,y,z,z));
shading faceted; view(3)
```

In the second example surf2patch calculates face, vertex, and color data from a surface whose handle has been passed as an argument.

```
s = surf(peaks);
pause
patch(surf2patch(s));
delete(s)
shading faceted; view(3)
```

See Also

patch, reducepatch, shrinkfaces, surface, surf

"Volume Visualization" for related functions

surface

Purpose

Create surface object

Syntax

```
surface(Z)
surface(Z,C)
surface(X,Y,Z)
surface(X,Y,Z,C)
surface(...'PropertyName',PropertyValue,...)
h = surface(...)
```

Description

`surface` is the low-level function for creating surface graphics objects. Surfaces are plots of matrix data created using the row and column indices of each element as the *x*- and *y*-coordinates and the value of each element as the *z*-coordinate.

`surface(Z)` plots the surface specified by the matrix `Z`. Here, `Z` is a single-valued function, defined over a geometrically rectangular grid.

`surface(Z,C)` plots the surface specified by `Z` and colors it according to the data in `C` (see "Examples").

`surface(X,Y,Z)` uses `C = Z`, so color is proportional to surface height above the *x*-*y* plane.

`surface(X,Y,Z,C)` plots the parametric surface specified by `X`, `Y`, and `Z`, with color specified by `C`.

`surface(x,y,Z)`, `surface(x,y,Z,C)` replaces the first two matrix arguments with vectors and must have `length(x) = n` and `length(y) = m` where `[m,n] = size(Z)`. In this case, the vertices of the surface facets are the triples `(x(j),y(i),Z(i,j))`. Note that `x` corresponds to the columns of `Z` and `y` corresponds to the rows of `Z`. For a complete discussion of parametric surfaces, see the `surf` function.

`surface(...'PropertyName',PropertyValue,...)` follows the `X`, `Y`, `Z`, and `C` arguments with property name/property value pairs to specify additional surface properties.

`h = surface(...)` returns a handle to the created surface object.

Remarks

surface does not respect the settings of the figure and axes NextPlot properties. It simply adds the surface object to the current axes.

If you do not specify separate color data (C), MATLAB uses the matrix (Z) to determine the coloring of the surface. In this case, color is proportional to values of Z. You can specify a separate matrix to color the surface independently of the data defining the area of the surface.

You can specify properties as property name/property value pairs, structure arrays, and cell arrays (see set and get for examples of how to specify these data types).

surface provides convenience forms that allow you to omit the property name for the XData, YData, ZData, and CData properties. For example,

```
surface('XData',X,'YData',Y,'ZData',Z,'CData',C)
```

is equivalent to

```
surface(X,Y,Z,C)
```

When you specify only a single matrix input argument,

```
surface(Z)
```

MATLAB assigns the data properties as if you specified

```
surface('XData',[1:size(Z,2)],...
        'YData',[1:size(Z,1)],...
        'ZData',Z,...
        'CData',Z)
```

The axis, caxis, colormap, hold, shading, and view commands set graphics properties that affect surfaces. You can also set and query surface property values after creating them using the set and get commands.

Example

This example creates a surface using the peaks M-file to generate the data, and colors it using the clown image. The ZData is a 49-by-49 element matrix, while the CData is a 200-by-320 matrix. You must set the surface's FaceColor to texturemap to use ZData and CData of different dimensions.

```
load clown
surface(peaks,flipud(X),...
        'FaceColor','texturemap',...
```

```
        'EdgeColor','none',...
        'CDataMapping','direct')
colormap(map)
view(-35,45)
```



Note the use of the `surface(Z,C)` convenience form combined with property name/property value pairs.

Since the clown data (`X`) is typically viewed with the `image` command, which MATLAB normally displays with `'ij'` axis numbering and `direct` `CDataMapping`, this example reverses the data in the vertical direction using `flipud` and sets the `CDataMapping` property to `direct`.

Object Hierarchy



Setting Default Properties

You can set default surface properties on the axes, figure, and root levels:

```
set(0,'DefaultSurfaceProperty',PropertyValue...)
set(gcf,'DefaultSurfaceProperty',PropertyValue...)
set(gca,'DefaultSurfaceProperty',PropertyValue...)
```

where *`Property`* is the name of the surface property whose default value you want to set and `PropertyValue` is the value you are specifying. Use `set` and `get` to access the surface properties.

See Also

`ColorSpec`, `patch`, `pcolor`, `surf`

Properties for surface graphics objects

"Creating Surfaces and Meshes" and "Object Creation Functions" for related functions

Surface Properties

Modifying Properties

You can set and query graphics object properties in two ways:

- The Property Editor is an interactive tool that enables you to see and change object property values.
- The `set` and `get` commands enable you to set and query the values of properties.

To change the default values of properties, see Setting Default Property Values.

See Core Objects for general information about this type of object.

Surface Property Descriptions

This section lists property names along with the types of values each accepts. Curly braces { } enclose default values.

`AlphaData` m-by-n matrix of `double` or `uint8`

The transparency data. A matrix of non-NaN values specifying the transparency of each face or vertex of the object. The `AlphaData` can be of class double or uint8.

MATLAB determines the transparency in one of three ways:

- Using the elements of `AlphaData` as transparency values (`AlphaDataMapping` set to `none`)
- Using the elements of `AlphaData` as indices into the current alphamap (`AlphaDataMapping` set to `direct`)
- Scaling the elements of `AlphaData` to range between the minimum and maximum values of the axes `ALim` property (`AlphaDataMapping` set to `scaled`, the default)

`AlphaDataMapping` `none | direct | {scaled}`

Transparency mapping method. This property determines how MATLAB interprets indexed alpha data. This property can be any of the following:

- `none` — The transparency values of `AlphaData` are between 0 and 1 or are clamped to this range (the default).
- `scaled` — Transform the `AlphaData` to span the portion of the alphamap indicated by the axes `ALim` property, linearly mapping data values to alpha values.

- `direct` — use the `AlphaData` as indices directly into the alphamap. When not scaled, the data are usually integer values ranging from `1` to `length(alphamap)`. MATLAB maps values less than `1` to the first alpha value in the alphamap, and values greater than `length(alphamap)` to the last alpha value in the alphamap. Values with a decimal portion are fixed to the nearest lower integer. If `AlphaData` is an array of `uint8` integers, then the indexing begins at `0` (i.e., MATLAB maps a value of `0` to the first alpha value in the alphamap).

`AmbientStrength` scalar >= 0 and <= 1

Strength of ambient light. This property sets the strength of the ambient light, which is a nondirectional light source that illuminates the entire scene. You must have at least one visible light object in the axes for the ambient light to be visible. The axes `AmbientLightColor` property sets the color of the ambient light, which is therefore the same on all objects in the axes.

You can also set the strength of the diffuse and specular contribution of light objects. See the surface `DiffuseStrength` and `SpecularStrength` properties.

`BackFaceLighting` `unlit | lit | reverselit`

Face lighting control. This property determines how faces are lit when their vertex normals point away from the camera.

- `unlit` — Face is not lit.
- `lit` — Face is lit in normal way.
- `reverselit` — Face is lit as if the vertex pointed towards the camera.

This property is useful for discriminating between the internal and external surfaces of an object. See Back Face Lighting for an example.

`BeingDeleted` `on | {off}` Read Only

This object is being deleted. The `BeingDeleted` property provides a mechanism that you can use to determine if objects are in the process of being deleted. MATLAB sets the `BeingDeleted` property to `on` when the object's delete function callback is called (see the `DeleteFcn` property). It remains set to `on` while the delete function executes, after which the object no longer exists.

For example, an object's delete function might call other functions that act on a number of different objects. These functions may not need to perform actions

on objects that are going to be deleted, and therefore, can check the object's `BeingDeleted` property before acting.

`BusyAction` `cancel | {queue}`

Callback routine interruption. The `BusyAction` property enables you to control how MATLAB handles events that potentially interrupt executing callback routines. If there is a callback routine executing, callback routines invoked subsequently always attempt to interrupt it. If the `Interruptible` property of the object whose callback is executing is set to `on` (the default), then interruption occurs at the next point where the event queue is processed. If the `Interruptible` property is `off`, the `BusyAction` property (of the object owning the executing callback) determines how MATLAB handles the event. The choices are

- `cancel` — Discard the event that attempted to execute a second callback routine.
- `queue` — Queue the event that attempted to execute a second callback routine until the current callback finishes.

`ButtonDownFcn` string or function handle

Button press callback routine. A callback routine that executes whenever you press a mouse button while the pointer is over the surface object. Define this routine as a string that is a valid MATLAB expression or the name of an M-file. The expression executes in the MATLAB workspace.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

`CData` matrix

Vertex colors. A matrix containing values that specify the color at every point in `ZData`. If you set the `FaceColor` property to `texturemap`, `CData` does not need to be the same size as `ZData`. In this case, MATLAB maps `CData` to conform to the surface defined by `ZData`.

You can specify color as indexed values or true color. Indexed color data specifies a single value for each vertex. These values are either scaled to map linearly into the current colormap (see `caxis`) or interpreted directly as indices into the colormap, depending on the setting of the `CDataMapping` property.

True color defines an RGB value for each vertex. If the coordinate data (`XData`, for example) are contained in *m*-by-*n* matrices, then `CData` must be an *m*-by-*n*-3 array. The first page contains the red components, the second the green components, and the third the blue components of the colors.

`CDataMapping` `{scaled} | direct`

Direct or scaled color mapping. This property determines how MATLAB interprets indexed color data used to color the surface. (If you use true color specification for `CData`, this property has no effect.)

- `scaled` — Transform the color data to span the portion of the colormap indicated by the axes `CLim` property, linearly mapping data values to colors. See the `caxis` reference page for more information on this mapping.
- `direct` — Use the color data as indices directly into the colormap. The color data should then be integer values ranging from 1 to `length(colormap)`. MATLAB maps values less than 1 to the first color in the colormap, and values greater than `length(colormap)` to the last color in the colormap. Values with a decimal portion are fixed to the nearest lower integer.

`Children` matrix of handles

Always the empty matrix; surface objects have no children.

`Clipping` `{on} | off`

Clipping to axes rectangle. When `Clipping` is `on`, MATLAB does not display any portion of the surface that is outside the axes rectangle.

`CreateFcn` string or function handle

Callback routine executed during object creation. This property defines a callback routine that executes when MATLAB creates a surface object. You must define this property as a default value for surfaces or set the `CreateFcn` property during object creation.

For example, the following statement creates a surface (assuming `x`, `y`, `z`, and `c` are defined), and executes the function referenced by the function handle `@myCreateFcn`.

```
surface(x,y,z,c,'CreateFcn',@myCreateFcn)
```

MATLAB executes this routine after setting all surface properties. Setting this property on an existing surface object has no effect.

The handle of the object whose `CreateFcn` is being executed is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

`DeleteFcn` string or function handle

Delete surface callback routine. A callback routine that executes when you delete the surface object (e.g., when you issue a `delete` command or clear the axes or figure). MATLAB executes the routine before destroying the object's properties so these values are available to the callback routine.

The handle of the object whose `DeleteFcn` is being executed is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

`DiffuseStrength` scalar >= 0 and <= 1

Intensity of diffuse light. This property sets the intensity of the diffuse component of the light falling on the surface. Diffuse light comes from light objects in the axes.

You can also set the intensity of the ambient and specular components of the light on the surface object. See the `AmbientStrength` and `SpecularStrength` properties.

`EdgeAlpha` `{scalar = 1} | flat | interp`

Transparency of the surface edges. This property can be any of the following:

- `scalar` — A single non-Nan scalar value between `0` and `1` that controls the transparency of all the edges of the object. `1` (the default) means fully opaque and `0` means completely transparent.
- `flat` — The alpha data (`AlphaData`) value for the first vertex of the face determines the transparency of the edges.
- `interp` — Linear interpolation of the alpha data (`AlphaData`) values at each vertex determines the transparency of the edge.

Note that you must specify `AlphaData` as a matrix equal in size to `ZData` to use `flat` or `interp` `EdgeAlpha`.

EdgeColor {ColorSpec} | none | flat | interp

Color of the surface edge. This property determines how MATLAB colors the edges of the individual faces that make up the surface:

- `ColorSpec` — A three-element RGB vector or one of the MATLAB predefined names, specifying a single color for edges. The default `EdgeColor` is black. See `ColorSpec` for more information on specifying color.
- `none` — Edges are not drawn.
- `flat` — The `CData` value of the first vertex for a face determines the color of each edge.



- `interp` — Linear interpolation of the `CData` values at the face vertices determines the edge color.

EdgeLighting {none} | flat | gouraud | phong

Algorithm used for lighting calculations. This property selects the algorithm used to calculate the effect of light objects on surface edges. Choices are

- `none` — Lights do not affect the edges of this object.
- `flat` — The effect of light objects is uniform across each edge of the surface.
- `gouraud` — The effect of light objects is calculated at the vertices and then linearly interpolated across the edge lines.
- `phong` — The effect of light objects is determined by interpolating the vertex normals across each edge line and calculating the reflectance at each pixel. Phong lighting generally produces better results than Gouraud lighting, but takes longer to render.

EraseMode {normal} | none | xor | background

Erase mode. This property controls the technique MATLAB uses to draw and erase surface objects. Alternative erase modes are useful for creating animated sequences, where control of the way individual objects are redrawn is necessary to improve performance and obtain the desired effect.

- `normal` — Redraw the affected region of the display, performing the three-dimensional analysis necessary to ensure that all objects are rendered correctly. This mode produces the most accurate picture, but is the slowest. The other modes are faster, but do not perform a complete redraw and are therefore less accurate.
- `none` — Do not erase the surface when it is moved or destroyed. While the object is still visible on the screen after erasing with `EraseMode none`, you cannot print it because MATLAB stores no information about its former location.
- `xor` — Draw and erase the surface by performing an exclusive OR (XOR) with each pixel index of the screen behind it. Erasing the surface does not damage the color of the objects behind it. However, surface color depends on the color of the screen behind it and is correctly colored only when over the axes background `Color`, or the figure background `Color` if the axes `Color` is set to `none`.
- `background` — Erase the surface by drawing it in the axes background `Color`, or the figure background `Color` if the axes `Color` is set to `none`. This damages objects that are behind the erased object, but surface objects are always properly colored.

Printing with Nonnormal Erase Modes. MATLAB always prints figures as if the `EraseMode` of all objects is `normal`. This means graphics objects created with `EraseMode` set to `none`, `xor`, or `background` can look different on screen than on paper. On screen, MATLAB may mathematically combine layers of colors (e.g., performing an XOR of a pixel color with that of the pixel behind it) and ignore three-dimensional sorting to obtain greater rendering speed. However, these techniques are not applied to the printed output.

You can use the MATLAB `getframe` command or other screen capture application to create an image of a figure containing nonnormal mode objects.

FaceAlpha {scalar = 1} | flat | interp | texturemap

Transparency of the surface faces. This property can be any of the following:

- scalar — A single non-NaN scalar value between 0 and 1 that controls the transparency of all the faces of the object. 1 (the default) means fully opaque and 0 means completely transparent (invisible).
- flat — The values of the alpha data (AlphaData) determine the transparency for each face. The alpha data at the first vertex determine the transparency of the entire face.
- interp — Bilinear interpolation of the alpha data (AlphaData) at each vertex determines the transparency of each face.
- texturemap — Use transparency for the texture map.

Note that you must specify AlphaData as a matrix equal in size to ZData to use flat or interp FaceAlpha.

FaceColor ColorSpec | none | {flat} | interp

Color of the surface face. This property can be any of the following:

- ColorSpec — A three-element RGB vector or one of the MATLAB predefined names, specifying a single color for faces. See ColorSpec for more information on specifying color.
- none — Do not draw faces. Note that edges are drawn independently of faces.
- flat — The values of CData determine the color for each face of the surface. The color data at the first vertex determine the color of the entire face.
- interp — Bilinear interpolation of the values at each vertex (the CData) determines the coloring of each face.
- texturemap — Texture map the CData to the surface. MATLAB transforms the color data so that it conforms to the surface. (See the texture mapping example.)

FaceLighting {none} | flat | gouraud | phong

Algorithm used for lighting calculations. This property selects the algorithm used to calculate the effect of light objects on the surface. Choices are

- none — Lights do not affect the faces of this object.
- flat — The effect of light objects is uniform across the faces of the surface. Select this choice to view faceted objects.

- `gouraud` — The effect of light objects is calculated at the vertices and then linearly interpolated across the faces. Select this choice to view curved surfaces.
- `phong` — The effect of light objects is determined by interpolating the vertex normals across each face and calculating the reflectance at each pixel. Select this choice to view curved surfaces. Phong lighting generally produces better results than Gouraud lighting, but takes longer to render.

`HandleVisibility` `{on} | callback | off`

Control access to object's handle by command-line users and GUIs. This property determines when an object's handle is visible in its parent's list of children. This property is useful for preventing command-line users from accidentally drawing into or deleting a figure that contains only user interface devices (such as a dialog box).

Handles are always visible when `HandleVisibility` is `on`.

Setting `HandleVisibility` to `callback` causes handles to be visible from within callback routines or functions invoked by callback routines, but not from within functions invoked from the command line. This provides a means to protect GUIs from command-line users, while allowing callback routines to have complete access to object handles.

Setting `HandleVisibility` to `off` makes handles invisible at all times. This might be necessary when a callback routine invokes a function that could potentially damage the GUI (such as evaluating a user-typed string), and so temporarily hides its own handles during the execution of that function.

When a handle is not visible in its parent's list of children, it cannot be returned by functions that obtain handles by searching the object hierarchy or querying handle properties. This includes `get`, `findobj`, `gca`, `gcf`, `gco`, `newplot`, `cla`, `clf`, and `close`.

When a handle's visibility is restricted using `callback` or `off`, the object's handle does not appear in its parent's `Children` property, figures do not appear in the root's `CurrentFigure` property, objects do not appear in the root's `CallbackObject` property or in the figure's `CurrentObject` property, and axes do not appear in their parent's `CurrentAxes` property.

You can set the root `ShowHiddenHandles` property to `on` to make all handles visible, regardless of their `HandleVisibility` settings (this does not affect the values of the `HandleVisibility` properties).

Handles that are hidden are still valid. If you know an object's handle, you can set and get its properties, and pass it to any function that operates on handles.

`HitTest` `{on} | off`

Selectable by mouse click. `HitTest` determines if the surface can become the current object (as returned by the `gco` command and the figure `CurrentObject` property) as a result of a mouse click on the surface. If `HitTest` is `off`, clicking on the surface selects the object below it (which may be the axes containing it).

`Interruptible` `{on} | off`

Callback routine interruption mode. The `Interruptible` property controls whether a surface callback routine can be interrupted by subsequently invoked callback routines. Only callback routines defined for the `ButtonDownFcn` are affected by the `Interruptible` property. MATLAB checks for events that can interrupt a callback routine only when it encounters a `drawnow`, `figure`, `getframe`, or `pause` command in the routine. See the `BusyAction` property for related information.

`LineStyle` `{-} | -- | : | -. | none`

Edge line type. This property determines the line style used to draw surface edges. The available line styles are shown in this table.

Symbol	Line Style
	Solid line (default)
	Dashed line
:	Dotted line
.	Dash-dot line
none	No line

`LineWidth` scalar

Edge line width. The width of the lines in points used to draw surface edges. The default width is 0.5 points (1 point = 1/72 inch).

`Marker` marker symbol (see table)

Marker symbol. The `Marker` property specifies symbols that are displayed at vertices. You can set values for the `Marker` property independently from the `LineStyle` property.

You can specify these markers.

Marker Specifier	Description
`+`	Plus sign
`o`	Circle
`*`	Asterisk
`.`	Point
`x`	Cross
`s`	Square
`d`	Diamond
`^`	Upward-pointing triangle
`v`	Downward-pointing triangle
`>`	Right-pointing triangle
`<`	Left-pointing triangle
`p`	Five-pointed star (pentagram)
`h`	Six-pointed star (hexagram)
`none`	No marker (default)

MarkerEdgeColor none | {auto} | flat | ColorSpec

Marker edge color. The color of the marker or the edge color for filled markers (circle, square, diamond, pentagram, hexagram, and the four triangles).

- `none` specifies no color, which makes nonfilled markers invisible.
- `auto` uses the same color as the `EdgeColor` property.
- `flat` uses the `CData` value of the vertex to determine the color of the maker edge.
- `ColorSpec` defines a single color to use for the edge (see `ColorSpec` for more information).

MarkerFaceColor {none} | auto | flat | ColorSpec

Marker face color. The fill color for markers that are closed shapes (circle, square, diamond, pentagram, hexagram, and the four triangles).

- `none` makes the interior of the marker transparent, allowing the background to show through.
- `auto` uses the axes `Color` for the marker face color.
- `flat` uses the `CData` value of the vertex to determine the color of the face.
- `ColorSpec` defines a single color to use for all markers on the surface (see `ColorSpec` for more information).

MarkerSize size in points

Marker size. A scalar specifying the marker size, in points. The default value for `MarkerSize` is 6 points (1 point = 1/72 inch). Note that MATLAB draws the point marker at 1/3 the specified marker size.

MeshStyle {both} | row | column

Row and column lines. This property specifies whether to draw all edge lines or just row or column edge lines.

- `both` draws edges for both rows and columns.
- `row` draws row edges only.
- `column` draws column edges only.

NormalMode {auto} | manual

MATLAB generated or user-specified normal vectors. When this property is `auto`, MATLAB calculates vertex normals based on the coordinate data. If you

specify your own vertex normals, MATLAB sets this property to `manual` and does not generate its own data. See also the `VertexNormals` property.

`Parent` handle of axes, hggroup, or hgtransform

Parent of surface object. This property contains the handle of the surface object's parent. The parent of a surface object is the axes, hggroup, or hgtransform object that contains it.

See Objects That Can Contain Other Objects for more information on parenting graphics objects.

`Selected` `on | {off}`

Is object selected? When this property is `on`, MATLAB displays a dashed bounding box around the surface if the `SelectionHighlight` property is also `on`. You can, for example, define the `ButtonDownFcn` to set this property, allowing users to select the object with the mouse.

`SelectionHighlight` `{on} | off`

Objects are highlighted when selected. When the `Selected` property is `on`, MATLAB indicates the selected state by drawing a dashed bounding box around the surface. When `SelectionHighlight` is `off`, MATLAB does not draw the handles.

`SpecularColorReflectance` scalar in the range 0 to 1

Color of specularly reflected light. When this property is 0, the color of the specularly reflected light depends on both the color of the object from which it reflects and the color of the light source. When set to 1, the color of the specularly reflected light depends only on the color or the light source (i.e., the light object `Color` property). The proportions vary linearly for values in between.

`SpecularExponent` scalar >= 1

Harshness of specular reflection. This property controls the size of the specular spot. Most materials have exponents in the range of 5 to 20.

`SpecularStrength` scalar >= 0 and <= 1

Intensity of specular light. This property sets the intensity of the specular component of the light falling on the surface. Specular light comes from light objects in the axes.

You can also set the intensity of the ambient and diffuse components of the light on the surface object. See the `AmbientStrength` and `DiffuseStrength` properties. Also see the `material` function.

`Tag` string

User-specified object label. The `Tag` property provides a means to identify graphics objects with a user-specified label. This is particularly useful when you are constructing interactive graphics programs that would otherwise need to define object handles as global variables or pass them as arguments between callback routines. You can define `Tag` as any string.

`Type` string (read only)

Class of the graphics object. The class of the graphics object. For surface objects, `Type` is always the string `'surface'`.

`UIContextMenu` handle of a uicontextmenu object

Associate a context menu with the surface. Assign this property the handle of a uicontextmenu object created in the same figure as the surface. Use the `uicontextmenu` function to create the context menu. MATLAB displays the context menu whenever you right-click over the surface.

`UserData` matrix

User-specified data. Any matrix you want to associate with the surface object. MATLAB does not use this data, but you can access it using the `set` and `get` commands.

`VertexNormals` vector or matrix

Surface normal vectors. This property contains the vertex normals for the surface. MATLAB generates this data to perform lighting calculations. You can supply your own vertex normal data, even if it does not match the coordinate data. This can be useful to produce interesting lighting effects.

`Visible` `{on} | off`

Surface object visibility. By default, all surfaces are visible. When set to `off`, the surface is not visible, but still exists, and you can query and set its properties.

XData vector or matrix

X-coordinates. The *x*-position of the surface points. If you specify a row vector, `surface` replicates the row internally until it has the same number of columns as `ZData`.

YData vector or matrix

Y-coordinates. The *y*-position of the surface points. If you specify a row vector, `surface` replicates the row internally until it has the same number of rows as `ZData`.

ZData matrix

Z-coordinates. The *z*-position of the surface points. See the Description section for more information.

Modifying Properties

You can set and query graphics object properties in two ways:

- The Property Editor is an interactive tool that enables you to see and change object property values.
- The `set` and `get` commands enable you to set and query the values of properties.

Note that you cannot define default properties for surfaceplot objects.

See Plot Objects for information on surfaceplot objects.

Surfaceplot Property Descriptions

This section lists property names along with the types of values each accepts. Curly braces { } enclose default values.

`AlphaData` m-by-n matrix of `double` or `uint8`

The transparency data. A matrix of non-NaN values specifying the transparency of each face or vertex of the object. The `AlphaData` can be of class double or uint8.

MATLAB determines the transparency in one of three ways:

- Using the elements of `AlphaData` as transparency values (`AlphaDataMapping` set to `none`)
- Using the elements of `AlphaData` as indices into the current alphamap (`AlphaDataMapping` set to `direct`)
- Scaling the elements of `AlphaData` to range between the minimum and maximum values of the axes `ALim` property (`AlphaDataMapping` set to `scaled`, the default)

`AlphaDataMapping` `none | direct | {scaled}`

Transparency mapping method. This property determines how MATLAB interprets indexed alpha data. This property can be any of the following:

- `none` — The transparency values of `AlphaData` are between 0 and 1 or are clamped to this range (the default).
- `scaled` — Transform the `AlphaData` to span the portion of the alphamap indicated by the axes `ALim` property, linearly mapping data values to alpha values.
- `direct` — use the `AlphaData` as indices directly into the alphamap. When not scaled, the data are usually integer values ranging from `1` to

`length(alphamap)`. MATLAB maps values less than `1` to the first alpha value in the alphamap, and values greater than `length(alphamap)` to the last alpha value in the alphamap. Values with a decimal portion are fixed to the nearest lower integer. If `AlphaData` is an array of `uint8` integers, then the indexing begins at `0` (i.e., MATLAB maps a value of `0` to the first alpha value in the alphamap).

`AmbientStrength` scalar >= 0 and <= 1

Strength of ambient light. This property sets the strength of the ambient light, which is a nondirectional light source that illuminates the entire scene. You must have at least one visible light object in the axes for the ambient light to be visible. The axes `AmbientLightColor` property sets the color of the ambient light, which is therefore the same on all objects in the axes.

You can also set the strength of the diffuse and specular contribution of light objects. See the surfaceplot `DiffuseStrength` and `SpecularStrength` properties.

`BackFaceLighting` `unlit | lit | reverselit`

Face lighting control. This property determines how faces are lit when their vertex normals point away from the camera.

- `unlit` — Face is not lit.
- `lit` — Face is lit in normal way.
- `reverselit` — Face is lit as if the vertex pointed towards the camera.

This property is useful for discriminating between the internal and external surfaces of an object. See Back Face Lighting for an example.

`BeingDeleted` `on | {off}` Read Only

This object is being deleted. The `BeingDeleted` property provides a mechanism that you can use to determine if objects are in the process of being deleted. MATLAB sets the `BeingDeleted` property to `on` when the object's delete function callback is called (see the `DeleteFcn` property). It remains set to `on` while the delete function executes, after which the object no longer exists.

For example, an object's delete function might call other functions that act on a number of different objects. These functions may not need to perform actions on objects that are going to be deleted, and therefore, can check the object's `BeingDeleted` property before acting.

BusyAction cancel | {queue}

Callback routine interruption. The BusyAction property enables you to control how MATLAB handles events that potentially interrupt executing callback routines. If there is a callback routine executing, callback routines invoked subsequently always attempt to interrupt it. If the Interruptible property of the object whose callback is executing is set to on (the default), then interruption occurs at the next point where the event queue is processed. If the Interruptible property is off, the BusyAction property (of the object owning the executing callback) determines how MATLAB handles the event. The choices are

- cancel — Discard the event that attempted to execute a second callback routine.
- queue — Queue the event that attempted to execute a second callback routine until the current callback finishes.

ButtonDownFcn string or function handle

Button press callback routine. A callback routine that executes whenever you press a mouse button while the pointer is over the surfaceplot object. Define this routine as a string that is a valid MATLAB expression or the name of an M-file. The expression executes in the MATLAB workspace.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

CData matrix

Vertex colors. A matrix containing values that specify the color at every point in ZData. If you set the FaceColor property to texturemap, CData does not need to be the same size as ZData. In this case, MATLAB maps CData to conform to the surfaceplot defined by ZData.

You can specify color as indexed values or true color. Indexed color data specifies a single value for each vertex. These values are either scaled to map linearly into the current colormap (see caxis) or interpreted directly as indices into the colormap, depending on the setting of the CDataMapping property.

True color defines an RGB value for each vertex. If the coordinate data (XData, for example) are contained in m-by-n matrices, then CData must be an m-by-n-3 array. The first page contains the red components, the second the green components, and the third the blue components of the colors.

CDataMapping {scaled} | direct

Direct or scaled color mapping. This property determines how MATLAB interprets indexed color data used to color the surfaceplot. (If you use true color specification for CData, this property has no effect.)

- scaled — Transform the color data to span the portion of the colormap indicated by the axes CLim property, linearly mapping data values to colors. See the caxis reference page for more information on this mapping.
- direct — Use the color data as indices directly into the colormap. The color data should then be integer values ranging from 1 to length(colormap). MATLAB maps values less than 1 to the first color in the colormap, and values greater than length(colormap) to the last color in the colormap. Values with a decimal portion are fixed to the nearest lower integer.

CDataMode {auto} | manual

Use automatic or user-specified color data values. If you specify CData, MATLAB sets this property to manual and uses the CData values to color the surfaceplot.

If you set CDataMode to auto after having specified CData, MATLAB resets the color data of the surfaceplot to that defined by ZData, overwriting any previous values for CData.

CDataSource string (MATLAB variable)

Link CData to MATLAB variable. Set this property to a MATLAB variable that is evaluated in the base workspace to generate the CData.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change CData.

You can use the refreshdata function to force an update of the object's data. refreshdata also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call refreshdata.

See the refreshdata reference page for more information.

Note If you change one data source property to return data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

Children matrix of handles

Always the empty matrix; surfaceplot objects have no children.

Clipping {on} | off

Clipping to axes rectangle. When Clipping is on, MATLAB does not display any portion of the surfaceplot that is outside the axes rectangle.

CreateFcn string or function handle

Callback routine executed during object creation. This property defines a callback that executes when MATLAB creates a surfaceplot object. You must specify the callback during the creation of the object. For example,

```
surf(peaks,'CreateFcn',@CallbackFcn)
```

where @*CallbackFcn* is a function handle that references the callback function.

MATLAB executes this routine after setting all other surfaceplot properties. Setting this property on an existing surfaceplot object has no effect.

The handle of the object whose CreateFcn is being executed is accessible only through the root CallbackObject property, which you can query using gcbo.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

DeleteFcn string or function handle

Delete surfaceplot callback routine. A callback routine that executes when you delete the surfaceplot object (e.g., when you issue a delete command or clear the axes or figure). MATLAB executes the routine before destroying the object's properties so these values are available to the callback routine.

The handle of the object whose DeleteFcn is being executed is accessible only through the root CallbackObject property, which you can query using gcbo.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

`DiffuseStrength` scalar >= 0 and <= 1

Intensity of diffuse light. This property sets the intensity of the diffuse component of the light falling on the surface. Diffuse light comes from light objects in the axes.

You can also set the intensity of the ambient and specular components of the light on the surfaceplot object. See the `AmbientStrength` and `SpecularStrength` properties.

`EdgeAlpha` `{scalar = 1} | flat | interp`

Transparency of the surfaceplot edges. This property can be any of the following:

- `scalar` — A single non-Nan scalar value between `0` and `1` that controls the transparency of all the edges of the object. `1` (the default) means fully opaque and `0` means completely transparent.
- `flat` — The alpha data (`AlphaData`) value for the first vertex of the face determines the transparency of the edges.
- `interp` — Linear interpolation of the alpha data (`AlphaData`) values at each vertex determines the transparency of the edge.

Note that you must specify `AlphaData` as a matrix equal in size to `ZData` to use `flat` or `interp` `EdgeAlpha`.

`EdgeColor` `{ColorSpec} | none | flat | interp`

Color of the surfaceplot edge. This property determines how MATLAB colors the edges of the individual faces that make up the surface:

- `ColorSpec` — A three-element RGB vector or one of the MATLAB predefined names, specifying a single color for edges. The default `EdgeColor` is black. See `ColorSpec` for more information on specifying color.
- `none` — Edges are not drawn.

- `flat` — The `CData` value of the first vertex for a face determines the color of each edge.



- `interp` — Linear interpolation of the `CData` values at the face vertices determines the edge color.

`EdgeLighting` `{none} | flat | gouraud | phong`

Algorithm used for lighting calculations. This property selects the algorithm used to calculate the effect of light objects on surfaceplot edges. Choices are

- `none` — Lights do not affect the edges of this object.
- `flat` — The effect of light objects is uniform across each edge of the surface.
- `gouraud` — The effect of light objects is calculated at the vertices and then linearly interpolated across the edge lines.
- `phong` — The effect of light objects is determined by interpolating the vertex normals across each edge line and calculating the reflectance at each pixel. Phong lighting generally produces better results than Gouraud lighting, but takes longer to render.

`EraseMode` `{normal} | none | xor | background`

Erase mode. This property controls the technique MATLAB uses to draw and erase surfaceplot objects. Alternative erase modes are useful for creating animated sequences, where control of the way individual objects are redrawn is necessary to improve performance and obtain the desired effect.

- `normal` — Redraw the affected region of the display, performing the three-dimensional analysis necessary to ensure that all objects are rendered correctly. This mode produces the most accurate picture, but is the slowest. The other modes are faster, but do not perform a complete redraw and are therefore less accurate.

- `none` — Do not erase the surfaceplot when it is moved or destroyed. While the object is still visible on the screen after erasing with `EraseMode none`, you cannot print it because MATLAB stores no information about its former location.
- `xor` — Draw and erase the surfaceplot by performing an exclusive OR (XOR) with each pixel index of the screen behind it. Erasing the surfaceplot does not damage the color of the objects behind it. However, surfaceplot color depends on the color of the screen behind it and is correctly colored only when over the axes background `Color`, or the figure background `Color` if the axes `Color` is set to `none`.
- `background` — Erase the surfaceplot by drawing it in the axes background `Color`, or the figure background `Color` if the axes `Color` is set to `none`. This damages objects that are behind the erased object, but surfaceplot objects are always properly colored.

Printing with Nonnormal Erase Modes. MATLAB always prints figures as if the `EraseMode` of all objects is `normal`. This means graphics objects created with `EraseMode` set to `none`, `xor`, or `background` can look different on screen than on paper. On screen, MATLAB may mathematically combine layers of colors (e.g., performing an XOR of a pixel color with that of the pixel behind it) and ignore three-dimensional sorting to obtain greater rendering speed. However, these techniques are not applied to the printed output.

You can use the MATLAB `getframe` command or other screen capture application to create an image of a figure containing nonnormal mode objects.

`FaceAlpha` `{scalar = 1} | flat | interp | texturemap`

Transparency of the surfaceplot faces. This property can be any of the following:

- `scalar` — A single non-NaN scalar value between `0` and `1` that controls the transparency of all the faces of the object. `1` (the default) means fully opaque and `0` means completely transparent (invisible).
- `flat` — The values of the alpha data (`AlphaData`) determine the transparency for each face. The alpha data at the first vertex determine the transparency of the entire face.
- `interp` — Bilinear interpolation of the alpha data (`AlphaData`) at each vertex determines the transparency of each face.
- `texturemap` — Use transparency for the texture map.

Note that you must specify `AlphaData` as a matrix equal in size to `ZData` to use `flat` or `interp` `FaceAlpha`.

`FaceColor` `ColorSpec | none | {flat} | interp`

Color of the surfaceplot face. This property can be any of the following:

- `ColorSpec` — A three-element RGB vector or one of the MATLAB predefined names, specifying a single color for faces. See `ColorSpec` for more information on specifying color.
- `none` — Do not draw faces. Note that edges are drawn independently of faces.
- `flat` — The values of `CData` determine the color for each face of the surface. The color data at the first vertex determine the color of the entire face.
- `interp` — Bilinear interpolation of the values at each vertex (the `CData`) determines the coloring of each face.
- `texturemap` — Texture map the `CData` to the surface. MATLAB transforms the color data so that it conforms to the surface. (See the texture mapping example.)

`FaceLighting` `{none} | flat | gouraud | phong`

Algorithm used for lighting calculations. This property selects the algorithm used to calculate the effect of light objects on the surface. Choices are

- `none` — Lights do not affect the faces of this object.
- `flat` — The effect of light objects is uniform across the faces of the surface. Select this choice to view faceted objects.
- `gouraud` — The effect of light objects is calculated at the vertices and then linearly interpolated across the faces. Select this choice to view curved surfaces.
- `phong` — The effect of light objects is determined by interpolating the vertex normals across each face and calculating the reflectance at each pixel. Select this choice to view curved surfaces. Phong lighting generally produces better results than Gouraud lighting, but takes longer to render.

`HandleVisibility` `{on} | callback | off`

Control access to object's handle by command-line users and GUIs. This property determines when an object's handle is visible in its parent's list of children. This property is useful for preventing command-line users from

accidentally drawing into or deleting a figure that contains only user interface devices (such as a dialog box).

Handles are always visible when `HandleVisibility` is `on`.

Setting `HandleVisibility` to `callback` causes handles to be visible from within callback routines or functions invoked by callback routines, but not from within functions invoked from the command line. This provides a means to protect GUIs from command-line users, while allowing callback routines to have complete access to object handles.

Setting `HandleVisibility` to `off` makes handles invisible at all times. This might be necessary when a callback routine invokes a function that could potentially damage the GUI (such as evaluating a user-typed string), and so temporarily hides its own handles during the execution of that function.

When a handle is not visible in its parent's list of children, it cannot be returned by functions that obtain handles by searching the object hierarchy or querying handle properties. This includes `get`, `findobj`, `gca`, `gcf`, `gco`, `newplot`, `cla`, `clf`, and `close`.

When a handle's visibility is restricted using `callback` or `off`, the object's handle does not appear in its parent's `Children` property, figures do not appear in the root's `CurrentFigure` property, objects do not appear in the root's `CallbackObject` property or in the figure's `CurrentObject` property, and axes do not appear in their parent's `CurrentAxes` property.

You can set the root `ShowHiddenHandles` property to `on` to make all handles visible, regardless of their `HandleVisibility` settings (this does not affect the values of the `HandleVisibility` properties).

Handles that are hidden are still valid. If you know an object's handle, you can set and get its properties, and pass it to any function that operates on handles.

`HitTest` `{on} | off`

Selectable by mouse click. `HitTest` determines if the surfaceplot can become the current object (as returned by the `gco` command and the figure `CurrentObject` property) as a result of a mouse click on the surface. If `HitTest` is `off`, clicking on the surfaceplot selects the object below it (which may be the axes containing it).

`Interruptible` `{on} | off`

Callback routine interruption mode. The `Interruptible` property controls whether a surfaceplot callback routine can be interrupted by subsequently invoked callback routines. Only callback routines defined for the `ButtonDownFcn` are affected by the `Interruptible` property. MATLAB checks for events that can interrupt a callback routine only when it encounters a `drawnow`, `figure`, `getframe`, or `pause` command in the routine. See the `BusyAction` property for related information.

`LineStyle` `{-} | -- | : | -. | none`

Edge line type. This property determines the line style used to draw surfaceplot edges. The available line styles are shown in this table.

Symbol	Line Style
	Solid line (default)
	Dashed line
:	Dotted line
.	Dash-dot line
none	No line

`LineWidth` scalar

Edge line width. The width of the lines in points used to draw surfaceplot edges. The default width is 0.5 points (1 point = 1/72 inch).

`Marker` marker symbol (see table)

Marker symbol. The `Marker` property specifies symbols that are displayed at vertices. You can set values for the `Marker` property independently from the `LineStyle` property.

You can specify these markers.

Marker Specifier	Description
`+`	Plus sign
`o`	Circle
`*`	Asterisk
`.`	Point
`x`	Cross
`s`	Square
`d`	Diamond
`^`	Upward-pointing triangle
`v`	Downward-pointing triangle
`>`	Right-pointing triangle
`<`	Left-pointing triangle
`p`	Five-pointed star (pentagram)
`h`	Six-pointed star (hexagram)
`none`	No marker (default)

`MarkerEdgeColor` `none | {auto} | flat | ColorSpec`

Marker edge color. The color of the marker or the edge color for filled markers (circle, square, diamond, pentagram, hexagram, and the four triangles).

- `none` specifies no color, which makes nonfilled markers invisible.
- `auto` uses the same color as the `EdgeColor` property.
- `flat` uses the `CData` value of the vertex to determine the color of the maker edge.
- `ColorSpec` defines a single color to use for the edge (see `ColorSpec` for more information).

MarkerFaceColor {none} | auto | flat | ColorSpec

Marker face color. The fill color for markers that are closed shapes (circle, square, diamond, pentagram, hexagram, and the four triangles).

- `none` makes the interior of the marker transparent, allowing the background to show through.
- `auto` uses the axes `Color` for the marker face color.
- `flat` uses the `CData` value of the vertex to determine the color of the face.
- `ColorSpec` defines a single color to use for all markers on the surfaceplot (see `ColorSpec` for more information).

MarkerSize size in points

Marker size. A scalar specifying the marker size, in points. The default value for `MarkerSize` is 6 points (1 point = 1/72 inch). Note that MATLAB draws the point marker at 1/3 the specified marker size.

MeshStyle {both} | row | column

Row and column lines. This property specifies whether to draw all edge lines or just row or column edge lines.

- `both` draws edges for both rows and columns.
- `row` draws row edges only.
- `column` draws column edges only.

NormalMode {auto} | manual

MATLAB generated or user-specified normal vectors. When this property is `auto`, MATLAB calculates vertex normals based on the coordinate data. If you specify your own vertex normals, MATLAB sets this property to `manual` and does not generate its own data. See also the `VertexNormals` property.

Parent handle of axes, hggroup, or hgtransform

Parent of surfaceplot object. This property contains the handle of the surfaceplot object's parent. The parent of a surfaceplot object is the axes, hggroup, or hgtransform object that contains it.

See Objects That Can Contain Other Objects for more information on parenting graphics objects.

Selected on | {off}

Is object selected? When this property is on, MATLAB displays a dashed bounding box around the surfaceplot if the SelectionHighlight property is also on. You can, for example, define the ButtonDownFcn to set this property, allowing users to select the object with the mouse.

SelectionHighlight {on} | off

Objects are highlighted when selected. When the Selected property is on, MATLAB indicates the selected state by drawing a dashed bounding box around the surface. When SelectionHighlight is off, MATLAB does not draw the handles.

SpecularColorReflectance scalar in the range 0 to 1

Color of specularly reflected light. When this property is 0, the color of the specularly reflected light depends on both the color of the object from which it reflects and the color of the light source. When set to 1, the color of the specularly reflected light depends only on the color or the light source (i.e., the light object Color property). The proportions vary linearly for values in between.

SpecularExponent scalar >= 1

Harshness of specular reflection. This property controls the size of the specular spot. Most materials have exponents in the range of 5 to 20.

SpecularStrength scalar >= 0 and <= 1

Intensity of specular light. This property sets the intensity of the specular component of the light falling on the surface. Specular light comes from light objects in the axes.

You can also set the intensity of the ambient and diffuse components of the light on the surfaceplot object. See the AmbientStrength and DiffuseStrength properties. Also see the material function.

Tag string

User-specified object label. The Tag property provides a means to identify graphics objects with a user-specified label. This is particularly useful when you are constructing interactive graphics programs that would otherwise need to define object handles as global variables or pass them as arguments between callback routines. You can define Tag as any string.

Type string (read only)

Class of the graphics object. The class of the graphics object. For surfaceplot objects, `Type` is always the string `'surface'`.

UIContextMenu handle of a uicontextmenu object

Associate a context menu with the surface. Assign this property the handle of a uicontextmenu object created in the same figure as the surface. Use the `uicontextmenu` function to create the context menu. MATLAB displays the context menu whenever you right-click over the surface.

UserData matrix

User-specified data. Any matrix you want to associate with the surfaceplot object. MATLAB does not use this data, but you can access it using the `set` and `get` commands.

VertexNormals vector or matrix

Surfaceplot normal vectors. This property contains the vertex normals for the surfaceplot. MATLAB generates this data to perform lighting calculations. You can supply your own vertex normal data, even if it does not match the coordinate data. This can be useful to produce interesting lighting effects.

Visible `{on} | off`

Surfaceplot object visibility. By default, all surfaceplots are visible. When set to `off`, the surfaceplot is not visible, but still exists, and you can query and set its properties.

XData vector or matrix

X-coordinates. The *x*-position of the surfaceplot data points. If you specify a row vector, MATLAB replicates the row internally until it has the same number of columns as `ZData`.

XDataMode `{auto} | manual`

Use automatic or user-specified x-axis values. If you specify `XData`, MATLAB sets this property to `manual`.

If you set `XDataMode` to `auto` after having specified `XData`, MATLAB resets the *x*-axis ticks and *x*-tick labels to the column indices of the `ZData`, overwriting any previous values for `XData`.

XDataSource string (MATLAB variable)

Link `XData` to MATLAB variable. Set this property to a MATLAB variable that is evaluated in the base workspace to generate the `XData`.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change `XData`.

You can use the `refreshdata` function to force an update of the object's data. `refreshdata` also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call `refreshdata`.

See the `refreshdata` reference page for more information.

Note If you change one data source property to return data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

YData vector or matrix

Y-coordinates. The *y*-position of the surfaceplot data points. If you specify a row vector, MATLAB replicates the row internally until it has the same number of rows as `ZData`.

YDataMode {`auto`} | `manual`

Use automatic or user-specified x-axis values. If you specify `XData`, MATLAB sets this property to `manual`.

If you set `YDataMode` to `auto` after having specified `YData`, MATLAB resets the *y*-axis ticks and *y*-tick labels to the row indices of the `ZData`, overwriting any previous values for `YData`.

YDataSource string (MATLAB variable)

Link `YData` to MATLAB variable. Set this property to a MATLAB variable that is evaluated in the base workspace to generate the `YData`.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change `YData`.

You can use the `refreshdata` function to force an update of the object's data. `refreshdata` also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call `refreshdata`.

See the `refreshdata` reference page for more information.

Note If you change one data source property to a variable that contains data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

`ZData` matrix

Z-coordinates. The *z*-position of the surfaceplot data points. See the Description section for more information.

`ZDataSource` string (MATLAB variable)

Link `YData` to MATLAB variable. Set this property to a MATLAB variable that is evaluated in the base workspace to generate the `ZData`.

MATLAB reevaluates this property only when you set it. Therefore, a change to workspace variables appearing in an expression does not change `ZData`.

You can use the `refreshdata` function to force an update of the object's data. `refreshdata` also enables you to specify that the data source variable be evaluated in the workspace of a function from which you call `refreshdata`.

See the `refreshdata` reference page for more information.

Note If you change one data source property to a variable that contains data of a different dimension, you might cause the function to generate a warning and not render the graph until you have changed all data source properties to appropriate values.

---

surfl

Purpose

Surface plot with colormap-based lighting

Syntax

```
surfl(Z)
surfl(X,Y,Z)
surfl(...,'light')
surfl(...,s)
surfl(X,Y,Z,s,k)
h = surfl(...)
```

Description

The `surfl` function displays a shaded surface based on a combination of ambient, diffuse, and specular lighting models.

`surfl(Z)` and `surfl(X,Y,Z)` create three-dimensional shaded surfaces using the default direction for the light source and the default lighting coefficients for the shading model. `X`, `Y`, and `Z` are vectors or matrices that define the x, y, and z components of a surface.

`surfl(...,'light')` produces a colored, lighted surface using a MATLAB light object. This produces results different from the default lighting method, `surfl(...,'cdata')`, which changes the color data for the surface to be the reflectance of the surface.

`surfl(...,s)` specifies the direction of the light source. `s` is a two- or three-element vector that specifies the direction from a surface to a light source. `s = [sx sy sz]` or `s = [azimuth elevation]`. The default `s` is 45° counterclockwise from the current view direction.

`surfl(X,Y,Z,s,k)` specifies the reflectance constant. `k` is a four-element vector defining the relative contributions of ambient light, diffuse reflection, specular reflection, and the specular shine coefficient. `k = [ka kd ks shine]` and defaults to `[.55,.6,.4,10]`.

`h = surfl(...)` returns a handle to a surface graphics object.

Remarks

For smoother color transitions, use colormaps that have linear intensity variations (e.g., `gray`, `copper`, `bone`, `pink`).

The ordering of points in the `X`, `Y`, and `Z` matrices defines the inside and outside of parametric surfaces. If you want the opposite side of the surface to reflect the

light source, use `surfl(X',Y',Z')`. Because of the way surface normal vectors are computed, `surfl` requires matrices that are at least 3-by-3.

Examples

View `peaks` using colormap-based lighting.

```
[x,y] = meshgrid( 3:1/8:3);
z = peaks(x,y);
surfl(x,y,z);
shading interp
colormap(gray);
axis([ 3  3   3  3   8  8])
```



To plot a lighted surface from a view direction other than the default,

```
view([10 10])
grid on
hold on
surfl(peaks)
shading interp
colormap copper
hold off
```



See Also

`colormap`, `shading`, `light`

“Creating Surfaces and Meshes” for functions related to surfaces

“Lighting” for functions related to lighting

Purpose

Compute and display 3-D surface normals

Syntax

```
surfnorm(Z)
surfnorm(X,Y,Z)
[Nx,Ny,Nz] = surfnorm(...)
```

Description

The `surfnorm` function computes surface normals for the surface defined by `X`, `Y`, and `Z`. The surface normals are unnormalized and valid at each vertex. Normals are not shown for surface elements that face away from the viewer.

`surfnorm(Z)` and `surfnorm(X,Y,Z)` plot a surface and its surface normals. `Z` is a matrix that defines the z component of the surface. `X` and `Y` are vectors or matrices that define the x and y components of the surface.

`[Nx,Ny,Nz] = surfnorm(...)` returns the components of the three-dimensional surface normals for the surface.

Remarks

The direction of the normals is reversed by calling `surfnorm` with transposed arguments:

```
surfnorm(X',Y',Z')
```

`surfl` uses `surfnorm` to compute surface normals when calculating the reflectance of a surface.

Algorithm

The surface normals are based on a bicubic fit of the data in `X`, `Y`, and `Z`. For each vertex, diagonal vectors are computed and crossed to form the normal.

Examples

Plot the normal vectors for a truncated cone.

```
[x,y,z] = cylinder(1:10);
surfnorm(x,y,z)
axis([-12 12 -12 12 -0.1 1])
```



See Also

`surf`, `quiver3`

“Colormaps” for related functions

Purpose

Singular value decomposition

Syntax

```
s = svd(X)
[U,S,V] = svd(X)
[U,S,V] = svd(X,0)
```

Description

The `svd` command computes the matrix singular value decomposition.

`s = svd(X)` returns a vector of singular values.

`[U,S,V] = svd(X)` produces a diagonal matrix `S` of the same dimension as `X`, with nonnegative diagonal elements in decreasing order, and unitary matrices `U` and `V` so that `X = U*S*V'`.

`[U,S,V] = svd(X,0)` produces the "economy size" decomposition. If `X` is `m`-by-`n` with `m > n`, then `svd` computes only the first `n` columns of `U` and `S` is `n`-by-`n`.

Examples

For the matrix

```
X =
     1     2
     3     4
     5     6
     7     8
```

the statement

```
[U,S,V] = svd(X)
```

produces

```
U =
    -0.1525   -0.8226   -0.3945   -0.3800
    -0.3499   -0.4214    0.2428    0.8007
    -0.5474   -0.0201    0.6979   -0.4614
    -0.7448    0.3812   -0.5462    0.0407

S =
    14.2691         0
          0    0.6268
```

```
            0         0
            0         0

V =
    -0.6414    0.7672
    -0.7672   -0.6414
```

The economy size decomposition generated by

```
[U,S,V] = svd(X,0)
```

produces

```
U =
    -0.1525   -0.8226
    -0.3499   -0.4214
    -0.5474   -0.0201
    -0.7448    0.3812
S =
    14.2691         0
         0    0.6268
V =
    -0.6414    0.7672
    -0.7672   -0.6414
```

Algorithm

`svd` uses LAPACK routines to compute the singular value decomposition.

Matrix	Routine
Real	`DGESVD`
Complex	`ZGESVD`

Diagnostics

If the limit of 75 QR step iterations is exhausted while seeking a singular value, this message appears:

```
Solution will not converge.
```

References

[1] Anderson, E., Z. Bai, C. Bischof, S. Blackford, J. Demmel, J. Dongarra, J. Du Croz, A. Greenbaum, S. Hammarling, A. McKenney, and D. Sorensen, *LAPACK User's Guide*

(http://www.netlib.org/lapack/lug/lapack_lug.html), Third Edition, SIAM, Philadelphia, 1999.

svds

Purpose

A few singular values

Syntax

```
s = svds(A)
s = svds(A,k)
s = svds(A,k,0)
[U,S,V] = svds(A,...)
```

Description

`svds(A)` computes the five largest singular values and associated singular vectors of the matrix `A`.

`svds(A,k)` computes the `k` largest singular values and associated singular vectors of the matrix `A`.

`svds(A,k,0)` computes the `k` smallest singular values and associated singular vectors.

With one output argument, `s` is a vector of singular values. With three output arguments and if `A` is `m`-by-`n`:

- `U` is `m`-by-`k` with orthonormal columns
- `S` is `k`-by-`k` diagonal
- `V` is `n`-by-`k` with orthonormal columns
- `U*S*V'` is the closest rank `k` approximation to `A`

Algorithm

`svds(A,k)` uses `eigs` to find the `k` largest magnitude eigenvalues and corresponding eigenvectors of `B = [0 A; A' 0]`.

`svds(A,k,0)` uses `eigs` to find the `2k` smallest magnitude eigenvalues and corresponding eigenvectors of `B = [0 A; A' 0]`, and then selects the `k` positive eigenvalues and their eigenvectors.

Example

`west0479` is a real 479-by-479 sparse matrix. `svd` calculates all 479 singular values. `svds` picks out the largest and smallest singular values.

```
load west0479
s = svd(full(west0479))
sl = svds(west0479,4)
ss = svds(west0479,6,0)
```

These plots show some of the singular values of `west0479` as computed by `svd` and `svds`.



The largest singular value of `west0479` can be computed a few different ways:

```
svds(west0479,1) =
 3.189517598808622e+05

max(svd(full(west0479))) =
 3.18951759880862e+05

norm(full(west0479)) =
 3.189517598808623e+05
```

and estimated:

```
normest(west0479) =
 3.189385666549991e+05
```

See Also

`svd`, `eigs`

Purpose

Switch among several cases based on expression

Syntax

```
switch switch_expr
  case case_expr
    statement,...,statement
  case {case_expr1,case_expr2,case_expr3,...}
    statement,...,statement
...
  otherwise
    statement,...,statement
end
```

Discussion

The `switch` statement syntax is a means of conditionally executing code. In particular, `switch` executes one set of statements selected from an arbitrary number of alternatives. Each alternative is called a *`case`*, and consists of

- The `case` statement
- One or more case expressions
- One or more statements

In its basic syntax, `switch` executes the statements associated with the first case where *`switch_expr == case_expr`*. When the case expression is a cell array (as in the second case above), the *`case_expr`* matches if any of the elements of the cell array matches the switch expression. If no case expression matches the switch expression, then control passes to the `otherwise` case (if it exists). After the case is executed, program execution resumes with the statement after the `end`.

The *`switch_expr`* can be a scalar or a string. A scalar *`switch_expr`* matches a *`case_expr`* if *`switch_expr==case_expr`*. A string *`switch_expr`* matches a *`case_expr`* if `strcmp(`*`switch_expr`*`,`*`case_expr`*`)` returns `1` (true).

Note for C Programmers Unlike the C language `switch` construct, the MATLAB `switch` does not "fall through." That is, `switch` executes only the first matching case; subsequent matching `case`s do not execute. Therefore, `break` statements are not used.

Examples

To execute a certain block of code based on what the string, `method`, is set to,

```
method = 'Bilinear';

switch lower(method)
   case {'linear','bilinear'}
      disp('Method is linear')
   case 'cubic'
      disp('Method is cubic')
   case 'nearest'
      disp('Method is nearest')
   otherwise
      disp('Unknown method.')
end

Method is linear
```

See Also

`case`, `end`, `if`, `otherwise`, `while`

symamd

Purpose

Symmetric approximate minimum degree permutation

Syntax

```
p = symamd(S)
p = symamd(S,knobs)
[p,stats] = symamd(S)
[p,stats] = symamd(S,knobs)
```

Description

`p = symamd(S)` for a symmetric positive definite matrix `S`, returns the permutation vector `p` such that `S(p,p)` tends to have a sparser Cholesky factor than `S`. To find the ordering for `S`, `symamd` constructs a matrix `M` such that `spones(M'*M) = spones (S)`, and then computes `p = colamd(M)`. The `symamd` function may also work well for symmetric indefinite matrices.

`S` must be square; only the strictly lower triangular part is referenced.

`knobs` is a scalar. If `S` is `n`-by-`n`, rows and columns with more than `knobs*n` entries are removed prior to ordering, and ordered last in the output permutation `p`. If the `knobs` parameter is not present, then `knobs = spparms('wh_frac')`.

`stats` is an optional vector that provides data about the ordering and the validity of the matrix `S`.

`stats(1)`	Number of dense or empty rows ignored by `symamd`
`stats(2)`	Number of dense or empty columns ignored by `symamd`
`stats(3)`	Number of garbage collections performed on the internal data structure used by `symamd` (roughly of size `8.4*nnz(tril(S,-1)) + 9n` integers)
`stats(4)`	`0` if the matrix is valid, or `1` if invalid
`stats(5)`	Rightmost column index that is unsorted or contains duplicate entries, or `0` if no such column exists
`stats(6)`	Last seen duplicate or out-of-order row index in the column index given by `stats(5)`, or `0` if no such row index exists
`stats(7)`	Number of duplicate and out-of-order row indices

Although, MATLAB built-in functions generate valid sparse matrices, a user may construct an invalid sparse matrix using the MATLAB C or Fortran APIs and pass it to `symamd`. For this reason, `symamd` verifies that `S` is valid:

- If a row index appears two or more times in the same column, `symamd` ignores the duplicate entries, continues processing, and provides information about the duplicate entries in `stats(4:7)`.
- If row indices in a column are out of order, `symamd` sorts each column of its internal copy of the matrix `S` (but does not repair the input matrix `S`), continues processing, and provides information about the out-of-order entries in `stats(4:7)`.
- If `S` is invalid in any other way, `symamd` cannot continue. It prints an error message, and returns no output arguments (`p` or `stats`) .

The ordering is followed by a symmetric elimination tree post-ordering.

Note `symamd` tends to be faster than `symmmd` and tends to return a better ordering.

See Also

`colamd`, `colmmd`, `colperm`, `spparms`, `symmmd`, `symrcm`

References

The authors of the code for `symamd` are Stefan I. Larimore and Timothy A. Davis (`davis@cise.ufl.edu`), University of Florida. The algorithm was developed in collaboration with John Gilbert, Xerox PARC, and Esmond Ng, Oak Ridge National Laboratory. Sparse Matrix Algorithms Research at the University of Florida: `http://www.cise.ufl.edu/research/sparse/`

symbfact

Purpose

Symbolic factorization analysis

Syntax

```
count = symbfact(A)
count = symbfact(A,'col')
count = symbfact(A,'sym')
[count,h,parent,post,R] = symbfact(...)
```

Description

`count = symbfact(A)` returns the vector of row counts for the upper triangular Cholesky factor of a symmetric matrix whose upper triangle is that of `A`, assuming no cancellation during the factorization. `symbfact` should be much faster than `chol(A)`.

`count = symbfact(A,'col')` analyzes `A' *A` (without forming it explicitly).

`count = symbfact(A,'sym')` is the same as `count = symbfact(A)`.

`[count,h,parent,post,R] = symbfact(...)` has several optional return values.

`h`	Height of the elimination tree
`parent`	The elimination tree itself
`post`	Postordering permutation of the elimination tree
`R`	0-1 matrix whose structure is that of `chol(A)`

See Also

`chol`, `etree`, `treelayout`

Purpose

Symmetric LQ method

Syntax

```
x = symmlq(A,b)
symmlq(A,b,tol)
symmlq(A,b,tol,maxit)
symmlq(A,b,tol,maxit,M)
symmlq(A,b,tol,maxit,M1,M2)
symmlq(A,b,tol,maxit,M1,M2,x0)
symmlq(afun,b,tol,maxit,m1fun,m2fun,x0,p1,p2,...)
[x,flag] = symmlq(A,b,...)
[x,flag,relres] = symmlq(A,b,...)
[x,flag,relres,iter] = symmlq(A,b,...)
[x,flag,relres,iter,resvec] = symmlq(A,b,...)
[x,flag,relres,iter,resvec,resveccg] = symmlq(A,b,...)
```

Description

`x = symmlq(A,b)` attempts to solve the system of linear equations `A*x=b` for `x`. The `n`-by-`n` coefficient matrix `A` must be symmetric but need not be positive definite. It should also be large and sparse. The column vector `b` must have length `n`. `A` can be a function `afun` such that `afun(x)` returns `A*x`.

If `symmlq` converges, a message to that effect is displayed. If `symmlq` fails to converge after the maximum number of iterations or halts for any reason, a warning message is printed displaying the relative residual `norm(b-A*x)/norm(b)` and the iteration number at which the method stopped or failed.

`symmlq(A,b,tol)` specifies the tolerance of the method. If `tol` is `[]`, then `symmlq` uses the default, `1e-6`.

`symmlq(A,b,tol,maxit)` specifies the maximum number of iterations. If `maxit` is `[]`, then `symmlq` uses the default, `min(n,20)`.

`symmlq(A,b,tol,maxit,M)` and `symmlq(A,b,tol,maxit,M1,M2)` use the symmetric positive definite preconditioner `M` or `M = M1*M2` and effectively solve the system `inv(sqrt(M))*A*inv(sqrt(M))*y = inv(sqrt(M))*b` for `y` and then return `x = inv(sqrt(M))*y`. If `M` is `[]` then `symmlq` applies no preconditioner. `M` can be a function that returns `M\x`.

`symmlq(A,b,tol,maxit,M1,M2,x0)` specifies the initial guess. If `x0` is `[]`, then `symmlq` uses the default, an all-zero vector.

`symmlq(afun,b,tol,maxit,m1fun,m2fun,x0,p1,p2,...)` passes parameters `p1,p2,...` to functions `afun(x,p1,p2,...)`, `m1fun(x,p1,p2,...)`, and `m2fun(x,p1,p2,...)`.

`[x,flag] = symmlq(A,b,tol,maxit,M1,M2,x0,p1,p2,...)` also returns a convergence flag.

Flag	Convergence
0	`symmlq` converged to the desired tolerance `tol` within `maxit` iterations.
1	`symmlq` iterated `maxit` times but did not converge.
2	Preconditioner `M` was ill-conditioned.
3	`symmlq` stagnated. (Two consecutive iterates were the same.)
4	One of the scalar quantities calculated during `symmlq` became too small or too large to continue computing.
5	Preconditioner `M` was not symmetric positive definite.

Whenever `flag` is not `0`, the solution `x` returned is that with minimal norm residual computed over all the iterations. No messages are displayed if the `flag` output is specified.

`[x,flag,relres] = symmlq(A,b,tol,maxit,M1,M2,x0,p1,p2,...)` also returns the relative residual `norm(b-A*x)/norm(b)`. If `flag` is `0`, `relres <= tol`.

`[x,flag,relres,iter] = symmlq(A,b,tol,maxit,M1,M2,x0,p1,p2,...)` also returns the iteration number at which `x` was computed, where `0 <= iter <= maxit`.

`[x,flag,relres,iter,resvec] = symmlq(A,b,tol,maxit,M1,M2,x0,p1,p2,...)` also returns a vector of estimates of the `symmlq` residual norms at each iteration, including `norm(b-A*x0)`.

`[x,flag,relres,iter,resvec,resveccg] = symmlq(A,b,tol,maxit,M1,M2,x0,p1,p2,...)` also returns a vector of estimates of the conjugate gradients residual norms at each iteration.

Examples

Example 1.

```
n = 100;
on = ones(n,1);
A = spdiags([-2*on 4*on -2*on],-1:1,n,n);
b = sum(A,2);
tol = 1e-10;
maxit = 50; M1 = spdiags(4*on,0,n,n);

x = symmlq(A,b,tol,maxit,M1,[],[]);
symmlq converged at iteration 49 to a solution with relative
residual 4.3e-015
```

Alternatively, use this matrix-vector product function

```
function y = afun(x,n)
   y = 4 * x;
   y(2:n) = y(2:n) - 2 * x(1:n-1);
   y(1:n-1) = y(1:n-1) - 2 * x(2:n);
```

as input to `symmlq`.

```
x1 = symmlq(@afun,b,tol,maxit,M1,[],[],n);
```

Example 2.

Use a symmetric indefinite matrix that fails with `pcg`.

```
A = diag([20:-1:1,-1:-1:-20]);
b = sum(A,2);      % The true solution is the vector of all ones.
x = pcg(A,b);      % Errors out at the first iteration.
pcg stopped at iteration 1 without converging to the desired
tolerance 1e-006 because a scalar quantity became too small or
too large to continue computing.
```

```
The iterate returned (number 0) has relative residual 1
```

However, `symmlq` can handle the indefinite matrix `A`.

```
x = symmlq(A,b,1e-6,40);
symmlq converged at iteration 39 to a solution with relative
residual 1.3e-007
```

See Also

`bicg`, `bicgstab`, `cgs`, `lsqr`, `gmres`, `minres`, `pcg`, `qmr`

`@` (function handle), `/` (slash)

References

[1] Barrett, R., M. Berry, T. F. Chan, et al., *Templates for the Solution of Linear Systems: Building Blocks for Iterative Methods*, SIAM, Philadelphia, 1994.

[2] Paige, C. C. and M. A. Saunders, "Solution of Sparse Indefinite Systems of Linear Equations." *SIAM J. Numer. Anal.*, Vol.12, 1975, pp. 617-629.

Purpose

Sparse symmetric minimum degree ordering

Syntax

```
p = symmmd(S)
```

Description

`p = symmmd(S)` returns a symmetric minimum degree ordering of `S`. For a symmetric positive definite matrix `S`, this is a permutation `p` such that `S(p,p)` tends to have a sparser Cholesky factor than `S`. Sometimes `symmmd` works well for symmetric indefinite matrices too.

Remarks

The minimum degree ordering is automatically used by `\` and `/` for the solution of symmetric, positive definite, sparse linear systems.

Some options and parameters associated with heuristics in the algorithm can be changed with `spparms`.

Algorithm

The symmetric minimum degree algorithm is based on the column minimum degree algorithm. In fact, `symmmd(A)` just creates a nonzero structure `K` such that `K'*K` has the same nonzero structure as `A` and then calls the column minimum degree code for `K`.

Examples

Here is a comparison of reverse Cuthill-McKee and minimum degree on the Bucky ball example mentioned in the `symrcm` reference page.

```
B = bucky+4*speye(60);
r = symrcm(B);
p = symmmd(B);
R = B(r,r);
S = B(p,p);
subplot(2,2,1), spy(R), title('B(r,r)')
subplot(2,2,2), spy(S), title('B(s,s)')
subplot(2,2,3), spy(chol(R)), title('chol(B(r,r))')
subplot(2,2,4), spy(chol(S)), title('chol(B(s,s))')
```



Even though this is a very small problem, the behavior of both orderings is typical. RCM produces a matrix with a narrow bandwidth which fills in almost completely during the Cholesky factorization. Minimum degree produces a structure with large blocks of contiguous zeros which do not fill in during the factorization. Consequently, the minimum degree ordering requires less time and storage for the factorization.

See Also

`colamd`, `colmmd`, `colperm`, `symamd`, `symrcm`

References

[1] Gilbert, John R., Cleve Moler, and Robert Schreiber, “Sparse Matrices in MATLAB: Design and Implementation,” *SIAM Journal on Matrix Analysis and Applications 13*, 1992, pp. 333-356.

Purpose

Sparse reverse Cuthill-McKee ordering

Syntax

```
r = symrcm(S)
```

Description

`r = symrcm(S)` returns the symmetric reverse Cuthill-McKee ordering of `S`. This is a permutation `r` such that `S(r,r)` tends to have its nonzero elements closer to the diagonal. This is a good preordering for LU or Cholesky factorization of matrices that come from long, skinny problems. The ordering works for both symmetric and nonsymmetric `S`.

For a real, symmetric sparse matrix, `S`, the eigenvalues of `S(r,r)` are the same as those of `S`, but `eig(S(r,r))` probably takes less time to compute than `eig(S)`.

Algorithm

The algorithm first finds a pseudoperipheral vertex of the graph of the matrix. It then generates a level structure by breadth-first search and orders the vertices by decreasing distance from the pseudoperipheral vertex. The implementation is based closely on the SPARSPAK implementation described by George and Liu.

Examples

The statement

```
B = bucky
```

uses an M-file in the `demos` toolbox to generate the adjacency graph of a truncated icosahedron. This is better known as a soccer ball, a Buckminster Fuller geodesic dome (hence the name `bucky`), or, more recently, as a 60-atom carbon molecule. There are 60 vertices. The vertices have been ordered by numbering half of them from one hemisphere, pentagon by pentagon; then reflecting into the other hemisphere and gluing the two halves together. With this numbering, the matrix does not have a particularly narrow bandwidth, as the first spy plot shows

```
subplot(1,2,1), spy(B), title('B')
```

The reverse Cuthill-McKee ordering is obtained with

```
p = symrcm(B);
R = B(p,p);
```

The spy plot shows a much narrower bandwidth.

```
subplot(1,2,2), spy(R), title('B(p,p)')
```



This example is continued in the reference pages for `symmmd`.

The bandwidth can also be computed with

```
[i,j] = find(B);
bw = max(i-j) + 1
```

The bandwidths of `B` and `R` are 35 and 12, respectively.

See Also

`colamd`, `colmmd`, `colperm`, `symamd`, `symmmd`

References

[1] George, Alan and Joseph Liu, *Computer Solution of Large Sparse Positive Definite Systems*, Prentice-Hall, 1981.

[2] Gilbert, John R., Cleve Moler, and Robert Schreiber, "Sparse Matrices in MATLAB: Design and Implementation," to appear in *SIAM Journal on Matrix Analysis*, 1992. A slightly expanded version is also available as a technical report from the Xerox Palo Alto Research Center.

Purpose

Determine the symbolic variables in an expression

Syntax

```
symvar 'expr'
s = symvar('expr')
```

Description

`symvar 'expr'` searches the expression, `expr`, for identifiers other than `i`, `j`, `pi`, `inf`, `nan`, `eps`, and common functions. `symvar` displays those variables that it finds or, if no such variable exists, displays an empty cell array, `{}`.

`s = symvar('expr')` returns the variables in a cell array of strings, `s`. If no such variable exists, `s` is an empty cell array.

Examples

`symvar` finds variables `beta1` and `x`, but skips `pi` and the `cos` function.

```
symvar 'cos(pi*x - beta1)'

ans =

    'beta1'
    'x'
```

See Also

`findstr`

system

Purpose

Run operating system command and return result

Description

`system('command')` calls upon the operating system to run `command`, for example `dir` or `ls` or a UNIX shell script, and directs the output to MATLAB. If `command` runs successfully, `ans` is `0`. If `command` fails or does not exist on your operating system, `ans` is a nonzero value and an explanatory message appears.

`[status, result] = system('command')` calls upon the operating system to run `command`, and directs the output to MATLAB. If `command` runs successfully, `status` is `0` and `result` contains the output from `command`. If `command` fails or does not exist on your operating system, `status` is a nonzero value, `result` is an empty matrix, and an explanatory message appears.

Examples

Display the current directory by accessing the operating system.

```
system('pwd')
```

MATLAB displays the current directory and shows that the command executed correctly because ans is 0.

```
D:/mymfiles/

ans =
     0
```

Similarly, run the operating system `pwd` command and assign the current directory to `curr_dir`.

```
[s, curr_dir] = system('pwd')
```

MATLAB displays

```
s =
     0

curr_dir =
     D:/mymfiles/
```

See Also

`!` (exclamation point), `dos`, `perl`, `unix`, `winopen`

2tan

Purpose

Tangent of an argument in radians

Syntax

```
Y = tan(X)
```

Description

The `tan` function operates element-wise on arrays. The function's domains and ranges include complex values. All angles are in radians.

`Y = tan(X)` returns the circular tangent of each element of `X`.

Examples

Graph the tangent function over the domain .

```
x = (-pi/2)+0.01:0.01:(pi/2)-0.01;
plot(x,tan(x)), grid on
```

The expression `tan(pi/2)` does not evaluate as infinite but as the reciprocal of the floating point accuracy `eps` since `pi` is only a floating-point approximation to the exact value of .

Definition

The tangent can be defined as

Algorithm

`tan` uses FDLIBM, which was developed at SunSoft, a Sun Microsystems, Inc. business, by Kwok C. Ng, and others. For information about FDLIBM, see `http://www.netlib.org`.

See Also

`atan`, `atan2`, `tanh`

tand

Purpose

Tangent of an argument in degrees

Syntax

```
Y = tand(X)
```

Description

`Y = tand(X)` is the tangent of the elements of `X`, expressed in degrees. For odd integers `n`, `tand(n*90)` is infinite, whereas `tan(n*pi/2)` is large but finite, reflecting the accuracy of the floating point value of `pi`.

See Also

`atand`, `tan`

Purpose

Hyperbolic tangent

Syntax

```
Y = tanh(X)
```

Description

The `tanh` function operates element-wise on arrays. The function's domains and ranges include complex values. All angles are in radians.

`Y = tanh(X)` returns the hyperbolic tangent of each element of `X`.

Examples

Graph the hyperbolic tangent function over the domain .

```
x = -5:0.01:5;
plot(x,tanh(x)), grid on
```

Definition

The hyperbolic tangent can be defined as

Algorithm

`tanh` uses FDLIBM, which was developed at SunSoft, a Sun Microsystems, Inc. business, by Kwok C. Ng, and others. For information about FDLIBM, see `http://www.netlib.org`.

See Also

`atan`, `atan2`, `tan`

tempdir

Purpose

Return the name of the system's temporary directory

Syntax

```
tmp_dir = tempdir
```

Description

`tmp_dir = tempdir` returns the name of the system's temporary directory, if one exists. This function does not create a new directory.

See Opening Temporary Files and Directories for more information.

See Also

`tempname`

Purpose

Unique name for temporary file

Syntax

```
tmp_nam = tempname
```

Description

`tmp_nam = tempname` returns a unique string, `tmp_nam`, suitable for use as a temporary filename.

Note The filename that `tempname` generates is not guaranteed to be unique; however, it is likely to be so.

See Opening Temporary Files and Directories for more information.

See Also

`tempdir`

tetramesh

Purpose

Tetrahedron mesh plot

Syntax

```
tetramesh(T,X,c)
tetramesh(T,X)
h = tetramesh(...)
tetramesh(...,'param','value','param','value'...)
```

Description

`tetramesh(T,X,c)` displays the tetrahedrons defined in the `m`-by-4 matrix `T` as mesh. `T` is usually the output of `delaunayn`. A row of `T` contains indices into `X` of the vertices of a tetrahedron. `X` is an `n`-by-3 matrix, representing `n` points in 3 dimension. The tetrahedron colors are defined by the vector `C`, which is used as indices into the current colormap.

Note If `T` is the output of `delaunay3`, then `X` is the concatenation of the `delaunay3` input arguments `x`, `y`, `z` interpreted as column vectors, i.e., `X = [x(:) y(:) z(:)]`.

`tetramesh(T,X)` uses `C = 1:m` as the color for the `m` tetrahedrons. Each tetrahedron has a different color (modulo the number of colors available in the current colormap).

`h = tetramesh(...)` returns a vector of tetrahedron handles. Each element of `h` is a handle to the set of patches forming one tetrahedron. You can use these handles to view a particular tetrahedron by turning the patch `'Visible'` property `'on'` or `'off'`.

`tetramesh(...,'param','value','param','value'...)` allows additional patch property name/property value pairs to be used when displaying the tetrahedrons. For example, the default transparency parameter is set to `0.9`. You can overwrite this value by using the property name/property value pair `('FaceAlpha',value)` where `value` is a number between `0` and `1`. See `Patch Properties` for information about the available properties.

Examples

Generate a 3-dimensional Delaunay tesselation, then use `tetramesh` to visualize the tetrahedrons that form the corresponding simplex.

```
d = [-1 1];
```

```
[x,y,z] = meshgrid(d,d,d);  % A cube
x = [x(:);0];
y = [y(:);0];
z = [z(:);0];
% [x,y,z] are corners of a cube plus the center.
X = [x(:) y(:) z(:)];
Tes = delaunayn(X)

Tes =
   9  1  5  6
   3  9  1  5
   2  9  1  6
   2  3  9  4
   2  3  9  1
   7  9  5  6
   7  3  9  5
   8  7  9  6
   8  2  9  6
   8  2  9  4
   8  3  9  4
   8  7  3  9

tetramesh(Tes,X);camorbit(20,0)
```

See Also

delaunayn, patch, Patch Properties, trimesh, trisurf

texlabel

Purpose

Produce TeX format from character string

Syntax

```
texlabel(f)
texlabel(f,'literal')
```

Description

`texlabel(f)` converts the MATLAB expression `f` into the TeX equivalent for use in text strings. It processes Greek variable names (e.g., lambda, delta, etc.) into a string that is displayed as actual Greek letters.

`texlabel(f,'literal')` prints Greek variable names as literals.

If the string is too long to fit into a figure window, then the center of the expression is replaced with a tilde ellipsis (~~~).

Examples

You can use `texlabel` as an argument to the `title`, `xlabel`, `ylabel`, `zlabel`, and `text` commands. For example,

```
title(texlabel('sin(sqrt(x^2 + y^2))/sqrt(x^2 + y^2)'))
```

By default, `texlabel` translates Greek variable names to the equivalent Greek letter. You can select literal interpretation by including the `literal` argument. For example, compare these two commands.

```
text(.5,.5,...
     texlabel('lambda12^(3/2)/pi - pi*delta^(2/3)'))
text(.25,.25,...
     texlabel('lambda12^(3/2)/pi - pi*delta^(2/3)','literal'))
```



See Also `text`, `title`, `xlabel`, `ylabel`, `zlabel`, the text `String` property

"Annotating Plots" for related functions

text

Purpose

Create text object in current axes

Syntax

```
text(x,y,'string')
text(x,y,z,'string')
text(...'PropertyName',PropertyValue...)
h = text(...)
```

Description

`text` is the low-level function for creating text graphics objects. Use `text` to place character strings at specified locations.

`text(x,y,'string')` adds the string in quotes to the location specified by the point `(x,y)`.

`text(x,y,z,'string')` adds the string in 3-D coordinates.

`text(x,y,z,'string','PropertyName',PropertyValue....)` adds the string in quotes to the location defined by the coordinates and uses the values for the specified text properties. See the text property list section at the end of this page for a list of text properties.

`text('PropertyName',PropertyValue....)` omits the coordinates entirely and specifies all properties using property name/property value pairs.

`h = text(...)` returns a column vector of handles to text objects, one handle per object. All forms of the `text` function optionally return this output argument.

See the `String` property for a list of symbols, including Greek letters.

Remarks

Specify the text location coordinates (the `x`, `y`, and `z` arguments) in the data units of the current axes (see "Examples"). The `Extent`, `VerticalAlignment`, and `HorizontalAlignment` properties control the positioning of the character string with regard to the text location point.

If the coordinates are vectors, `text` writes the string at all locations defined by the list of points. If the character string is an array the same length as `x`, `y`, and `z`, `text` writes the corresponding row of the string array at each point specified.

When specifying strings for multiple text objects, the string can be

- A cell array of strings

- A padded string matrix
- A string vector using vertical slash characters (`'|'`) as separators.

Each element of the specified string array creates a different text object.

When specifying the string for a single text object, cell arrays of strings and padded string matrices result in a text object with a multiline string, while vertical slash characters are not interpreted as separators and result in a single line string containing vertical slashes.

`text` is a low-level function that accepts property name/property value pairs as input arguments. However, the convenience form,

```
text(x,y,z,'string')
```

is equivalent to

```
text('XData',x,'YData',y,'ZData',z,'String','string')
```

You can specify other properties only as property name/property value pairs. See the text property list at the end of this page for a description of each property. You can specify properties as property name/property value pairs, structure arrays, and cell arrays (see the `set` and `get` reference pages for examples of how to specify these data types).

`text` does not respect the setting of the figure or axes `NextPlot` property. This allows you to add text objects to an existing axes without setting `hold` to `on`.

Examples

The statements

```
plot(0:pi/20:2*pi,sin(0:pi/20:2*pi))
text(pi,0,' \leftarrow sin(\pi)','FontSize',18)
```

annotate the point at `(pi,0)` with the string `sin(π)`



The statement

```
text(x,y,'\ite^{i\omega\tau} = cos(\omega\tau) + i sin(\omega\tau)')
```

uses embedded TeX sequences to produce

$$e^{i\omega\tau} = cos(\omega\tau) + i\ sin(\omega\tau)$$

See Also

`gtext`, `int2str`, `num2str`, `title`, `xlabel`, `ylabel`, `zlabel`

The “Labeling Graphs” topic in the online Using MATLAB Graphics manual discusses positioning text.

See the `annotation` function for information about text annotations.

Object Hierarchy



Setting Default Properties

You can set default text properties on the axes, figure, and root levels:

```
set(0,'Defaulttext<i>Property</i>',PropertyValue...)
set(gcf,'Defaulttext<i>Property</i>',PropertyValue...)
set(gca,'Defaulttext<i>Property</i>',PropertyValue...)
```

Where *`Property`* is the name of the text property and `PropertyValue` is the value you are specifying. Use `set` and `get` to access text properties.

Property List

The following table lists all text properties and provides a brief description of each. The property name links take you to an expanded description of the properties.

Property Name	Property Description	Property Value
Defining the Character String		
`Editing`	Enables or disables editing mode	Values: `on`, `off` Default: `off`
`Interpreter`	Enables or disables TeX two levels of interpretation	Values: `latex`, `tex`, `none` Default: `tex`
`String`	The character string (including list of TeX character sequences)	Value: character string
Positioning the character string		
`Extent`	Position and size of text object	Values: `[left, bottom, width, height]`

Property Name	Property Description	Property Value
`HorizontalAlignment`	Horizontal alignment of text string	Values: `left`, `center`, `right` Default: `left`
`Position`	Position of text `Extent` rectangle	Values: [x, y, z] coordinates Default: `[]` (empty matrix)
`Rotation`	Orientation of text object	Value: scalar (degrees) Default: `0`
`Units`	Units for `Extent` and `Position` properties	Values: `pixels`, `normalized`, `inches`, `centimeters`, `points`, `data` Default: `data`
`VerticalAlignment`	Vertical alignment of text string	Values: `top`, `cap`, `middle`, `baseline`, `bottom` Default: `middle`
Text Bounding Box		
`BackgroundColor`	Color of text extent rectangle	Value: `ColorSpec` Default: none
`EdgeColor`	Color of edge drawn around text extent rectangle	Value: `ColorSpec` Default: none
`LineWidth`	Width of the line (in points) used to draw the box around the text extent rectangle	Value: scalar (points) Default: 0.5
`LineStyle`	Style of the line used to draw the box around the text extent rectangle	Values: –, ––, `:`, –., `none` Default: –
`Margin`	Distance in pixels from the text extent to the edge of the box enclosing the text	Value: scalar (pixels) Default: 2
Specifying the Font		

Property Name	Property Description	Property Value
FontAngle	Selects italic-style font	Values: normal, italic, oblique Default: normal
FontName	Selects font family	Value: a font supported by your system or the string FixedWidth Default: Helvetica
FontSize	Size of font	Value: size in FontUnits Default: 10 points
FontUnits	Units for FontSize property	Values: points, normalized, inches, centimeters, pixels Default: points
FontWeight	Weight of text characters	Values: light, normal, demi, bold Default: normal
Controlling the Appearance		
Clipping	Clipping to axes rectangle	Values: on, off Default: on
EraseMode	Method of drawing and erasing the text (useful for animation)	Values: normal, none, xor, background Default: normal
SelectionHighlight	Highlights text when selected (Selected property is set to on)	Values: on, off Default: on
Visible	Makes the text visible or invisible	Values: on, off Default: on
Color	Color of the text	ColorSpec
Controlling Access to Text Objects		
HandleVisibility	Determines if and when the text's handle is visible to other functions	Values: on, callback, off Default: on

Property Name	Property Description	Property Value
`HitTest`	Determines if the text can become the current object (see the figure `CurrentObject` property)	Values: `on`, `off` Default: `on`
General Information About Text Objects		
`Children`	Text objects have no children.	Value: `[]` (empty matrix)
`Parent`	The parent of a text object is an axes hggroup, or hgtransform object.	Value: object handle
`Selected`	Indicates whether the text is in a selected state	Values: `on`, `off` Default: `off`
`Tag`	User-specified label	Value: any string Default: `''` (empty string)
`Type`	The type of graphics object (read only)	Value: the string `'text'`
`UserData`	User-specified data	Value: any matrix Default: `[]` (empty matrix)
Controlling Callback Routine Execution		
`BeingDeleted`	Query to see if object is being deleted.	Values: `on | off` Read only
`BusyAction`	Specifies how to handle callback routine interruption	Values: `cancel`, `queue` Default: `queue`
`ButtonDownFcn`	Defines a callback routine that executes when a mouse button is pressed on over the text	Value: string or function handle Default: `''` (empty string)
`CreateFcn`	Defines a callback routine that executes when a text is created	Value: string or function handle Default: `''` (empty string)

Property Name	Property Description	Property Value
`DeleteFcn`	Defines a callback routine that executes when the text is deleted (via `close` or `delete`)	Value: string or function handle Default: `''` (empty string)
`Interruptible`	Determines if callback routine can be interrupted	Values: `on`, `off` Default: `on` (can be interrupted)
`UIContextMenu`	Associates a context menu with the text	Value: handle of a uicontextmenu

Text Properties

Modifying Properties

You can set and query graphics object properties using the property editor or the `set` and `get` commands.

- The Property Editor is an interactive tool that enables you to see and change object property values.
- The `set` and `get` commands enable you to set and query the values of properties.

To change the default values of properties, see Setting Default Property Values.

See Core Objects for general information about this type of object.

Text Property Descriptions

This section lists property names along with the types of values each accepts. Curly braces { } enclose default values.

`BackgroundColor` `ColorSpec | {none}`

Color of text extent rectangle. This property enables you to define a color for the rectangle that encloses the text `Extent`. For example, the following code creates a text object that labels a plot and sets the background color to light green.

```
text(3*pi/4,sin(3*pi/4),...
   ['sin(3*pi/4) = ',num2str(sin(3*pi/4))],...
   'HorizontalAlignment','center',...
   'BackgroundColor',[.7 .9 .7]);
```



For additional features, see the following properties:

- `EdgeColor` — Color of the rectangle's edge (`none` by default).
- `LineStyle` — Style of the rectangle's edge line (first set `EdgeColor`)
- `LineWidth` — Width of the rectangle's edge line (first set `EdgeColor`)
- `Margin` — Increase the size of the rectangle by adding a margin to the existing text extent rectangle.

See also "Drawing Text in a Box" in the MATLAB Graphics documentation for an example using background color with contour labels.

`BeingDeleted` `on | {off}` read only

This object is being deleted. The `BeingDeleted` property provides a mechanism that you can use to determine if objects are in the process of being deleted. MATLAB sets the `BeingDeleted` property to `on` when the object's delete function callback is called (see the `DeleteFcn` property) It remains set to `on` while the delete function executes, after which the object no longer exists.

For example, an object's delete function might call other functions that act on a number of different objects. These functions may not need to perform actions on objects that are going to be deleted, and therefore can check the object's `BeingDeleted` property before acting.

`BusyAction` `cancel | {queue}`

Callback routine interruption. The `BusyAction` property enables you to control how MATLAB handles events that potentially interrupt executing callback routines. If there is a callback routine executing, callback routines invoked subsequently always attempt to interrupt it. If the `Interruptible` property of the object whose callback is executing is set to `on` (the default), then interruption occurs at the next point where the event queue is processed. If the `Interruptible` property is set to `off`, the `BusyAction` property (of the object owning the executing callback) determines how MATLAB handles the event. The choices are

- `cancel` — Discard the event that attempted to execute a second callback routine.
- `queue` — Queue the event that attempted to execute a second callback routine until the current callback finishes.

ButtonDownFcn string or function handle

Button press callback routine. A callback routine that executes whenever you press a mouse button while the pointer is over the text object. Define this routine as a string that is a valid MATLAB expression or the name of an M-file. The expression executes in the MATLAB workspace.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

Children matrix (read only)

The empty matrix; text objects have no children.

Clipping `on | {off}`

Clipping mode. When `Clipping` is `on`, MATLAB does not display any portion of the text that is outside the axes.

Color `ColorSpec`

Text color. A three-element RGB vector or one of the predefined names, specifying the text color. The default value for `Color` is white. See `ColorSpec` for more information on specifying color.

CreateFcn string or function handle

Callback routine executed during object creation. This property defines a callback routine that executes when MATLAB creates a text object. You must define this property as a default value for text or in a call to the `text` function that creates a new text object. For example, the statement

```
set(0,'DefaultTextCreateFcn',...
    'set(gcf,''Pointer'',''crosshair'')')
```

defines a default value on the root level that sets the figure `Pointer` property to crosshairs whenever you create a text object. MATLAB executes this routine after setting all text properties. Setting this property on an existing text object has no effect.

The handle of the object whose `CreateFcn` is being executed is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

`DeleteFcn` string or function handle

Delete text callback routine. A callback routine that executes when you delete the text object (e.g., when you issue a `delete` command or clear the axes or figure). MATLAB executes the routine before destroying the object's properties so these values are available to the callback routine.

The handle of the object whose `DeleteFcn` is being executed is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

`EdgeColor` `ColorSpec | {none}`

Color of edge drawn around text extent rectangle. This property enables you to specify the color of a box drawn around the text `Extent`. For example, the following code draws a red rectangle around text that labels a plot.

```
text(3*pi/4,sin(3*pi/4),...
'\leftarrowsin(t) = .707',...
'EdgeColor','red');
```



For additional features, see the following properties:

- `BackgroundColor` — Color of the rectangle's interior (`none` by default)
- `LineStyle` — Style of the rectangle's edge line (first set `EdgeColor`)
- `LineWidth` — Width of the rectangle's edge line (first set `EdgeColor`)

- `Margin` — Increases the size of the rectangle by adding a margin to the existing text extent rectangle

`Editing` `on | {off}`

Enable or disable editing mode. When this property is set to the default `off`, you cannot edit the text string interactively (i.e., you must change the `String` property to change the text). When this property is set to `on`, MATLAB places an insert cursor at the beginning of the text string and enables editing. To apply the new text string,

1. Press the **Esc** key.
2. Click in any figure window (including the current figure).
3. Reset the `Editing` property to `off`.

MATLAB then updates the `String` property to contain the new text and resets the `Editing` property to `off`. You must reset the `Editing` property to `on` to resume editing.

`EraseMode` `{normal} | none | xor | background`

Erase mode. This property controls the technique MATLAB uses to draw and erase text objects. Alternative erase modes are useful for creating animated sequences where controlling the way individual objects are redrawn is necessary to improve performance and obtain the desired effect.

- `normal` — Redraw the affected region of the display, performing the three-dimensional analysis necessary to ensure that all objects are rendered correctly. This mode produces the most accurate picture, but is the slowest. The other modes are faster, but do not perform a complete redraw and are therefore less accurate.
- `none` — Do not erase the text when it is moved or destroyed. While the object is still visible on the screen after erasing with `EraseMode none`, you cannot print it because MATLAB stores no information about its former location.
- `xor` — Draw and erase the text by performing an exclusive OR (XOR) with each pixel index of the screen beneath it. When the text is erased, it does not damage the objects beneath it. However, when text is drawn in `xor` mode, its color depends on the color of the screen beneath it. It is correctly colored only when it is over axes background `Color`, or the figure background `Color` if the axes `Color` is set to `none`.

- `background` — Erase the text by drawing it in the axes background `Color`, or the figure background `Color` if the axes `Color` is set to `none`. This damages objects that are behind the erased text, but text is always properly colored.

Printing with Nonnormal Erase Modes. MATLAB always prints figures as if the `EraseMode` of all objects is set to `normal`. This means graphics objects created with `EraseMode` set to `none`, `xor`, or `background` can look differently on screen than on paper. On screen, MATLAB may mathematically combine layers of colors (e.g., performing an XOR of a pixel color with that of the pixel behind it) and ignore three-dimensional sorting to obtain greater rendering speed. However, these techniques are not applied to the printed output.

You can use the MATLAB `getframe` command or other screen capture application to create an image of a figure containing nonnormal mode objects.

`Extent` position rectangle (read only)

Position and size of text. A four-element read-only vector that defines the size and position of the text string

```
[left,bottom,width,height]
```

If the `Units` property is set to `data` (the default), `left` and `bottom` are the *x*- and *y*-coordinates of the lower left corner of the text `Extent`.

For all other values of `Units`, `left` and `bottom` are the distance from the lower left corner of the axes position rectangle to the lower left corner of the text `Extent`. `width` and `height` are the dimensions of the `Extent` rectangle. All measurements are in units specified by the `Units` property.

`FontAngle` `{normal} | italic | oblique`

Character slant. MATLAB uses this property to select a font from those available on your particular system. Generally, setting this property to `italic` or `oblique` selects a slanted font.

`FontName` A name, such as `Courier`, or the string `FixedWidth`

Font family. A string specifying the name of the font to use for the text object. To display and print properly, this must be a font that your system supports. The default font is Helvetica.

Specifying a Fixed-Width Font

If you want text to use a fixed-width font that looks good in any locale, you should set `FontName` to the string `FixedWidth`:

```
set(text_handle,'FontName','FixedWidth')
```

This eliminates the need to hard-code the name of a fixed-width font, which may not display text properly on systems that do not use ASCII character encoding (such as in Japan where multibyte character sets are used). A properly written MATLAB application that needs to use a fixed-width font should set `FontName` to `FixedWidth` (note that this string is case sensitive) and rely on `FixedWidthFontName` to be set correctly in the end user's environment.

End users can adapt a MATLAB application to different locales or personal environments by setting the root `FixedWidthFontName` property to the appropriate value for that locale from `startup.m`.

Note that setting the root `FixedWidthFontName` property causes an immediate update of the display to use the new font.

`FontSize` size in `FontUnits`

Font size. A value specifying the font size to use for text in units determined by the `FontUnits` property. The default point size is 10 (1 point = 1/72 inch).

`FontWeight` `light | {normal} | demi | bold`

Weight of text characters. MATLAB uses this property to select a font from those available on your particular system. Generally, setting this property to `bold` or `demi` causes MATLAB to use a bold font.

`FontUnits` `{points} | normalized | inches | centimeters | pixels`

Font size units. MATLAB uses this property to determine the units used by the `FontSize` property. Normalized units interpret `FontSize` as a fraction of the height of the parent axes. When you resize the axes, MATLAB modifies the screen `FontSize` accordingly. `pixels`, `inches`, `centimeters`, and `points` are absolute units (1 point = 1/72 inch).

`HandleVisibility` `{on} | callback | off`

Control access to object's handle by command-line users and GUIs. This property determines when an object's handle is visible in its parent's list of children. `HandleVisibility` is useful for preventing command-line users from

accidentally drawing into or deleting a figure that contains only user interface devices (such as a dialog box).

Handles are always visible when `HandleVisibility` is set to `on`.

Setting `HandleVisibility` to `callback` causes handles to be visible from within callback routines or functions invoked by callback routines, but not from within functions invoked from the command line. This provides a means to protect GUIs from command-line users, while allowing callback routines to have complete access to object handles.

Setting `HandleVisibility` to `off` makes handles invisible at all times. This may be necessary when a callback routine invokes a function that might potentially damage the GUI (such as evaluating a user-typed string), and so temporarily hides its own handles during the execution of that function.

When a handle is not visible in its parent's list of children, it cannot be returned by functions that obtain handles by searching the object hierarchy or querying handle properties. This includes `get`, `findobj`, `gca`, `gcf`, `gco`, `newplot`, `cla`, `clf`, and `close`.

When a handle's visibility is restricted using `callback` or `off`,

- The object's handle does not appear in its parent's `Children` property.
- Figures do not appear in the root's `CurrentFigure` property.
- Objects do not appear in the root's `CallbackObject` property or in the figure's `CurrentObject` property.
- Axes do not appear in their parent's `CurrentAxes` property.

You can set the root `ShowHiddenHandles` property to `on` to make all handles visible regardless of their `HandleVisibility` settings (this does not affect the values of the `HandleVisibility` properties).

Handles that are hidden are still valid. If you know an object's handle, you can set and get its properties, and pass it to any function that operates on handles.

`HitTest` `{on} | off`

Selectable by mouse click. `HitTest` determines if the text can become the current object (as returned by the `gco` command and the figure `CurrentObject` property) as a result of a mouse click on the text. If `HitTest` is set to `off`,

clicking the text selects the object below it (which is usually the axes containing it).

For example, suppose you define the button down function of an image (see the `ButtonDownFcn` property) to display text at the location you click with the mouse.

First define the callback routine.

```
function bd_function
pt = get(gca,'CurrentPoint');
text(pt(1,1),pt(1,2),pt(1,3),...
   '{\fontsize{20}\oplus} The spot to label',...
   'HitTest','off')
```

Now display an image, setting its `ButtonDownFcn` property to the callback routine.

```
load earth
image(X,'ButtonDownFcn','bd_function'); colormap(map)
```

When you click the image, MATLAB displays the text string at that location. With `HitTest` set to `off`, existing text cannot intercept any subsequent button down events that occur over the text. This enables the image's button down function to execute.

`HorizontalAlignment``{left} | center | right`

Horizontal alignment of text. This property specifies the horizontal justification of the text string. It determines where MATLAB places the string with regard to the point specified by the `Position` property. The following picture illustrates the alignment options.

`HorizontalAlignment` viewed with the `VerticalAlignment` set to middle (the default).



See the `Extent` property for related information.

Interpreter `latex | {tex} | none`

Interpret T_EX instructions. This property controls whether MATLAB interprets certain characters in the `String` property as T_EX instructions (default) or displays all characters literally. See the `String` property for a list of supported T_EX instructions.

Latex Interpreter

To enable the LaT_EX interpreter for text objects, set the `Interpreter` property to `latex`. For example, the following statement displays an equation in a figure at the point [.5 .5], and enlarges the font to 16 points.

```
text('Interpreter','latex',...
    'String','$$\int_0^x\!\int_y dF(u,v)$$',...
    'Position',[.5 .5],...
    'FontSize',16)
```



Information About Using T_EX

The following references may be useful to people who are not familiar with T_EX.

- Donald E. Knuth, *The $T_EX$book*, Addison Wesley, 1986.
- The T_EX Users Group home page: `http://www.tug.org`

`Interruptible` `{on} | off`

Callback routine interruption mode. The `Interruptible` property controls whether a text callback routine can be interrupted by subsequently invoked callback routines. Text objects have three properties that define callback routines: `ButtonDownFcn`, `CreateFcn`, and `DeleteFcn`. See the `BusyAction` property for information on how MATLAB executes callback routines.

`LineStyle` `{-} | -- | : | -. | none`

Edge line type. This property determines the line style used to draw the edges of the text `Extent`. The available line styles are shown in the following table.

Symbol	Line Style
–	Solid line (default)
––	Dashed line
:	Dotted line
–.	Dash-dot line
`none`	No line

For example, the following code draws a red rectangle with a dotted line style around text that labels a plot.

```
text(3*pi/4,sin(3*pi/4),...
     '\leftarrowsin(t) = .707',...
     'EdgeColor','red',...
     'LineWidth',2,...
     'LineStyle',':');
```



For additional features, see the following properties:

- `BackgroundColor` — Color of the rectangle's interior (`none` by default)
- `EdgeColor` — Color of the rectangle's edge (`none` by default)
- `LineWidth` — Width of the rectangle's edge line (first set `EdgeColor`)
- `Margin` — Increases the size of the rectangle by adding a margin to the existing text extent rectangle

`LineWidth` scalar (points)

Width of line used to draw text extent rectangle. When you set the text `EdgeColor` property to a color (the default is `none`), MATLAB displays a rectangle around the text `Extent`. Use the `LineWidth` property to specify the width of the rectangle edge. For example, the following code draws a red rectangle around text that labels a plot and specifies a line width of 3 points:

```
text(3*pi/4,sin(3*pi/4),...
'\leftarrowsin(t) = .707',...
'EdgeColor','red',...
'LineWidth',3);
```



For additional features, see the following properties:

- `BackgroundColor` — Color of the rectangle's interior (`none` by default)
- `EdgeColor` — Color of the rectangle's edge (`none` by default)
- `LineStyle` — Style of the rectangle's edge line (first set `EdgeColor`)
- `Margin` — Increases the size of the rectangle by adding a margin to the existing text extent rectangle

`Margin` scalar (pixels)

Distance between the text extent and the rectangle edge. When you specify a color for the `BackgroundColor` or `EdgeColor` text properties, MATLAB draws a rectangle around the area defined by the text `Extent` plus the value specified by the `Margin`. For example, the following code displays a light green rectangle with a 10-pixel margin.

```
text(5*pi/4,sin(5*pi/4),...
   ['sin(5*pi/4) = ',num2str(sin(5*pi/4))],...
   'HorizontalAlignment','center',...
   'BackgroundColor',[.7 .9 .7],...
   'Margin',10);
```



For additional features, see the following properties:

- `BackgroundColor` — Color of the rectangle's interior (`none` by default)
- `EdgeColor` — Color of the rectangle's edge (`none` by default)
- `LineStyle` — Style of the rectangle's edge line (first set `EdgeColor`)
- `LineWidth` — Width of the rectangle's edge line (first set `EdgeColor`)

`Parent` handle of axes, hggroup, or hgtransform

Parent of text object. This property contains the handle of the text object's parent. The parent of a text object is the axes, hggroup, or hgtransform object that contains it.

See Objects That Can Contain Other Objects for more information on parenting graphics objects.

`Position` `[x,y,[z]]`

Location of text. A two- or three-element vector, `[x y [z]]`, that specifies the location of the text in three dimensions. If you omit the `z` value, it defaults to 0. All measurements are in units specified by the `Units` property. Initial value is `[0 0 0]`.

`Rotation` scalar (default = 0)

Text orientation. This property determines the orientation of the text string. Specify values of rotation in degrees (positive angles cause counterclockwise rotation).

Selected on | {off}

Is object selected? When this property is set to on, MATLAB displays selection handles if the SelectionHighlight property is also set to on. You can, for example, define the ButtonDownFcn to set this property, allowing users to select the object with the mouse.

SelectionHighlight {on} | off

Objects are highlighted when selected. When the Selected property is set to on, MATLAB indicates the selected state by drawing four edge handles and four corner handles. When SelectionHighlight is set to off, MATLAB does not draw the handles.

String string

The text string. Specify this property as a quoted string for single-line strings, or as a cell array of strings, or a padded string matrix for multiline strings. MATLAB displays this string at the specified location. Vertical slash characters are not interpreted as line breaks in text strings, and are drawn as part of the text string. See Mathematical Symbols, Greek Letters, and TeX Characters for an example.

When the text Interpreter property is set to Tex (the default), you can use a subset of TeX commands embedded in the string to produce special characters such as Greek letters and mathematical symbols. The following table lists these characters and the character sequences used to define them.

Character Sequence	Symbol	Character Sequence	Symbol	Character Sequence	Symbol
\alpha	α	\upsilon	υ	\sim	~
\beta	β	\phi	ϕ	\leq	≤
\gamma	γ	\chi	χ	\infty	∞
\delta	δ	\psi	ψ	\clubsuit	♣
\epsilon	ε	\omega	ω	\diamondsuit	♦
\zeta	ζ	\Gamma	Γ	\heartsuit	♥
\eta	η	\Delta	Δ	\spadesuit	♠

Character Sequence	Symbol	Character Sequence	Symbol	Character Sequence	Symbol
\theta	θ	\Theta	Θ	\leftrightarrow	↔
\vartheta	ϑ	\Lambda	Λ	\leftarrow	←
\iota	ι	\Xi	Ξ	\uparrow	↑
\kappa	κ	\Pi	Π	\rightarrow	→
\lambda	λ	\Sigma	Σ	\downarrow	↓
\mu	μ	\Upsilon	Υ	\circ	°
\nu	ν	\Phi	Φ	\pm	±
\xi	ξ	\Psi	Ψ	\geq	≥
\pi	π	\Omega	Ω	\propto	∝
\rho	ρ	\forall	∀	\partial	∂
\sigma	σ	\exists	∃	\bullet	•
\varsigma	ς	\ni	∋	\div	÷
\tau	τ	\cong	≅	\neq	≠
\equiv	≡	\approx	≈	\aleph	ℵ
\Im	ℑ	\Re	ℜ	\wp	℘
\otimes	⊗	\oplus	⊕	\oslash	∅
\cap	∩	\cup	∪	\supseteq	⊇
\supset	⊃	\subseteq	⊆	\subset	⊂
\int	∫	\in	∈	\o	o
\rfloor	⌋	\lceil	⌈	\nabla	∇
\lfloor	⌊	\cdot	·	\ldots	…
\perp	⊥	\neg	¬	\prime	′

Character Sequence	Symbol	Character Sequence	Symbol	Character Sequence	Symbol
\wedge	∧	\times	×	\0	∅
\rceil	⌉	\surd	√	\mid	|
\vee	∨	\varpi	ϖ	\copyright	©
\langle	⟨	\rangle	⟩		

You can also specify stream modifiers that control the font used. The first four modifiers are mutually exclusive. However, you can use `\fontname` in combination with one of the other modifiers:

- `\bf` — Bold font
- `\it` — Italic font
- `\sl` — Oblique font (rarely available)
- `\rm` — Normal font
- `\fontname{`*`fontname`*`}` — Specify the name of the font family to use.
- `\fontsize{`*`fontsize`*`}` — Specify the font size in `FontUnits`.

Stream modifiers remain in effect until the end of the string or only within the context defined by braces { }.

Specifying Subscript and Superscript Characters

The subscript character "_" and the superscript character "^" modify the character or substring defined in braces immediately following.

To print the special characters used to define the TeX strings when `Interpreter` is `Tex`, prefix them with the backslash "\" character: `\\`, `\{`, `\}` `\_`, `\^`.

See the example in the `text` reference page for more information.

When `Interpreter` is set to `none`, no characters in the `String` are interpreted, and all are displayed when the text is drawn.

When `Interpreter` is set to `latex`, MATLAB provides a complete $\LaTeX$ interpreter for text objects. See the `Interpreter` property for more information.

Tag string

User-specified object label. The `Tag` property provides a means to identify graphics objects with a user-specified label. This is particularly useful when you are constructing interactive graphics programs that would otherwise need to define object handles as global variables or pass them as arguments between callback routines. You can define `Tag` as any string.

Type string (read only)

Class of graphics object. For text objects, `Type` is always the string `'text'`.

Units `pixels | normalized | inches | centimeters | points | {data}`

Units of measurement. This property specifies the units MATLAB uses to interpret the `Extent` and `Position` properties. All units are measured from the lower left corner of the axes plot box.

- `Normalized` units map the lower left corner of the rectangle defined by the axes to (0,0) and the upper right corner to (1.0,1.0).
- `pixels`, `inches`, `centimeters`, and `points` are absolute units (1 point = $1/72$ inch).
- `data` refers to the data units of the parent axes.

If you change the value of `Units`, it is good practice to return it to its default value after completing your computation so as not to affect other functions that assume `Units` is set to the default value.

UserData matrix

User-specified data. Any data you want to associate with the text object. MATLAB does not use this data, but you can access it using `set` and `get`.

UIContextMenu handle of a uicontextmenu object

Associate a context menu with the text. Assign this property the handle of a uicontextmenu object created in the same figure as the text. Use the `uicontextmenu` function to create the context menu. MATLAB displays the context menu whenever you right-click over the text.

VerticalAlignment `top | cap | {middle} | baseline | bottom`

Vertical alignment of text. This property specifies the vertical justification of the text string. It determines where MATLAB places the string with regard to the value of the `Position` property. The possible values mean

- `top` — Place the top of the string's `Extent` rectangle at the specified *y*-position.
- `cap` — Place the string so that the top of a capital letter is at the specified *y*-position.
- `middle` — Place the middle of the string at the specified *y*-position.
- `baseline` — Place font baseline at the specified *y*-position.
- `bottom` — Place the bottom of the string's `Extent` rectangle at the specified *y*-position.

The following picture illustrates the alignment options.

Text `VerticalAlignment` property viewed with the `HorizontalAlignment` property set to `left` (the default).



Visible `{on} | off`

Text visibility. By default, all text is visible. When set to `off`, the text is not visible, but still exists, and you can query and set its properties.

Purpose

Read data from text file, write to multiple outputs

Graphical Interface

As an alternative to `textread`, use the Import Wizard. To activate the Import Wizard, select **Import Data** from the **File** menu.

Syntax

```
[A,B,C,...] = textread('filename','format')
[A,B,C,...] = textread('filename','format',N)
[...] = textread(...,'param','value',...)
```

Description

`[A,B,C,...] = textread('filename','format')` reads data from the file `'filename'` into the variables `A,B,C,` and so on, using the specified `format`, until the entire file is read. `textread` is useful for reading text files with a known format. `textread` handles both fixed and free format files.

Note When reading large text files, reading from a specific point in a file, or reading file data into a cell array rather than multiple outputs, you might prefer to use the `textscan` function.

`textread` matches and converts groups of characters from the input. Each input field is defined as a string of non-white-space characters that extends to the next white-space or delimiter character, or to the maximum field width. Repeated delimiter characters are significant, while repeated white-space characters are treated as one.

The `format` string determines the number and types of return arguments. The number of return arguments is the number of items in the `format` string. The `format` string supports a subset of the conversion specifiers and conventions of the C language `fscanf` routine. Values for the `format` string are listed in the table below. White-space characters in the `format` string are ignored.

format	Action	Output
Literals (ordinary characters)	Ignore the matching characters. For example, in a file that has `Dept` followed by a number (for department number), to skip the `Dept` and read only the number, use `'Dept'` in the `format` string.	None
`%d`	Read a signed integer value.	Double array
`%u`	Read an integer value.	Double array
`%f`	Read a floating-point value.	Double array
`%s`	Read a white-space or delimiter-separated string.	Cell array of strings
`%q`	Read a string, which could be in double quotes.	Cell array of strings. Does not include the double quotes.
`%c`	Read characters, including white space.	Character array
`%[...]`	Read the longest string containing characters specified in the brackets.	Cell array of strings
`%[^...]`	Read the longest nonempty string containing characters that are not specified in the brackets.	Cell array of strings
`%*...` instead of `%`	Ignore the matching characters specified by `*`.	No output
`%w...` instead of `%`	Read field width specified by `w`. The `%f` format supports `%w.pf`, where `w` is the field width and `p` is the precision.	

`[A,B,C,...] = textread('filename','format',N)` reads the data, reusing the `format` string `N` times, where `N` is an integer greater than zero. If `N` is smaller than zero, `textread` reads the entire file.

`[...] = textread(...,'param','value',...)` customizes `textread` using `param/value` pairs, as listed in the table below.

param	value	Action

	`' '`
	`\b`
	`\n`
	`\r`
	`\t`
		Space
		Backspace
		Newline
		Carriage return
		Horizontal tab

`bufsize`	Positive integer	Specifies the maximum string length, in bytes. Default is `4095`.
`commentstyle`	`matlab`	Ignores characters after `%`.
`commentstyle`	`shell`	Ignores characters after `#`.
`commentstyle`	`c`	Ignores characters between `/*` and `*/`.
`commentstyle`	`c++`	Ignores characters after `//`.
`delimiter`	One or more characters	Act as delimiters between elements. Default is none.
`emptyvalue`	Scalar double	Value given to empty cells when reading delimited files. Default is 0.
`endofline`	Single character or `'\r\n'`	Character that denotes the end of a line. Default is determined from file
`expchars`	Exponent characters	Default is `eEdD`.

param	value	Action
`headerlines`	Positive integer	Ignores the specified number of lines at the beginning of the file.
`whitespace`	Any from the list below:	Treats vector of characters as white space. Default is `' \b\t'`.

Note When `textread` reads a consecutive series of `whitespace` values, it treats them as one white space. When it reads a consecutive series of `delimiter` values, it treats each as a separate delimiter.

Examples

Example 1 — Read All Fields in Free Format File Using %

The first line of `mydata.dat` is

```
Sally    Level1 12.34 45 Yes
```

Read the first line of the file as a free format file using the `%` format.

```
[names, types, x, y, answer] = textread('mydata.dat', ...
'%s %s %f %d %s', 1)
```

returns

```
names =
    'Sally'
types =
    'Level1'
x =
  12.34000000000000
y =
    45
answer =
    'Yes'
```

Example 2 — Read as Fixed Format File, Ignoring the Floating Point Value

The first line of `mydata.dat` is

```
Sally    Level1 12.34 45 Yes
```

Read the first line of the file as a fixed format file, ignoring the floating-point value.

```
[names, types, y, answer] = textread('mydata.dat', ...
'%9c %5s %*f %2d %3s', 1)
```

returns

```
names =
Sally
types =
    'Level1'
y =
    45
answer =
    'Yes'
```

`%*f` in the `format` string causes `textread` to ignore the floating point value, in this case, `12.34`.

Example 3 — Read Using Literal to Ignore Matching Characters

The first line of `mydata.dat` is

```
Sally    Level1 12.34 45 Yes
```

Read the first line of the file, ignoring the characters `Type` in the second field.

```
[names, typenum, x, y, answer] = textread('mydata.dat', ...
'%s Type%d %f %d %s', 1)
```

returns

```
names =
    'Sally'
typenum =
    1
x =
  12.34000000000000
```

```
y =
    45
answer =
    'Yes'
```

`Type%d` in the `format` string causes the characters `Type` in the second field to be ignored, while the rest of the second field is read as a signed integer, in this case, `1`.

Example 4 — Specify Value to Fill Empty Cells

For files with empty cells, use the `emptyvalue` parameter. Suppose the file `data.csv` contains:

```
1,2,3,4,,6
7,8,9,,11,12
```

Read the file using `NaN` to fill any empty cells:

```
data = textread('data.csv', '', 'delimiter', ',', ...
         'emptyvalue', NaN);
```

Example 5 — Read M-File into a Cell Array of Strings

Read the file `fft.m` into cell array of strings.

```
file = textread('fft.m','%s','delimiter','\n','whitespace','');
```

See Also

`textscan`, `dlmread`, `csvread`, `fscanf`

Purpose

Read data from text file, convert, and write to cell array

Syntax

```
C = textscan(fid, 'format')
C = textscan(fid, 'format', N)
C = textscan(fid, 'format', param, value, ...)
C = textscan(fid, 'format', N, param, value, ...)
```

Description

Before reading a file with `textscan`, you must open the file with the `fopen` function. `fopen` supplies the `fid` input required by `textscan`. When you are finished reading from the file, you should close the file by calling `fclose(fid)`.

`C = textscan(fid, 'format')` reads data from an open text file identified by file identifier `fid` into cell array `C`. MATLAB parses the data into fields and converts it according to the conversion specifiers in the `format` string. These conversion specifiers determine the type of each cell in the output cell array. The number of specifiers determines the number of cells in the cell array.

`C = textscan(fid, 'format', N)` reads data from the file, reusing the `format` conversion specifier `N` times. If `N` is `-1`, or is unspecified, `textscan` reads the entire file. You can resume reading from the file after `N` cycles by calling `textscan` again using the original `fid`.

`C = textscan(fid, 'format', param, value, ...)` reads data from the file using nondefault parameter settings specified by one or more pairs of `param` and `value` arguments. The section "User Configurable Options" on page 2-2264 lists all valid parameter strings, value descriptions, and defaults.

`C = textscan(fid, 'format', N, param, value, ...)` reads data from the file, reusing the `format` conversion specifier `N` times, and using nondefault parameter settings specified by pairs of `param` and `value` arguments.

Note If `textscan` fails to convert a data field, it stops reading and returns all fields read before the failure. You can resume reading from the same file by calling `textscan` again using the same file identifier, `fid`.

The Difference Between the textscan and textread Functions

The `textscan` function differs from `textread` in the following ways:

- The `textscan` function offers better performance than `textread`, making it a better choice when reading large files.
- With `textscan`, you can start reading at any point in the file. Once the file is open, (`textscan` requires that you open the file first), you can seek to any position in the file and begin the `textscan` at that point. The `textread` function requires that you start reading from the beginning of the file.
- Subsequent `textscan`s start reading the file at the point where the last `textscan` left off. The `textread` function always begins at the start of the file, regardless of any prior `textread`.
- `textscan` returns a single cell array regardless of how many fields you read. With `textscan`, you don't need to match the number of output arguments to the number of fields being read as you would with `textread`.
- `textscan` offers more choices in how the data being read is converted.
- `textscan` offers more user-configurable options.

Field Delimiters

The `textscan` function regards a text file as consisting of blocks. Each block consists of a number of internally consistent fields. Each field consists of a group of characters delimited by a field delimiter character. Fields can span a number of rows. Each row is delimited by an end-of-line (`EOL`) character sequence.

The default field delimiter is the white-space character, (i.e., any character that returns `true` from a call to the `isspace` function). You can set the delimiter to a different character by specifying a `'delimiter'` parameter in the `textscan` command (see "User Configurable Options" on page 2-2264). If a nondefault delimiter is specified, repeated delimiter characters are treated as separate delimiters. When using the default delimiter, repeated white-space characters are treated as a single delimiter.

The default end-of-line character sequence depends on which operating system you are using. You can set end-of-line to a different character sequence by specifying an `'endofline'` parameter in the `textscan` command (see "User Configurable Options" on page 2-2264). If you set the `delimiter` parameter to `'EOL'` (using the third syntax shown above), `textscan` reads complete rows.

Conversion Specifiers

This table shows the conversion type specifiers supported by `textscan`.

Specifier	Description
`%n`	Read a number and convert to `double`.
`%d`	Read a number and convert to `int32`.
`%d8`	Read a number and convert to `int8`.
`%d16`	Read a number and convert to `int16`.
`%d32`	Read a number and convert to `int32`.
`%d64`	Read a number and convert to `int64`.
`%u`	Read a number and convert to `uint32`.
`%u8`	Read a number and convert to `int8`.
`%u16`	Read a number and convert to `int16`.
`%u32`	Read a number and convert to `int32`.
`%u64`	Read a number and convert to `int64`.
`%f`	Read a number and convert to `double`.
`%f32`	Read a number and convert to `single`.
`%f64`	Read a number and convert to `double`.
`%s`	Read a string.
`%q`	Read a (possibly double-quoted) string.
`%c`	Read one character, including white space.

Specifier	Description
`%[...]`	Read characters that match characters between the brackets. Stop reading at the first nonmatching character or white-space. Use `%[]...]` to include `]` in the set.
`%[^...]`	Read characters that do not match characters between the brackets. Stop reading at the first matching character or white-space. Use `%[^]...]` to exclude `]` from the set.

Specifying Field Length

To read a certain number of characters or digits from a field, specify that number directly following the percent sign. For example, if the file you are reading contains the string

```
'Blackbird singing in the dead of night'
```

then the following command returns only five characters of the first field:

```
C = textscan(fid, '%5s', 1);
C{:}
ans =
   'Black'
```

If you continue reading from the file, `textscan` resumes the operation at the point in the string where you left off. It applies the next format specifier to that portion of the field. For example, execute this command on the same file:

```
C = textscan(fid, '%s %s', 1);
```

Note Spaces between the conversion specifiers are shown only to make the example easier to read. They are not required.

`textscan` reads starting from where it left off and continues to the next whitespace, returning `'bird'`. The second `%s` reads the word `'singing'`.

The results are

```
C{:}
ans =
```

```
    'bird'
ans =
    'singing'
```

Skipping Fields

To skip any field, put an asterisk directly after the percent sign. MATLAB does not create an output cell for any fields that are skipped.

Refer to the example from the last section, where the file you are reading contains the string

```
'Blackbird singing in the dead of night'
```

Seek to the beginning of the file and then reread the line, this time skipping the second, fifth, and sixth fields:

```
fseek(fid, 0, -1);
C = textscan(fid, '%s %*s %s %s %*s %*s %s', 1);
```

C is a cell array of cell arrays, each containing a string. Piece together the string and display it:

```
str = '';
for k = 1:length(C)
   str = [str char(C{k}) ' '];
   if k == 4,  disp(str),  end
end

Blackbird in the night
```

Skipping Literal Strings

In addition to skipping entire fields, you can have `textscan` skip leading literal characters in a string. Reading a file containing the following data,

```
Sally    Level1  12.34
Joe      Level2  23.54
Bill     Level3  34.90
```

this command removes the substring `'Level'` from the output and converts the level number to a `uint8`:

```
C = textscan(fid, '%s Level%u8 %f');
```

This returns a cell array `C` with the second cell containing only the unsigned integers:

```
C{1} = {'Sally'; 'Joe'; 'Bill'}       class cell
C{2} = [1; 2; 3]                      class uint8
C{3} = [12.34; 23.54; 34.90]          class double
```

Specifying Numeric Field Length and Decimal Digits

With numeric fields, you can specify the number of digits to read in the same manner described for strings in the section "Specifying Field Length" on page 2-2258. The next example uses a file containing the line

```
'405.36801 551.94387 298.00752 141.90663'
```

This command returns the starting 7 digits of each number in the line. Note that the decimal point counts as a digit.

```
C = textscan(fid, '%7f32 %*n');
C{:} =
   [405.368; 551.943; 298.007; 141.906]
```

You can also control the number of digits that are read to the right of the decimal point for any numeric field of type `%f`, `%f32`, or `%f64`. The format specifier in this command uses a `%9.1` prefix to cause `textscan` to read the first 9 digits of each number, but only include 1 digit of the decimal value in the number it returns:

```
C = textscan(fid, '%9.1f32 %*n');
C{:} =
   [405.3; 551.9; 298.0; 141.9]
```

Conversion of Numeric Fields

This table shows how `textscan` interprets the numeric field specifiers.

Format Specifier	Action Taken
`%n`, `%d`, `%u`, `%f`, and variants thereof	Read to the first delimiter. Example: `%n` reads `'473.238 '` as `473.238`.
`%Nn`, `%Nd`, `%Nu`, `%Nf`, and variants thereof	Read `N` digits (counting a decimal point as a digit), or up to the first delimiter, whichever comes first. Example: `%5f32` reads `'473.238 '` as `473.2`.
Specifiers that start with `%N.Df`	Read `N` digits (counting a decimal point as a digit), or up to the first delimiter, whichever comes first. Return `D` decimal digits in the output. Example: `%7.2f` reads `'473.238 '` as `473.23`.

Conversion specifiers `%n`, `%d`, `%u`, `%f`, or any variant thereof (e.g., `%d16`) return a `K`-by-1 MATLAB numeric vector of the type indicated by the conversion specifier, where `K` is the number of times that specifier was found in the file. `textscan` converts the numeric fields from the field content to the output type according to the conversion specifier and MATLAB rules regarding overflow and truncation. `NaN`, `Inf`, and `-Inf` are converted according to applicable MATLAB rules.

`textscan` imports any complex number as a whole into a complex numeric field, converting the real and imaginary parts to the specified numeric type. Valid forms for a complex number are

Form	Example
`–<real>–<imag>i|j`	`5.7-3.1i`
`–<imag>i|j`	`-7j`

Embedded white-space in a complex number is invalid and is regarded as a field delimiter.

Conversion of Strings

This table shows how `textscan` interprets the string field specifiers.

Format Specifier	Action Taken
`%s` or `%q`	Read to the first delimiter. Example: `%s` reads `'summer '` as `'summer'`.
`%Ns` or `%Nq`	Read `N` characters, or to the first delimiter, whichever comes first. Example: `%3s` reads `'summer '` as `'sum'`.
`%[abc]`	Read up to the first character not specified within the brackets (i.e., read up to the first character that is not an `a`, `b`, or `c`). Example: `%[mus]` reads `'summer '` as `'summ'`.
`%N[abc]`	Read `N` characters, or up to the first character not specified within the brackets, whichever comes first. Example: `%2[mus]` reads `'summer '` as `'su'`.
`%[^abc]`	Read up to the first character that is specified within the brackets, (i.e., read up to the first occurrence of an `a`, `b`, or `c`). Example: `%[^xrg]` reads `'summer '` as `'summe'`.
`%N[^abc]`	Read `N` characters, or up to the first character that is specified within the brackets, whichever comes first. Example: `%2[^xrg]` reads `'summer '` as `'su'`.

Conversion specifiers `%s`, `%q`, `%[...]`, and `%[^...]` return a `K`-by-1 MATLAB cell vector of strings, where `K` is the number of times that specifier was found in the file. If you set the `delimiter` parameter to a non-white-space character, or set the `whitespace` parameter to `''`, `textscan` returns all characters in the string field, including white-space. Otherwise each string terminates at the beginning of white-space.

Conversion of Characters

This table shows how `textscan` interprets the character field specifiers.

Format Specifier	Action Taken
`%c`	Read one character. Example: `%c` reads `'Let's go!'` as `'L'`.
`%Nc`	Read `N` characters, including delimiter characters. Example: `%9c` reads `'Let's go!'` as `'Let's go!'`.

Conversion specifier `%Nc` returns a `K`-by-`N` MATLAB character array, where `K` is the number of times that specifier was found in the file. `textscan` returns all characters, including white-space but excluding the delimiter.

Conversion of Empty Fields

An empty field in the text file is defined by two adjacent delimiters indicating an empty set of characters, or, in all cases except `%c`, white-space. The empty field is returned as `NaN` by default, but is user definable. In addition, you may specify custom strings to be used as empty values, in *numeric fields only*. `textscan` does not examing nonnumeric fields for custom empty values. See "User Configurable Options" on page 2-2264.

Note MATLAB represents integer `NaN` as zero. If `textscan` reads an empty field that is assigned an integer format specifier (one that starts with `%d` or `%u`), it returns the empty value as zero rather than as `NaN`. (See the value returned in C{5} in "Example 6 — Using a Nondefault Empty Value".

User Configurable Options

This table shows the valid `param-value` options and their default values.

Parameter	Value	Default
`bufSize`	Maximum string length in bytes	`4095`
`commentStyle`	Symbol(s) designating text to be ignored (see “Values for commentStyle”, below)	None
`delimiter`	Delimiter characters	None
`emptyValue`	Empty cell value in delimited files	`NaN`
`endOfLine`	End-of-line character	Determined from the file
`expChars`	Exponent characters	`'eEdD'`
`headerLines`	Number of lines at beginning of file to skip	0
`returnOnError`	Behavior on failing to read or convert (1=`true` or 0)	`1`
`treatAsEmpty`	String(s) to be treated as an empty value. A single string or cell array of strings can be used.	None
`whitespace`	White-space characters	`' \b\t'`

Values for commentStyle

Possible values for the `commentStyle` parameter are

Value	Description	Example
Single string, `S`	Ignore any characters that follow string `S` and are on the same line.	`'%', '//'`
Cell array of two strings, `C`	Ignore any characters that lie between the opening and closing strings in `C`.	`{'/*', '*/'}, {'/%', '%/'}`

Examples

Example 1— Reading Different Types of Data

Text file `scan1.dat` contains data in the following form:

```
Sally  Level1 12.34 45 1.23e10 inf NaN Yes
Joe    Level2 23.54 60 9e19 -inf 0.001 No
Bill   Level3 34.90 12 2e5 10 100 No
```

Read each column into a variable:

```
fid = fopen('scan1.dat');
C = textscan(fid, '%s %s %f32 %d8 %u %f %f %s');
fclose(fid);
```

Note Spaces between the conversion specifiers are shown only to make the example easier to read. They are not required.

`textscan` returns a 1-by-8 cell array `C` with the following cells:

```
C{1} = {'Sally'; 'Joe'; 'Bill'}          class cell
C{2} = {'Level1'; 'Level2'; 'Level3'}    class cell
C{3} = [12.34; 23.54; 34.90]             class single
C{4} = [45; 60; 12]                      class int8
C{5} = [1.23e10; 9e19; 2e5]              class uint32
C{6} = [Inf; -Inf; 10]                   class double
C{7} = [NaN; 0.001; 100]                 class double
C{8} = {'Yes'; 'No'; 'No'}               class cell
```

Example 2 — Reading All But One Field

Read the file as a fixed-format file, skipping the third field:

```
fid = fopen('scan1.dat');
C = textscan(fid, '%7c %6s %*f %d8 %u %f %f %s');
fclose(fid);
```

`textscan` returns a 1-by-8 cell array `C` with the following cells:

```
C{1} = ['Sally  '; 'Joe    '; 'Bill   ']   class char
C{2} = {'Level1'; 'Level2'; 'Level3'}      class cell
C{3} = [45; 60; 12]                        class int8
C{4} = [1.23e10; 9e19; 2e5]                class uint32
C{5} = [Inf; -Inf; 10]                     class double
C{6} = [NaN; 0.001; 100]                   class double
C{7} = {'Yes'; 'No'; 'No'}                 class cell
```

Example 3 — Reading Only the First Field

Read the first column into a cell array, skipping the rest of the line:

```
fid = fopen('scan1.dat');
names = textscan(fid, '%s%*[^\n]');
fclose(fid);
```

`textscan` returns a 1-by-1 cell array `names`:

```
size(names)
ans =
     1     1
```

The one cell contains

```
names{1} = {'Sally'; 'Joe'; 'Bill'}       class cell
```

Example 4 — Removing a Literal String in the Output

The second `format` specifier in this example, `%sLevel`, tells `textscan` to read the second field from a line in the file, but to ignore the initial string `'Level'` within that field. All that is left of the field is a numeric digit. `textscan` assigns the next specifier, `%f`, to that digit, converting it to a `double`.

See `C{2}` in the results:

```
fid = fopen('scan1.dat');
```

```
C = textscan(fid, '%s Level%u8 %f32 %d8 %u %f %f %s');
fclose(fid);
```

`textscan` returns a 1-by-8 cell array, `C`, with cells

```
C{1} = {'Sally'; 'Joe'; 'Bill'}       class cell
C{2} = [1; 2; 3]                      class uint8
C{3} = [12.34; 23.54; 34.90]          class single
C{4} = [45; 60; 12]                   class int8
C{5} = [1.23e10; 9e19; 2e5]           class uint32
C{6} = [Inf; -Inf; 10]                class double
C{7} = [NaN; 0.001; 100]              class double
C{8} = {'Yes'; 'No'; 'No'}            class cell
```

Example 5 — Using a Nondefault Delimiter and White-Space

Read the M-file into a cell array of strings:

```
fid = fopen('fft.m');
file = textscan(fid, '%s', 'delimiter', '\n', 'whitespace', '');
fclose(fid);
```

`textscan` returns a 1-by-1 cell array, `file`, that contains a 37-by-1 cell array:

```
file =
    {37x1 cell}
```

Show the first three lines of the file:

```
lines = file{1};
lines{1:3, :}
ans =
    'function [varargout] = fft(varargin)'
ans =
    '%FFT Discrete Fourier transform.'
ans =
    '%   FFT(X) is the discrete Fourier transform (DFT) of vector
X.  For'
```

Example 6 — Using a Nondefault Empty Value

Read files with empty cells, setting the `emptyvalue` parameter. The file `data.csv` contains

```
1,  2,  3,  4,   ,  6
7,  8,  9,   , 11, 12
```

Read the file as shown here, using `-Inf` in empty cells:

```
fid = fopen('data.csv');
C = textscan(fid, '%f%f%f%f%u32%f', 'delimiter', ',', ...
             'emptyValue', -Inf);
fclose(fid);
```

`textscan` returns a 1-by-6 cell array `C` with the following cells:

```
C{1} = [1; 7]            class double
C{2} = [2; 8]            class double
C{3} = [3; 9]            class double
C{4} = [4; NaN]          class double
C{5} = [-Inf; 11]           class uint32 (-Inf converted to 0)
C{6} = [6; 12]           class double
```

Example 7 — Using Custom Empty Values and Comments

You have a file `data.csv` that contains the lines

```
abc, 2, NA, 3, 4
// Comment Here
def, na, 5, 6, 7
```

Designate what should be treated as empty values and as comments. Read in all other values from the file:

```
fid = fopen('data5.csv');
C = textscan(fid, '%s%n%n%n%n', 'delimiter', ',', ...
             'treatAsEmpty', {'NA', 'na'}, ...
             'commentStyle', '//');
fclose(fid);
```

This returns the following data in cell array `C`:

```
C{:}
ans =
    'abc'
    'def'
ans =
     2
   NaN
ans =
   NaN
     5
ans =
     3
     6
ans =
     4
     7
```

See Also

`dlmread`, `dlmwrite`, `xlswrite`, `fopen`, `importdata`

textwrap

Purpose

Return wrapped string matrix for given uicontrol

Syntax

```
outstring = textwrap(h,instring)
[outstring,position] = textwrap(h,instring)
```

Description

`outstring = textwrap(h,instring)` returns a wrapped string cell array, `outstring`, that fits inside the uicontrol with handle `h`. `instring` is a cell array, with each cell containing a single line of text. `outstring` is the wrapped string matrix in cell array format. Each cell of the input string is considered a paragraph.

`[outstring,position]=textwrap(h,instring)` returns the recommended position of the uicontrol in the units of the uicontrol. `position` considers the extent of the multiline text in the *x* and *y* directions.

Example

Place a text-wrapped string in a uicontrol:

```
pos = [10 10 100 10];
h = uicontrol('Style','Text','Position',pos);
string = {'This is a string for the uicontrol.',
          'It should be correctly wrapped inside.'};
[outstring,newpos] = textwrap(h,string);
pos(4) = newpos(4);
set(h,'String',outstring,'Position',[pos(1),pos(2),pos(3)+10,pos
(4)])
```

See Also

`uicontrol`

Purpose

Stopwatch timer

Syntax

```
tic
    any statements
toc
t = toc
```

Description

`tic` starts a stopwatch timer.

`toc` prints the elapsed time since `tic` was used.

`t = toc` returns the elapsed time in `t`.

Examples

This example measures how the time required to solve a linear system varies with the order of a matrix.

```
for n = 1:100
    A = rand(n,n);
    b = rand(n,1);
    tic
    x = A\b;
    t(n) = toc;
end
plot(t)
```

See Also

`clock`, `cputime`, `etime`, `profile`

timer

Purpose

Construct timer object

Syntax

```
T = timer
T = timer( PropertyName1', PropertyValue1, 'PropertyName2',
   PropertyValue2,...)
```

Description

`T = timer` constructs a timer object with default attributes.

`T = timer('PropertyName1', PropertyValue1, 'PropertyName2', PropertyValue2,...)` constructs a timer object in which the given property name/value pairs are set on the object. See "Timer Object Properties" on page 2-2272 for a list of all the properties supported by the timer object.

Note that the property name/property value pairs can be in any format supported by the `set` function, i.e., property/value string pairs, structures, and property/value cell array pairs.

Examples

This example constructs a timer object with a timer callback function handle, `mycallback`, and a 10 second interval.

```
t = timer('TimerFcn',@mycallback, 'Period', 10.0);
```

See Also

`delete`, `disp`, `get`, `isvalid`, `set`, `start`, `startat`, `stop`, `timerfind`, `timerfindall`, `wait`

Timer Object Properties

The timer object supports the following properties that control its attributes. The table includes information about the data type of each property and its default value.

To view the value of the properties of a particular timer object, use the `get` function. To set the value of the properties of a timer object, use the `set` function.

Property Name	Property Description	Data Types, Values, and Defaults	

`AveragePeriod`	The average time between `TimerFcn` executions since the timer started.
	Note: Value is `NaN` until timer executes two timer callbacks.
		Data type:
		Default:
		Read only:
			`double`
			`NaN`
			Always

`BusyMode`	Action taken when a timer has to execute `TimerFcn` before the completion of previous execution of `TimerFcn`.
	• `'drop'` — Do not execute the function.
	• `'error'` — Generate an error.
	• `'queue'` — Execute function at next opportunity.
		Data type:
		Values:
		
		Default:
		Read only:
			Enumerated string
			`'drop'`
			`'error'`
			`'queue'`
			`'drop'`
			While `Running = 'on'`

`ErrorFcn`	Function that the timer executes when an error occurs. This function executes before the `StopFcn`. See “Creating Timer Callback Functions” for more information.	Data type: Default: Read only:	Text string, function handle, or cell array None Never

`ExecutionMode`	Determines how the timer object schedules timer events. See “Timer Execution Modes” for more information.	Data type:
		Values:
		
		Default:
		Read only:
			Enumerated string
			`'singleShot'`
			`'fixedDelay'`
			`'fixedRate'`
			`'fixedSpacing`
			`'singleShot'`
			While `Running = 'on'`

Property Name	Property Description	Data Types, Values, and Defaults	

`InstantPeriod`	The time between the last two executions of `TimerFcn`.	Data type:
		Default:
		Read only:
			`double`
			`NaN`
			`Always`

`Name`	User-supplied name	Data type: Default: Read only:	Text string `'timer-`*`i`*`'`, where *`i`* is a number indicating the `i`th timer object created this session. To reset *`i`* to 1, execute the `clear classes` command. Never

`ObjectVisibility`	Provides a way for application developers to prevent end-user access to the timer objects created by their application. The `timerfind` function does not return an object whose `ObjectVisibility` property is set to `'off'`. Objects that are not visible are still valid. If you have access to the object (for example, from within the M-file that created it), you can set its properties.	Data type:
		Values:
		
		Default:
		Read only:
			Enumerated string
			`'off'`
			`'on'`
			`'on'`
			Never

`Period`	Specifies the delay, in seconds, between executions of `TimerFcn`.	Data type: Value: Default: Read only:	`double` Any number > 0.001 1.0 While `Running = 'on'`

Property Name	Property Description	Data Types, Values, and Defaults	

`Running`	Indicates whether the timer is currently executing.	Data type:
		Values:
		
		Default:
		Read only:
			Enumerated string
			`'off'`
			`'on'`
			`'off'`
			Always

`StartDelay`	Specifies the delay, in seconds, between the start of the timer and the first execution of the function specified in `TimerFcn`.	Data type: Value: Default: Read only:	`double` Any number >= 0 0 While `Running` `='on'`
`StartFcn`	Function the timer calls when it starts. See "Creating Timer Callback Functions" for more information.	Data type: Default: Read only:	Text string, function handle, or cell array None Never
`StopFcn`	Function the timer calls when it stops. The timer stops when • You call the timer `stop` function • The timer finishes executing `TimerFcn`, i.e., the value of `TasksExecuted` reaches the limit set by `TasksToExecute`. • An error occurs (The `ErrorFcn` is called first, followed by the `StopFcn`.) See "Creating Timer Callback Functions" for more information.	Data type: Default: Read only:	Text string, function handle, or cell array None Never
`Tag`	User supplied label	Data type: Default: Read only:	Text string `''`(empty string) Never

Property Name	Property Description	Data Types, Values, and Defaults	
`TasksToExecute`	Specifies the number of times the timer should execute the function specified in the `TimerFcn` property.	Data type: Value: Default Read only:	`double` Any number > 0 1 Never
`TasksExecuted`	The number of times the timer has executed `TimerFcn` since the timer was started.	Data type: Value: Default: Read only:	`double` Any number >= 0 0 Always
`TimerFcn`	Timer callback function. See “Creating Timer Callback Functions” for more information.	Data type: Default: Read only:	Text string, function handle, or cell array None Never
`Type`	Identifies the object type	Data type: Value: Read only:	Text string `'timer'` Always
`UserData`	User-supplied data	Data type: Default: Read only:	User-defined `[]` Never

Purpose

Find timer objects

Syntax

```
out = timerfind
out = timerfind('P1', V1, 'P2', V2,...)
out = timerfind(S)
out = timerfind(obj, 'P1', V1, 'P2', V2,...)
```

Description

`out = timerfind` returns an array, `out`, of all the timer objects that exist in memory.

`out = timerfind('P1', V1, 'P2', V2,...)` returns an array, `out`, of timer objects whose property values match those passed as parameter/value pairs, `P1`, `V1`, `P2`, `V2`. Parameter/value pairs may be specified as a cell array.

`out = timerfind(S)` returns an array, `out`, of timer objects whose property values match those defined in the structure, `S`. The field names of `S` are timer object property names and the field values are the corresponding property values.

`out = timerfind(obj, 'P1', V1, 'P2', V2,...)` restricts the search for matching parameter/value pairs to the timer objects listed in `obj`. `obj` can be an array of timer objects.

Note When specifying parameter/value pairs, you can use any mixture of strings, structures, and cell arrays in the same call to `timerfind`.

Note that, for most properties, `timerfind` performs case-sensitive searches of property values. For example, if the value of an object's `Name` property is `'MyObject'`, `timerfind` will not find a match if you specify `'myobject'`. Use the `get` function to determine the exact format of a property value. However, properties that have an enumerated list of possible values are not case sensitive. For example, `timerfind` will find an object with an `ExecutionMode` property value of `'singleShot'` or `'singleshot'`.

Examples

These examples use `timerfind` to find timer objects with the specified property values.

```
t1 = timer('Tag', 'broadcastProgress', 'Period', 5);
t2 = timer('Tag', 'displayProgress');
out1 = timerfind('Tag', 'displayProgress')
out2 = timerfind({'Period', 'Tag'}, {5, 'broadcastProgress'})
```

See Also

get, timer, timerfindall

Purpose

Find timer objects, including invisible objects

Syntax

```
out = timerfindall
out = timerfindall('P1', V1, 'P2', V2,...)
out = timerfindall(S)
out = timerfindall(obj, 'P1', V1, 'P2', V2,...)
```

Description

`out = timerfindall` returns an array, `out`, containing all the timer objects that exist in memory, regardless of the value of the object's `ObjectVisibility` property.

`out = timerfindall('P1', V1, 'P2', V2,...)` returns an array, `out`, of timer objects whose property values match those passed as parameter/value pairs, `P1`, `V1`, `P2`, `V2`. Parameter/value pairs may be specified as a cell array.

`out = timerfindall(S)` returns an array, `out`, of timer objects whose property values match those defined in the structure, `S`. The field names of `S` are timer object property names and the field values are the corresponding property values.

`out = timerfindall(obj, 'P1', V1, 'P2', V2,...)` restricts the search for matching parameter/value pairs to the timer objects listed in `obj`. `obj` can be an array of timer objects.

Note When specifying parameter/value pairs, you can use any mixture of strings, structures, and cell arrays in the same call to `timerfindall`.

Note that, for most properties, `timerfindall` performs case-sensitive searches of property values. For example, if the value of an object's `Name` property is `'MyObject'`, `timerfindall` will not find a match if you specify `'myobject'`. Use the `get` function to determine the exact format of a property value. However, properties that have an enumerated list of possible values are not case sensitive. For example, `timerfindall` will find an object with an `ExecutionMode` property value of `'singleShot'` or `'singleshot'`.

Examples

Create several timer objects.

```
t1 = timer;
t2 = timer;
t3 = timer;
```

Set the `ObjectVisibility` property of one of the objects to `'off'`.

```
t2.ObjectVisibility = 'off';
```

Use `timerfind` to get a listing of all the timer objects in memory. Note that the listing does not include the timer object (`timer-2`) whose `ObjectVisibility` property is set to `'off'`.

```
timerfind

Timer Object Array

   Index:  ExecutionMode:  Period:  TimerFcn:   Name:
   1       singleShot      1        ''          timer-1
   2       singleShot      1        ''          timer-3
```

Use `timerfindall` to get a listing of all the timer objects in memory. This listing includes the timer object whose `ObjectVisibility` property is set to `'off'`.

```
timerfindall

Timer Object Array

   Index:  ExecutionMode:  Period:  TimerFcn:   Name:
   1       singleShot      1        ''          timer-1
   2       singleShot      1        ''          timer-2
   3       singleShot      1        ''          timer-3
```

See Also

`get`, `timer`, `timerfind`

Purpose

Add title to current axes

Syntax

```
title('string')
title(fname)
title(...,'PropertyName',PropertyValue,...)
h = title(...)
```

Description

Each axes graphics object can have one title. The title is located at the top and in the center of the axes.

`title('string')` outputs the string at the top and in the center of the current axes.

`title(fname)` evaluates the function that returns a string and displays the string at the top and in the center of the current axes.

`title(...,'PropertyName',PropertyValue,...)` specifies property name and property value pairs for the text graphics object that `title` creates.

`h = title(...)` returns the handle to the text object used as the title.

Examples

Display today's date in the current axes:

```
title(date)
```

Include a variable's value in a title:

```
f = 70;
c = (f 32)/1.8;
title(['Temperature is ',num2str(c),'C'])
```

Include a variable's value in a title and set the color of the title to yellow:

```
n = 3;
title(['Case number #',int2str(n)],'Color','y')
```

Include Greek symbols in a title:

```
title('\ite^{\omega\tau} = cos(\omega\tau) + isin(\omega\tau)')
```

Include a superscript character in a title:

```
title('\alpha^2')
```

Include a subscript character in a title:

```
title('X_1')
```

The text object `String` property lists the available symbols.

Create a multiline title using a multiline cell array.

```
title({'First line';'Second line'})
```

Remarks

`title` sets the `Title` property of the current axes graphics object to a new text graphics object. See the text `String` property for more information.

See Also

`gtext`, `int2str`, `num2str`, `text`, `xlabel`, `ylabel`, `zlabel`

"Annotating Plots" for related functions

Adding Titles to Graphs for more information on ways to add titles

Purpose

Convert CDF epoch object to MATLAB datenum

Syntax

```
n = todatenum(ep_obj)
```

Description

`n = todatenum(obj)` converts the CDF epoch object `ep_obj` into a MATLAB serial date number. Note that a CDF epoch is the number of milliseconds since `01-Jan-0000` whereas a MATLAB datenum is the number of days since `00-Jan-0000`.

Examples

Construct a CDF epoch object from a date string, and then convert the object back into a MATLAB date string:

```
dstr = datestr(today)
dstr =
   08-Oct-2003

obj = cdfepoch(dstr)
obj =
     cdfepoch object:
     08-Oct-2003 00:00:00

dstr2 = datestr(todatenum(obj))
dstr2 =
   08-Oct-2003
```

See Also

`cdfepoch`, `cdfinfo`, `cdfread`, `cdfwrite`, `datenum`

toeplitz

Purpose

Toeplitz matrix

Syntax

```
T = toeplitz(c,r)
T = toeplitz(r)
```

Description

A *Toeplitz* matrix is defined by one row and one column. A *symmetric Toeplitz* matrix is defined by just one row. `toeplitz` generates Toeplitz matrices given just the row or row and column description.

`T = toeplitz(c,r)` returns a nonsymmetric Toeplitz matrix `T` having `c` as its first column and `r` as its first row. If the first elements of `c` and `r` are different, a message is printed and the column element is used.

`T = toeplitz(r)` returns the symmetric or Hermitian Toeplitz matrix formed from vector `r`, where `r` defines the first row of the matrix.

Examples

A Toeplitz matrix with diagonal disagreement is

```
c = [1  2  3  4  5];
r = [1.5  2.5  3.5  4.5  5.5];
toeplitz(c,r)
Column wins diagonal conflict:
ans =
    1.000    2.500    3.500    4.500    5.500
    2.000    1.000    2.500    3.500    4.500
    3.000    2.000    1.000    2.500    3.500
    4.000    3.000    2.000    1.000    2.500
    5.000    4.000    3.000    2.000    1.000
```

See Also

`hankel`

Purpose

Sum of diagonal elements

Syntax

```
b = trace(A)
```

Description

`b = trace(A)` is the sum of the diagonal elements of the matrix `A`.

Algorithm

`trace` is a single-statement M-file.

```
t = sum(diag(A));
```

See Also

`det`, `eig`

trapz

Purpose

Trapezoidal numerical integration

Syntax

```
Z = trapz(Y)
Z = trapz(X,Y)
Z = trapz(...,dim)
```

Description

`Z = trapz(Y)` computes an approximation of the integral of `Y` via the trapezoidal method (with unit spacing). To compute the integral for spacing other than one, multiply `Z` by the spacing increment.

If `Y` is a vector, `trapz(Y)` is the integral of `Y`.

If `Y` is a matrix,`trapz(Y)` is a row vector with the integral over each column.

If `Y` is a multidimensional array, `trapz(Y)` works across the first nonsingleton dimension.

`Z = trapz(X,Y)` computes the integral of `Y` with respect to `X` using trapezoidal integration.

If `X` is a column vector and `Y` an array whose first nonsingleton dimension is `length(X)`, `trapz(X,Y)` operates across this dimension.

`Z = trapz(...,dim)` integrates across the dimension of `Y` specified by scalar `dim`. The length of `X`, if given, must be the same as `size(Y,dim)`.

Examples

The exact value of is 2.

To approximate this numerically on a uniformly spaced grid, use

```
X = 0:pi/100:pi;
Y = sin(x);
```

Then both

```
Z = trapz(X,Y)
```

and

```
Z = pi/100*trapz(Y)
```

produce

```
Z =
    1.9998
```

A nonuniformly spaced example is generated by

```
X = sort(rand(1,101)*pi);
Y = sin(X);
Z = trapz(X,Y);
```

The result is not as accurate as the uniformly spaced grid. One random sample produced

```
Z =
    1.9984
```

See Also

`cumsum`, `cumtrapz`

treelayout

Purpose

Lay out tree or forest

Syntax

```
[x,y] = treelayout(parent,post)
[x,y,h,s] = treelayout(parent,post)
```

Description

`[x,y] = treelayout(parent,post)` lays out a tree or a forest. `parent` is the vector of parent pointers, with `0` for a root. `post` is an optional postorder permutation on the tree nodes. If you omit `post`, `treelayout` computes it. `x` and `y` are vectors of coordinates in the unit square at which to lay out the nodes of the tree to make a nice picture.

`[x,y,h,s] = treelayout(parent,post)` also returns the height of the tree `h` and the number of vertices `s` in the top-level separator.

See Also

`etree`, `treeplot`, `etreeplot`, `symbfact`

Purpose

Plot picture of tree

Syntax

```
treeplot(p)
treeplot(p,nodeSpec,edgeSpec)
```

Description

`treeplot(p)` plots a picture of a tree given a vector of parent pointers, with `p(i)` = 0 for a root.

`treeplot(p,nodeSpec,edgeSpec)` allows optional parameters `nodeSpec` and `edgeSpec` to set the node or edge color, marker, and linestyle. Use `''` to omit one or both.

See Also

`etree`, `etreeplot`, `treelayout`

tril

Purpose

Lower triangular part of a matrix

Syntax

```
L = tril(X)
L = tril(X,k)
```

Description

`L = tril(X)` returns the lower triangular part of `X`.

`L = tril(X,k)` returns the elements on and below the kth diagonal of `X`. `k = 0` is the main diagonal, `k > 0` is above the main diagonal, and `k < 0` is below the main diagonal.

Examples

```
tril(ones(4,4),-1)

ans =

     0     0     0     0
     1     0     0     0
     1     1     0     0
     1     1     1     0
```

See Also

`diag`, `triu`

Purpose

Triangular mesh plot

Syntax

```
trimesh(Tri,X,Y,Z)
trimesh(Tri,X,Y,Z,C)
trimesh(...'PropertyName',PropertyValue...)
h = trimesh(...)
```

Description

`trimesh(Tri,X,Y,Z)` displays triangles defined in the *m*-by-3 face matrix `Tri` as a mesh. Each row of `Tri` defines a single triangular face by indexing into the vectors or matrices that contain the `X`, `Y`, and `Z` vertices.

`trimesh(Tri,X,Y,Z,C)` specifies color defined by `C` in the same manner as the `surf` function. MATLAB performs a linear transformation on this data to obtain colors from the current colormap.

`trimesh(...'PropertyName',PropertyValue...)` specifies additional patch property names and values for the patch graphics object created by the function.

`h = trimesh(...)` returns a handle to a patch graphics object.

Example

Create vertex vectors and a face matrix, then create a triangular mesh plot.

```
x = rand(1,50);
y = rand(1,50);
z = peaks(6*x 3,6*x 3);
tri = delaunay(x,y);
trimesh(tri,x,y,z)
```

See Also

`patch`, `tetramesh`, `triplot`, `trisurf`, `delaunay`

"Creating Surfaces and Meshes" for related functions

triplequad

Purpose

Numerically evaluate triple integral

Syntax

```
triplequad(fun,xmin,xmax,ymin,ymax,zmin,zmax)
triplequad(fun,xmin,xmax,ymin,ymax,zmin,zmax,tol)
triplequad(fun,xmin,xmax,ymin,ymax,zmin,zmax,tol,method)
```

Description

`triplequad(fun,xmin,xmax,ymin,ymax,zmin,zmax)` evaluates the triple integral `fun(x,y,z)` over the three dimensional rectangular region `xmin <= x <= xmax`, `ymin <= y <= ymax`, `zmin <= z <= zmax`. `fun` is a function handle for either an M-file function or an anonymous function. `fun(x,y,z)` must accept a vector `x` and scalars `y` and `z`, and return a vector of values of the integrand.

Parameterizing Functions Called by Function Functions, in the online MATLAB documentation, explains how to provide addition parameters to the function `fun`, if necessary.

`triplequad(fun,xmin,xmax,ymin,ymax,zmin,zmax,tol)` uses a tolerance `tol` instead of the default, which is `1.0e-6`.

`triplequad(fun,xmin,xmax,ymin,ymax,zmin,zmax,tol,method)` uses the quadrature function specified as `method`, instead of the default `quad`. Valid values for `method` are `@quadl` or the function handle of a user-defined quadrature method that has the same calling sequence as `quad` and `quadl`.

Examples

Pass M-file function handle `@integrnd` to `triplequad`:

```
Q = triplequad(@integrnd,0,pi,0,1,-1,1);
```

where the M-file `integrnd.m` is

```
function f = integrnd(x,y,z)
f = y*sin(x)+z*cos(x);
```

Pass anonymous function handle `F` to `triplequad`:

```
F = @(x,y,z)y*sin(x)+z*cos(x);
Q = triplequad(F,0,pi,0,1,-1,1);
```

This example integrates `y*sin(x)+z*cos(x)` over the region `0 <= x <= pi`, `0 <= y <= 1`, `-1 <= z <= 1`. Note that the integrand can be evaluated with a vector `x` and scalars `y` and `z`.

See Also `dblquad`, `quad`, `quadl`, `@` (function handle), anonymous functions

triplot

Purpose

2-D triangular plot

Syntax

```
triplot(TRI,x,y)
triplot(TRI,x,y,color)
h = triplot(...)
triplot(...,'param','value','param','value'...)
```

Description

`triplot(TRI,x,y)` displays the triangles defined in the `m`-by-3 matrix `TRI`. A row of `TRI` contains indices into the vectors `x` and `y` that define a single triangle. The default line color is blue.

`triplot(TRI,x,y,color)` uses the string `color` as the line color. `color` can also be a line specification. See `ColorSpec` for a list of valid color strings. See `LineSpec` for information about line specifications.

`h = triplot(...)` returns a vector of handles to the displayed triangles.

`triplot(...,'param','value','param','value'...)` allows additional line property name/property value pairs to be used when creating the plot. See `Line Properties` for information about the available properties.

Examples

This code plots the Delaunay triangulation for 10 randomly generated points.

```
rand('state',7);
x = rand(1,10);
y = rand(1,10);
TRI = delaunay(x,y);
triplot(TRI,x,y,'red')
```

See Also

`ColorSpec`, `delaunay`, `line`, `Line Properties`, `LineSpec`, `plot`, `trimesh`, `trisurf`

Purpose

Triangular surface plot

Syntax

```
trisurf(Tri,X,Y,Z)
trisurf(Tri,X,Y,Z,C)
trisurf(...'PropertyName',PropertyValue...)
h = trisurf(...)
```

Description

`trisurf(Tri,X,Y,Z)` displays triangles defined in the *m*-by-3 face matrix `Tri` as a surface. Each row of `Tri` defines a single triangular face by indexing into the vectors or matrices that contain the `X`, `Y`, and `Z` vertices.

`trisurf(Tri,X,Y,Z,C)` specifies color defined by `C` in the same manner as the `surf` function. MATLAB performs a linear transformation on this data to obtain colors from the current colormap.

`trisurf(...'PropertyName',PropertyValue...)` specifies additional patch property names and values for the patch graphics object created by the function.

`h = trisurf(...)` returns a patch handle.

Example

Create vertex vectors and a face matrix, then create a triangular surface plot.

```
x = rand(1,50);
y = rand(1,50);
z = peaks(6*x 3,6*x 3);
tri = delaunay(x,y);
trisurf(tri,x,y,z)
```

See Also

`patch`, `surf`, `tetramesh`, `trimesh`, `triplot`, `delaunay`

"Creating Surfaces and Meshes" for related functions

triu

Purpose

Upper triangular part of a matrix

Syntax

```
U = triu(X)
U = triu(X,k)
```

Description

`U = triu(X)` returns the upper triangular part of `X`.

`U = triu(X,k)` returns the element on and above the kth diagonal of `X`. `k = 0` is the main diagonal, `k > 0` is above the main diagonal, and `k < 0` is below the main diagonal.

Examples

```
triu(ones(4,4),-1)

ans =

     1     1     1     1
     1     1     1     1
     0     1     1     1
     0     0     1     1
```

See Also

`diag`, `tril`

Purpose

True array

Syntax

```
true
true(n)
true(m, n)
true(m, n, p, ...)
true(size(A))
```

Description

`true` is shorthand for `logical 1`.

`true(n)` is an `n`-by-`n` matrix of logical ones.

`true(m, n)` or `true([m, n])` is an `m`-by-`n` matrix of logical ones.

`true(m, n, p, ...)` or `true([m n p ...])` is an `m`-by-`n`-by-`p`-by-`...` array of logical ones.

`true(size(A))` is an array of logical ones that is the same size as array `A`.

Remarks

`true(n)` is much faster and more memory efficient than `logical(ones(n))`.

See Also

`false`, `logical`

try

Purpose

Begin `try` block

Description

The general form of a `try` statement is

```
try,
   statement,
   ...,
   statement,
catch,
   statement,
   ...,
   statement,
end
```

Normally, only the statements between the `try` and `catch` are executed. However, if an error occurs during execution of any of the statements, the error is captured into `lasterr`, and the statements between the `catch` and `end` are executed. If an error occurs within the `catch` statements, execution stops unless caught by another `try...catch` block. The error string produced by a failed `try` block can be obtained with `lasterr`.

See Also

`catch`, `end`, `lasterr`, `eval`, `evalin`

Purpose

Search for enclosing Delaunay triangle

Syntax

```
T = tsearch(x,y,TRI,xi,yi)
```

Description

`T = tsearch(x,y,TRI,xi,yi)` returns an index into the rows of `TRI` for each point in `xi`, `yi`. The `tsearch` command returns `NaN` for all points outside the convex hull. Requires a triangulation `TRI` of the points `x`,`y` obtained from `delaunay`.

See Also

`delaunay`, `delaunayn`, `dsearch`, `tsearchn`

tsearchn

Purpose

N-dimensional closest simplex search

Syntax

```
t = tsearchn(X,TES,XI)
[t,P] = tsearchn(X,TES,XI)
```

Description

`t = tsearchn(X,TES,XI)` returns the indices `t` of the enclosing simplex of the Delaunay tessellation `TES` for each point in `XI`. `X` is an `m`-by-`n` matrix, representing `m` points in N-dimensional space. `XI` is a `p`-by-`n` matrix, representing `p` points in N-dimensional space. `tsearchn` returns `NaN` for all points outside the convex hull of `X`. `tsearchn` requires a tessellation `TES` of the points `X` obtained from `delaunayn`.

`[t,P] = tsearchn(X,TES,XI)` also returns the barycentric coordinate `P` of `XI` in the simplex `TES`. `P` is a `p`-by-`n+1` matrix. Each row of `P` is the Barencentric coordinate of the corresponding point in `XI`. It is useful for interpolation.

See Also

`delaunayn`, `griddatan`, `tsearch`

2uibuttongroup

Purpose

Container object to exclusively manage radio buttons and toggle buttons

Syntax

```
uibuttongroup('PropertyName1',Value1,'PropertyName2',Value2,...)
handle = uibuttongroup(...)
```

Description

A uibuttongroup groups components and manages exclusive selection behavior for radio buttons and toggle buttons that it contains. It can also contain other user interface controls, axes, uipanels, and uibuttongroups. It cannot contain ActiveX controls.

`uibuttongroup('PropertyName1',Value1,'PropertyName2',Value2,...)` creates a visible container component in the current figure window. This component manages exclusive selection behavior for uicontrols of style `radiobutton` and `togglebutton`.

Use the `Parent` property to specify the parent as a figure, uipanel, or uibuttongroup. If you do not specify a parent, `uibuttongroup` adds the button group to the current figure. If no figure exists, one is created.

A `uibuttongroup` object can have `axes`, `uicontrol`, `uipanel`, and `uibuttongroup` objects as children. However, only uicontrols of style `radiobutton` and `togglebutton` are managed by the component.

For the children of a `uibuttongroup` object, the `Position` property is interpreted relative to the button group. If you move the button group, the children automatically move with it and maintain their positions in the button group.

Note Include code for uicontrols of style `radiobutton` and `togglebutton` that are managed by a uibuttongroup in the `SelectionChangeFcn` callback function, not in the individual uicontrol `Callback` functions. `uibuttongroup` overwrites the `Callback` properties of radio buttons and toggle buttons that it manages. See the `SelectionChangeFcn` property and the example on this reference page for more information.

`handle = uibuttongroup(...)` creates a uibuttongroup object and returns a handle to it in `handle`.

After creating a uibuttongroup, you can set and query its property values using `set` and `get`. Run `get(handle)` to see a list of properties and their current values. Run `set(handle)` to see a list of object properties you can set and their legal values.

Properties

This table lists all properties useful to `uibuttongroup` objects, grouping them by function. Each property name acts as a link to a description of the property. Curly braces denote the default value, if any.

Property Name	Description	Property Value
Controlling Style and Appearance		
`BackgroundColor`	Color of the uibuttongroup background	`ColorSpec`. Default is the same as the default uicontrol background.
`BorderType`	Type of border around the uibuttongroup area.	`[ none | {etchedin} | etchedout | beveledin | beveledout | line ]`
`BorderWidth`	Width in pixels of the button group border.	Integer. Default is `1`.
`Clipping`	Clipping of child axes, uipanels, and uibuttongroups to the uibuttongroup. Does not affect child uicontrols.	`[{on}|off]`
`ForegroundColor`	Title font color and color of 2-D border line	`ColorSpec`. Default is `[0 0 0]` (black).
`HighlightColor`	3-D frame highlight color	`ColorSpec`. Default is `[1 1 1]` (white).
`SelectionHighlight`	Object highlighted when selected	`[{on}|off]`
`ShadowColor`	3-D frame shadow color	`ColorSpec`. Default is `[.5 .5 .5]` (grey).

Property Name	Description	Property Value
`Visible`	Uibuttongroup visibility. Note: Controls the `Visible` property of child axes, uipanels, and uibuttongroups. Does not affect child uicontrols.	`[{on}|off]`
General Information About the Object		
`Children`	All children of the `uibuttongroup` object	Vector of handles
`Parent`	`uibuttongroup` object's parent	Scalar figure, uipanel, or uibuttongroup handle
`Selected`	Whether object is selected	`[on|{off}]`
`SelectedObject`	Currently selected radio button or toggle button	Scalar handle. Default is the first uicontrol radio button or toggle button added. Set to `[]` for no selection.
`Tag`	User-specified object identifier	String
`UserData`	User-specified data	Matrix
Controlling the Object Position		
`Position`	Button group position relative to parent figure, panel, or button group	Position spec `[x y w h]`. Default is `[0 0 1 1]`
`Units`	Units used to interpret the position vector	`[inches|centimeters|{normalized}|points|pixels|characters]`

Property Name	Description	Property Value
Controlling Fonts and Labels		
`FontAngle`	Title font angle	`[{normal}|italic|oblique]`
`FontName`	Title font name	String. Default is system dependent.
`FontSize`	Title font size	Integer. Default is system dependent.
`FontUnits`	Title font units	`[inches|centimeters|normalized|{points}|pixels]`
`FontWeight`	Title font weight	`[light|{normal}|demi|bold]`
`Title`	Title string	String
`TitlePosition`	Location of title string in relation to the button group	`[{lefttop}|centertop|righttop|leftbottom|centerbottom|rightbottom]`
Controlling Callback Routine Execution		
`BusyAction`	Interruption of other callback routines	`[{queue}|cancel]`
`ButtonDownFcn`	Button-press callback routine	String or function handle
`CreateFcn`	Callback routine executed during object creation	String or function handle
`DeleteFcn`	Callback routine executed during object deletion	String or function handle
`Interruptible`	Callback routine interruption mode	`[{on}|off]`

Property Name	Description	Property Value
`ResizeFcn`	User-specified resize routine	String or function handle
`SelectionChangeFcn`	Callback routine executed when the selected radio button or toggle button changes.	String or function handle
`UIContextMenu`	Associates a uicontextmenu with the uibuttongroup	Scalar handle
Controlling Access to Objects		
`HandleVisibility`	Handle accessibility from commandline and GUIs	`[{on}|callback|off]`
`HitTest`	Selectable by mouse click	`[{on}|off]`

Examples

This example creates a uibuttongroup with three radiobuttons. It manages the radiobuttons with the `SelectionChangeFcn` callback, `selcbk`.

When you select a new radio button, `selcbk` displays the uibuttongroup handle on one line, the `EventName`, `OldValue`, and `NewValue` fields of the event data structure on a second line, and the value of the `SelectedObject` property on a third line.

```
h = uibuttongroup('visible','off','Position',[0 0 .2 1]);
u0 = uicontrol('Style','Radio','String','Option 1',...
    'pos',[10 350 100 30],'parent',h,'HandleVisibility','off');
u1 = uicontrol('Style','Radio','String','Option 2',...
    'pos',[10 250 100 30],'parent',h,'HandleVisibility','off');
u2 = uicontrol('Style','Radio','String','Option 3',...
    'pos',[10 150 100 30],'parent',h,'HandleVisibility','off');
set(h,'SelectionChangeFcn',@selcbk);
set(h,'SelectedObject',[]);  % No selection
set(h,'Visible','on');
```

For the `SelectionChangeFcn` callback, `selcbk`, the source and event data structure arguments are available only if `selcbk` is called using a function handle. See `SelectionChangeFcn` for more information.

```
function selcbk(source,eventdata)
disp(source);
disp([eventdata.EventName,'  ',...
     get(eventdata.OldValue,'String'),'  ', ...
     get(eventdata.NewValue,'String')]);
disp(get(get(source,'SelectedObject'),'String'));
```



If you click `Option 2` with no option selected, the `SelectionChangeFcn` callback, `selcbk`, displays:

```
     3.0011

SelectionChanged    Option 2
Option 2
```

If you then click `Option 1`, the `SelectionChangeFcn` callback, `selcbk`, displays:

```
      3.0011

  SelectionChanged  Option 2  Option 1
  Option 1
```

See Also

`uicontrol`, `uipanel`

Uibuttongroup Properties

Modifying Properties

You can set and query graphics object properties in two ways:

- The Property Inspector is an interactive tool that enables you to see and change object property values. The Property inspector is available from GUIDE, or use the `inspect` function at the command line.
- The `set` and `get` functions enable you to set and query the values of properties.

Uibuttongroup takes its default property values from uipanel. To set a uibuttongroup default property value, set the default for the corresponding `uipanel` property. Note that you can set no default values for the uibuttongroup `SelectedObject` and `SelectionChangeFcn` properties.

For more information about changing the default value of a property see Setting Default Property Values. For an example, see the `CreateFcn` property.

Uibuttongroup Properties

This section describes all properties useful to `uibuttongroup` objects and lists valid values. Curly braces { } enclose default values.

Property Name	Description
`BackgroundColor`	Color of the uibuttongroup background
`BorderType`	Type of border around the uibuttongroup area.
`BorderWidth`	Width of the button group border in pixels.
`BusyAction`	Interruption of other callback routines
`ButtonDownFcn`	Button-press callback routine
`Children`	All children of the uibuttongroup
`Clipping`	Clipping of child axes, uipanels, and uibuttongroups to the uibuttongroup. Does not affect child uicontrols.
`CreateFcn`	Callback routine executed during object creation
`DeleteFcn`	Callback routine executed during object deletion
`FontAngle`	Title font angle

Property Name	Description
FontName	Title font name
FontSize	Title font size
FontUnits	Title font units
FontWeight	Title font weight
ForegroundColor	Title font color and color of 2-D border line
HandleVisibility	Handle accessibility from command line and GUIs
HighlightColor	3-D frame highlight color
HitTest	Selectable by mouse click
Interruptible	Callback routine interruption mode
Parent	uibuttongroup object's parent
Position	Uibuttongroup position relative to parent figure, uipanel, or uibuttongroup
ResizeFcn	User-specified resize routine
Selected	Whether object is selected
SelectedObject	Currently selected uicontrol of style radiobutton or togglebutton
SelectionChangeFcn	Callback routine executed when the selected radio button or toggle button changes.
SelectionHighlight	Object highlighted when selected
ShadowColor	3-D frame shadow color
Tag	User-specified object identifier
Title	Title string
TitlePosition	Location of title string in relation to the button group
UIContextMenu	Associates uicontext menu with the uibuttongroup

Property Name	Description
Units	Units used to interpret the position vector
UserData	User-specified data
Visible	Uibuttongroup visibility. Note: Controls the Visible property of child axes, uipanels, and uibuttongroups. Does not affect child uicontrols.

BackgroundColor ColorSpec

Color of the uibuttongroup background. A three-element RGB vector or one of the MATLAB predefined names, specifying the background color. See the ColorSpec reference page for more information on specifying color.

BorderType none | {etchedin} | etchedout | beveledin | beveledout | line

Border of the uibuttongroup area. Used to define the button group area graphically. Etched and beveled borders provide a 3-D look. Use the HighlightColor and ShadowColor properties to specify the border color of etched and beveled borders. A line border is 2-D. Use the ForegroundColor property to specify its color.

BorderWidth integer

Width of the button group border. The width of the button group borders in pixels. The default border width is 1 pixel. 3-D borders wider than 3 may not appear correctly at the corners.

BusyAction cancel | {queue}

Callback routine interruption. If a callback is executing and the user triggers an event (such as a mouse click) on an object for which a callback is defined, the callback associated with the new event uses the value of BusyAction to decide whether or not to attempt to interrupt the executing callback.

- If the value is cancel, the event is discarded and the second callback does not execute.
- If the value is queue, and the Interruptible property of the first callback is on, the second callback is added to the event queue and executes in its turn after the first callback finishes execution.

Note If the interrupting callback is a `DeleteFcn` or `CreateFcn` callback or a figure's `CloseRequest` or `ResizeFcn` callback, it interrupts an executing callback regardless of the value of that object's `Interruptible` property. See the `Interruptible` property for information about controlling a callback's interruptibility.

`ButtonDownFcn` string or function handle

Button-press callback routine. A callback routine that executes when you press a mouse button while the pointer is in a 5-pixel wide border around the uibuttongroup. This is useful for implementing actions to interactively modify object properties, such as size and position, when they are clicked on (using the `selectmoveresize` function, for example).

If you define this routine as a string, the string can be a valid MATLAB expression or the name of an M-file. The expression executes in the MATLAB workspace.

`Children` vector of handles

Children of the uibuttongroup. A vector containing the handles of all children of the uibuttongroup. Although a uibuttongroup manages only uicontrols of style `radiobutton` and `togglebutton`, its children can be axes, uipanels, uibuttongroups, and other uicontrols. You can use this property to reorder the children.

`Clipping` `{on} | off`

Clipping mode. By default, MATLAB clips a uibuttongroup's child axes, uipanels, and uibuttongroups to the uibuttongroup rectangle. If you set `Clipping` to `off`, the axis, uipanel, or uibuttongroup is displayed outside the button group rectangle. This property does not affect child uicontrols which, by default, can display outside the button group rectangle.

`CreateFcn` string or function handle

Callback routine executed during object creation. The specified function executes when MATLAB creates a `uibuttongroup` object. MATLAB sets all property values for the uibuttongroup before executing the `CreateFcn` callback so these values are available to the callback. Within the function, use `gcbo` to get the handle of the uibuttongroup being created.

Setting this property on an existing uibuttongroup object has no effect.

To define a default `CreateFcn` callback for all new uibuttongroups you must define the same default for all uipanels. This default applies unless you override it by specifying a different `CreateFcn` callback when you call `uibuttongroup`. For example, the code

```
set(0,'DefaultUipanelCreateFcn','set(gcbo,...
    ''FontName'',''arial'',''FontSize'',12)')
```

creates a default `CreateFcn` callback that runs whenever you create a new panel or button group. It sets the default font name and font size of the uipanel or uibuttongroup title.

To override this default and create a button group whose `FontName and FontSize` properties are set to different values, call `uibuttongroup` with code similar to

```
hpt = uibuttongroup(...,'CreateFcn','set(gcbo,...
''FontName'',''times'',''FontSize'',14)')
```

Note To override a default `CreateFcn` callback you must provide a new callback and not just provide different values for the specified properties. This is because the `CreateFcn` callback runs after the property values are set, and can override property values you have set explicitly in the `uibuttongroup` call. In the example above, if instead of redefining the `CreateFcn` property for this uibuttongroup, you had explicitly set `FontSize` to `14`, the default `CreateFcn` callback would have set `FontSize` back to the system dependent default.

See Function Handle Callbacks for information on how to use function handles to define a callback function.

`DeleteFcn` string or function handle

Callback routine executed during object deletion. A callback routine that executes when you delete the uibuttongroup object (e.g., when you issue a delete command or clear the figure containing the uibuttongroup). MATLAB executes the routine before destroying the object's properties so these values are available to the callback routine. The handle of the object whose `DeleteFcn`

is being executed is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

`FontAngle` `{normal} | italic | oblique`

Character slant used in the Title. MATLAB uses this property to select a font from those available on your particular system. Setting this property to `italic` or `oblique` selects a slanted version of the font, when it is available on your system.

`FontName` string

Font family used in the Title. The name of the font in which to display the `Title`. To display and print properly, this must be a font that your system supports. The default font is system dependent. To eliminate the need to hard code the name of a fixed-width font, which may not display text properly on systems that do not use ASCII character encoding (such as in Japan), set FontName to the string FixedWidth. This string value is case insensitive.

```
set(uicontrol_handle,'FontName','FixedWidth')
```

This then uses the value of the root `FixedWidthFontName` property, which can be set to the appropriate value for a locale from `startup.m` in the end user's environment. Setting the root `FixedWidthFontName` property causes an immediate update of the display to use the new font.

`FontSize` integer

Title font size. A number specifying the size of the font in which to display the Title, in units determined by the `FontUnits` property. The default size is system dependent.

`FontUnits` `inches | centimeters | normalized | {points} |pixels`

Title font size units. `Normalized` units interpret `FontSize` as a fraction of the height of the uibuttongroup. When you resize the uibuttongroup, MATLAB modifies the screen `FontSize` accordingly. `pixels`, `inches`, `centimeters`, and `points` are absolute units (1 point = 1/72 inch).

`FontWeight` `light | {normal} | demi | bold`

Weight of characters in the title. MATLAB uses this property to select a font from those available on your particular system. Setting this property to bold causes MATLAB to use a bold version of the font, when it is available on your system.

ForegroundColor ColorSpec

Color used for title font and 2-D border line. A three-element RGB vector or one of the MATLAB predefined names, specifying the font or line color. See the ColorSpec reference page for more information on specifying color.

HandleVisibility {on} | callback | off

Control access to object's handle. This property determines when an object's handle is visible in its parent's list of children. When a handle is not visible in its parent's list of children, it is not returned by functions that obtain handles by searching the object hierarchy or querying handle properties. This includes get, findobj, gca, gcf, gco, newplot, cla, clf, and close. Neither is the handle visible in the parent figure's CurrentObject property. Handles that are hidden are still valid. If you know an object's handle, you can set and get its properties, and pass it to any function that operates on handles.

- Handles are always visible when HandleVisibility is on.
- Setting HandleVisibility to callback causes handles to be visible from within callback routines or functions invoked by callback routines, but not from within functions invoked from the command line. This provides a means to protect GUIs from command-line users, while allowing callback routines to have complete access to object handles.
- Setting HandleVisibility to off makes handles invisible at all times. This may be necessary when a callback routine invokes a function that might potentially damage the GUI (such as evaluating a user-typed string), and so temporarily hides its own handles during the execution of that function.

Note Uicontrols of style radiobutton and togglebutton that are managed by a uibuttongroup should not be accessed outside the button group. Set the HandleVisibility of such radio buttons and toggle buttons to off or callback to prevent inadvertent access.

You can set the root ShowHiddenHandles property to on to make all handles visible, regardless of their HandleVisibility settings. This does not affect the values of the HandleVisibility properties.

HighlightColor ColorSpec

3-D frame highlight color. A three-element RGB vector or one of the MATLAB predefined names, specifying the highlight color. See the ColorSpec reference page for more information on specifying color.

HitTest {on} | off

Selectable by mouse click. HitTest determines if the figure can become the current object (as returned by the gco command and the figure CurrentObject property) as a result of a mouse click on the figure. If HitTest is off, clicking the figure sets the CurrentObject to the empty matrix.

Interruptible {on} | off

Callback routine interruption mode. If a callback is executing and the user triggers an event (such as a mouse click) on an object for which a callback is defined, that callback attempts to interrupt the first callback. MATLAB processes the callbacks according to these factors:

- The Interruptible property of the object whose callback is executing
- Whether the executing callback contains drawnow, figure, getframe, pause, or waitfor statements
- The BusyAction property of the object whose callback is waiting to execute

If the Interruptible property of the object whose callback is executing is on (the default), the callback can be interrupted. Whenever the callback calls one of the drawnow, figure, getframe, pause, or waitfor functions, the function processes any events in the event queue, including the waiting callback, before performing its defined task.

If the Interruptible property of the object whose callback is executing is off, the callback cannot be interrupted (except by certain callbacks; see the note below). The BusyAction property of the object whose callback is waiting to execute determines what happens to the waiting callback.

Note If the interrupting callback is a DeleteFcn or CreateFcn callback or a figure's CloseRequest or ResizeFcn callback, it interrupts an executing callback regardless of the value of that object's Interruptible property. The interrupting callback starts execution at the next drawnow, figure, getframe, pause, or waitfor statement. A figure's WindowButtonDownFcn callback

routine, or an object's `ButtonDownFcn` or `Callback` routine are processed according to the rules described above.

`Parent` handle

Uibuttongroup parent. The handle of the uibuttongroup's parent figure, uipanel, or uibuttongroup. You can move a uibuttongroup object to another figure, uipanel, or uibuttongroup by setting this property to the handle of the new parent.

`Position` position rectangle

Size and location of uibuttongroup relative to parent. The rectangle defined by this property specifies the size and location of the button group within the parent figure window, uipanel, or uibuttongroup. Specify `Position` as

```
[left bottom width height]
```

`left` and `bottom` are the distance from the lower-left corner of the parent object to the lower-left corner of the `uibuttongroup` object. `width` and `height` are the dimensions of the uibuttongroup rectangle, including the title. All measurements are in units specified by the `Units` property.

`ResizeFcn` string or function handle

Resize callback routine. MATLAB executes this callback routine whenever a user resizes the uibuttongroup and the figure Resize property is set to on, or in GUIDE, the Resize behavior option is set to `Other`. You can query the uibuttongroup `Position` property to determine its new size and position. During execution of the callback routine, the handle to the figure being resized is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

You can use `ResizeFcn` to maintain a GUI layout that is not directly supported by the MATLAB `Position`/`Units` paradigm.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

See Resize Behavior for information on creating resize functions using GUIDE.

Selected on | off (read only)

Is object selected? This property indicates whether the figure is selected. When this property is on, MATLAB displays selection handles if the SelectionHighlight property is also on. You can, for example, define the ButtonDownFcn to set this property, allowing users to select the object with the mouse.

SelectedObject scalar handle

Currently selected radio button or toggle button uicontrol in the managed group of components. Use this property to determine the currently selected component or to initialize selection of one of the radio buttons or toggle buttons. By default, SelectedObject is set to the first uicontrol radio button or toggle button that is added. Set it to [] if you want no selection. Note that SelectionChangeFcn does not execute when this property is set by the user.

SelectionChangeFcn string or function handle

Callback routine executed when the selected radio button or toggle button changes. If this routine is called as a function handle, uibuttongroup passes it two arguments. The first argument is the handle of the uibuttongroup. The second argument is an event data structure that contains the fields shown in the following table.

Event Data Structure Field	Description
EventName	'SelectionChanged'
OldValue	Handle of the object selected before this event. [] if none was selected.
NewValue	Handle of the currently selected object.

Include code for uicontrol radio buttons and toggle buttons that are managed by a uibuttongroup in the SelectionChangeFcn callback function, not in the individual uicontrol Callback functions. uibuttongroup overwrites the Callback properties of radio buttons and toggle buttons that it manages.

SelectionHighlight {on} | off

Object highlighted when selected. When the Selected property is on, MATLAB indicates the selected state by drawing four edge handles and four corner handles. When SelectionHighlight is off, MATLAB does not draw the handles.

ShadowColor ColorSpec

3-D frame shadow color. ShadowColor is a three-element RGB vector or one of the MATLAB predefined names, specifying the shadow color. See the ColorSpec reference page for more information on specifying color.

Tag string

User-specified object identifier. The Tag property provides a means to identify graphics objects with a user-specified label. You can define Tag as any string.

With the findobj function, you can locate an object with a given Tag property value. This saves you from defining object handles as global variables. For example, this function call returns the handles of all children (of the specified figures) that have the Tag value 'FormatTb'.

```
h = findobj(figurehandles,'Tag','FormatTb')
```

Title string

Title string. The text displayed in the button group title. You can position the title using the TitlePosition property.

If the string value is specified as a cell array of strings or padded string matrix, only the first string of a cell array or of a padded string matrix is displayed; the rest are ignored. Vertical slash ('|') characters are not interpreted as line breaks and instead show up in the text displayed in the uibuttongroup title.

Setting a property value to default, remove, or factory produces the effect described in Setting Default Values. To set Title to one of these words, you must precede the word with the backslash character. For example,

```
hp = uibuttongroup(...,'Title','\Default');
```

TitlePosition {lefttop} | centertop | righttop | leftbottom | centerbottom | rightbottom

Location ofthe title. This property determines the location of the title string, in relation to the uibuttongroup.

UIContextMenu handle

Associate a context menu with a uibuttongroup. Assign this property the handle of a `Uicontextmenu` object. MATLAB displays the context menu whenever you right-click the `uibuttongroup`. Use the `uicontextmenu` function to create the context menu.

Units `inches | centimeters | {normalized} | points | pixels | characters`

Units of measurement. MATLAB uses these units to interpret the `Position` property. All units are measured from the lower-left corner of the figure window.

- `Normalized` units map the lower-left corner of the figure window to (0,0) and the upper-right corner to (1.0,1.0).
- `pixels`, `inches`, `centimeters`, and `points` are absolute units (1 point = 1/72 inch).
- `Character` units are characters using the default system font; the width of one character is the width of the letter x, the height of one character is the distance between the baselines of two lines of text.

If you change the value of `Units`, it is good practice to return it to its default value after completing your computation so as not to affect other functions that assume `Units` is set to the default value.

UserData matrix

User-specified data. Any data you want to associate with the `uibuttongroup` object. MATLAB does not use this data, but you can access it using `set` and `get`.

Visible `{on} | off`

Uibuttongroup visibility. By default, a `uibuttongroup` object is visible. When set to `off`, the uibuttongroup is not visible, but still exists and you can query and set its properties.

Note The value of a uibuttongroup's `Visible` property also controls the `Visible` property of child axes, uipanels, and uibuttongroups. This property does not affect the `Visible` property of child uicontrols.

---

uicontextmenu

Purpose

Create a context menu

Syntax

```
handle = uicontextmenu('PropertyName',PropertyValue,...);
```

Description

`uicontextmenu` creates a context menu, which is a menu that appears when the user right-clicks on a graphics object.

You create context menu items using the `uimenu` function. Menu items appear in the order the `uimenu` statements appear. You associate a context menu with an object using the `UIContextMenu` property for the object and specifying the context menu's handle as the property value.

Properties

This table lists all properties useful to `uibuttongroup` objects, grouping them by function. Each property name acts as a link to a description of the property. Curly braces denote the default value, if any.

This table lists the properties that are useful to `uicontextmenu` objects, grouping them by function. Each property name acts as a link to a description of the property.

Property Name	Property Description	Property Value
Controlling Style and Appearance		
`Visible`	Uicontextmenu visibility	Value: `on`, `off` Default: `off`
`Position`	Location of uicontextmenu when `Visible` is set to `on`	Value: two-element vector Default: `[0 0]`
General Information About the Object		
`Children`	The uimenus defined for the uicontextmenu	Value: matrix
`Parent`	Uicontextmenu object's parent	Value: scalar figure handle
`Tag`	User-specified object identifier	Value: string
`Type`	Class of graphics object	Value: string (read-only) Default: `uicontrol`

Property Name	Property Description	Property Value
`UserData`	User-specified data	Value: matrix
Controlling Callback Routine Execution		
`BusyAction`	Callback routine interruption	Value: `cancel`, `queue` Default: `queue`
`Callback`	Control action	Value: string
`CreateFcn`	Callback routine executed during object creation	Value: string
`DeleteFcn`	Callback routine executed during object deletion	Value: string
`Interruptible`	Callback routine interruption mode	Value: `on`, `off` Default: `on`
Controlling Access to Objects		
`HandleVisibility`	Whether handle is accessible from command line and GUIs	Value: `on`, `callback`, `off` Default: `on`

Example

These statements define a context menu associated with a line. When the user extend-clicks anywhere on the line, the menu appears. Menu items enable the user to change the line style.

```
% Define the context menu
cmenu = uicontextmenu;
% Define the line and associate it with the context menu
hline = plot(1:10, 'UIContextMenu', cmenu);
% Define callbacks for context menu items
cb1 = ['set(hline, ''LineStyle'', ''--'')'];
cb2 = ['set(hline, ''LineStyle'', '':'')'];
cb3 = ['set(hline, ''LineStyle'', ''-'')'];
% Define the context menu items
item1 = uimenu(cmenu, 'Label', 'dashed', 'Callback', cb1);
item2 = uimenu(cmenu, 'Label', 'dotted', 'Callback', cb2);
item3 = uimenu(cmenu, 'Label', 'solid', 'Callback', cb3);
```

When the user extend-clicks on the line, the context menu appears, as shown in this figure:



See Also

`uibuttongroup`, `uicontrol`, `uimenu`, `uipanel`

Modifying Properties

You can set and query graphics object properties in two ways:

- The Property Inspector is an interactive tool that enables you to see and change object property values. The Property inspector is available from GUIDE, or use the `inspect` function at the command line.
- The `set` and `get` functions enable you to set and query the values of properties.

For more information about changing the default value of a property see Setting Default Property Values. For an example, see the `CreateFcn` property.

Uicontextmenu Properties

This section lists all properties useful to `uicontextmenu` objects along with valid values and descriptions of their use. Curly braces {} enclose default values.

Property	Purpose
`BusyAction`	Callback routine interruption
`Callback`	Control action
`Children`	The uimenus defined for the uicontextmenu
`CreateFcn`	Callback routine executed during object creation
`DeleteFcn`	Callback routine executed during object deletion
`HandleVisibility`	Whether handle is accessible from command line and GUIs
`Interruptible`	Callback routine interruption mode
`Parent`	Uicontextmenu object's parent
`Position`	Location of uicontextmenu when `Visible` is set to `on`
`Tag`	User-specified object identifier
`Type`	Class of graphics object
`UserData`	User-specified data
`Visible`	Uicontextmenu visibility

BusyAction cancel | {queue}

Callback routine interruption. If a callback is executing and the user triggers an event (such as a mouse click) on an object for which a callback is defined, the callback associated with the new event uses the value of `BusyAction` to decide whether or not to attempt to interrupt the executing callback.

- If the value is `cancel`, the event is discarded and the second callback does not execute.
- If the value is `queue`, and the `Interruptible` property of the first callback is `on`, the second callback is added to the event queue and executes in its turn after the first callback finishes execution.

Note If the interrupting callback is a `DeleteFcn` or `CreateFcn` callback or a figure's `CloseRequest` or `ResizeFcn` callback, it interrupts an executing callback regardless of the value of that object's `Interruptible` property. See the `Interruptible` property for information about controlling a callback's interruptibility.

ButtonDownFcn string

This property has no effect on uicontextmenu objects.

Callback string

Control action. A routine that executes whenever you right-click an object for which a context menu is defined. The routine executes immediately before the context menu is posted. Define this routine as a string that is a valid MATLAB expression or the name of an M-file. The expression executes in the MATLAB workspace.

Children matrix

The uimenus defined for the uicontextmenu.

Clipping {on} | off

This property has no effect on uicontextmenu objects.

CreateFcn string

Callback routine executed during object creation. The specified function executes when MATLAB creates a `uicontextmenu` object. MATLAB sets all

property values for the uicontextmenu before executing the `CreateFcn` callback so these values are available to the callback. Within the function, use `gcbo` to get the handle of the uicontextmenu being created.

Setting this property on an existing uicontextmenu object has no effect.

You can define a default `CreateFcn` callback for all new uicontextmenus. This default applies unless you override it by specifying a different `CreateFcn` callback when you call `uicontextmenu`. For example, the code

```
set(0,'DefaultUicontextmenuCreateFcn','set(gcbo,...
    ''Visible'',''on'')')
```

creates a default `CreateFcn` callback that runs whenever you create a new context menu. It sets the default `Visible` property of a context menu.

To override this default and create a context menu whose `Visible` property is set to a different value, call `uicontextmenu` with code similar to

```
hpt = uicontextmenu(...,'CreateFcn','set(gcbo,...
''Visible'',''off'')')
```

Note To override a default `CreateFcn` callback you must provide a new callback and not just provide different values for the specified properties. This is because the `CreateFcn` callback runs after the property values are set, and can override property values you have set explicitly in the `uicontextmenu` call. In the example above, if instead of redefining the `CreateFcn` property for this uicontextmenu, you had explicitly set `Visible` to `off`, the default `CreateFcn` callback would have set `Visible` back to the default, i.e., `on`.

See Function Handle Callbacks for information on how to use function handles to define a callback function.

`DeleteFcn` string

Delete uicontextmenu callback routine. A callback routine that executes when you delete the uicontextmenu object (e.g., when you issue a `delete` command or clear the figure containing the uicontextmenu). MATLAB executes the routine before destroying the object's properties so these values are available to the callback routine.

The handle of the object whose `DeleteFcn` is being executed is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define a callback function.

`HandleVisibility` `{on} | callback | off`

Control access to object's handle. This property determines when an object's handle is visible in its parent's list of children. When a handle is not visible in its parent's list of children, it is not returned by functions that obtain handles by searching the object hierarchy or querying handle properties. This includes `get`, `findobj`, `gca`, `gcf`, `gco`, `newplot`, `cla`, `clf`, and `close`. Neither is the handle visible in the parent figure's `CurrentObject` property. Handles that are hidden are still valid. If you know an object's handle, you can `set` and `get` its properties, and pass it to any function that operates on handles.

- Handles are always visible when `HandleVisibility` is `on`.
- Setting `HandleVisibility` to `callback` causes handles to be visible from within callback routines or functions invoked by callback routines, but not from within functions invoked from the command line. This provides a means to protect GUIs from command-line users, while allowing callback routines to have complete access to object handles.
- Setting `HandleVisibility` to `off` makes handles invisible at all times. This may be necessary when a callback routine invokes a function that might potentially damage the GUI (such as evaluating a user-typed string), and so temporarily hides its own handles during the execution of that function.

You can set the root `ShowHiddenHandles` property to `on` to make all handles visible, regardless of their `HandleVisibility` settings. This does not affect the values of the `HandleVisibility` properties.

`HitTest` `{on} | off`

This property has no effect on uicontextmenu objects.

`Interruptible` `{on} | off`

Callback routine interruption mode. If a callback is executing and the user triggers an event (such as a mouse click) on an object for which a callback is defined, that callback attempts to interrupt the first callback. MATLAB processes the callbacks according to these factors:

- The `Interruptible` property of the object whose callback is executing
- Whether the executing callback contains `drawnow`, `figure`, `getframe`, `pause`, or `waitfor` statements
- The `BusyAction` property of the object whose callback is waiting to execute

If the `Interruptible` property of the object whose callback is executing is `on` (the default), the callback can be interrupted. Whenever the callback calls one of the `drawnow`, `figure`, `getframe`, `pause`, or `waitfor` functions, the function processes any events in the event queue, including the waiting callback, before performing its defined task.

If the `Interruptible` property of the object whose callback is executing is `off`, the callback cannot be interrupted (except by certain callbacks; see the note below). The `BusyAction` property of the object whose callback is waiting to execute determines what happens to the callback.

Note If the interrupting callback is a `DeleteFcn` or `CreateFcn` callback or a figure's `CloseRequest` or `ResizeFcn` callback, it interrupts an executing callback regardless of the value of that object's `Interruptible` property. The interrupting callback starts execution at the next `drawnow`, `figure`, `getframe`, `pause`, or `waitfor` statement. A figure's `WindowButtonDownFcn` callback routine, or an object's `ButtonDownFcn` or `Callback` routine are processed according to the rules described above.

`Parent` handle

Uicontextmenu's parent. The handle of the uicontextmenu's parent object. You can move a uicontextmenu object to another figure, uipanel, or uibuttongroup by setting this property to the handle of the new parent.

`Position` vector

Uicontextmenu's position. A two-element vector that defines the location of a context menu posted by setting the `Visible` property value to `on`. Specify `Position` as

```
[x y]
```

where vector elements represent the horizontal and vertical distances in pixels from the bottom left corner of the figure window, panel, or button group to the top left corner of the context menu.

`Selected` `on | {off}`

This property has no effect on uicontextmenu objects.

`SelectionHighlight` `{on} | off`

This property has no effect on uicontextmenu objects.

`Tag` string

User-specified object label. The `Tag` property provides a means to identify graphics objects with a user-specified label. This is particularly useful when constructing interactive graphics programs that would otherwise need to define object handles as global variables or pass them as arguments between callback routines. You can define `Tag` as any string.

`Type` string

Class of graphics object. For uicontextmenu objects, `Type` is always the string `'uicontextmenu'`.

`UIContextMenu` handle

This property has no effect on uicontextmenus.

`UserData` matrix

User-specified data. Any data you want to associate with the uicontextmenu object. MATLAB does not use this data, but you can access it using `set` and `get`.

`Visible` `on | {off}`

Uicontextmenu visibility. The `Visible` property can be used in two ways:

- Its value indicates whether the context menu is currently posted. While the context menu is posted, the property value is `on`; when the context menu is not posted, its value is `off`.
- Its value can be set to `on` to force the posting of the context menu. Similarly, setting the value to `off` forces the context menu to be removed. When used in this way, the `Position` property determines the location of the posted context menu.

Purpose

Create user interface control object

Syntax

```
handle = uicontrol('PropertyName',PropertyValue,...)
handle = uicontrol(parent,'PropertyName',PropertyValue,...)
handle = uicontrol
uicontrol(uich)
```

Description

`uicontrol` creates a uicontrol graphics objects (user interface controls), which you use to implement graphical user interfaces.

`handle = uicontrol('PropertyName',PropertyValue,...)` creates a uicontrol and assigns the specified properties and values to it. It assigns the default values to any properties you do not specify. The default uicontrol style is a pushbutton. The default parent is the current figure. See “Properties” on page 2-2332 for information about these and other properties.

`handle = uicontrol(parent,'PropertyName',PropertyValue,...)` creates a uicontrol in the object specified by the handle, `parent`. If you also specify a different value for the `Parent` property, the value of the `Parent` property takes precedence. `parent` can be the handle of a figure, uipanel, or uibuttongroup.

`handle = uicontrol` creates a pushbutton in the current figure. The `uicontrol` function assigns all properties their default values.

`uicontrol(uich)` gives focus to the uicontrol specified by the handle, `uich`.

When selected, most uicontrol objects perform a predefined action. MATLAB supports numerous styles of uicontrols, each suited for a different purpose:

- Check boxes
- Editable text fields
- List boxes
- Pop-up menus
- Push buttons
- Radio buttons
- Sliders
- Static text labels
- Toggle buttons

For information on using these uicontrols within GUIDE, the MATLAB GUI development environment, see

- Setting Component Properties — the Property Inspector
- Programming Callbacks for GUI Components

Specifying the Uicontrol Style

To create a specific type of uicontrol, set the `Style` property as one of the following strings:

- `'checkbox'`– Check boxes generate an action when selected. These devices are useful when providing the user with a number of independent choices. To activate a check box, click the mouse button on the object. The state of the device is indicated on the display.
- `'edit'` – Editable text fields enable users to enter or modify text values. Use editable text when you want text as input. If `Max-Min>1`, then multiple lines are allowed. For multi-line edit boxes, a vertical scrollbar enables scrolling, as do the arrow keys.
- `'listbox'` – List boxes display a list of items (defined using the `String` property) and enable users to select one or more items. The `Min` and `Max` properties control the selection mode:

  If `Max-Min>1`, then multiple selection is allowed.

  If `Max-Min<=1`, then only single selection is allowed.

  The `Value` property indicates selected entries and contains the indices into the list of strings; a vector value indicates multiple selections. MATLAB evaluates the list box's callback routine after any mouse button up event that changes the `Value` property. Therefore, you may need to add a "Done" button to delay action caused by multiple clicks on list items. List boxes differentiate between single and double clicks and set the figure `SelectionType` property to `normal` or `open` accordingly before evaluating the list box's `Callback` property.

- `'popupmenu'` – Pop-up menus open to display a list of choices (defined using the `String` property) when pressed. When not open, a pop-up menu indicates the current choice. Pop-up menus are useful when you want to provide users with a number of mutually exclusive choices, but do not want to take up the

amount of space that a series of radio buttons requires. You must specify a value for the `String` property.

- `'pushbutton'` – Push buttons generate an action when pressed. To activate a push button, click the mouse button on the push button.
- `'radiobutton'` – Radio buttons are similar to check boxes, but are intended to be mutually exclusive within a group of related radio buttons (i.e., only one is in a pressed state at any given time). To activate a radio button, click the mouse button on the object. The state of the device is indicated on the display. Note that your code can implement the mutually exclusive behavior of radio buttons.
- `'slider'` – Sliders accept numeric input within a specific range by enabling the user to move a sliding bar. Users move the bar by pressing the mouse button and dragging the pointer over the bar, or by clicking in the trough or on an arrow. The location of the bar indicates a numeric value, which is selected by releasing the mouse button. You can set the minimum, maximum, and current values of the slider.
- `'text'` – Static text boxes display lines of text. Static text is typically used to label other controls, provide directions to the user, or indicate values associated with a slider. Users cannot change static text interactively and there is no way to invoke the callback routine associated with it.
- `'toggle'` – Toggle buttons are controls that execute callbacks when clicked on and indicate their state, either on or off. Toggle buttons are useful for building toolbars.

Remarks

The `uicontrol` function accepts property name/property value pairs, structures, and cell arrays as input arguments and optionally returns the handle of the created object. You can also set and query property values after creating the object using the `set` and `get` functions.

A `uicontrol` object is a child of a figure, uipanel, or uibuttongroup and therefore does not require an axes to exist when placed in a figure window, uipanel, or uibuttongroup.

Properties

This table lists all properties useful for `uicontrol` objects, grouping them by function. Each property name acts as a link to a description of the property.

Property Name	Property Description	Property Value
Controlling Style and Appearance		
`BackgroundColor`	Object background color	Value: `ColorSpec` Default: system dependent
`CData`	Truecolor image displayed on the control	Value: matrix
`ForegroundColor`	Color of text	Value: `ColorSpec` Default: `[0 0 0]`
`SelectionHighlight`	Object highlighted when selected	Value: `on`, `off` Default: `on`
`String`	Uicontrol label, also list box and pop-up menu items	Value: string
`Visible`	Uicontrol visibility	Value: `on`, `off` Default: `on`
General Information About the Object		
`Children`	Uicontrol objects have no children	
`Enable`	Enable or disable the uicontrol	Value: `on`, `inactive`, `off` Default: `on`
`Parent`	Uicontrol object's parent	Value: figure, uipanel, or uibuttongroup handle
`Selected`	Whether object is selected	Value: `on`, `off` Default: `off`
`SliderStep`	Slider step size	Value: two-element vector Default: `[0.01 0.1]`

Property Name	Property Description	Property Value
`Style`	Type of uicontrol object	Value: `pushbutton`, `togglebutton`, `radiobutton`, `checkbox`, `edit`, `text`, `slider`, `listbox`, `popupmenu` Default: `pushbutton`
`Tag`	User-specified object identifier	Value: string
`TooltipString`	Content of object's tooltip	Value: string
`Type`	Class of graphics object	Value: string (read-only) Default: `uicontrol`
`UserData`	User-specified data	Value: matrix
Controlling the Object Position		
`Position`	Size and location of uicontrol object	Value: position rectangle Default: `[20 20 60 20]`
`Units`	Units to interpret `position` vector	Value: `pixels`, `normalized`, `inches`, `centimeters`, `points`, `characters` Default: `pixels`
Controlling Fonts and Labels		
`FontAngle`	Character slant	Value: `normal`, `italic`, `oblique` Default: `normal`
`FontName`	Font family	Value: string Default: system dependent
`FontSize`	Font size	Value: size in `FontUnits` Default: system dependent

Property Name	Property Description	Property Value
FontUnits	Font size units	Value: points, normalized, inches, centimeters, pixels Default: points
FontWeight	Weight of text characters	Value: light, normal, demi, bold Default: normal
HorizontalAlignment	Alignment of label string	Value: left, center, right Default: depends on uicontrol object
String	Uicontrol object label, also list box and pop-up menu items	Value: string
Controlling Callback Routine Execution		
BusyAction	Callback routine interruption	Value: cancel, queue Default: queue
ButtonDownFcn	Button-press callback routine	Value: string or function handle
Callback	Control action	Value: string or function handle
CreateFcn	Callback routine executed during object creation	Value: string or function handle
DeleteFcn	Callback routine executed during object deletion	Value: string or function handle
Interruptible	Callback routine interruption mode	Value: on, off Default: on
KeyPressFcn	Key press callback routine	Value: string or function handle
UIContextMenu	Uicontextmenu object associated with the uicontrol	Value: handle

Property Name	Property Description	Property Value
Information About the Current State		
`ListboxTop`	Index of top-most string displayed in list box	Value: scalar Default: `[1]`
`Max`	Maximum value (depends on uicontrol object)	Value: scalar Default: object dependent
`Min`	Minimum value (depends on uicontrol object)	Value: scalar Default: object dependent
`Value`	Current value of uicontrol object	Value: scalar or vector Default: object dependent
Controlling Access to Objects		
`HandleVisibility`	Whether handle is accessible from command line and GUIs	Value: `on`, `callback`, `off` Default: `on`
`HitTest`	Whether selectable by mouse click	Value: `on`, `off` Default: `on`

Examples

Example 1. The following statement creates a push button that clears the current axes when pressed.

```
h = uicontrol('Style', 'pushbutton', 'String', 'Clear',...
    'Position', [20 150 100 70], 'Callback', 'cla');
```

This statement gives focus to the pushbutton.

```
uicontrol(h)
```

Example 2. You can create a uicontrol object that changes figure colormaps by specifying a pop-up menu and supplying an M-file name as the object's `Callback`:

```
hpop = uicontrol('Style', 'popup',...
       'String', 'hsv|hot|cool|gray',...
       'Position', [20 320 100 50],...
       'Callback', 'setmap');
```

The above call to `uicontrol` defines four individual choices in the menu: `hsv`, `hot`, `cool`, and `gray`. You specify these choices with the `String` property, separating the choices with the "|" character.

The `Callback`, in this case `setmap`, is the name of an M-file that defines a more complicated set of instructions than a single MATLAB command. `setmap` contains these statements:

```
val = get(hpop,'Value');
if val == 1
    colormap(hsv)
elseif val == 2
    colormap(hot)
elseif val == 3
    colormap(cool)
elseif val == 4
    colormap(gray)
end
```

The `Value` property contains a number that indicates the selected choice. The choices are numbered sequentially from one to four. The `setmap` M-file can get and then test the contents of the `Value` property to determine what action to take.

See Also

`textwrap`, `uibuttongroup`, `uimenu`, `uipanel`

Modifying Properties

You can set and query graphics object properties in two ways:

- The Property Inspector is an interactive tool that enables you to see and change object property values. The Property inspector is available from GUIDE, or use the `inspect` function at the command line.
- The `set` and `get` commands enable you to set and query the values of properties

To change the default value of properties see Setting Default Property Values. You can also set default uicontrol properties on the root and figure levels:

```
set(0,'DefaultUicontrolProperty',PropertyValue...)
set(gcf,'DefaultUicontrolProperty',PropertyValue...)
```

where *`Property`* is the name of the uicontrol property whose default value you want to set and `PropertyValue` is the value you are specifying as the default. Use `set` and `get` to access uicontrol properties.

For information on using these uicontrols within GUIDE, the MATLAB GUI development environment, see

- Setting Component Properties — the Property Inspector
- Programming Callbacks for GUI Components

Uicontrol Properties

This section lists all properties useful to `uicontrol` objects along with valid values and descriptions of their use. Curly braces {} enclose default values.

Property	Purpose
`BackgroundColor`	Object background color
`BusyAction`	Callback routine interruption
`ButtonDownFcn`	Button-press callback routine
`Callback`	Control action
`CData`	Truecolor image displayed on the control
`Children`	Uicontrol objects have no children

Property	Purpose
CreateFcn	Callback routine executed during object creation
DeleteFcn	Callback routine executed during object deletion
Enable	Enable or disable the uicontrol
FontAngle	Character slant
FontName	Font family
FontSize	Font size
FontUnits	Font size units
FontWeight	Weight of text characters
ForegroundColor	Color of text
HandleVisibility	Whether handle is accessible from command line and GUIs
HitTest	Whether selectable by mouse click
HorizontalAlignment	Alignment of label string
Interruptible	Callback routine interruption mode
KeyPressFcn	Key press callback routine
ListboxTop	Index of top-most string displayed in list box
Max	Maximum value (depends on uicontrol object)
Min	Minimum value (depends on uicontrol object)
Parent	Uicontrol object's parent
Position	Size and location of uicontrol object
Selected	Whether object is selected
SelectionHighlight	Object highlighted when selected

Property	Purpose
SliderStep	Slider step size
String	Uicontrol label, also list box and pop-up menu items
String	Uicontrol object label, also list box and pop-up menu items
Style	Type of uicontrol object
Tag	User-specified object identifier
TooltipString	Content of object's tooltip
Type	Class of graphics object
UIContextMenu	Uicontextmenu object associated with the uicontrol
Units	Units to interpret position vector
UserData	User-specified data
Value	Current value of uicontrol object
Visible	Uicontrol visibility

BackgroundColor ColorSpec

Object background color. The color used to fill the uicontrol rectangle. Specify a color using a three-element RGB vector or one of the MATLAB predefined names. The default color is determined by system settings. See ColorSpec for more information on specifying color.

BusyAction cancel | {queue}

Callback routine interruption. If a callback is executing and the user triggers an event (such as a mouse click) on an object for which a callback is defined, the callback associated with the new event uses the value of BusyAction to decide whether or not to attempt to interrupt the executing callback.

- If the value is cancel, the event is discarded and the second callback does not execute.

- If the value is `queue`, and the `Interruptible` property of the first callback is `on`, the second callback is added to the event queue and executes in its turn after the first callback finishes execution.

Note If the interrupting callback is a `DeleteFcn` or `CreateFcn` callback or a figure's `CloseRequest` or `ResizeFcn` callback, it interrupts an executing callback regardless of the value of that object's `Interruptible` property. See the `Interruptible` property for information about controlling a callback's interruptibility.

`ButtonDownFcn` string or function handle (GUIDE sets this property)

Button-press callback routine. A callback routine that executes when you press a mouse button while the pointer is in a 5-pixel wide border around the uicontrol. When the uicontrol's `Enable` property is set to `inactive` or `off`, the `ButtonDownFcn` executes when you click the mouse in the 5-pixel border or on the control itself. This is useful for implementing actions to interactively modify control object properties, such as size and position, when they are clicked on (using `selectmoveresize`, for example).

Define this routine as a string that is a valid MATLAB expression or the name of an M-file. The expression executes in the MATLAB workspace.

To add a `ButtonDownFcn` callback in GUIDE, select `View Callbacks` from the Layout Editor **View** menu, then select `ButtonDownFcn`. GUIDE sets this property to the appropriate string and adds the callback to the M-file the next time you save the GUI. Alternatively, you can set this property to the string `%automatic`. The next time you save the GUI, GUIDE sets this property to the appropriate string and adds the callback to the M-file.

Use the `Callback` property to specify the callback routine that executes when you activate the enabled uicontrol (e.g., click on a push button).

`Callback` string (GUIDE sets this property)

Control action. A routine that executes whenever you activate the uicontrol object (e.g., when you click on a push button or move a slider). Define this routine as a string that is a valid MATLAB expression or the name of an M-file. The expression executes in the MATLAB workspace.

To execute the callback routine for an edit text control, type in the desired text and then do one of the following:

- Click another component, the menu bar, or the background of the GUI.
- For a single line editable text box, press **Enter**, or
- For a multiline editable text box, press **Ctl+Enter**.

Callback routines defined for static text do not execute because no action is associated with these objects.

`CData` matrix

Truecolor image displayed on control. A three-dimensional matrix of RGB values that defines a truecolor image displayed on either a push button or toggle button. Each value must be between 0.0 and 1.0.

`Children` matrix

The empty matrix; uicontrol objects have no children.

`Clipping` `{on} | off`

This property has no effect on uicontrols.

`CreateFcn` string

Callback routine executed during object creation. The specified function executes when MATLAB creates a `uicontrol` object. MATLAB sets all property values for the uiconrtol before executing the `CreateFcn` callback so these values are available to the callback. Within the function, use `gcbo` to get the handle of the uicontrol being created.

Setting this property on an existing uicontrol object has no effect.

You can define a default `CreateFcn` callback for all new uicontrols. This default applies unless you override it by specifying a different `CreateFcn` callback when you call `uicontrol`. For example, the code

```
set(0,'DefaultUicontrolCreateFcn','set(gcbo,...
    ''BackgroundColor'',''white'')')
```

creates a default `CreateFcn` callback that runs whenever you create a new uicontrol. It sets the default background color of all new uicontrols.

To override this default and create a uicontrol whose `BackgroundColor` is set to a different value, call `uicontrol` with code similar to

```
hpt = uicontrol(...,'CreateFcn','set(gcbo,...
''BackgroundColor'',''blue'')')
```

Note To override a default `CreateFcn` callback you must provide a new callback and not just provide different values for the specified properties. This is because the `CreateFcn` callback runs after the property values are set, and can override property values you have set explicitly in the `uicontrol` call. In the example above, if instead of redefining the `CreateFcn` property for this uicontrol, you had explicitly set `BackgroundColor` to `blue`, the default `CreateFcn` callback would have set `BackgroundColor` back to the default, i.e., `white`.

See Function Handle Callbacks for information on how to use function handles to define a callback function.

`DeleteFcn` string

Delete uicontrol callback routine. A callback routine that executes when you delete the uicontrol object (e.g., when you issue a `delete` command or clear the figure containing the uicontrol). MATLAB executes the routine before destroying the object's properties so these values are available to the callback routine.

The handle of the object whose `DeleteFcn` is being executed is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define a callback function.

`Enable` `{on} | inactive | off`

Enable or disable the uicontrol. This property controls how uicontrols respond to mouse button clicks, including which callback routines execute.

- `on` – The uicontrol is operational (the default).
- `inactive` – The uicontrol is not operational, but looks the same as when `Enable` is `on`.
- `off` – The uicontrol is not operational and its image (set by the `Cdata` property) is grayed out.

When you left-click on a uicontrol whose `Enable` property is `on`, MATLAB performs these actions in this order:

1. Sets the figure's `SelectionType` property.
2. Executes the uicontrol's `ClickedCallback` routine.
3. Does not set the figure's `CurrentPoint` property and does not execute either the control's `ButtonDownFcn` or the figure's `WindowButtonDownFcn` callback.

When you left-click on a uitoggletool whose `Enable` property is `off`, or when you right-click a uicontrol whose `Enable` property has any value, MATLAB performs these actions in this order:

1. Sets the figure's `SelectionType` property.
2. Sets the figure's `CurrentPoint` property.
3. Executes the figure's `WindowButtonDownFcn` callback.

`Extent` position rectangle (read only)

Size of uicontrol character string. A four-element vector that defines the size and position of the character string used to label the uicontrol. It has the form:

```
[0,0,width,height]
```

The first two elements are always zero. `width` and `height` are the dimensions of the rectangle. All measurements are in units specified by the `Units` property.

Since the `Extent` property is defined in the same units as the uicontrol itself, you can use this property to determine proper sizing for the uicontrol with regard to its label. Do this by

- Defining the `String` property and selecting the font using the relevant properties.
- Getting the value of the `Extent` property.
- Defining the `width` and `height` of the `Position` property to be somewhat larger than the `width` and `height` of the `Extent`.

For multiline strings, the `Extent` rectangle encompasses all the lines of text. For single line strings, the Extent is returned as a single line, even if the string wraps when displayed on the control.

FontAngle {normal} | italic | oblique

Character slant. MATLAB uses this property to select a font from those available on your particular system. Setting this property to `italic` or `oblique` selects a slanted version of the font, when it is available on your system.

FontName string

Font family. The name of the font in which to display the `String`. To display and print properly, this must be a font that your system supports. The default font is system dependent.

To use a fixed-width font that looks good in any locale (and displays properly in Japan, where multibyte character sets are used), set `FontName` to the string `FixedWidth` (this string value is case sensitive):

```
set(uicontrol_handle, 'FontName', 'FixedWidth')
```

This parameter value eliminates the need to hard code the name of a fixed-width font, which may not display text properly on systems that do not use ASCII character encoding (such as in Japan). A properly written MATLAB application that needs to use a fixed-width font should set `FontName` to `FixedWidth` and rely on the root `FixedWidthFontName` property to be set correctly in the end user's environment.

End users can adapt a MATLAB application to different locales or personal environments by setting the root `FixedWidthFontName` property to the appropriate value for that locale from `startup.m`. Setting the root `FixedWidthFontName` property causes an immediate update of the display to use the new font.

FontSize size in `FontUnits`

Font size. A number specifying the size of the font in which to display the `String`, in units determined by the `FontUnits` property. The default point size is system dependent.

FontUnits {points} | normalized | inches | centimeters | pixels

Font size units. This property determines the units used by the `FontSize` property. `Normalized` units interpret `FontSize` as a fraction of the height of the uicontrol. When you resize the uicontrol, MATLAB modifies the screen `FontSize` accordingly. `pixels`, `inches`, `centimeters`, and `points` are absolute units (1 point = $^1/_{72}$ inch).

FontWeight light | {normal} | demi | bold

Weight of text characters. MATLAB uses this property to select a font from those available on your particular system. Setting this property to bold causes MATLAB to use a bold version of the font, when it is available on your system.

ForegroundColor ColorSpec

Color of text. This property determines the color of the text defined for the String property (the uicontrol label). Specify a color using a three-element RGB vector or one of MATLAB 's predefined names. The default text color is black. See ColorSpec for more information on specifying color.

HandleVisibility {on} | callback | off

Control access to object's handle. This property determines when an object's handle is visible in its parent's list of children. When a handle is not visible in its parent's list of children, it is not returned by functions that obtain handles by searching the object hierarchy or querying handle properties. This includes get, findobj, gca, gcf, gco, newplot, cla, clf, and close. Neither is the handle visible in the parent figure's CurrentObject property. Handles that are hidden are still valid. If you know an object's handle, you can set and get its properties, and pass it to any function that operates on handles.

- Handles are always visible when HandleVisibility is on.
- Setting HandleVisibility to callback causes handles to be visible from within callback routines or functions invoked by callback routines, but not from within functions invoked from the command line. This provides a means to protect GUIs from command-line users, while allowing callback routines to have complete access to object handles.
- Setting HandleVisibility to off makes handles invisible at all times. This may be necessary when a callback routine invokes a function that might potentially damage the GUI (such as evaluating a user-typed string), and so temporarily hides its own handles during the execution of that function.

You can set the root ShowHiddenHandles property to on to make all handles visible, regardless of their HandleVisibility settings. This does not affect the values of the HandleVisibility properties.

Note Radio buttons and toggle buttons that are managed by a uibuttongroup should not be accessed outside the button group. Set the `HandleVisibility` of such radio buttons and toggle buttons to `off` to prevent inadvertent access.

`HitTest` `{on} | off`

Selectable by mouse click. This property has no effect on uicontrol objects.

`HorizontalAlignment` `left | {center} | right`

Horizontal alignment of label string. This property determines the justification of the text defined for the `String` property (the uicontrol label):

- `left` — Text is left justified with respect to the uicontrol.
- `center` — Text is centered with respect to the uicontrol.
- `right` — Text is right justified with respect to the uicontrol.

On Microsoft Windows systems, this property affects only `edit` and `text` uicontrols.

`Interruptible` `{on} | off`

Callback routine interruption mode. If a callback is executing and the user triggers an event (such as a mouse click) on an object for which a callback is defined, that callback attempts to interrupt the first callback. MATLAB processes the callbacks according to these factors:

- The `Interruptible` property of the object whose callback is executing
- Whether the executing callback contains `drawnow`, `figure`, `getframe`, `pause`, or `waitfor` statements
- The `BusyAction` property of the object whose callback is waiting to execute

If the `Interruptible` property of the object whose callback is executing is `on` (the default), the callback can be interrupted. Whenever the callback calls one of the `drawnow`, `figure`, `getframe`, `pause`, or `waitfor` functions, the function processes any events in the event queue, including the waiting callback, before performing its defined task.

If the `Interruptible` property of the object whose callback is executing is `off`, the callback cannot be interrupted (except by certain callbacks; see the note

below). The BusyAction property of the object whose callback is waiting to execute determines what happens to the callback.

Note If the interrupting callback is a DeleteFcn or CreateFcn callback or a figure's CloseRequest or ResizeFcn callback, it interrupts an executing callback regardless of the value of that object's Interruptible property. The interrupting callback starts execution at the next drawnow, figure, getframe, pause, or waitfor statement. A figure's WindowButtonDownFcn callback routine, or an object's ButtonDownFcn or Callback routine are processed according to the rules described above.

KeyPressFcn string or function handle

Key press callback function. A callback routine invoked by a key press when the callback's uicontrol object has focus. Focus is denoted by a border or a dotted border, respectively, in UNIX and Microsoft Windows. If no uicontrol has focus, the figure's key press callback function, if any, is invoked. KeyPressFcn can be a function handle, the name of an M-file, or any legal MATLAB expression.

If the specified value is the name of an M-file, the callback routine can query the figure's CurrentCharacter property to determine what particular key was pressed and thereby limit the callback execution to specific keys.

If the specified value is a function handle, the callback routine can retrieve information about the key that was pressed from its event data structure argument.

Event Data Structure Field	Description	Examples:			
		a	=	Shift	Shift/a
`Character`	Character interpretation of the key that was pressed.	`'a'`	`'='`	`''`	`'A'`
`Modifier`	Current modifier, such as `'control'`, or an empty cell array if there is no modifier	`{1x0 cell}`	`{1x0 cell}`	`{'shift'}`	`{'shift'}`
`Key`	Name of the key that was pressed.	`'a'`	`'equal'`	`'shift'`	`'a'`

See Function Handle Callbacks for information on how to use function handles to define the callback function.

`ListboxTop` scalar

Index of top-most string displayed in list box. This property applies only to the `listbox` style of uicontrol. It specifies which string appears in the top-most position in a list box that is not large enough to display all list entries. `ListboxTop` is an index into the array of strings defined by the `String` property and must have a value between 1 and the number of strings. Noninteger values are fixed to the next lowest integer.

`Max` scalar

Maximum value. This property specifies the largest value allowed for the `Value` property. Different styles of uicontrols interpret `Max` differently:

- Check boxes – `Max` is the setting of the `Value` property while the check box is selected.

- Editable text – If `Max` – `Min` > 1, then editable text boxes accept multiline input. If `Max` – `Min` <= 1, then editable text boxes accept only single line input.
- List boxes – If `Max` – `Min` > 1, then list boxes allow multiple item selection. If `Max` – `Min` <= 1, then list boxes do not allow multiple item selection.
- Radio buttons – `Max` is the setting of the `Value` property when the radio button is selected.
- Sliders – `Max` is the maximum slider value and must be greater than the `Min` property. The default is 1.
- Toggle buttons – `Max` is the value of the `Value` property when the toggle button is selected. The default is 1.
- Pop-up menus, push buttons, and static text do not use the `Max` property.

`Min` scalar

Minimum value. This property specifies the smallest value allowed for the `Value` property. Different styles of uicontrols interpret `Min` differently:

- Check boxes – `Min` is the setting of the `Value` property while the check box is not selected.
- Editable text – If `Max` – `Min` > 1, then editable text boxes accept multiline input. If `Max` – `Min` <= 1, then editable text boxes accept only single line input.
- List boxes – If `Max` – `Min` > 1, then list boxes allow multiple item selection. If `Max` – `Min` <= 1, then list boxes allow only single item selection.
- Radio buttons – `Min` is the setting of the `Value` property when the radio button is not selected.
- Sliders – `Min` is the minimum slider value and must be less than `Max`. The default is 0.
- Toggle buttons – `Min` is the value of the `Value` property when the toggle button is not selected. The default is 0.
- Pop-up menus, push buttons, and static text do not use the `Min` property.

`Parent` handle

Uicontrol parent. The handle of the uicontrol's parent object. You can move a uicontrol object to another figure, uipanel, or uibuttongroup by setting this property to the handle of the new parent.

Position position rectangle

Size and location of uicontrol. The rectangle defined by this property specifies the size and location of the control within the parent figure window, uipanel, or uibuttongroup. Specify `Position` as

```
[left bottom width height]
```

`left` and `bottom` are the distance from the lower-left corner of the parent object to the lower-left corner of the uicontrol object. `width` and `height` are the dimensions of the uicontrol rectangle. All measurements are in units specified by the `Units` property.

On Microsoft Windows systems, the height of pop-up menus is automatically determined by the size of the font. The value you specify for the `height` of the `Position` property has no effect.

The `width` and `height` values determine the orientation of sliders. If `width` is greater than `height`, then the slider is oriented horizontally, If `height` is greater than `width`, then the slider is oriented vertically.

Selected `on | {off}` (read only)

Is object selected. When this property is `on`, MATLAB displays selection handles if the `SelectionHighlight` property is also `on`. You can, for example, define the `ButtonDownFcn` to set this property, allowing users to select the object with the mouse.

SelectionHighlight `{on} | off`

Object highlight when selected. When the `Selected` property is on, MATLAB indicates the selected state by drawing four edge handles and four corner handles. When `SelectionHighlight` is `off`, MATLAB does not draw the handles.

SliderStep `[min_step max_step]`

Slider step size. This property controls the amount the slider `Value` changes when you click the mouse on the arrow button (`min_step`) or on the slider trough (`max_step`). Specify `SliderStep` as a two-element vector; each value must be in the range `[0, 1]`. The actual step size is a function of the specified `SliderStep` and the total slider range (`Max` – `Min`). The default, `[0.01 0.10]`, provides a 1 percent change for clicks on the arrow button and a 10 percent change for clicks in the trough.

For example, if you create the following slider,

```
uicontrol('Style','slider','Min',1,'Max',7,...
          'SliderStep',[0.1 0.6])
```

clicking on the arrow button moves the indicator by,

```
0.1*(7 1)
ans =
     0.6000
```

and clicking in the trough moves the indicator by,

```
0.6*(7 1)
ans =
     3.6000
```

Note that if the specified step size moves the slider to a value outside the range, the indicator moves only to the `Max` or `Min` value.

See also the `Max`, `Min`, and `Value` properties.

`String` string

Uicontrol label, *list box items*, *pop-up menu choices*. For **check boxes, editable text, push buttons, radio buttons, static text,** and **toggle buttons**, the text displayed on the object. For list boxes and pop-up menus, the set of entries or items displayed in the object.

For uicontrol objects that display only one line of text, if the string value is specified as a cell array of strings or padded string matrix, only the first string of a cell array or of a padded string matrix is displayed; the rest are ignored. Vertical slash (`'|'`) characters are not interpreted as line breaks and instead show up in the text displayed in the uicontrol.

For multiple line editable text or static text controls, line breaks occur between each row of the string matrix, each cell of a cell array of strings, and after any `\n` characters embedded in the string. Vertical slash (`'|'`) characters are not interpreted as line breaks, and instead show up in the text displayed in the uicontrol.

For multiple items on a list box or pop-up menu, you can specify items as a cell array of strings, a padded string matrix, or within a string vector separated

by vertical slash (`'|'`) characters. Use the `Value` property to set the index of the initial item selected.

For **editable text**, this property value is set to the string entered by the user.

Setting the String Property to a Reserved Word

Setting a property value to `default`, `remove`, or `factory` produces the effect described in Setting Default Values. To set a property to one of these words (e.g., `String` property set to the word `'Default'`), you must precede the word with the backslash character. For example,

```
h = uicontrol('Style','edit','String','\Default');
```

`Style` `{pushbutton} | togglebutton | radiobutton | checkbox | edit | text | slider | listbox | popupmenu`

Style of uicontrol object to create. The `Style` property specifies the kind of uicontrol to create. See the `uicontrol` Description section for information on each type.

`Tag` string (GUIDE sets this property)

User-specified object label. The `Tag` property provides a means to identify graphics objects with a user-specified label. This is particularly useful when constructing interactive graphics programs that would otherwise need to define object handles as global variables or pass them as arguments between callback routines. You can define `Tag` as any string.

`TooltipString` string

Content of tooltip for object. The `TooltipString` property specifies the text of the tooltip associated with the uicontrol. When the user moves the mouse pointer over the control and leaves it there, the tooltip is displayed.

`Type` string (read only)

Class of graphics object. For uicontrol objects, `Type` is always the string `'uicontrol'`.

`UIContextMenu` handle

Associate a context menu with uicontrol. Assign this property the handle of a `uicontextmenu` object. MATLAB displays the context menu whenever you right-click over the uicontrol. Use the `uicontextmenu` function to create the context menu.

Units {pixels} | normalized | inches | centimeters | points | characters
(GUIDE default: normalized)

Units of measurement. MATLAB uses these units to interpret the Extent and Position properties. All units are measured from the lower-left corner of the parent object.

- Normalized units map the lower-left corner of the parent object to (0,0) and the upper-right corner to (1.0,1.0).
- pixels, inches, centimeters, and points are absolute units (1 point = 1/72 inch).
- Character units are characters using the default system font; the width of one character is the width of the letter x, the height of one character is the distance between the baselines of two lines of text.

If you change the value of Units, it is good practice to return it to its default value after completing your computation so as not to affect other functions that assume Units is set to the default value.

UserData matrix

User-specified data. Any data you want to associate with the uicontrol object. MATLAB does not use this data, but you can access it using set and get.

Value scalar or vector

Current value of uicontrol. The uicontrol style determines the possible values this property can have:

- Check boxes set Value to Max when they are on (when selected) and Min when off (not selected).
- List boxes set Value to a vector of indices corresponding to the selected list entries, where 1 corresponds to the first item in the list.
- Pop-up menus set Value to the index of the item selected, where 1 corresponds to the first item in the menu. The Examples section shows how to use the Value property to determine which item has been selected.
- Radio buttons set Value to Max when they are on (when selected) and Min when off (not selected).
- Sliders set Value to the number indicated by the slider bar.

- Toggle buttons set `Value` to `Max` when they are down (selected) and `Min` when up (not selected).
- Editable text, push buttons, and static text do not set this property.

Set the `Value` property either interactively with the mouse or through a call to the `set` function. The display reflects changes made to `Value`.

`Visible` `{on} | off`

Uicontrol visibility. By default, all uicontrols are visible. When set to `off`, the uicontrol is not visible, but still exists and you can query and set its properties.

Purpose

Standard dialog box for selecting a directory

Syntax

```
directory_name = uigetdir
directory_name = uigetdir('start_path')
directory_name = uigetdir('start_path','dialog_title')
directory_name = uigetdir('start_path','dialog_title',x,y)
```

Description

`uigetdir` displays a dialog box enabling the user to browse through the directory structure and select a directory.

`directory_name = uigetdir` opens a dialog box in the current directory displaying the default title.

`directory_name = uigetdir('start_path')` opens a dialog box in the directory specified by `start_path`.

`directory_name = uigetdir('start_path','dialog_title')` opens a dialog box with the specified title.

`directory_name = uigetdir('start_path','dialog_title',x,y)` positions the dialog box at position [`x`,`y`], where `x` and `y` are the distance in pixel units from the left and top edges of the screen. This feature is only supported on UNIX platforms.

Remarks

Returned directory_name

`directory_name` is a string containing the path to the directory selected in the dialog box. If the user presses the **Cancel** button or closes the dialog window, `directory_name` is returned as the number `0`.

Specifying start_path

`start_path` specifies the directory to display when the dialog is first opened. If `start_path` is a string representing a valid directory path, the dialog box opens in the specified directory.

If `start_path` is an empty string (`''`), the dialog box opens in the current working directory.

If `start_path` is not a valid directory path, the dialog box opens in the base directory:

- On Windows systems, the base directory is the Windows desktop directory.
- On UNIX systems, the base directory is the directory from which MATLAB is started.

Specifying dialog_title

The placement of `dialog_title` in the dialog box depends on the computer system:

- On Windows systems, the string replaces the default caption inside the dialog box for specifying instructions to the user.
- On UNIX systems, the string replaces the default title of the dialog box.

If you do not specify the `dialog_title` argument, MATLAB uses the default string `Select Directory to Open`.

Adding and Moving Directories

On Windows systems, users can click the **New Folder** button to add a new directory to the directory structure displayed. Users can also drag and drop existing directories.

Examples

Example 1

The following statement displays the directories on the `C:` drive.

```
dname = uigetdir('C:\');
```

The dialog box is shown in the following figure.



If the user selects the directory `MATLAB6.5\help\techdoc`, as shown in the figure, and clicks **OK**, `uigetdir` returns

```
dname =
C:\MATLAB6.5\help\techdoc
```

Example 2

The following statement uses the `matlabroot` command to display the MATLAB root directory in the dialog box:

```
uigetdir(matlabroot,'MATLAB Root Directory')
```



If the user selects the directory `MATLAB6.5/notebook/pc`, as shown in the figure, `uigetdir` returns a string like

```
C:\MATLAB6.5\notebook\pc
```

assuming that MATLAB is installed on drive `C:\`.

See Also

`uigetfile`, `uiputfile`

Purpose

Standard dialog box for retrieving files

Syntax

```
uigetfile
uigetfile('FilterSpec')
uigetfile('FilterSpec','DialogTitle')
uigetfile('FilterSpec','DialogTitle','DefaultName')
uigetfile(...,'Location',[x y])
uigetfile(...,'MultiSelect',selectmode)
[FileName,PathName] = uigetfile(...)
[FileName,PathName,FilterIndex] = uigetfile(...)
```

Description

`uigetfile` displays a dialog box used to retrieve one or more files. The dialog box lists the files and directories in the current directory.

`uigetfile('FilterSpec')` displays a dialog box that lists files in the current directory. `FilterSpec` determines the initial display of files and can include the `*` wildcard. For example, `'*.m'` lists all the MATLAB M-files.

If `FilterSpec` is a string or cell array, `uigetfile` appends `'All Files'` to the list of file types. If `FilterSpec` is a cell array, the first column contains the list of extensions, and the second column contains the list of descriptions. `FilterSpec` can also be a filename. In this case the filename becomes the default filename and the file's extension is used as the default filter. If `FilterSpec` is not specified, `uigetfile` uses the default list of file types (i.e., all MATLAB files).

`uigetfile('FilterSpec','DialogTitle')` displays a dialog box that has the title `DialogTitle`.

`uigetfile('FilterSpec','DialogTitle','DefaultName')` displays a dialog box in which a specified string, in this case `'DefaultName'`, appears in the **File name** field. `'Default Name'` can be a filename or the name of a directory. If it is the name of a directory, you must follow it with a slash `(/)` or backslash `(\)` separator.

`uigetfile(...,'Location',[x y])` positions the dialog box at position `[x,y]`, where `x` and `y` are the distances in pixel units from the left and top edges of the screen. This feature is supported only on UNIX platforms.

`uigetfile(...,'MultiSelect',selectmode)` specifies if multiple file selection is enabled for the `uigetfile` dialog. Valid values for `selectmode` are `'on'` and `'off'`(default). If the value of `'MultiSelect'` is `'on'` and the user selects more than one file in the dialog box, then `FileName` is a cell array of strings, each of which represents the name of a selected file. Otherwise, `Filename` is a string representing the selected filename. Because multiple selections are always in the same directory, `PathName` is always a string that represents a single directory.

`[FileName,PathName] = uigetfile(...)` returns the name and path of the file selected in the dialog box. After the user clicks the **Done** button, `FileName` contains the name of the file selected and `PathName` contains the name of the path selected. If the user clicks the **Cancel** button or closes the dialog window, `FileName` and `PathName` are set to `0`.

`[FileName,PathName,FilterIndex] = uigetfile(...)` returns the index of the filter selected in the dialog box. The indexing starts at 1. If the user clicks the **Cancel** button or closes the dialog window, `FilterIndex` is set to `0`.

Remarks

A successful return occurs only if all the selected files exist. If the user selects a file that does not exist, an error message is displayed and control returns to the dialog box.

Examples

Example 1. The following statement displays a dialog box that enables the user to retrieve a file. The statement lists all MATLAB M-files within a selected directory. The name and path of the selected file are returned in `FileName` and `PathName`. Note that `uigetfile` appends `All Files(*.*)` to the file types when `FilterSpec` is a string.

```
[FileName,PathName] = uigetfile('*.m','Select the M-file');
```

The dialog box is shown in the following figure.



Example 2. To create a list of file types that appears in the **Files of type** list box, separate the file extensions with semicolons, as in the following code. Note that `uigetfile` displays a default description for each known file type, such as "Simulink Models" for `.mdl` files.

```
[filename, pathname] = ...
     uigetfile({'*.m';'*.mdl';'*.mat';'*.*'},'File Selector');
```



Example 3. If you want to create a list of file types and give them descriptions that are different from the defaults, use a cell array, as in the following code. This example also associates multiple file types with the `'MATLAB Files'` description.

```
[filename, pathname] = uigetfile( ...
{'*.m;*.fig;*.mat;*.mdl','MATLAB Files (*.m,*.fig,*.mat,*.mdl)';
   '*.m',  'M-files (*.m)'; ...
   '*.fig','Figures (*.fig)'; ...
   '*.mat','MAT-files (*.mat)'; ...
   '*.mdl','Models (*.mdl)'; ...
   '*.*',  'All Files (*.*)'}, ...
   'Pick a file');
```

The first column of the cell array contains the file extensions, while the second contains the descriptions you want to provide for the the file types. Note that the first entry of column one contains several extensions, separated by semicolons, all of which are associated with the description `'MATLAB Files (*.m,*.fig,*.mat,*.mdl)'`. The code produces the dialog box shown in the following figure.



Example 4. The following code checks for the existence of the file and displays a message about the result of the open operation.

```
[filename, pathname] = uigetfile('*.m', 'Pick an M-file');
if isequal(filename,0)
   disp('User selected Cancel')
else
   disp(['User selected', fullfile(pathname, filename)])
end
```



Example 5. This example creates a list of file types and gives them descriptions that are different from the defaults, then enables multiple file selection. The user can select multiple files by holding down the **Shift** or **Ctrl** key and clicking on a file.

```
[filename, pathname, filterindex] = uigetfile( ...
{  '*.mat','MAT-files (*.mat)'; ...
   '*.mdl','Models (*.mdl)'; ...
   '*.*',  'All Files (*.*)'}, ...
   'Pick a file', ...
   'MultiSelect', 'on');
```



See Also `uiputfile`, `uigetdir`

Purpose

Open Import Wizard, the graphical user interface to import data

Syntax

```
uiimport
uiimport(filename)
uiimport('-file')
uiimport('-pastespecial')
S = uiimport(...)
```

Description

`uiimport` starts the Import Wizard in the current directory, presenting options to load data from a file or the clipboard.

`uiimport(filename)` starts the Import Wizard, opening the file specified in `filename`. The Import Wizard displays a preview of the data in the file.

`uiimport('-file')` works as above but presents the file selection dialog first.

`uiimport('-pastespecial')` works as above but presents the clipboard contents first.

`S = uiimport(...)` works as above with resulting variables stored as fields in the struct `S`.

Note For ASCII data, you must verify that the Import Wizard correctly identified the column delimiter.

See Also

`load`, `clipboard`

uimenu

Purpose

Create menus on figure windows

Syntax

```
uimenu('PropertyName',PropertyValue,...)
uimenu(parent,'PropertyName',PropertyValue,...)
handle = uimenu('PropertyName',PropertyValue,...)
handle = uimenu(parent,'PropertyName',PropertyValue,...)
```

Description

`uimenu` creates a hierarchy of menus and submenus that are displayed in the figure window's menu bar. You can also use `uimenu` to create menu items for context menus.

`handle = uimenu('PropertyName',PropertyValue,...)` creates a menu in the current figure's menu bar using the values of the specified properties and assigns the menu handle to `handle`.

`handle = uimenu(parent,'PropertyName',PropertyValue,...)` creates a submenu of a parent menu or a menu item on a context menu specified by `parent` and assigns the menu handle to `handle`. If `parent` refers to a figure instead of another uimenu object or a uicontextmenu, MATLAB creates a new menu on the referenced figure's menu bar.

Remarks

MATLAB adds the new menu to the existing menu bar. Each menu choice can itself be a menu that displays its submenu when selected.

`uimenu` accepts property name/property value pairs, as well as structures and cell arrays of properties as input arguments. The uimenu `Callback` property defines the action taken when you activate the menu item. `uimenu` optionally returns the handle to the created uimenu object.

Uimenus only appear in figures whose `WindowStyle` is `normal`. If a figure containing uimenu children is changed to `WindowStyle modal`, the uimenu children still exist and are contained in the `Children` list of the figure, but are not displayed until the `WindowStyle` is changed to `normal`.

The value of the figure `MenuBar` property affects the location of the uimenu on the figure menu bar. When `MenuBar` is `figure`, a set of built-in menus precedes the uimenus on the menu bar (MATLAB controls the built-in menus and their handles are not available to the user). When `MenuBar` is `none`, uimenus are the only items on the menu bar (that is, the built-in menus do not appear).

You can set and query property values after creating the menu using `set` and `get`.

Properties

This table lists all properties useful to `uimenu` objects, grouping them by function. Each property name acts as a link to a description of the property.

Property Name	Property Description	Property Value
Controlling Style and Appearance		
`Checked`	Menu check indicator	Value: `on`, `off` Default: `off`
`ForegroundColor`	Color of text	Value: `ColorSpec` Default: `[0 0 0]`
`Label`	Menu label	Value: string
`Separator`	Separator line mode	Value: `on`, `off` Default: `off`
`Visible`	Uimenu visibility	Value: `on`, `off` Default: `on`
General Information About the Object		
`Accelerator`	Keyboard equivalent	Value: character
`Children`	Handles of submenus	Value: vector of handles
`Enable`	Enable or disable the uimenu	Value: `on`, `off` Default: `on`
`Parent`	Uimenu object's parent	Value: handle
`Tag`	User-specified object identifier	Value: string
`Type`	Class of graphics object	Value: string (read-only) Default: `uimenu`
`UserData`	User-specified data	Value: matrix
Controlling the Object Position		

Property Name	Property Description	Property Value
`Position`	Relative uimenu position	Value: scalar Default: `[1]`
Controlling Callback Routine Execution		
`BusyAction`	Callback routine interruption	Value: `cancel`, `queue` Default: `queue`
`Callback`	Control action	Value: string
`CreateFcn`	Callback routine executed during object creation	Value: string
`DeleteFcn`	Callback routine executed during object deletion	Value: string
`Interruptible`	Callback routine interruption mode	Value: `on`, `off` Default: `on`
Controlling Access to Objects		
`HandleVisibility`	Whether handle is accessible from command line and GUIs	Value: `on`, `callback`, `off` Default: `on`

Examples

This example creates a menu labeled **Workspace** whose choices allow users to create a new figure window, save workspace variables, and exit out of MATLAB. In addition, it defines an accelerator key for the Quit option.

```
f = uimenu('Label','Workspace');
    uimenu(f,'Label','New Figure','Callback','figure');
    uimenu(f,'Label','Save','Callback','save');
    uimenu(f,'Label','Quit','Callback','exit',...
           'Separator','on','Accelerator','Q');
```

See Also

`uicontrol`, `uicontextmenu`, `gcbo`, `set`, `get`, `figure`

Modifying Properties

You can set and query graphics object properties in two ways:

- The Property Inspector is an interactive tool that enables you to see and change object property values. The Property inspector is available from GUIDE, or use the `inspect` function at the command line.
- The `set` and `get` commands enable you to set and query the values of properties

You can set default Uimenu properties on the root, figure and menu levels:

```
set(0,'DefaultUimenuPropertyName',PropertyValue...)
set(gcf,'DefaultUimenuPropertyName',PropertyValue...)
set(menu_handle,'DefaultUimenuPropertyName',PropertyValue...)
```

Where *`PropertyName`* is the name of the Uimenu property and `PropertyValue` is the value you specify as the default for that property.

For more information about changing the default value of property see Setting Default Property Values.

Uimenu Properties

This section lists all properties useful to `uimenu` objects along with valid values and instructions for their use. Curly braces { } enclose default values.

Property Name	Property Description
`Accelerator`	Keyboard equivalent
`BusyAction`	Callback routine interruption
`Callback`	Control action
`Checked`	Menu check indicator
`Children`	Handles of submenus
`CreateFcn`	Callback routine executed during object creation
`DeleteFcn`	Callback routine executed during object deletion
`Enable`	Enable or disable the uimenu

Property Name	Property Description
`ForegroundColor`	Color of text
`HandleVisibility`	Whether handle is accessible from command line and GUIs
`Interruptible`	Callback routine interruption mode
`Label`	Menu label
`Parent`	Uimenu object's parent
`Position`	Relative uimenu position
`Separator`	Separator line mode
`Tag`	User-specified object identifier
`Type`	Class of graphics object
`UserData`	User-specified data
`Visible`	Uimenu visibility

`Accelerator` character

Keyboard equivalent. A character specifying the keyboard equivalent for the menu item. This allows users to select a particular menu choice by pressing the specified character in conjunction with another key, instead of selecting the menu item with the mouse. The key sequence is platform specific:

- For Microsoft Windows systems, the sequence is **Ctrl**+`Accelerator`. These keys are reserved for default menu items: c, v, and x.
- For UNIX systems, the sequence is **Ctrl**+`Accelerator`. These keys are reserved for default menu items: o, p, s, and w.

You can define an accelerator only for menu items that do not have children menus. Accelerators work only for menu items that directly execute a callback routine, not items that bring up other menus.

Note that the menu item does not have to be displayed (e.g., a submenu) for the accelerator key to work. However, the window focus must be in the figure when the key sequence is entered.

To remove an accelerator, set `Accelerator` to an empty string, `''`.

`BusyAction` `cancel | {queue}`

Callback routine interruption. If a callback is executing and the user triggers an event (such as a mouse click) on an object for which a callback is defined, the callback associated with the new event uses the value of `BusyAction` to decide whether or not to attempt to interrupt the executing callback.

- If the value is `cancel`, the event is discarded and the second callback does not execute.
- If the value is `queue`, and the `Interruptible` property of the first callback is `on`, the second callback is added to the event queue and executes in its turn after the first callback finishes execution.

Note If the interrupting callback is a `DeleteFcn` or `CreateFcn` callback or a figure's `CloseRequest` or `ResizeFcn` callback, it interrupts an executing callback regardless of the value of that object's `Interruptible` property. See the `Interruptible` property for information about controlling a callback's interruptibility.

`Callback` string

Menu action. A callback routine that executes whenever you select the menu. Define this routine as a string that is a valid MATLAB expression or the name of an M-file. The expression executes in the MATLAB workspace.

A menu with children (submenus) executes its callback routine before displaying the submenus. A menu without children executes its callback routine when you *release* the mouse button (i.e., on the button up event).

`Checked` `on | {off}`

Menu check indicator. Setting this property to `on` places a check mark next to the corresponding menu item. Setting it to `off` removes the check mark. You can use this feature to create menus that indicate the state of a particular option. For example, suppose you have a menu item called **Show axes** that toggles the visibility of an axes between visible and invisible each time the user selects the menu item. If you want a check to appear next to the menu item

when the axes are visible, add the following code to the callback for the **Show axes** menu item:

```
if strcmp(get(gcbo, 'Checked'),'on')
    set(gcbo, 'Checked', 'off');
else
    set(gcbo, 'Checked', 'on');
end
```

This changes the value of the `Checked` property of the menu item from `on` to `off` or vice versa each time a user selects the menu item.

Note that there is no formal mechanism for indicating that an unchecked menu item will become checked when selected. Also, this property does not display the check mark on top level menus or submenus, although you can change the value of the property for these menus.

Note the following platform differences:

- On UNIX, the check mark is *not* displayed on submenus that have submenus.
- On Windows, the check mark is displayed on submenus, whether or not they have submenus.

`Children` vector of handles

Handles of submenus. A vector containing the handles of all children of the uimenu object. The children objects of uimenus are other uimenus, which function as submenus. You can use this property to reorder the menus.

`CreateFcn` string or function handle

Callback routine executed during object creation. The specified function executes when MATLAB creates a `uimenu` object. MATLAB sets all property values for the uimenu before executing the `CreateFcn` callback so these values are available to the callback. Within the function, use `gcbo` to get the handle of the uimenu being created.

Setting this property on an existing uimenu object has no effect.

You can define a default `CreateFcn` callback for all new uimenus. This default applies unless you override it by specifying a different `CreateFcn` callback when you call `uimenu`. For example, the code

```
set(0,'DefaultUimenuCreateFcn','set(gcbo,...
    ''Visible'',''on'')')
```

creates a default `CreateFcn` callback that runs whenever you create a new menu. It sets the default `Visible` property of a `uimenu` object.

To override this default and create a menu whose `Visible` property is set to a different value, call `uimenu` with code similar to

```
hpt = uimenu(...,'CreateFcn','set(gcbo,...
''Visible'',''off'')')
```

Note To override a default `CreateFcn` callback you must provide a new callback and not just provide different values for the specified properties. This is because the `CreateFcn` callback runs after the property values are set, and can override property values you have set explicitly in the `uimenu` call. In the example above, if instead of redefining the `CreateFcn` property for this uimenu, you had explicitly set `Visible` to `off`, the default `CreateFcn` callback would have set `Visible` back to the default, i.e., `on`.

See Function Handle Callbacks for information on how to use function handles to define a callback function.

`DeleteFcn` string or function handle

Delete uimenu callback routine. A callback routine that executes when you delete the uimenu object (e.g., when you issue a `delete` command or cause the figure containing the uimenu to reset). MATLAB executes the routine before destroying the object's properties so these values are available to the callback routine.

The handle of the object whose `DeleteFcn` is being executed is accessible only through the root `CallbackObject` property, which is more simply queried using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define a callback function.

Enable {on} | off

Enable or disable the uimenu. This property controls whether a menu item can be selected. When not enabled (set to off), the menu Label appears dimmed, indicating the user cannot select it.

ForegroundColor ColorSpec X-Windows only

Color of menu label string. This property determines color of the text defined for the Label property. Specify a color using a three-element RGB vector or one of the MATLAB predefined names. The default text color is black. See ColorSpec for more information on specifying color.

HandleVisibility {on} | callback | off

Control access to object's handle. This property determines when an object's handle is visible in its parent's list of children. When a handle is not visible in its parent's list of children, it is not returned by functions that obtain handles by searching the object hierarchy or querying handle properties. This includes get, findobj, gca, gcf, gco, newplot, cla, clf, and close. Neither is the handle visible in the parent figure's CurrentObject property. Handles that are hidden are still valid. If you know an object's handle, you can set and get its properties, and pass it to any function that operates on handles.

- Handles are always visible when HandleVisibility is on.
- Setting HandleVisibility to callback causes handles to be visible from within callback routines or functions invoked by callback routines, but not from within functions invoked from the command line. This provides a means to protect GUIs from command-line users, while allowing callback routines to have complete access to object handles.
- Setting HandleVisibility to off makes handles invisible at all times. This may be necessary when a callback routine invokes a function that might potentially damage the GUI (such as evaluating a user-typed string), and so temporarily hides its own handles during the execution of that function.

You can set the root ShowHiddenHandles property to on to make all handles visible, regardless of their HandleVisibility settings. This does not affect the values of the HandleVisibility properties.

Interruptible {on} | off

Callback routine interruption mode. If a callback is executing and the user triggers an event (such as a mouse click) on an object for which a callback is

defined, that callback attempts to interrupt the first callback. MATLAB processes the callbacks according to these factors:

- The `Interruptible` property of the object whose callback is executing
- Whether the executing callback contains `drawnow`, `figure`, `getframe`, `pause`, or `waitfor` statements
- The `BusyAction` property of the object whose callback is waiting to execute

If the `Interruptible` property of the object whose callback is executing is `on` (the default), the callback can be interrupted. Whenever the callback calls one of the `drawnow`, `figure`, `getframe`, `pause`, or `waitfor` functions, the function processes any events in the event queue, including the waiting callback, before performing its defined task.

If the `Interruptible` property of the object whose callback is executing is `off`, the callback cannot be interrupted (except by certain callbacks; see the note below). The `BusyAction` property of the object whose callback is waiting to execute determines what happens to the callback.

Note If the interrupting callback is a `DeleteFcn` or `CreateFcn` callback or a figure's `CloseRequest` or `ResizeFcn` callback, it interrupts an executing callback regardless of the value of that object's `Interruptible` property. The interrupting callback starts execution at the next `drawnow`, `figure`, `getframe`, `pause`, or `waitfor` statement. A figure's `WindowButtonDownFcn` callback routine, or an object's `ButtonDownFcn` or `Callback` routine are processed according to the rules described above.

`Label` string

Menu label. A string specifying the text label on the menu item. You can specify a mnemonic using the "&" character. Whatever character follows the "&" in the string appears underlined and selects the menu item when you type that character while the menu is visible. The "&" character is not displayed. To display the "&" character in a label, use two "&" characters in the string:

`O&pen selection'` yields **O<u>p</u>en selection**

`Save && Go'` yields **Save & Go**

Parent handle

Uimenu's parent. The handle of the uimenu's parent object. The parent of a uimenu object is the figure on whose menu bar it displays, or the uimenu of which it is a submenu. You can move a uimenu object to another figure by setting this property to the handle of the new parent.

Position scalar

Relative menu position. The value of `Position` indicates placement on the menu bar or within a menu. Top-level menus are placed from left to right on the menu bar according to the value of their `Position` property, with 1 representing the left-most position. The individual items within a given menu are placed from top to bottom according to the value of their `Position` property, with 1 representing the top-most position.

Separator `on | {off}`

Separator line mode. Setting this property to `on` draws a dividing line above the menu item.

Tag string

User-specified object label. The `Tag` property provides a means to identify graphics objects with a user-specified label. This is particularly useful when constructing interactive graphics programs that would otherwise need to define object handles as global variables or pass them as arguments between callback routines. You can define `Tag` as any string.

Type string (read only)

Class of graphics object. For uimenu objects, `Type` is always the string `'uimenu'`.

UserData matrix

User-specified data. Any matrix you want to associate with the uimenu object. MATLAB does not use this data, but you can access it using the `set` and `get` commands.

Visible `{on} | off`

Uimenu visibility. By default, all uimenus are visible. When set to `off`, the uimenu is not visible, but still exists and you can query and set its properties.

Purpose

Convert to unsigned integer

Syntax

```
I = uint8(X)
I = uint16(X)
I = uint32(X)
I = uint64(X)
```

Description

`I = uint*(X)` converts the elements of array `X` into unsigned integers. `X` can be any numeric object (such as a `double`). The results of a `uint*` operation are shown in the next table.

Operation	Output Range	Output Type	Bytes per Element	Output Class
`uint8`	0 to 255	Unsigned 8-bit integer	1	`uint8`
`uint16`	0 to 65,535	Unsigned 16-bit integer	2	`uint16`
`uint32`	0 to 4,294,967,295	Unsigned 32-bit integer	4	`uint32`
`uint64`	0 to 18,446,744,073,709,551,615	Unsigned 64-bit integer	8	`uint64`

`double` and `single` values are rounded to the nearest `uint*` value on conversion. A value of `X` that is above or below the range for an integer class is mapped to one of the endpoints of the range. For example,

```
uint16(70000)
ans =
   65535
```

If `X` is already an unsigned integer of the same class, then `uint*` has no effect.

You can define or overload your own methods for `uint*` (as you can for any object) by placing the appropriately named method in an `@uint*` directory within a directory on your path. Type `help datatypes` for the names of the methods you can overload.

Remarks

Most operations that manipulate arrays without changing their elements are defined for integer values. Examples are `reshape`, `size`, the logical and relational operators, subscripted assignment, and subscripted reference.

Some arithmetic operations are defined for integer arrays on interaction with other integer arrays of the same class (e.g., where both operands are `uint16`). Examples of these operations are `+`, `-`, `.*`, `./`, `.\` and `.^`. If at least one operand is scalar, then `*`, `/`, `\`, and `^` are also defined. Integer arrays may also interact with scalar `double` variables, including constants, and the result of the operation is an integer array of the same class. Integer arrays saturate on overflow in arithmetic.

A particularly efficient way to initialize a large array is by specifying the data type (i.e., class name) for the array in the `zeros`, `ones`, or `eye` function. For example, to create a 100-by-100 `uint64` array initialized to zero, type

```
I = zeros(100, 100, 'uint64');
```

An easy way to find the range for any MATLAB integer type is to use the `intmin` and `intmax` functions as shown here for `uint32`:

```
intmin('uint32')              intmax('uint32')
ans =                         ans =
   0                             4294967295
```

See Also

`double`, `single`, `int8`, `int16`, `int32`, `int64`, `intmax`, `intmin`

Purpose

Display a file selection dialog with appropriate file filters

Syntax

```
uiopen
```

Description

`uiopen` displays a file selection dialog from which a user can select a file to open. The dialog is the same as the one displayed when you select **Open** from the **File** menu in the MATLAB desktop.

Selecting a file in the dialog and clicking **Open** does the following:

- Gets the file using `uigetfile`
- Opens the file in the base workspace using the `open` command

Note `uiopen` cannot be compiled. If you want to create a file selection dialog that can be compiled, use `uigetfile`.

`uiopen`, or `uiopen('MATLAB')` displays the dialog with the file filter set to all MATLAB files.

`uiopen('LOAD')` displays the dialog with the file filter set to MAT-files (*.mat).

`uiopen('FIGURE')` displays the dialog with the file filter set to figure files (*.fig).

`uiopen('SIMULINK')` displays the dialog with the file filter set to model files (*.mdl).

`uiopen('EDITOR')` displays the dialog with the file filter set to all MATLAB files except for MAT-files and FIG-files. All files are opened in the MATLAB Editor.

See Also

`uigetfile`, `uiputfile`, `uisave`

uipanel

Purpose

Uipanel container object

Syntax

```
h = uipanel('PropertyName1',value1,'PropertyName2',value2,...)
```

Description

A uipanel groups components. It can contain user interface controls with which the user interacts directly. It can also contain axes, other uipanels, and uibuttongroups. It cannot contain ActiveX controls.

`h = uipanel` creates a `uipanel` container object in a figure, uipanel, or uibuttongroup. Use the `Parent` property to specify the parent figure, uipanel, or uibuttongroup. If you do not specify a parent, `uipanel` adds the panel to the current figure. If no figure exists, one is created.

A `uipanel` object can have `axes`, `uicontrol`, `uipanel`, and `uibuttongroup` objects as children. For the children of a uipanel, the `Position` property is interpreted relative to the uipanel. If you move the panel, the children automatically move with it and maintain their positions relative to the panel.

After creating a `uipanel` object, you can set and query its property values using `set` and `get`.

Properties

This table lists all properties useful to `uipanel` objects, grouping them by function. Each property name acts as a link to a description of the property. Curly braces denote the default value, if any

Property Name	Description	Property Value
Controlling Style and Appearance		
`BackgroundColor`	Color of the uipanel background	`ColorSpec`. Default is the same as the default uicontrol background.
`BorderType`	Type of border around the uipanel area.	`[none|{etchedin}|etchedout|beveledin|beveledout|line]`
`BorderWidth`	Width of the panel border.	Integer. Default is `1`.

Property Name	Description	Property Value
`Clipping`	Clipping of child axes, uipanels, and uibuttongroups to the uipanel. Does not affect child uicontrols.	`[{on}|off]`
`ForegroundColor`	Title font color and/or color of 2-D border line	`ColorSpec`. Default is `[0 0 0]` (black).
`HighlightColor`	3-D frame highlight color	`ColorSpec`. Default is `[1 1 1]` (white).
`SelectionHighlight`	Object highlighted when selected	`[{on}|off]`
`ShadowColor`	3-D frame shadow color	`ColorSpec`. Default is `[.5 .5 .5]` (grey).
`Visible`	Uipanel visibility. Note: Controls the `Visible` property of child axes, uibuttongroups. and uipanels. Does not affect child uicontrols.	`[{on}|off]`
General Information About the Object		
`Children`	All children of the uipanel	Vector of handles
`Parent`	Uipanel object's parent	Figure, uipanel, or uibuttongroup handle
`Selected`	Whether object is selected	`[on|{off}]`
`Tag`	User-specified object identifier	String
`UserData`	User-specified data	Matrix

Property Name	Description	Property Value
Controlling the Object Position		
`Position`	Panel position relative to parent figure, uipanel, or uibuttongroup	Position spec `[x y w h]`. Default is `[0 0 1 1]`
`Units`	Units usd to interpret the position vector	`[inches|centimeters|{normalized}|points|pixels|characters]`
Controlling Fonts and Labels		
`FontAngle`	Title font angle	`[{normal}|italic|oblique]`
`FontName`	Title font name	String. Default is system dependent.
`FontSize`	Title font size	Integer. Default is system dependent.
`FontUnits`	Title font units	`[inches|centimeters|normalized|{points}|pixels]`
`FontWeight`	Title font weight	`[light|{normal}|demi|bold]`
`Title`	Title string	String
`TitlePosition`	Location of title string in relation to the panel	`[{lefttop}|centertop|righttop|leftbottom|centerbottom|rightbottom]`
Controlling Callback Routine Execution		
`BusyAction`	Interruption of other callback routines	`[{queue}|cancel]`
`ButtonDownFcn`	Button-press callback routine	String or function handle

Property Name	Description	Property Value
`CreateFcn`	Callback routine executed during object creation	String or function handle
`DeleteFcn`	Callback routine executed during object deletion	String or function handle
`Interruptible`	Callback routine interruption mode	`[{on}|off]`
`ResizeFcn`	User-specified resize routine	String or function handle
`UIContextMenu`	Associates a uicontextmenu with the uipanel	Handle
Controlling Access to Objects		
`HandleVisibility`	Handle accessibility from commandline and GUIs	`[{on}|callback|off]`
`HitTest`	Selectable by mouse click	`[{on}|off]`

Examples

This example creates a uipanel in a figure, then creates a subpanel in the first panel. Finally, it adds a pushbutton to the subpanel. Both panels use the default `Units` property value, `normalized`. Note that default `Units` for the `uicontrol` pushbutton is pixels.

```
h = figure;
hp = uipanel('Title','Main Panel','FontSize',12,...
             'BackgroundColor','white',...
             'Position',[.25 .1 .67 .67]);
hsp = uipanel('Parent',hp,'Title','Subpanel','FontSize',12,...
              'Position',[.4 .1 .5 .5]);
hbsp = uicontrol('Parent',hsp,'String','Push here',...
              'Position',[18 18 72 36]);
```



See Also `hgtransform`, `uibuttongroup`, `uicontrol`

Modifying Properties

You can set and query graphics object properties in two ways:

- The Property Inspector is an interactive tool that enables you to see and change object property values. The Property inspector is available from GUIDE, or use the `inspect` function at the command line.
- The `set` and `get` functions enable you to set and query the values of properties.

You can set default uipanel properties by typing:

```
set(h,'DefaultUipanelPropertyName',PropertyValue...)
```

Where h can be the root handle (0), a figure handle, or a uipanel handle. *`PropertyName`* is the name of the uipanel property and `PropertyValue` is the value you specify as the default for that property.

Note Default properties you set for uipanels also apply to uibuttongroups.

For more information about changing the default value of a property see Setting Default Property Values. For an example, see the `CreateFcn` property.

Uipanel Properties

This section lists all properties useful to `uipanel` objects along with valid values and a descriptions of their use. Curly braces { } enclose default values.

Property Name	Description
`BackgroundColor`	Color of the uipanel background
`BorderType`	Type of border around the uipanel area.
`BorderWidth`	Width of the panel border.
`BusyAction`	Interruption of other callback routines
`ButtonDownFcn`	Button-press callback routine
`Children`	All children of the uipanel

Property Name	Description
`Clipping`	Clipping of child axes, uipanels, and uibuttongroups to the uipanel. Does not affect child uicontrols.
`CreateFcn`	Callback routine executed during object creation
`DeleteFcn`	Callback routine executed during object deletion
`FontAngle`	Title font angle
`FontName`	Title font name
`FontSize`	Title font size
`FontUnits`	Title font units
`FontWeight`	Title font weight
`ForegroundColor`	Title font color and/or color of 2-D border line
`HandleVisibility`	Handle accessibility from commandline and GUIs
`HighlightColor`	3-D frame highlight color
`HitTest`	Selectable by mouse click
`Interruptible`	Callback routine interruption mode
`Parent`	Uipanel object's parent
`Position`	Panel position relative to parent figure or uipanel
`ResizeFcn`	User-specified resize routine
`Selected`	Whether object is selected
`SelectionHighlight`	Object highlighted when selected
`ShadowColor`	3-D frame shadow color
`Tag`	User-specified object identifier
`Title`	Title string
`TitlePosition`	Location of title string in relation to the panel

Property Name	Description
UIContextMenu	Associates uicontext menu with the uipanel
Units	Units used to interpret the position vector
UserData	User-specified data
Visible	Uipanel visibility. Note: Controls the Visible property of child axes, uibuttongroups. and uipanels. Does not affect child uicontrols.

BackgroundColor ColorSpec

Color of the uipanel background. A three-element RGB vector or one of the MATLAB predefined names, specifying the background color. See the ColorSpec reference page for more information on specifying color.

BorderType none | {etchedin} | etchedout | beveledin | beveledout | line

Border of the uipanel area. Used to define the panel area graphically. Etched and beveled borders provide a 3-D look. Use the HighlightColor and ShadowColor properties to specify the border color of etched and beveled borders. A line border is 2-D. Use the ForegroundColor property to specify its color.

BorderWidth integer

Width of the panel border. The width of the panel borders in pixels. The default border width is 1 pixel. 3-D borders wider than 3 may not appear correctly at the corners.

BusyAction cancel | {queue}

Callback routine interruption. If a callback is executing and the user triggers an event (such as a mouse click) on an object for which a callback is defined, the callback associated with the new event uses the value of BusyAction to decide whether or not to attempt to interrupt the executing callback.

- If the value is cancel, the event is discarded and the second callback does not execute.

- If the value is `queue`, and the `Interruptible` property of the first callback is `on`, the second callback is added to the event queue and executes in its turn after the first callback finishes execution.

Note If the interrupting callback is a `DeleteFcn` or `CreateFcn` callback or a figure's `CloseRequest` or `ResizeFcn` callback, it interrupts an executing callback regardless of the value of that object's `Interruptible` property. See the `Interruptible` property for information about controlling a callback's interruptibility.

`ButtonDownFcn` string or function handle

Button-press callback routine. A callback routine that executes when you press a mouse button while the pointer is in a 5-pixel wide border around the uipanel. This is useful for implementing actions to interactively modify control object properties, such as size and position, when they are clicked on (using the `selectmoveresize` function, for example).

If you define this routine as a string, the string can be a valid MATLAB expression or the name of an M-file. The expression executes in the MATLAB workspace.

`Children` vector of handles

Children of the uipanel. A vector containing the handles of all children of the uipanel. A `uipanel` object's children are axes, uipanels, uibuttongroups, and uicontrols. You can use this property to reorder the children.

`Clipping` `{on} | off`

Clipping mode. By default, MATLAB clips a uipanel's child axes, uipanels, and uibuttongroups to the uipanel rectangle. If you set `Clipping` to `off`, the axis, uipanel, or uibuttongroup is displayed outside the panel rectangle. This property does not affect child uicontrols which, by default, can display outside the panel rectangle.

`CreateFcn` string or function handle

Callback routine executed during object creation. The specified function executes when MATLAB creates a `uipanel` object. MATLAB sets all property values for the uipanel before executing the `CreateFcn` callback so these values

are available to the callback. Within the function, use `gcbo` to get the handle of the uipanel being created.

Setting this property on an existing uipanel object has no effect.

You can define a default `CreateFcn` callback for all new uipanels. This default applies unless you override it by specifying a different `CreateFcn` callback when you call `uipanel`. For example, the code

```
set(0,'DefaultUipanelCreateFcn','set(gcbo,...
    ''FontName'',''arial'',''FontSize'',12)')
```

creates a default `CreateFcn` callback that runs whenever you create a new panel. It sets the default font name and font size of the uipanel title.

Note Uibuttongroup takes its default property values from uipanel. Defining a default property for all uipanels defines the same default property for all uibuttongroups.

To override this default and create a panel whose `FontName and FontSize` properties are set to different values, call `uipanel` with code similar to

```
hpt = uipanel(...,'CreateFcn','set(gcbo,...
''FontName'',''times'',''FontSize'',14)')
```

Note To override a default `CreateFcn` callback you must provide a new callback and not just provide different values for the specified properties. This is because the `CreateFcn` callback runs after the property values are set, and can override property values you have set explicitly in the `uipushtool` call. In the example above, if instead of redefining the `CreateFcn` property for this uipanel, you had explicitly set `Fontsize` to `14`, the default `CreateFcn` callback would have set `FontSize` back to the system dependent default.

See Function Handle Callbacks for information on how to use function handles to define a callback function.

DeleteFcn string or function handle

Callback routine executed during object deletion. A callback routine that executes when you delete the uipanel object (e.g., when you issue a delete command or clear the figure containing the uipanel). MATLAB executes the routine before destroying the object's properties so these values are available to the callback routine. The handle of the object whose `DeleteFcn` is being executed is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

FontAngle `{normal} | italic | oblique`

Character slant used in the Title. MATLAB uses this property to select a font from those available on your particular system. Setting this property to `italic` or `oblique` selects a slanted version of the font, when it is available on your system.

FontName string

Font family used in the Title. The name of the font in which to display the `Title`. To display and print properly, this must be a font that your system supports. The default font is system dependent. To eliminate the need to hard code the name of a fixed-width font, which may not display text properly on systems that do not use ASCII character encoding (such as in Japan), set `FontName` to the string `FixedWidth` (this string value is case insensitive).

```
set(uicontrol_handle,'FontName','FixedWidth')
```

This then uses the value of the root `FixedWidthFontName` property which can be set to the appropriate value for a locale from `startup.m` in the end user's environment. Setting the root `FixedWidthFontName` property causes an immediate update of the display to use the new font

FontSize integer

Title font size. A number specifying the size of the font in which to display the Title, in units determined by the `FontUnits` property. The default size is system dependent.

FontUnits `inches | centimeters | normalized | {points} |pixels`

Title font size units. `Normalized` units interpret `FontSize` as a fraction of the height of the uipanel. When you resize the uipanel, MATLAB modifies the

screen FontSize accordingly. pixels, inches, centimeters, and points are absolute units (1 point = 1/72 inch).

FontWeight light | {normal} | demi | bold

Weight of characters in the title. MATLAB uses this property to select a font from those available on your particular system. Setting this property to bold causes MATLAB to use a bold version of the font, when it is available on your system.

ForegroundColor ColorSpec

Color used for title font and 2-D border line. A three-element RGB vector or one of the MATLAB predefined names, specifying the font or line color. See the ColorSpec reference page for more information on specifying color.

HandleVisibility {on} | callback | off

Control access to object's handle. This property determines when an object's handle is visible in its parent's list of children. When a handle is not visible in its parent's list of children, it is not returned by functions that obtain handles by searching the object hierarchy or querying handle properties. This includes get, findobj, gca, gcf, gco, newplot, cla, clf, and close. Neither is the handle visible in the parent figure's CurrentObject property. Handles that are hidden are still valid. If you know an object's handle, you can set and get its properties, and pass it to any function that operates on handles.

- Handles are always visible when HandleVisibility is on.
- Setting HandleVisibility to callback causes handles to be visible from within callback routines or functions invoked by callback routines, but not from within functions invoked from the command line. This provides a means to protect GUIs from command-line users, while allowing callback routines to have complete access to object handles.
- Setting HandleVisibility to off makes handles invisible at all times. This may be necessary when a callback routine invokes a function that might potentially damage the GUI (such as evaluating a user-typed string), and so temporarily hides its own handles during the execution of that function.

You can set the root ShowHiddenHandles property to on to make all handles visible, regardless of their HandleVisibility settings. This does not affect the values of the HandleVisibility properties.

HighlightColor ColorSpec

3-D frame highlight color. A three-element RGB vector or one of the MATLAB predefined names, specifying the highlight color. See the ColorSpec reference page for more information on specifying color.

HitTest {on} | off

Selectable by mouse click. HitTest determines if the figure can become the current object (as returned by the gco command and the figure CurrentObject property) as a result of a mouse click on the figure. If HitTest is off, clicking the figure sets the CurrentObject to the empty matrix.

Interruptible {on} | off

Callback routine interruption mode. If a callback is executing and the user triggers an event (such as a mouse click) on an object for which a callback is defined, that callback attempts to interrupt the first callback. MATLAB processes the callbacks according to these factors:

- The Interruptible property of the object whose callback is executing
- Whether the executing callback contains drawnow, figure, getframe, pause, or waitfor statements
- The BusyAction property of the object whose callback is waiting to execute

If the Interruptible property of the object whose callback is executing is on (the default), the callback can be interrupted. Whenever the callback calls one of the drawnow, figure, getframe, pause, or waitfor functions, the function processes any events in the event queue, including the waiting callback, before performing its defined task.

If the Interruptible property of the object whose callback is executing is off, the callback cannot be interrupted (except by certain callbacks; see the note below). The BusyAction property of the object whose callback is waiting to execute determines what happens to the callback.

Note If the interrupting callback is a DeleteFcn or CreateFcn callback or a figure's CloseRequest or ResizeFcn callback, it interrupts an executing callback regardless of the value of that object's Interruptible property. The interrupting callback starts execution at the next drawnow, figure, getframe, pause, or waitfor statement. A figure's WindowButtonDownFcn callback

routine, or an object's `ButtonDownFcn` or `Callback` routine are processed according to the rules described above.

`Parent` handle

Uipanel parent. The handle of the uipanel's parent figure, uipanel, or uibuttongroup. You can move a uipanel object to another figure, uipanel, or uibuttongroup by setting this property to the handle of the new parent.

`Position` position rectangle

Size and location of uipanel relative to parent. The rectangle defined by this property specifies the size and location of the panel within the parent figure window, uipanel, or uibuttongroup. Specify `Position` as

```
[left bottom width height]
```

`left` and `bottom` are the distance from the lower-left corner of the parent object to the lower-left corner of the `uipanel` object. `width` and `height` are the dimensions of the uipanel rectangle, including the title. All measurements are in units specified by the `Units` property.

`ResizeFcn` string or function handle

Resize callback routine. MATLAB executes this callback routine whenever a user resizes the uipanel and the figure `Resize` property is set to `on`, or in GUIDE, the Resize behavior option is set to `Other`. You can query the uipanel `Position` property to determine its new size and position. During execution of the callback routine, the handle to the figure being resized is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

You can use `ResizeFcn` to maintain a GUI layout that is not directly supported by the MATLAB `Position`/`Units` paradigm.

See Function Handle Callbacks for information on how to use function handles to define the callback function.

See Resize Behavior for information on creating resize functions using GUIDE.

`Selected` `on | off` (read only)

Is object selected? This property indicates whether the figure is selected. When this property is `on`, MATLAB displays selection handles if the `SelectionHighlight` property is also `on`. You can, for example, define the

ButtonDownFcn to set this property, allowing users to select the object with the mouse.

SelectionHighlight {on} | off

Object highlighted when selected. When the Selected property is on, MATLAB indicates the selected state by drawing four edge handles and four corner handles. When SelectionHighlight is off, MATLAB does not draw the handles.

ShadowColor ColorSpec

3-D frame shadow color. A three-element RGB vector or one of the MATLAB predefined names, specifying the shadow color. See the ColorSpec reference page for more information on specifying color.

Tag string

User-specified object identifier. The Tag property provides a means to identify graphics objects with a user-specified label. You can define Tag as any string.

With the findobj function, you can locate an object with a given Tag property value. This saves you from defining object handles as global variables. For example, this function call returns the handles of all children (of the specified figures) that have the Tag value 'FormatTb'.

```
h = findobj(figurehandles,'Tag','FormatTb')
```

Title string

Title string. The text displayed in the panel title. You can position the title using the TitlePosition property.

If the string value is specified as a cell array of strings or padded string matrix, only the first string of a cell array or of a padded string matrix is displayed; the rest are ignored. Vertical slash ('|') characters are not interpreted as line breaks and instead show up in the text displayed in the uipanel title.

Setting a property value to default, remove, or factory produces the effect described in Setting Default Values. To set Title to one of these words, you must precede the word with the backslash character. For example,

```
hp = uipanel(...,'Title','\Default');
```

TitlePosition `{lefttop} | centertop | righttop | leftbottom | centerbottom | rightbottom`

Location ofthe title. This property determines the location of the title string, in relation to the uipanel.

UIContextMenu handle

Associate a context menu with a uipanel. Assign this property the handle of a `Uicontextmenu` object. MATLAB displays the context menu whenever you right-click the `uipanel`. Use the `uicontextmenu` function to create the context menu.

Units `inches | centimeters | {normalized} | points | pixels | characters`

Units of measurement. MATLAB uses these units to interpret the `Position` property. All units are measured from the lower-left corner of the figure window.

- `Normalized` units map the lower-left corner of the figure window to (0,0) and the upper-right corner to (1.0,1.0).
- `pixels`, `inches`, `centimeters`, and `points` are absolute units (1 point = 1/72 inch).
- `Character` units are characters using the default system font; the width of one character is the width of the letter `x`, the height of one character is the distance between the baselines of two lines of text.

If you change the value of `Units`, it is good practice to return it to its default value after completing your computation so as not to affect other functions that assume `Units` is set to the default value.

UserData matrix

User-specified data. Any data you want to associate with the `uipanel` object. MATLAB does not use this data, but you can access it using `set` and `get`.

Visible `{on} | off`

Uipanel visibility. By default, a `uipanel` object is visible. When set to `off`, the uipanel is not visible, but still exists and you can query and set its properties.

Note The value of a uipanel's `Visible` property also controls the `Visible` property of child axes, uipanels, and uibuttongroups. This property does not affect the `Visible` property of child uicontrols.

Purpose

Create a push button on the current or specified toolbar

Syntax

```
htt = uipushtool('PropertyName1',value1,...
   'PropertyName2',value2,...)
htt = uipushtool(ht,...)
```

Description

`uipushtool('PropertyName1',value1,'PropertyName2',value2,...)` creates a push button on the uitoolbar at the top of the current figure window, and returns a handle to it. `uipushtool` assigns the specified property values, and assigns default values to the remaining properties. You can change the property values at a later time using the `set` function.

Type `get(htt)` to see a list of uipushtool object properties and their current values. Type `set(htt)` to see a list of uipushtool object properties that you can set and their legal property values. See the Uipushtool Properties reference page for more information.

`uipushtool(ht,...)` creates a button with `ht` as a parent. `ht` must be a uitoolbar handle.

Remarks

`uipushtool` accepts property name/property value pairs, as well as structures and cell arrays of properties as input arguments.

Uipushtools only appear in figures whose `WindowStyle` is `normal`. If a figure containing a uitoolbar and its uipushtool children is changed to `WindowStyle modal`, the uipushtools still exist and are contained in the `Children` list of the uitoolbar, but are not displayed until the `WindowStyle` is changed to `normal`.

Properties

This table lists all properties useful to `uipushtool` objects, grouping them by function. Each property name acts as a link to a more detailed description of the property.

Property Name	Property Description	Property Value
Controlling Style and Appearance		
`CData`	Truecolor image displayed on the uipushtool	Value: m-by-n-by-3 array

Property Name	Property Description	Property Value
`Separator`	Separator line mode	Value: `on`, `off` Default: `off`
`Visible`	Uipushtool visibility	Value: `on`, `off` Default: `on`
General Information About the Object		
`BeingDeleted`	This object is being deleted	Value: `on`, `off` (read-only) Default: `off`
`Enable`	Enable or disable the uipushtool	Value: `on`, `inactive`, `off` Default: `on`
`Parent`	Uipushtool object's parent toolbar.	Value: handle
`Tag`	User-specified object identifier	Value: string
`TooltipString`	Content of object's tooltip	Value: string
`Type`	Class of graphics object	Value: string (read-only) Default: `uipushtool`
`UserData`	User-specified data	Value: array
Controlling Callback Routine Execution		
`BusyAction`	Interruption of other callback routines	Value: `cancel`, `queue` Default: `queue`
`ClickedCallback`	Control action.	Value: string or function handle
`CreateFcn`	Callback routine executed during object creation	Value: string or function handle
`DeleteFcn`	Callback routine executed during object deletion	Value: string or function handle
`Interruptible`	Callback routine interruption mode	Value: `on`, `off` Default: `on`

Property Name	Property Description	Property Value
Controlling Access to Objects		
`HandleVisibility`	Handle accessibility from command line and code associated with the GUIs.	Value: `on`, `callback`, `off` Default: `on`

Examples

This example creates a uitoolbar object and places a uipushtool object on it.

```
h = figure('ToolBar','none')
ht = uitoolbar(h)
a = [.05:.05:0.95];
b(:,:,1) = repmat(a,19,1)';
b(:,:,2) = repmat(a,19,1);
b(:,:,3) = repmat(flipdim(a,2),19,1);
hpt = uipushtool(ht,'CData',b,'TooltipString','Hello')
```



Object Hierarchy



See Also

`get`, `set`, `uicontrol`, `uitoggletool`, `uitoolbar`

Modifying Properties

You can set and query graphics object properties in two ways:

- The Property Inspector is an interactive tool that enables you to see and change object property values. The Property inspector is available from GUIDE, or use the `inspect` function at the command line.
- The `set` and `get` functions enable you to set and query the values of properties.

You can set default Uipushtool properties by typing:

```
set(h,'DefaultUipushtool<PropertyName>',PropertyValue...)
```

Where h can be the root handle (0), a figure handle, a uitoolbar handle, or a uipushtool handle. *`PropertyName`* is the name of the Uipushtool property and `PropertyValue` is the value you specify as the default for that property.

For more information about changing the default value of a property see Setting Default Property Values.

Uipushtool Properties

This section lists all properties useful to `uipushtool` objects along with valid values and a descriptions of their use. Curly braces { } enclose default values.

Property	Purpose
`BeingDeleted`	This object is being deleted.
`BusyAction`	Callback routine interruption.
`CData`	Truecolor image displayed on the control.
`ClickedCallback`	Control action.
`CreateFcn`	Callback routine executed during object creation.
`DeleteFcn`	Delete uipushtool callback routine.
`Enable`	Enable or disable the uipushtool.
`HandleVisibility`	Control access to object's handle.
`Interruptible`	Callback routine interruption mode.
`Parent`	Handle of uipushtool's parent.

Property (Continued)	Purpose
Separator	Separator line mode
Tag	User-specified object label.
TooltipString	Content of object's tooltip.
Type	Object class.
UserData	User specified data.
Visible	Uipushtool visibility.

BeingDeleted on | {off} (read only)

This object is being deleted. The BeingDeleted property provides a mechanism that you can use to determine if objects are in the process of being deleted. MATLAB sets the BeingDeleted property to on when the object's delete function callback is called (see the DeleteFcn property) It remains set to on while the delete function executes, after which the object no longer exists.

For example, some functions may not need to perform actions on objects that are being deleted, and therefore, can check the object's BeingDeleted property before acting.

BusyAction cancel | {queue}

Callback routine interruption. If a callback is executing and the user triggers an event (such as a mouse click) on an object for which a callback is defined, the callback associated with the new event uses the value of BusyAction to decide whether or not to attempt to interrupt the executing callback.

- If the value is cancel, the event is discarded and the second callback does not execute.
- If the value is queue, and the Interruptible property of the first callback is on, the second callback is added to the event queue and executes in its turn after the first callback finishes execution.

Note If the interrupting callback is a DeleteFcn or CreateFcn callback or a figure's CloseRequest or ResizeFcn callback, it interrupts an executing

callback regardless of the value of that object's `Interruptible` property. See the `Interruptible` property for information about controlling a callback's interruptibility.

`CData` `3-dimensional array`

Truecolor image displayed on control. An *n*-by-*m*-by-3 array of RGB values that defines a truecolor image displayed on either a push button or toggle button. Each value must be between 0.0 and 1.0. The largest image that fits on the push tool is 20-by-20. If the array is larger, only the center 20-by-20 part of the array is used.

`ClickedCallback` `string or function handle`

Control action. A routine that executes when the uipushtool's `Enable` property is set to `on`, and you press a mouse button while the pointer is on the push tool itself or in a 5-pixel wide border around it.

`CreateFcn` string or function handle

Callback routine executed during object creation. The specified function executes when MATLAB creates a uipushtool object. MATLAB sets all property values for the uipushtool before executing the `CreateFcn` callback so these values are available to the callback. Within the function, use `gcbo` to get the handle of the push tool being created.

Setting this property on an existing uipushtool object has no effect.

You can define a default `CreateFcn` callback for all new uipushtools. This default applies unless you override it by specifying a different `CreateFcn` callback when you call `uipushtool`. For example, the code

```
imga(:,:,1) = rand(20);
imga(:,:,2) = rand(20);
imga(:,:,3) = rand(20);
set(0,'DefaultUipushtoolCreateFcn','set(gcbo,''Cdata'',imga)'
```

creates a default `CreateFcn` callback that runs whenever you create a new push tool. It sets the default image `imga` on the push tool.

To override this default and create a push tool whose `Cdata` property is set to a different image, call `uipushtool` with code similar to

```
a = [.05:.05:0.95];
imgb(:,:,1) = repmat(a,19,1)';
imgb(:,:,2) = repmat(a,19,1);
imgb(:,:,3) = repmat(flipdim(a,2),19,1);
hpt = uipushtool(...,'CreateFcn','set(gcbo,''CData'',imgb)',...)
```

Note To override a default `CreateFcn` callback you must provide a new callback and not just provide different values for the specified properties. This is because the `CreateFcn` callback runs after the property values are set, and can override property values you have set explicitly in the `uipushtool` call. In the example above, if instead of redefining the `CreateFcn` property for this push tool, you had explicitly set `CData` to `imgb`, the default `CreateFcn` callback would have set `CData` back to `imga`.

See Function Handle Callbacks for information on how to use function handles to define a callback function.

`DeleteFcn` string or function handle

Callback routine executed during object deletion. A callback routine that executes when you delete the uipushtool object (e.g., when you call the `delete` function or cause the figure containing the uipushtool to reset). MATLAB executes the routine before destroying the object's properties so these values are available to the callback routine.

The handle of the object whose `DeleteFcn` is being executed is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define a callback function.

`Enable` `{on} | off`

Enable or disable the uipushtool. This property controls how uipushtools respond to mouse button clicks, including which callback routines execute.

- `on` – The uipushtool is operational (the default).
- `off` – The uipushtool is not operational and its image (set by the `Cdata` property) is grayed out.

When you left-click on a uipushtool whose `Enable` property is `on`, MATLAB performs these actions in this order:

1. Sets the figure's `SelectionType` property.
2. Executes the push tool's `ClickedCallback` routine.
3. Does not set the figure's `CurrentPoint` property and does not execute the figure's `WindowButtonDownFcn` callback.

When you left-click on a uipushtool whose `Enable` property is `off`, or when you right-click a uipushtool whose `Enable` property has any value, MATLAB performs these actions in this order:

1. Sets the figure's `SelectionType` property.
2. Sets the figure's `CurrentPoint` property.
3. Executes the figure's `WindowButtonDownFcn` callback.
4. Does not execute the push tool's `ClickedCallback` routine.

`HandleVisibility` `{on} | callback | off`

Control access to object's handle. This property determines when an object's handle is visible in its parent's list of children. When a handle is not visible in its parent's list of children, it is not returned by functions that obtain handles by searching the object hierarchy or querying handle properties. This includes `get`, `findobj`, `gca`, `gcf`, `gco`, `newplot`, `cla`, `clf`, and `close`. Neither is the handle visible in the parent figure's `CurrentObject` property. Handles that are hidden are still valid. If you know an object's handle, you can `set` and `get` its properties, and pass it to any function that operates on handles.

- Handles are always visible when `HandleVisibility` is `on`.
- Setting `HandleVisibility` to `callback` causes handles to be visible from within callback routines or functions invoked by callback routines, but not from within functions invoked from the command line. This provides a means to protect GUIs from command-line users, while allowing callback routines to have complete access to object handles.
- Setting `HandleVisibility` to `off` makes handles invisible at all times. This may be necessary when a callback routine invokes a function that might potentially damage the GUI (such as evaluating a user-typed string), and so temporarily hides its own handles during the execution of that function.

You can set the root ShowHiddenHandles property to on to make all handles visible, regardless of their HandleVisibility settings. This does not affect the values of the HandleVisibility properties.

Interruptible {on} | off

Callback routine interruption mode. If a callback is executing and the user triggers an event (such as a mouse click) on an object for which a callback is defined, that callback attempts to interrupt the first callback. MATLAB processes the callbacks according to these factors:

- The Interruptible property of the object whose callback is executing
- Whether the executing callback contains drawnow, figure, getframe, pause, or waitfor statements
- The BusyAction property of the object whose callback is waiting to execute

If the Interruptible property of the object whose callback is executing is on (the default), the callback can be interrupted. Whenever the callback calls one of the drawnow, figure, getframe, pause, or waitfor functions, the function processes any events in the event queue, including the waiting callback, before performing its defined task.

If the Interruptible property of the object whose callback is executing is off, the callback cannot be interrupted (except by certain callbacks; see the note below). The BusyAction property of the object whose callback is waiting to execute determines what happens to the callback.

Note If the interrupting callback is a DeleteFcn or CreateFcn callback or a figure's CloseRequest or ResizeFcn callback, it interrupts an executing callback regardless of the value of that object's Interruptible property. The interrupting callback starts execution at the next drawnow, figure, getframe, pause, or waitfor statement. A figure's WindowButtonDownFcn callback routine, or an object's ButtonDownFcn or Callback routine are processed according to the rules described above.

Parent handle

Uipushtool parent. The handle of the uipushtool's parent toolbar. You can move a uipushtool object to another toolbar by setting this property to the handle of the new parent.

Separator `on | {off}`

Separator line mode. Setting this property to `on` draws a dividing line to the left of the uipushtool.

Tag string

User-specified object identifier. The `Tag` property provides a means to identify graphics objects with a user-specified label. You can define `Tag` as any string.

With the `findobj` function, you can locate an object with a given `Tag` property value. This saves you from defining object handles as global variables. For example, this function call returns the handles of all children (of the specified toolbars) that have the `Tag` value `'Copy'`.

```
h = findobj(uitoolbarhandles,'Tag','Copy')
```

TooltipString `string`

Content of tooltip for object. The `TooltipString` property specifies the text of the tooltip associated with the uipushtool. When the user moves the mouse pointer over the control and leaves it there, the tooltip is displayed.

Type `string` (read-only)

Object class. This property identifies the kind of graphics object. For uipushtool objects, `Type` is always the string `'uipushtool'`.

UserData array

User specified data. You can specify `UserData` as any array you want to associate with the uipushtool object. The object does not use this data, but you can access it using the `set` and `get` functions.

Visible `{on} | off`

Uipushtool visibility. By default, all uipushtools are visible. When set to `off`, the uipushtool is not visible, but still exists and you can query and set its properties.

uiputfile

Purpose

Standard dialog box for saving files

Syntax

```
uiputfile
uiputfile('FilterSpec')
uiputfile('FilterSpec','DialogTitle')
uiputfile('FilterSpec','DialogTitle', 'DefaultName')
uiputfile(...,'Location',[x y])
[FileName,PathName] = uiputfile(...)
[FileName,PathName,FilterIndex] = uiputfile(...)
```

Description

`uiputfile` displays a dialog box used to select a file for saving. The dialog box lists the files and directories in the current directory.

`uiputfile('FilterSpec')` displays a dialog box that lists files in the current directory. `FilterSpec` determines what files are displayed initially in the dialog box. For example `'*.m'` lists all MATLAB M-files.

If `FilterSpec` is a string or cell array, `uiputfile` appends `'All Files'` to the list of file types. If `FilterSpec` is a cell array, the first column is used as the list of extensions, and the second column is used as the list of descriptions. `FilterSpec` can also be a filename. In this case the filename becomes the default filename and the file's extension is used as the default filter. If `FilterSpec` is not specified, `uiputfile` uses the default list of file types (i.e., all MATLAB files).

`uiputfile('FilterSpec','DialogTitle')` displays a dialog box that has the title `DialogTitle`. To use the default file types and specify a dialog title, enter

```
uiputfile('','DialogTitle')
```

`uiputfile('FilterSpec','DialogTitle','DefaultName')` displays a dialog box in which a specified string, in this case `'DefaultName'`, appears in the **File name** field. `'Default Name'` can be a filename or the name of a directory. If it is the name of a directory, you must follow it with a slash `(/)` or backslash `(\)` separator.

`uiputfile(...,'Location',[x y])` positions the dialog box at screen position `[x,y]`, where `x` and `y` are the distances in pixel units from the left and top edges of the screen. This feature is supported only on UNIX platforms.

`[FileName,PathName] = uiputfile(...)` returns the name and path of the file selected in the dialog box. If the user clicks the **Cancel** button or closes the dialog window, `FileName` and `PathName` are set to `0`.

`[FileName,PathName,FilterIndex] = uiputfile(...)` returns the index of the filter selected in the dialog box. The indexing starts at 1. If the user clicks the **Cancel** button or closes the dialog window, `FilterIndex` is set to `0`.

Remarks

If the user specifies or selects an existing filename, a warning message is displayed asking whether the user wants to overwrite the file. If the user selects `Yes`, the existing file is overwritten and `uiputfile` returns successfully. If the user selects `No`, control returns to the dialog. For a successful return, the specified filename must be valid.

Examples

Example 1. The following statement displays a dialog box titled `'Save file name'` with the **Filename** field set to `animinit.m` and the filter set to `M-files (*.m)`. Because `FilterSpec` is a string, the filter also includes `All Files (*.*)`

```
[file,path] = uiputfile('animinit.m','Save file name');
```



Example 2. The following statement displays a dialog box titled `'Save Workspace As'` with the filter specifier set to MAT-files.

```
[file,path] = uiputfile('*.mat','Save Workspace As');
```



Example 3. To display several file types in the **Save as type** list box, separate each file extension with a semicolon, as in the following code. Note that `uiputfile` displays a default description for each known file type, such as "Simulink Models" for `.mdl` files.

```
[filename, pathname] = uiputfile( ...
 {'*.m';'*.mdl';'*.mat';'*.*'}, ...
 'Save as');
```



Example 4. If you want to create a list of file types and give them descriptions that are different from the defaults, use a cell array, as in the following code. This example also associates multiple file types with the `'MATLAB Files'` description.

```
[filename, pathname, filterindex] = uiputfile( ...
{'*.m;*.fig;*.mat;*.mdl','MATLAB Files (*.m,*.fig,*.mat,*.mdl)';
 '*.m', 'M-files (*.m)'; ...
 '*.fig','Figures (*.fig)'; ...
 '*.mat','MAT-files (*.mat)'; ...
 '*.mdl','Models (*.mdl)'; ...
 '*.*',  'All Files (*.*)'}, ...
 'Save as');
```

The first column of the cell array contains the file extensions, while the second contains the descriptions you want to provide for the the file types. Note that the first entry of column one contains several extensions, separated by semicolons, all of which are associated with the description `'MATLAB Files (*.m,*.fig,*.mat,*.mdl)'`. The code produces the dialog box shown in the following figure.



Example 5. The following code checks for the existence of the file and displays a message about the result of the open operation.

```
[filename, pathname] = uigetfile('*.m', 'Pick an M-file');
if isequal(filename,0) | isequal(pathname,0)
   disp('User selected Cancel')
else
   disp(['User selected',fullfile(pathname,filename)])
end
```

See Also

uigetfile

Purpose

Control program execution

Syntax

```
uiwait(h)
uiwait(h,timeout)
uiresume(h)
```

Description

The `uiwait` and `uiresume` functions block and resume MATLAB program execution.

`uiwait` blocks execution until `uiresume` is called or the current figure is deleted. This syntax is the same as `uiwait(gcf)`.

`uiwait(h)` blocks execution until `uiresume` is called or the figure `h` is deleted.

`uiwait(h,timeout)` blocks execution until `uiresume` is called, the figure `h` is deleted, or `timeout` seconds elapse.

`uiresume(h)` resumes the M-file execution that `uiwait` suspended.

Remarks

When creating a dialog, you should have a uicontrol with a callback that calls `uiresume` or a callback that destroys the dialog box. These are the only methods that resume program execution after the `uiwait` function blocks execution.

`uiwait` is a convenient way to use the `waitfor` command. You typically use it in conjunction with a dialog box. It provides a way to block the execution of the M-file that created the dialog, until the user responds to the dialog box. When used in conjunction with a modal dialog, `uiwait/uiresume` can block the execution of the M-file *and* restrict user interaction to the dialog only.

See Also

`uicontrol`, `uimenu`, `waitfor`, `figure`, `dialog`

uisave

Purpose

Display a dialog for saving workspace variables

Syntax

```
uisave
```

Description

`uisave` displays a dialog for saving workspace variables to a MAT-file, as shown in the figure below.



If you type a name in the **File name** field, such as `my_vars`, and click **Save**, the dialog saves all workspace variables as `my_vars.mat`.

Note `uisave` cannot be compiled. If you want to create a dialog that can be compiled, use `uiputfile`.

See Also

`uigetfile`, `uiputfile`, `uiopen`

Purpose

Set an object's `ColorSpec` from a dialog box interactively

Syntax

```
c = uisetcolor(h_or_c, 'DialogTitle');
```

Description

`uisetcolor` displays a dialog box for the user to fill in, then applies the selected color to the appropriate property of the graphics object identified by the first argument.

`h_or_c` can be either a handle to a graphics object or an RGB triple. If you specify a handle, it must specify a graphics object that have a `Color` property. If you specify a color, it must be a valid RGB triple (e.g., [1 0 0] for red). The color specified is used to initialize the dialog box. If no initial RGB is specified, the dialog box initializes the color to black.

`DialogTitle` is a string that is used as the title of the dialog box.

`c` is the RGB value selected by the user. If the user presses **Cancel** from the dialog box, or if any error occurs, `c` is set to the input RGB triple, if provided; otherwise, it is set to 0.

See Also

`ColorSpec`

uisetfont

Purpose

Modify font characteristics for objects interactively

Syntax

```
uisetfont
uisetfont(h)
uisetfont(S)
uisetfont(h,'DialogTitle')
uisetfont(S,'DialogTitle')
S = uisetfont(...)
```

Description

`uisetfont` enables you to change font properties (`FontName`, `FontUnits`, `FontSize`, `FontWeight`, and `FontAngle`) for a text, axes, or uicontrol object. The function returns a structure consisting of font properties and values. You can specify an alternate title for the dialog box.

`uisetfont` displays the dialog box and returns the selected font properties.

`uisetfont(h)` displays a dialog box, initializing the font property values with the values of those properties for the object whose handle is `h`. Selected font property values are applied to the current object. If a second argument is supplied, it specifies a name for the dialog box.

`uisetfont(S)` displays a dialog box, initializing the font property values with the values defined for the specified structure (`S`). `S` must define legal values for one or more of these properties: `FontName`, `FontUnits`, `FontSize`, `FontWeight`, and `FontAngle` and the field names must match the property names exactly. If other properties are defined, they are ignored. If a second argument is supplied, it specifies a name for the dialog box.

`uisetfont('DialogTitle')` displays a dialog box with the title `DialogTitle` and returns the values of the font properties selected in the dialog box.

If a left-hand argument is specified, the properties `FontName`, `FontUnits`, `FontSize`, `FontWeight`, and `FontAngle` are returned as fields in a structure. If the user presses **Cancel** from the dialog box or if an error occurs, the output value is set to 0.

Example

These statements create a text object, then display a dialog box (labeled Update Font) that enables you to change the font characteristics:

```
h = text(.5,.5,'Figure Annotation');
```

```
uisetfont(h,'Update Font')
```

These statements create two push buttons, then set the font properties of one based on the values set for the other:

```
% Create push button with string ABC
c1 = uicontrol('Style', 'pushbutton', ...
     'Position', [10 10 100 20], 'String', 'ABC');
% Create push button with string XYZ
c2 = uicontrol('Style', 'pushbutton', ...
     'Position', [10 50 100 20], 'String', 'XYZ');
% Display set font dialog box for c1, make selections, save to d
d = uisetfont(c1);
% Apply those settings to c2
set(c2, d)
```

See Also

axes, text, uicontrol

uistack

Purpose

Restack objects

Syntax

```
uistack(h)
uistack(h, stackopt)
```

Description

`uistack` enables you to change the stacking order of objects.

`uistack(h, stackopt)` moves `h` in the stacking order, where *`stackopt`* is one of the following:

- `'up'` – moves `h` up one position in the stacking order
- `'down'` – moves `h` down one position in the stacking order
- `'top'` – moves `h` to the top of the current stack
- `'bottom'` – moves `h` to the bottom of the current stack

`uistack(h, 'up', n)` moves `h` up `n` steps

`uistack(h, 'down', n)` moves `h` down `n` steps

Example

The following code moves the child that is third in the stacking order of the figure handle `hObject` down two positions.

```
v = allchild(hObject)
uistack(v(3), 'down', 2)
```

Purpose

Create a toggle button on the current or specified toolbar

Syntax

```
htt = uitoggletool('PropertyName1',value1,...
   'PropertyName2',value2,...)
htt = uitoggletool(ht,...)
```

Description

`uitoggletool('PropertyName1',value1,'PropertyName2',value2,...)` creates a toggle button on the uitoolbar at the top of the current figure window, and returns a handle to it. `uitoggletool` assigns the specified property values, and assigns default values to the remaining properties. You can change the property values at a later time using the `set` function.

Type `get(htt)` to see a list of uitoggletool object properties and their current values. Type `set(htt)` to see a list of uitoggletool object properties you can set and legal property values. See the Uitoggletool Properties reference page for more information.

`uitoggletool(ht,...)` creates a button with `ht` as a parent. `ht` must be a uitoolbar handle.

Remarks

`uitoggletool` accepts property name/property value pairs, as well as structures and cell arrays of properties as input arguments.

Uitoggletools only appear in figures whose `WindowStyle` is `normal`. If a figure containing a uitoolbar and its uitoggletool children is changed to `WindowStyle modal`, the uitoggletools still exist and are contained in the `Children` list of the uitoolbar, but are not displayed until the `WindowStyle` is changed to `normal`.

Properties

This table lists all properties useful to `uitoggletool` objects, grouping them by function. Each property name acts as a link to a more detailed description of the property.

Property Name	Property Description	Property Value
Controlling Style and Appearance		
`CData`	Truecolor image displayed on the uitoggletool	Value: m-by-n-by-3 array

Property Name	Property Description	Property Value
`Separator`	Separator line mode	Value: `on`, `off` Default: `off`
`Visible`	Uitoggletool visibility	Value: `on`, `off` Default: `on`
General Information About the Object		
`BeingDeleted`	This object is being deleted	Value: `on`, `off` (read-only) Default: `off`
`Enable`	Enable or disable the uitoggletool	Value: `on`, `inactive`, `off` Default: `on`
`Parent`	Uitoggletool object's parent toolbar	Value: handle
`State`	Uioggletool state	Value: `on`, `off` Default: `off`
`Tag`	User-specified object identifier	Value: string
`TooltipString`	Content of object's tooltip	Value: string
`Type`	Class of graphics object	Value: string (read-only) Default: `uitoggletool`
`UserData`	User-specified data	Value: array
Controlling Callback Routine Execution		
`BusyAction`	Interruption of other callback routines	Value: `cancel`, `queue` Default: `queue`
`ClickedCallback`	Control action independent of toggle tool position	Value: string or function handle
`CreateFcn`	Callback routine executed during object creation	Value: string or function handle
`DeleteFcn`	Callback routine executed during object deletion	Value: string or function handle

Property Name	Property Description	Property Value
`Interruptible`	Callback routine interruption mode	Value: `on`, `off` Default: `on`
`OffCallback`	Control action when uitoggletool is set to the off position	Value: string or function handle
`OnCallback`	Control action when uitoggletool is set to the on position	Value: string or function handle
Controlling Access to Objects		
`HandleVisibility`	Handle accessibility from command line and code associated with the GUIs	Value: `on`, `callback`, `off` Default: `on`

Examples

This example creates a `uitoolbar` object and places a `uitoggletool` object on it.

```
h = figure('ToolBar','none')
ht = uitoolbar(h)
a(:,:,1) = rand(20);
a(:,:,2) = rand(20);
a(:,:,3) = rand(20);
htt = uitoggletool(ht,'CData',a,'TooltipString','Hello')
```



Object Hierarchy



See Also

`get`, `set`, `uicontrol`, `uipushtool`, `uitoolbar`

Modifying Properties

You can set and query graphics object properties in two ways:

- The Property Inspector is an interactive tool that enables you to see and change object property values. The Property inspector is available from GUIDE, or use the `inspect` function at the command line.
- The `set` and `get` functions enable you to set and query the values of properties.

You can set default Uitoggletool properties by typing:

```
set(h,'DefaultUitoggletool<PropertyName>',PropertyValue...)
```

Where h can be the root handle (0), a figure handle, a uitoolbar handle, or a uitoggletool handle. *`PropertyName`* is the name of the Uitoggletool property and `PropertyValue` is the value you specify as the default for that property.

For more information about changing the default value of a property see Setting Default Property Values.

Properties

This section lists all properties useful to `uitoggletool` objects along with valid values and a descriptions of their use. Curly braces { } enclose default values.

Property	Purpose
`BeingDeleted`	This object is being deleted.
`BusyAction`	Callback routine interruption.
`CData`	Truecolor image displayed on the toggle tool.
`ClickedCallback`	Control action independent of the toggle tool position.
`CreateFcn`	Callback routine executed during object creation.
`DeleteFcn`	Callback routine executed during object deletion.
`Enable`	Enable or disable the uitoggletool.
`HandleVisibility`	Control access to object's handle.
`Interruptible`	Callback routine interruption mode.

Property (Continued)	Purpose
OffCallback	Control action when toggle tool is set to the off position.
OnCallback	Control action when toggle tool is set to the on position.
Parent	Handle of uitoggletool's parent toolbar.
Separator	Separator line mode.
State	Uitoggletool state.
Tag	User-specified object label.
TooltipString	Content of object's tooltip.
Type	Object class.
UserData	User specified data.
Visible	Uitoggletool visibility.

BeingDeleted on | {off} (read only)

This object is being deleted. The BeingDeleted property provides a mechanism that you can use to determine if objects are in the process of being deleted. MATLAB sets the BeingDeleted property to on when the object's delete function callback is called (see the DeleteFcn property) It remains set to on while the delete function executes, after which the object no longer exists.

For example, some functions may not need to perform actions on objects that are being deleted, and therefore, can check the object's BeingDeleted property before acting.

BusyAction cancel | {queue}

Callback routine interruption. If a callback is executing and the user triggers an event (such as a mouse click) on an object for which a callback is defined, the callback associated with the new event uses the value of BusyAction to decide whether or not to attempt to interrupt the executing callback.

- If the value is `cancel`, the event is discarded and the second callback does not execute.
- If the value is `queue`, and the `Interruptible` property of the first callback is `on`, the second callback is added to the event queue and executes in its turn after the first callback finishes execution.

Note If the interrupting callback is a `DeleteFcn` or `CreateFcn` callback or a figure's `CloseRequest` or `ResizeFcn` callback, it interrupts an executing callback regardless of the value of that object's `Interruptible` property. See the `Interruptible` property for information about controlling a callback's interruptibility.

`CData` `3-dimensional array`

Truecolor image displayed on control. An *n*-by-*m*-by-3 array of RGB values that defines a truecolor image displayed on either a push button or toggle button. Each value must be between 0.0 and 1.0. The largest image that fits on the toggle tool is 20-by-20. If the array is larger, only the center 20-by-20 part of the array is used.

`ClickedCallback` string or function handle

Control action independent of the toggle tool position. A routine that executes after either the `OnCallback` routine or `OffCallback` routine runs to completion. The uitoggletool's `Enable` property must be set to `on`.

`CreateFcn` string or function handle

Callback routine executed during object creation. The specified function executes when MATLAB creates a uitoggletool object. MATLAB sets all property values for the uitoggletool before executing the `CreateFcn` callback so these values are available to the callback. Within the function, use `gcbo` to get the handle of the toggle tool being created.

Setting this property on an existing uitoggletool object has no effect.

You can define a default `CreateFcn` callback for all new uitoggletools. This default applies unless you override it by specifying a different `CreateFcn` callback when you call `uitoggletool`. For example, the statement,

```
set(0,'DefaultUitoggletoolCreateFcn','set(gcbo,''Enable'',...
```

```
''off'')'
```

creates a default `CreateFcn` callback that runs whenever you create a new toggle tool. It sets the toggle tool `Enable` property to `off`.

To override this default and create a toggle tool whose `Enable` property is set to `on`, you could call `uitoggletool` with code similar to

```
htt = uitoggletool(...,'CreateFcn','set(gcbo,''Enable'',...
                   ''on'')',...)
```

Note To override a default `CreateFcn` callback you must provide a new callback and not just provide different values for the specified properties. This is because the `CreateFcn` callback runs after the property values are set, and can override property values you have set explicitly in the `uitoggletool` call. In the example above, if instead of redefining the `CreateFcn` property for this toggle tool, you had explicitly set `Enable` to `on`, the default `CreateFcn` callback would have set `CData` back to `off`.

See Function Handle Callbacks for information on how to use function handles to define a callback function.

`DeleteFcn` string or function handle

Callback routine executed during object deletion. A callback routine that executes when you delete the uitoggletool object (e.g., when you call the `delete` function or cause the figure containing the uitoggletool to reset). MATLAB executes the routine before destroying the object's properties so these values are available to the callback routine.

The handle of the object whose `DeleteFcn` is being executed is accessible only through the root `CallbackObject` property, which you can query using `gcbo`.

See Function Handle Callbacks for information on how to use function handles to define a callback function.

`Enable` `{on} | off`

Enable or disable the uitoggletool. This property controls how uitoggletools respond to mouse button clicks, including which callback routines execute.

- `on` – The uitoggletool is operational (the default).
- `off` – The uitoggletool is not operational and its image (set by the `Cdata` property) is grayed out.

When you left-click on a uitoggletool whose `Enable` property is `on`, MATLAB performs these actions in this order:

1. Sets the figure's `SelectionType` property.
2. Executes the toggle tool's `ClickedCallback` routine.
3. Does not set the figure's `CurrentPoint` property and does not execute the figure's `WindowButtonDownFcn` callback.

When you left-click on a uitoggletool whose `Enable` property is `off`, or when you right-click a uitoggletool whose `Enable` property has any value, MATLAB performs these actions in this order:

1. Sets the figure's `SelectionType` property.
2. Sets the figure's `CurrentPoint` property.
3. Executes the figure's `WindowButtonDownFcn` callback.
4. Does not execute the toggle tool's `OnCallback`, `OffCallback`, or `ClickedCallback` routines.

`HandleVisibility` `{on} | callback | off`

Control access to object's handle. This property determines when an object's handle is visible in its parent's list of children. When a handle is not visible in its parent's list of children, it is not returned by functions that obtain handles by searching the object hierarchy or querying handle properties. This includes `get`, `findobj`, `gca`, `gcf`, `gco`, `newplot`, `cla`, `clf`, and `close`. Neither is the handle visible in the parent figure's `CurrentObject` property. Handles that are hidden are still valid. If you know an object's handle, you can `set` and `get` its properties, and pass it to any function that operates on handles.

- Handles are always visible when `HandleVisibility` is `on`.
- Setting `HandleVisibility` to `callback` causes handles to be visible from within callback routines or functions invoked by callback routines, but not from within functions invoked from the command line. This provides a means to protect GUIs from command-line users, while allowing callback routines to have complete access to object handles.

- Setting `HandleVisibility` to `off` makes handles invisible at all times. This may be necessary when a callback routine invokes a function that might potentially damage the GUI (such as evaluating a user-typed string), and so temporarily hides its own handles during the execution of that function.

You can set the root `ShowHiddenHandles` property to `on` to make all handles visible, regardless of their `HandleVisibility` settings. This does not affect the values of the `HandleVisibility` properties.

`Interruptible` `{on} | off`

Callback routine interruption mode. If a callback is executing and the user triggers an event (such as a mouse click) on an object for which a callback is defined, that callback attempts to interrupt the first callback. MATLAB processes the callbacks according to these factors:

- The `Interruptible` property of the object whose callback is executing
- Whether the executing callback contains `drawnow`, `figure`, `getframe`, `pause`, or `waitfor` statements
- The `BusyAction` property of the object whose callback is waiting to execute

If the `Interruptible` property of the object whose callback is executing is `on` (the default), the callback can be interrupted. Whenever the callback calls one of the `drawnow`, `figure`, `getframe`, `pause`, or `waitfor` functions, the function processes any events in the event queue, including the waiting callback, before performing its defined task.

If the `Interruptible` property of the object whose callback is executing is `off`, the callback cannot be interrupted (except by certain callbacks; see the note below).

Note If the interrupting callback is a `DeleteFcn` or `CreateFcn` callback or a figure's `CloseRequest` or `ResizeFcn` callback, it interrupts an executing callback regardless of the value of that object's `Interruptible` property. The interrupting callback starts execution at the next `drawnow`, `figure`, `getframe`, `pause`, or `waitfor` statement.

`OffCallback` string or function handle

Control action. A routine that executes if the uitoggletool's `Enable` property is set to `on`, and either

- The toggle tool `State` is set to `off`.
- The toggle tool is set to the `off` position by pressing a mouse button while the pointer is on the toggle tool itself or in a 5-pixel wide border around it.

The `ClickedCallback` routine, if there is one, runs after the `OffCallback` routine runs to completion.

`OnCallback` string or function handle

Control action. A routine that executes if the uitoggletool's `Enable` property is set to `on`, and either

- The toggle tool `State` is set to `on`.
- The toggle tool is set to the `on` position by pressing a mouse button while the pointer is on the toggle tool itself or in a 5-pixel wide border around it.

The `ClickedCallback` routine, if there is one, runs after the `OffCallback` routine runs to completion.

`Parent` handle

Uitoggletool parent. The handle of the uitoggletool's parent toolbar. You can move a uitoggletool object to another toolbar by setting this property to the handle of the new parent.

`Separator` `on | {off}`

Separator line mode. Setting this property to `on` draws a dividing line to left of the uitoggletool.

`State` `on | {off}`

Uitoggletool state. When the state is `on`, the toggle tool appears in the down, or pressed, position. When the state is `off`, it appears in the up position. Changing the state causes the appropriate `OnCallback` or `OffCallback` routine to run.

`Tag` string

User-specified object identifier. The `Tag` property provides a means to identify graphics objects with a user-specified label. You can define `Tag` as any string.

With the `findobj` function, you can locate an object with a given `Tag` property value. This saves you from defining object handles as global variables. For example, this function call returns the handles of all children (of the specified toolbars) that have the `Tag` value `'Bold'`.

```
h = findobj(uitoolbarhandles, 'Tag', 'Bold')
```

`TooltipString` `string`

Content of tooltip for object. The `TooltipString` property specifies the text of the tooltip associated with the uitoggletool. When the user moves the mouse pointer over the control and leaves it there, the tooltip is displayed.

`Type` `string` (read-only)

Object class. This property identifies the kind of graphics object. For uitoggletool objects, `Type` is always the string `'uitoggletool'`.

`UserData` array

User specified data. You can specify `UserData` as any array you want to associate with the uitoggletool object. The object does not use this data, but you can access it using the `set` and `get` functions.

`Visible` `{on} | off`

Uitoggletool visibility. By default, all uitoggletools are visible. When set to `off`, the uitoggletool is not visible, but still exists and you can query and set its properties.

Purpose

Create a toolbar on the current or specified figure

Syntax

```
ht = uitoolbar('PropertyName1',value1,'PropertyName2',value2,...)
ht = uitoolbar(h,...)
```

Description

`ht = uitoolbar('PropertyName1',value1,'PropertyName2',value2,...)` creates an empty toolbar at the top of the current figure window, and returns a handle to it. `uitoolbar` assigns the specified property values, and assigns default values to the remaining properties. You can change the property values at a later time using the `set` function.

Type `get(ht)` to see a list of `uitoolbar` object properties and their current values. Type `set(ht)` to see a list of `uitoolbar` object properties that you can set and legal property values. See the Uitoolbar Properties reference page for more information.

`ht = uitoolbar(h,...)` creates a toolbar with `h` as a parent. `h` must be a figure handle.

Remarks

`uitoolbar` accepts property name/property value pairs, as well as structures and cell arrays of properties as input arguments.

Uitoolbars only appear in figures whose `WindowStyle` is `normal` or `docked`. If a figure containing a uitoolbar is changed to `WindowStyle modal`, the uitoolbar still exists and is contained in the `Children` list of the figure, but is not displayed until the `WindowStyle` is changed to `normal`.

Properties

This table lists all properties useful to `uitoolbar` objects, grouping them by function. Each property name acts as a link to a more detailed description of the property.

Property Name	Property Description	Property Value
Controlling Style and Appearance		
`Visible`	Uitoolbar visibility	Value: `on`, `off` Default: `on`

Property Name	Property Description	Property Value
General Information About the Object		
`BeingDeleted`	This object is being deleted	Value: `on`, `off` (read-only) Default: `off`
`Children`	Uitoolbar object's uipushtool and uitoggletool children	Value: vector of handles
`Parent`	Uitoolbar object's parent figure.	Value: handle
`Tag`	User-specified object identifier	Value: string
`Type`	Class of graphics object	Value: string (read-only) Default: `uitoolbar`
`UserData`	User-specified data	Value: array
Controlling Callback Routine Execution		
`BusyAction`	Interruption of other callback routines	Value: `cancel`, `queue` Default: `queue`
`CreateFcn`	Callback routine executed during object creation	Value: string or function handle
`DeleteFcn`	Callback routine executed during object deletion	Value: string or function handle
`Interruptible`	Callback routine interruption mode	Value: `on`, `off` Default: `on`
Controlling Access to Objects		
`HandleVisibility`	Handle accessibility from command line and code associated with the GUIs.	Value: `on`, `callback`, `off` Default: `on`

Example

This example creates a figure with no toolbar, then adds a toolbar to it.

```
h = figure('ToolBar','none')
ht = uitoolbar(h)
```



Object Hierarchy



See Also

`set`, `get`, `uicontrol`, `uipushtool`, `uitoggletool`

Uitoolbar Properties

Modifying Properties

You can set and query graphics object properties in two ways:

- The Property Inspector is an interactive tool that enables you to see and change object property values. The Property inspector is available from GUIDE, or use the `inspect` function at the command line.
- The `set` and `get` functions enable you to set and query the values of properties.

You can set default Uitoolbar properties by typing:

```
set(h,'DefaultUitoolbar<PropertyName>',PropertyValue...)
```

Where h can be the root handle (0), a figure handle, or a uitoolbar handle. *`PropertyName`* is the name of the Uitoolbar property and `PropertyValue` is the value you specify as the default for that property.

For more information about changing the default value of a property see Setting Default Property Values.

Uitoolbar Properties

This section lists all properties useful to `uitoolbar` objects along with valid values and a descriptions of their use. Curly braces { } enclose default values.

Property	Purpose
`BeingDeleted`	This object is being deleted.
`BusyAction`	Callback routine interruption.
`Children`	Handles of uitoolbar's children.
`CreateFcn`	Callback routine executed during object creation.
`DeleteFcn`	Callback routine executed during object deletion.
`HandleVisibility`	Control access to object's handle.
`Interruptible`	Callback routine interruption mode.
`Parent`	Handle of uitoolbar's parent.
`Tag`	User-specified object identifier.
`Type`	Object class.

Property (Continued)	Purpose
UserData	User specified data.
Visible	Uitoolbar visibility.

BeingDeleted on | {off} (read-only)

This object is being deleted. The BeingDeleted property provides a mechanism that you can use to determine if objects are in the process of being deleted. MATLAB sets the BeingDeleted property to on when the object's delete function callback is called (see the DeleteFcn property) It remains set to on while the delete function executes, after which the object no longer exists.

For example, some functions may not need to perform actions on objects that are being deleted, and therefore, can check the object's BeingDeleted property before acting.

BusyAction cancel | {queue}

Callback routine interruption. If a callback is executing and the user triggers an event (such as a mouse click) on an object for which a callback is defined, the callback associated with the new event uses the value of BusyAction to decide whether or not to attempt to interrupt the executing callback.

- If the value is cancel, the event is discarded and the second callback does not execute.
- If the value is queue, and the Interruptible property of the first callback is on, the second callback is added to the event queue and executes in its turn after the first callback finishes execution.

Note If the interrupting callback is a DeleteFcn or CreateFcn callback or a figure's CloseRequest or ResizeFcn callback, it interrupts an executing callback regardless of the value of that object's Interruptible property. See the Interruptible property for information about controlling a callback's interruptibility.

Children vector of handles

Handles of tools on the toolbar. A vector containing the handles of all children of the uitoolbar object, in the order in which they appear on the toolbar. The children objects of uitoolbars are uipushtools and uitoggletools. You can use this property to reorder the children.

CreateFcn string or function handle

Callback routine executed during object creation. The specified function executes when MATLAB creates a uitoolbar object. MATLAB sets all property values for the uitoolbar before executing the `CreateFcn` callback so these values are available to the callback. Within the function, use `gcbo` to get the handle of the toolbar being created.

Setting this property on an existing uitoolbar object has no effect.

You can define a default `CreateFcn` callback for all new uitoolbars. This default applies unless you override it by specifying a different `CreateFcn` callback when you call `uitoolbar`. For example, the statement,

```
set(0,'DefaultUitoolbarCreateFcn','set(gcbo,''Visibility'',...
    ''off'')')
```

creates a default `CreateFcn` callback that runs whenever you create a new toolbar. It sets the toolbar visibility to `off`.

To override this default and create a toolbar whose `Visibility` property is set to `on`, you could call `uitoolbar` with a call similar to

```
ht = uitoolbar(...,'CreateFcn','set(gcbo,''Visibility'',...
                ''on'')',...)
```

Note To override a default `CreateFcn` callback you must provide a new callback and not just provide different values for the specified properties. This is because the `CreateFcn` callback runs after the property values are set, and can override property values you have set explicitly in the `uitoolbar` call. In the example above, if instead of redefining the `CreateFcn` property for this toolbar, you had explicitly set `Visibility` to `on`, the default `CreateFcn` callback would have set `Visibility` back to `off`.

See Function Handle Callbacks for information on how to use function handles to define a callback function.

`DeleteFcn` string or function handle

Callback routine executed during object deletion. A callback function that executes when the uitoolbar object is deleted (e.g., when you call the `delete` function or cause the figure containing the uitoolbar to reset). MATLAB executes the routine before destroying the object's properties so these values are available to the callback routine.

Within the function, use `gcbo` to get the handle of the toolbar being deleted.

`HandleVisibility` `{on} | callback | off`

Control access to object's handle. This property determines when an object's handle is visible in its parent's list of children. When a handle is not visible in its parent's list of children, it is not returned by functions that obtain handles by searching the object hierarchy or querying handle properties. This includes `get`, `findobj`, `gca`, `gcf`, `gco`, `newplot`, `cla`, `clf`, and `close`. Neither is the handle visible in the parent figure's `CurrentObject` property. Handles that are hidden are still valid. If you know an object's handle, you can `set` and `get` its properties, and pass it to any function that operates on handles.

- Handles are always visible when `HandleVisibility` is `on`.
- Setting `HandleVisibility` to `callback` causes handles to be visible from within callback routines or functions invoked by callback routines, but not from within functions invoked from the command line. This provides a means to protect GUIs from command-line users, while allowing callback routines to have complete access to object handles.
- Setting `HandleVisibility` to `off` makes handles invisible at all times. This may be necessary when a callback routine invokes a function that might potentially damage the GUI (such as evaluating a user-typed string), and so temporarily hides its own handles during the execution of that function.

You can set the root `ShowHiddenHandles` property to `on` to make all handles visible, regardless of their `HandleVisibility` settings. This does not affect the values of the `HandleVisibility` properties.

`Interruptible` `{on} | off`

Callback routine interruption mode. If a callback is executing and the user triggers an event (such as a mouse click) on an object for which a callback is

defined, that callback attempts to interrupt the first callback. MATLAB processes the callbacks according to these factors:

- The `Interruptible` property of the object whose callback is executing
- Whether the executing callback contains `drawnow`, `figure`, `getframe`, `pause`, or `waitfor` statements
- The `BusyAction` property of the object whose callback is waiting to execute

If the `Interruptible` property of the object whose callback is executing is `on` (the default), the callback can be interrupted. Whenever the callback calls one of the `drawnow`, `figure`, `getframe`, `pause`, or `waitfor` functions, the function processes any events in the event queue, including the waiting callback, before performing its defined task.

If the `Interruptible` property of the object whose callback is executing is `off`, the callback cannot be interrupted (except by certain callbacks; see the note below). The `BusyAction` property of the object whose callback is waiting to execute determines what happens to the callback.

Note If the interrupting callback is a `DeleteFcn` or `CreateFcn` callback or a figure's `CloseRequest` or `ResizeFcn` callback, it interrupts an executing callback regardless of the value of that object's `Interruptible` property. The interrupting callback starts execution at the next `drawnow`, `figure`, `getframe`, `pause`, or `waitfor` statement. A figure's `WindowButtonDownFcn` callback routine, or an object's `ButtonDownFcn` or `Callback` routine are processed according to the rules described above.

`Parent` handle

Uitoolbar parent. The handle of the uitoolbar's parent figure. You can move a uitoolbar object to another figure by setting this property to the handle of the new parent.

`Tag` string

User-specified object identifier. The `Tag` property provides a means to identify graphics objects with a user-specified label. You can define `Tag` as any string.

With the `findobj` function, you can locate an object with a given `Tag` property value. This saves you from defining object handles as global variables. For example, this function call returns the handles of all children (of the specified figures) that have the `Tag` value `'FormatTb'`.

```
h = findobj(figurehandles,'Tag','FormatTb')
```

`Type` `string` (read-only)

Object class. This property identifies the kind of graphics object. For uitoolbar objects, `Type` is always the string `'uitoolbar'`.

`UserData` array

User specified data. You can specify `UserData` as any array you want to associate with the uitoolbar object. The object does not use this data, but you can access it using the `set` and `get` functions.

`Visible` `{on} | off`

Uitoolbar visibility. By default, all uitoolbars are visible. When set to `off`, the uitoolbar is not visible, but still exists and you can query and set its properties.

undocheckout

Purpose

Undo previous checkout from source control system

Graphical Interface

As an alternative to the `undocheckout` function, use **Source Control Undo Checkout** in the Editor, Simulink, or Stateflow **File** menu.

Syntax

```
undocheckout('filename')
undocheckout({'filename1','filename2','filename3', ...})
```

Description

`undocheckout('filename')` makes the file `filename` available for checkout, where `filename` does not reflect any of the changes you made after you last checked it out. `filename` must be the full pathname for the file.

`undocheckout({'filename1','filename2','filename3', ...})` makes the `filename1` through `filenamen` available for checkout, where the files do not reflect any of the changes you made after you last checked them out. Use the full pathnames for the files.

Examples

Typing

```
undocheckout({'/matlab/mymfiles/clock.m', ...
'/matlab/mymfiles/calendar.m'})
```

undoes the checkouts of `/matlab/mymfiles/clock.m` and `/matlab/mymfiles/calendar.m` from the source control system.

See Also

`checkin`, `checkout`

Purpose

Set union of two vectors

Syntax

```
c = union(A, B)
c = union(A, B, 'rows')
[c, ia, ib] = union(...)
```

Description

`c = union(A, B)` returns the combined values from `A` and B but with no repetitions. The resulting vector is sorted in ascending order. In set theoretic terms, `c = A` $\cup$ B. A and B can be cell arrays of strings.

`c = union(A, B, 'rows')` when `A` and `B` are matrices with the same number of columns returns the combined rows from `A` and `B` with no repetitions.

`[c, ia, ib] = union(...)` also returns index vectors `ia` and `ib` such that `c = a(ia)` $\cup$ `b(ib)`, or for row combinations, `c = a(ia,:)` $\cup$ `b(ib,:)`. If a value appears in both `a` and `b`, `union` indexes its occurrence in `b`. If a value appears more than once in `b` or in `a` (but not in `b`), `union` indexes the last occurrence of the value.

Examples

```
a = [-1 0 2 4 6];
b = [-1 0 1 3];
[c, ia, ib] = union(a, b);
c =

    -1     0     1     2     3     4     6

ia =

     3     4     5

ib =

     1     2     3     4
```

See Also

`intersect`, `setdiff`, `setxor`, `unique`, `ismember`, `issorted`

unique

Purpose

Unique elements of a vector

Syntax

```
b = unique(A)
b = unique(A, 'rows')
[b, m, n] = unique(...)
```

Description

`b = unique(A)` returns the same values as in `A` but with no repetitions. The resulting vector is sorted in ascending order. `A` can be a cell array of strings.

`b = unique(A, 'rows')` returns the unique rows of `A`.

`[b, m, n] = unique(...)` also returns index vectors `m` and `n` such that `b = A(m)` and `A = b(n)`. Each element of `m` is the greatest subscript such that `b = A(m)`. For row combinations, `b = A(m,:)` and `A = b(n,:)`.

Examples

```
A = [1 1 5 6 2 3 3 9 8 6 2 4]
A =
    1    1    5    6    2    3    3    9    8    6    2    4

[b, m, n] = unique(A)
b =
    1    2    3    4    5    6    8    9
m =
    2   11    7   12    3   10    9    8
n =
    1    1    5    6    2    3    3    8    7    6    2    4

A(m)
ans =
    1    2    3    4    5    6    8    9

b(n)
ans =
    1    1    5    6    2    3    3    9    8    6    2    4
```

Because NaNs are not equal to each other, unique treats them as unique elements.

```
unique([1 1 NaN NaN])
ans =
     1 NaN NaN
```

See Also

intersect, ismember, issorted, setdiff, setxor, union

unix

Purpose

Execute a UNIX command and return result

Syntax

```
unix command
status = unix('command')
[status,result] = unix('command')
[status,result] = unix('command','-echo')
```

Description

`unix command` calls upon the UNIX operating system to execute the given command.

`status = unix('command')` returns completion status to the `status` variable.

`[status, result] = unix('command')` returns the standard output to the `result` variable, in addition to completion status.

`[status,result] = unix('command','-echo')` forces the output to the Command Window, even though it is also being assigned into a variable.

Examples

List all users that are currently logged in. It returns a zero (success) in `s` and a string containing the list of users in `w`.

```
[s,w] = unix('who');
```

The next example returns a nonzero value in `s` to indicate failure and returns an error message in `w` because `why` is not a UNIX command.

```
[s,w] = unix('why')
s =
     1
w =
why: Command not found.
```

When including the `-echo` flag, MATLAB displays the results of the command in the Command Window as it executes as well as assigning the results to the return variable, `w`.

```
[s,w] = unix('who','-echo');
```

See Also

`dos`, `!` (exclamation point), `perl`, `system`

Purpose

Piecewise polynomial details

Syntax

```
[breaks,coefs,l,k,d] = unmkpp(pp)
```

Description

`[breaks,coefs,l,k,d] = unmkpp(pp)` extracts, from the piecewise polynomial `pp`, its breaks `breaks`, coefficients `coefs`, number of pieces `l`, order `k`, and dimension `d` of its target. Create `pp` using `spline` or the spline utility `mkpp`.

Examples

This example creates a description of the quadratic polynomial

as a piecewise polynomial `pp`, then extracts the details of that description.

```
pp = mkpp([-8 -4],[-1/4 1 0]);
[breaks,coefs,l,k,d] = unmkpp(pp)

breaks =
    -8    -4

coefs =
   -0.2500    1.0000         0

l =
     1

k =
     3

d =
     1
```

See Also

`mkpp`, `ppval`, `spline`

Purpose

Correct phase angles to produce smoother phase plots

Syntax

```
Q = unwrap(P)
Q = unwrap(P,tol)
Q = unwrap(P,[],dim)
Q = unwrap(P,tol,dim)
```

Description

`Q = unwrap(P)` corrects the radian phase angles in a vector `P` by adding multiples of when absolute jumps between consecutive elements of `P` are greater than the default jump tolerance of radians. If `P` is a matrix, `unwrap` operates columnwise. If `P` is a multidimensional array, `unwrap` operates on the first nonsingleton dimension.

`Q = unwrap(P,tol)` uses a jump tolerance `tol` instead of the default value, .

`Q = unwrap(P,[],dim)` unwraps along `dim` using the default tolerance.

`Q = unwrap(P,tol,dim)` uses a jump tolerance of `tol`.

Note A jump tolerance less than has the same effect as a tolerance of . For a tolerance less than , if a jump is greater than the tolerance but less than , adding would result in a jump larger than the existing one, so `unwrap` chooses the current point. If you want to eliminate jumps that are less than , try using a finer grid in the domain.

Examples

Example 1. The following phase data comes from the frequency response of a third-order transfer function. The phase curve jumps `3.5873` radians between `w = 3.0` and `w = 3.5`, from `-1.8621` to `1.7252`.

```
w = [0:.2:3,3.5:1:10];
p = [    0
     -1.5728
     -1.5747
     -1.5772
     -1.5790
     -1.5816
     -1.5852
```

```
      -1.5877
      -1.5922
      -1.5976
      -1.6044
      -1.6129
      -1.6269
      -1.6512
      -1.6998
      -1.8621
       1.7252
       1.6124
       1.5930
       1.5916
       1.5708
       1.5708
       1.5708 ];
semilogx(w,p,'b*-'), hold
```

Using `unwrap` to correct the phase angle, the resulting jump is `2.6959`, which is less than the default jump tolerance . This figure plots the new curve over the original curve.

```
semilogx(w,unwrap(p),'r*-')
```

Note If you have the Control System Toolbox, you can create the data for this example with the following code.

```
h = freqresp(tf(1,[1 .1 10 0]));
p = angle(h(:));
```

Example 2. Array `P` features smoothly increasing phase angles except for discontinuities at elements `(3,1)` and `(1,2)`.

```
P = [      0    7.0686    1.5708    2.3562
      0.1963    0.9817    1.7671    2.5525
      6.6759    1.1781    1.9635    2.7489
```

```
    0.5890    1.3744    2.1598    2.9452 ]
```

The function `Q = unwrap(P)` eliminates these discontinuities.

```
Q =
         0    7.0686    1.5708    2.3562
    0.1963    7.2649    1.7671    2.5525
    0.3927    7.4613    1.9635    2.7489
    0.5890    7.6576    2.1598    2.9452
```

See Also

`abs`, `angle`

Purpose

Extract contents of zip file

Syntax

```
unzip('zipfilename')
unzip('zipfilename','directory')
```

Description

`unzip('zipfilename')` extracts the contents of (unzips) the zip file named `zipfilename` into the current directory, where `zipfilename` was created using the `zip` function or any standard zip application. The path for `zipfilename` is relative to the current directory.

`unzip('zipfilename','directory')` extracts the contents of the zip file named `zipfilename` into the specified directory. The paths for `zipfilename` and `directory` are relative to the current directory.

Examples

Extract the contents of `d:/mymfiles/viewlet.zip`, putting the resulting files in the current directory.

```
unzip('d:/mymfiles/viewlet.zip')
```

Unzip the zip file `mymfiles` in the current directory, putting the resulting files in the directory `archives`, which is at the same level as the current directory.

```
unzip('mymfiles','../archives')
```

See Also

`zip`

upper

Purpose

Convert string to uppercase

Syntax

```
t  = upper('str')
B = upper(A)
```

Description

`t  = upper('str')` converts any lowercase characters in the string `str` to the corresponding uppercase characters and leaves all other characters unchanged.

`B = upper(A)` when `A` is a cell array of strings, returns a cell array the same size as `A` containing the result of applying `upper` to each string within `A`.

Examples

`upper('attention!')` is `ATTENTION!`.

Remarks

Character sets supported:

- PC: Windows Latin-1
- Other: ISO Latin-1 (ISO 8859-1)

See Also

`lower`

Purpose

Read contents at URL

Syntax

```
s = urlread('url')
s = urlread('url','method','params')
[s,status] = urlread(...)
```

Description

`s = urlread('url')` reads the content at a URL into the string `s`. If the server returns binary data, `s` will be unreadable.

`s = urlread('url','method','params')` reads the content at a URL into the string `s`, passing information to the server as part of the request where *`method`* can be `get` or `post`, and `params` is a cell array of parameter-value pairs.

`[s,status] = urlread(...)` catches any errors and returns the error code.

Note If you need to specify a proxy server to connect to the Internet, select **File -> Preferences -> Web** and enter your proxy server address and port. Use this feature if you have a firewall.

Examples

Download Content from Web Page

Use `urlread` to download the contents of the Authors list at the MATLAB Central File Exchange:

```
urlstring = sprintf('%s%s', ...
   'http://www.mathworks.com/matlabcentral/', ...
   'fileexchange/loadAuthorIndex.do');

s = urlread(urlstring);
```

Download Content from File on FTP Server

```
s = urlread('ftp://ftp.mathworks.com/pub/pentium/Moler_1.txt')
```

The file `Moler_1.txt` displays in the MATLAB Command Window.

Download Content from Local File

```
s = urlread('file:///c:/winnt/matlab.ini')
```

See Also urlwrite

2vander

Purpose

Vandermonde matrix

Syntax

```
A = vander(v)
```

Description

`A = vander(v)` returns the Vandermonde matrix whose columns are powers of the vector `v`, that is, `A(i,j) = v(i)^(n-j)`, where `n = length(v)`.

Examples

```
vander(1:.5:3)

ans =

    1.0000    1.0000    1.0000    1.0000    1.0000
    5.0625    3.3750    2.2500    1.5000    1.0000
   16.0000    8.0000    4.0000    2.0000    1.0000
   39.0625   15.6250    6.2500    2.5000    1.0000
   81.0000   27.0000    9.0000    3.0000    1.0000
```

See Also

`gallery`

var

Purpose

Variance

Syntax

```
var(X)
var(X,1)
var(X,w)
```

Description

`var(X)` returns the variance of `X` for vectors. For matrices, `var(X)`is a row vector containing the variance of each column of `X`. `var(X)` normalizes by N-1 where N is the sequence length. This makes `var(X)` the best unbiased estimate of the variance if `X` is a sample from a normal distribution.

`var(X,1)` normalizes by N and produces the second moment of the sample about its mean.

`var(X,W)` computes the variance using the weight vector `W`. The number of elements in `W` must equal the number of rows in `X` unless `W = 1`, which is treated as a short-cut for a vector of ones. The elements of `W` must be positive. `var` normalizes `W` by dividing each element in `W` by the sum of all its elements.

The variance is the square of the standard deviation (STD).

See Also

`corrcoef`, `cov`, `std`

Purpose

Pass or return variable numbers of arguments

Syntax

```
function varargout = foo(n)
function y = bar(varargin)
```

Description

`function varargout = foo(n)` returns a variable number of arguments from function `foo.m`.

`function y = bar(varargin)` accepts a variable number of arguments into function `bar.m`.

The `varargin` and `varargout` statements are used only inside a function M-file to contain the optional arguments to the function. Each must be declared as the last argument to a function, collecting all the inputs or outputs from that point onwards. In the declaration, `varargin` and `varargout` must be lowercase.

Examples

The function

```
function myplot(x,varargin)
plot(x,varargin{:})
```

collects all the inputs starting with the second input into the variable `varargin`. `myplot` uses the comma-separated list syntax `varargin{:}` to pass the optional parameters to `plot`. The call

```
myplot(sin(0:.1:1),'color',[.5 .7 .3],'linestyle',':')
```

results in `varargin` being a 1-by-4 cell array containing the values `'color'`, `[.5 .7 .3]`, `'linestyle'`, and `':'`.

The function

```
function [s,varargout] = mysize(x)
nout = max(nargout,1)-1;
s = size(x);
for k=1:nout, varargout(k) = {s(k)}; end
```

returns the size vector and, optionally, individual sizes. So

```
[s,rows,cols] = mysize(rand(4,5));
```

returns `s = [4 5], rows = 4, cols = 5`.

See Also nargin, nargout, nargchk, nargoutchk, inputname

Purpose

Vectorize expression

Syntax

```
vectorize(s)
vectorize(fun)
```

Description

`vectorize(s)` where `s` is a string expression, inserts a `.` before any `^`, `*` or `/` in `s`. The result is a character string.

`vectorize(fun)` when `fun` is an inline function object, vectorizes the formula for `fun`. The result is the vectorized version of the inline function.

See Also

`inline`, `cd`, `dbtype`, `delete`, `dir`, `partialpath`, `path`, `what`, `who`

ver

Purpose

Display version information for MathWorks products

Graphical Interface

As an alternative to the `ver` function, select **About** from the **Help** menu in any product that has a **Help** menu.

Syntax

```
ver
ver product
v = ver('product')
```

Description

`ver` displays a header containing the current version number, license number, operating system, and Java VM version for MATLAB, followed by the version numbers for Simulink, if installed, and all other MathWorks products installed.

`ver product` displays the MATLAB header information followed by the current version number for `product`. The name `product` corresponds to the directory name that holds the `Contents.m` file for that product. For example, `Contents.m` for the Control Systems Toolbox resides in the `control` directory. You therefore use `ver control` to obtain the version of this toolbox.

`v = ver('product')` returns the version information to structure array, `v`, having fields `Name`, `Version`, `Release`, and `Date`.

Remarks

To use `ver` with your own product, the first two lines of the `Contents.m` file for the product must be of the form

```
% Toolbox Description
% Version xxx dd-mmm-yyyy
```

Do not include any spaces in the date and use a two-character day; that is, use `02-Sep-2002` instead of `2-Sep-2002`.

Examples

Return version information for the Control Systems Toolbox by typing

```
ver control
```

MATLAB returns

```
---------------------------------------------------------------------
MATLAB Version 7.0.0.19220 (R14)
MATLAB License Number: %$#)^(%()$^
```

```
Operating System: Microsoft Windows 2000 Version 5.0 (Build 2195:
Service Pack 3)
Java VM Version: Java 1.4.2 with Sun Microsystems Inc. Java
HotSpot(TM) Client VM
-----------------------------------------------------------------
Control System Toolbox                  Version 6.0       (R14)
```

Return version information for the Control System Toolbox in a structure array, v.

```
v = ver('control')
v =
        Name: 'Control System Toolbox'
    Version: '6.0'
    Release: '(R14)'
        Date: '19-Apr-2004'
```

See Also

`help`, `hostid`, `license`, `version`, `whatsnew`

Also, type `help info` at the Command Window prompt.

verctrl

Purpose

Version control operations on PC platforms

Graphical Interface

As an alternative to the `verctrl` function, use **Source Contro**l in the Editor, Simulink, or Stateflow **File** menu.

Syntax

```
fileChange =
   verctrl('command',{'filename1','filename2',....},handle)
verctrl('command',{'filename1','filename2',....}, handle)
fileChange = verctrl('command','file', handle)
verctrl('command','file', handle)
list = verctrl('all_systems')
```

Description

`fileChange=verctrl('command',{'filename1','filename2',....}, handle)` performs forms the version control specified by `'command'` on a single file or multiple files. Specify files with a cell array using the full pathnames for `'filename'`. On Windows, specify a Windows handle in the `handle` argument. These commands return a logical 1 to the workspace if the file has changed on disk or a logical 0 to the workspace if the file has not changed on disk. Available values for `'command'` with this syntax are as follows:

command Argument	Purpose
`'get'`	Retrieves file(s) for viewing and compiling, but not editing. The file(s) will be tagged read-only. The list of files should contain either files or directories but not both.
`'checkout'`	Retrieves file(s) for editing.
`'checkin'`	Checks file(s) into the version control system, storing the changes and creating a new version.
`'uncheckout'`	Cancels a previous check-out operation and restores the contents of the selected file(s) to the precheckout version. All changes made to the file since the check-out are lost.

command Argument	Purpose
`'add'`	Adds file(s) into the version control system.
`'history'`	Displays the history of file(s).

`verctrl('command',{'filename1','filename2',....},handle)` performs the version control specified by `'command'` on a single file or multiple files. Specify the files with a cell array using the full pathnames for `'filename'`. On Windows, specify a Windows handle in the `handle` argument. Available values for `'command'` with this syntax are as follows:

command argument	Purpose
`'remove'`	Removes file(s) from the version control system. It does not delete the file(s) from the local hard drive, only from the version control system.

`fileChange = verctrl('command','file',handle)` performs the version control specified by `'command'` on a single file. Use the full pathname for `'file'`. On Windows, specify a Windows handle in the `handle` argument. These commands return a logical `1` to the workspace if the file has changed on disk or a logical `0` to the workspace if the file has not changed on disk. Available values for `'command'` with this syntax are as follows:

command argument	Purpose
`'properties'`	Displays the properties of a file.
`'isdiff'`	Compares a file with the latest checked in version of the file in the version control system. Returns logical `1` to the workspace if the files are different and it returns logical `0` to the workspace if the files are identical.

`verctrl('command','file')` performs the version control specified by `'command'` on a single file. Use the full pathname for `'file'`. Available values for `'command'` with this syntax are as follows:

command argument	Purpose
`'showdiff'`	Displays the differences between a file and the latest checked in version of the file in the version control system.

Examples

Create a Windows Handle

The `verctrl` function supports different version control commands on PC platforms. When you use verctrl on Windows, you must create a Windows handle. To create a Windows handle, enter the following commands in the MATLAB Command Window:

```
>> import java.awt.*;
>> frame = Frame('Test frame');
>> frame.setVisible(1);
>> winhandle =
com.mathworks.util.NativeJava.hWndFromComponent(frame)
```

List Installed Source Control Systems

Return a List in the Command Window of All Version Control Systems Installed in the Machine

```
list = verctrl('all_systems')
list =
           'Microsoft Visual SourceSafe'
```

Check Out a File

Check out `D:\file1.ext` from the version control system. This command opens `'checkout'` window and returns a logical `1` to the workspace if the file has changed on disk or a logical `0` to the workspace if the file has not changed on disk.

```
fileChange = verctrl('checkout',{'D:\file1.ext'}, 0)
```

Add Files

Add `D:\file1.ext` and `D:\file2.ext` to the version control system. This command opens 'add' window and returns a logical `1` to the workspace if the file has changed on disk or a logical `0` to the workspace if the file has not changed on disk.

```
fileChange = verctrl('add',{'D:\file1.ext','D:\file2.ext'}, 0)
```

Display the Properties of a File

Display the properties of `D:\file1.ext`. This command opens `'properties'` window and returns a logical `1` to the workspace if the file has changed on disk or a logical `0` to the workspace if the file has not changed on disk.

```
fileChange = verctrl('properties','D:\file1.ext', 0)
```

See Also

`checkin`, `checkout`, `undocheckout`, `cmopts`

version

Purpose

Get MATLAB version number

Graphical Interface

As an alternative to the `version` function, select **About** from the **Help** menu in the MATLAB desktop.

Syntax

```
version
version -java
v = version
[v,d] = version
```

Description

`version` displays the MATLAB version number.

`version -java` displays the version of the Java VM (JVM) used by MATLAB.

`v = version` returns a string `v` containing the MATLAB version number.

`[v,d] = version` also returns a string `d` containing the date of the version.

Remarks

On the PC and UNIX platforms, MATLAB includes a JVM and uses that version. If you use the MATLAB Java interface and the Java classes you want to use require a different JVM than the version provided with MATLAB, it is possible to run MATLAB with a different JVM. For details, see Solution 26612 on the MathWorks Support Web site.

On the Macintosh platform, MATLAB does not include a JVM, but uses whatever JVM is currently running on the machine.

Examples

```
[v,d]=version

v =
7.0.0.275711 (R14)

d =
Apr 16 2004
```

See Also

`ver`, `whatsnew`

Purpose

Vertical concatenation

Syntax

```
C = vertcat(A1, A2, ...)
```

Description

`C = vertcat(A1, A2, ...)` vertically concatenates matrices `A1`, `A2`, and so on. All matrices in the argument list must have the same number of columns.

`vertcat` concatenates N-dimensional arrays along the first dimension. The remaining dimensions must match.

MATLAB calls `C = vertcat(A1, A2, ...)` for the syntax `C = [A1; A2; ...]` when any of `A1`, `A2`, etc. is an object.

Examples

Create a 5-by-3 matrix, `A`, and a 3-by-3 matrix, `B`. Then vertically concatenate `A` and `B`.

```
A = magic(5);            % Create 5-by-3 matrix, A
A(:, 4:5) = []

A =

    17    24     1
    23     5     7
     4     6    13
    10    12    19
    11    18    25


B = magic(3)*100         % Create 3-by-3 matrix, B

B =

   800   100   600
   300   500   700
   400   900   200


C = vertcat(A,B)         % Vertically concatenate A and B

C =
```

```
    17    24     1
    23     5     7
     4     6    13
    10    12    19
    11    18    25
   800   100   600
   300   500   700
   400   900   200
```

See Also horzcat, cat

Purpose

Viewpoint specification

Syntax

```
view(az,el)
view([az,el])
view([x,y,z])
view(2)
view(3)
view(T)

[az,el] = view
T = view
```

Description

The position of the viewer (the viewpoint) determines the orientation of the axes. You specify the viewpoint in terms of azimuth and elevation, or by a point in three-dimensional space.

`view(az,el)` and `view([az,el])` set the viewing angle for a three-dimensional plot. The azimuth, `az`, is the horizontal rotation about the *z*-axis as measured in degrees from the negative *y*-axis. Positive values indicate counterclockwise rotation of the viewpoint. `el` is the vertical elevation of the viewpoint in degrees. Positive values of elevation correspond to moving above the object; negative values correspond to moving below the object.

`view([x,y,z])` sets the viewpoint to the Cartesian coordinates `x`, `y`, and `z`. The magnitude of `(x,y,z)` is ignored.

`view(2)` sets the default two-dimensional view, `az = 0, el = 90`.

`view(3)` sets the default three-dimensional view, `az = 37.5, el = 30`.

`view(T)` sets the view according to the transformation matrix `T`, which is a 4-by-4 matrix such as a perspective transformation generated by `viewmtx`.

`[az,el] = view` returns the current azimuth and elevation.

`T = view` returns the current 4-by-4 transformation matrix.

Remarks

Azimuth is a polar angle in the *x*-*y* plane, with positive angles indicating counterclockwise rotation of the viewpoint. Elevation is the angle above (positive angle) or below (negative angle) the *x*-*y* plane.

This diagram illustrates the coordinate system. The arrows indicate positive directions.



Examples

View the object from directly overhead.

```
az = 0;
el = 90;
view(az, el);
```

Set the view along the *y*-axis, with the *x*-axis extending horizontally and the *z*-axis extending vertically in the figure.

```
view([0 0]);
```

Rotate the view about the *z*-axis by 180°.

```
az = 180;
el = 90;
view(az, el);
```

See Also

`viewmtx`, `axes`, `rotate3d`

"Controlling the Camera Viewpoint" for related functions

Axes graphics object properties `CameraPosition`, `CameraTarget`, `CameraViewAngle`, `Projection`

Defining the View for more information on viewing concepts and techniques

Purpose

View transformation matrices

Syntax

```
T = viewmtx(az,el)
T = viewmtx(az,el,phi)
T = viewmtx(az,el,phi,xc)
```

Description

`viewmtx` computes a 4-by-4 orthographic or perspective transformation matrix that projects four-dimensional homogeneous vectors onto a two-dimensional view surface (e.g., your computer screen).

`T = viewmtx(az,el)` returns an *orthographic* transformation matrix corresponding to azimuth `az` and elevation `el`. `az` is the azimuth (i.e., horizontal rotation) of the viewpoint in degrees. `el` is the elevation of the viewpoint in degrees. This returns the same matrix as the commands

```
view(az,el)
T = view
```

but does not change the current view.

`T = viewmtx(az,el,phi)` returns a *perspective* transformation matrix. `phi` is the perspective viewing angle in degrees. `phi` is the subtended view angle of the normalized plot cube (in degrees) and controls the amount of perspective distortion.

Phi	Description
0 degrees	Orthographic projection
10 degrees	Similar to telephoto lens
25 degrees	Similar to normal lens
60 degrees	Similar to wide-angle lens

You can use the matrix returned to set the view transformation with `view(T)`. The 4-by-4 perspective transformation matrix transforms four-dimensional homogeneous vectors into unnormalized vectors of the form (x,y,z,w), where w is not equal to 1. The x- and y-components of the normalized vector (x/w, y/w, z/w, 1) are the desired two-dimensional components (see example below).

`T = viewmtx(az,el,phi,xc)` returns the perspective transformation matrix using `xc` as the target point within the normalized plot cube (i.e., the camera is looking at the point `xc`). `xc` is the target point that is the center of the view. You specify the point as a three-element vector, `xc = [xc,yc,zc]`, in the interval [0,1]. The default value is `xc = [0,0,0]`.

Remarks

A four-dimensional homogenous vector is formed by appending a 1 to the corresponding three-dimensional vector. For example, `[x,y,z,1]` is the four-dimensional vector corresponding to the three-dimensional point `[x,y,z]`.

Examples

Determine the projected two-dimensional vector corresponding to the three-dimensional point (0.5,0.0,-3.0) using the default view direction. Note that the point is a column vector.

```
A = viewmtx(-37.5,30);
x4d = [.5  0  -3  1]';
x2d = A*x4d;
x2d = x2d(1:2)
x2d =
     0.3967
    -2.4459
```

Vectors that trace the edges of a unit cube are

```
x = [0  1  1  0  0  0  1  1  0  0  1  1  1  1  0  0];
y = [0  0  1  1  0  0  0  1  1  0  0  0  1  1  1  1];
z = [0  0  0  0  0  1  1  1  1  1  1  0  0  1  1  0];
```

Transform the points in these vectors to the screen, then plot the object.

```
A = viewmtx(-37.5,30);
[m,n] = size(x);
x4d = [x(:),y(:),z(:),ones(m*n,1)]';
x2d = A*x4d;
x2 = zeros(m,n); y2 = zeros(m,n);
x2(:) = x2d(1,:);
y2(:) = x2d(2,:);
plot(x2,y2)
```



Use a perspective transformation with a 25 degree viewing angle:

```
A = viewmtx(-37.5,30,25);
x4d = [.5  0  -3  1]';
x2d = A*x4d;
x2d = x2d(1:2)/x2d(4)   % Normalize
x2d =
     0.1777
    -1.8858
```

Transform the cube vectors to the screen and plot the object:

```
A = viewmtx(-37.5,30,25);
[m,n] = size(x);
x4d = [x(:),y(:),z(:),ones(m*n,1)]';
x2d = A*x4d;
x2 = zeros(m,n); y2 = zeros(m,n);
x2(:) = x2d(1,:)./x2d(4,:);
y2(:) = x2d(2,:)./x2d(4,:);
plot(x2,y2)
```



See Also

`view`, `hgtransform`

“Controlling the Camera Viewpoint” for related functions

Defining the View for more information on viewing concepts and techniques

volumebounds

Purpose

Return coordinate and color limits for volume data

Syntax

```
lims = volumebounds(X,Y,Z,V)
lims = volumebounds(X,Y,Z,U,V,W)
lims = volumebounds(V), lims = volumebounds(U,V,W)
```

Description

`lims = volumebounds(X,Y,Z,V)` returns the x,y,z and color limits of the current axes for scalar data. `lims` is returned as a vector:

```
[xmin xmax ymin ymax zmin zmax cmin cmax]
```

You can pass this vector to the `axis` command.

`lims = volumebounds(X,Y,Z,U,V,W)` returns the x, y, and z limits of the current axes for vector data. `lims` is returned as a vector:

```
[xmin xmax ymin ymax zmin zmax]
```

`lims = volumebounds(V), lims = volumebounds(U,V,W)` assumes `X`, `Y`, and `Z` are determined by the expression

```
[X Y Z] = meshgrid(1:n,1:m,1:p)
```

where `[m n p] = size(V)`.

Examples

This example uses `volumebounds` to set the axis and color limits for an `isosurface` generated by the `flow` function.

```
[x y z v] = flow;
p = patch(isosurface(x,y,z,v,-3));
isonormals(x,y,z,v,p)
daspect([1 1 1])
isocolors(x,y,z,flipdim(v,2),p)
shading interp
axis(volumebounds(x,y,z,v))
view(3)
camlight
lighting phong
```



See Also

`isosurface`, `streamslice`

"Volume Visualization" for related functions

voronoi

Purpose

Voronoi diagram

Syntax

```
voronoi(x,y)
voronoi(x,y,TRI)
voronoi(X,Y,options)
voronoi(AX,...)
voronoi(...,'LineSpec')
h = voronoi(...)
[vx,vy] = voronoi(...)
```

Definition

Consider a set of coplanar points . For each point in the set , you can draw a boundary enclosing all the intermediate points lying closer to than to other points in the set . Such a boundary is called a *Voronoi polygon*, and the set of all Voronoi polygons for a given point set is called a *Voronoi diagram*.

Description

`voronoi(x,y)` plots the bounded cells of the Voronoi diagram for the points `x,y`. Cells that contain a point at infinity are unbounded and are not plotted.

`voronoi(x,y,TRI)` uses the triangulation `TRI` instead of computing it via `delaunay`.

`voronoi(X,Y,options)` specifies a cell array of strings to be used as options in Qhull via `delaunay`.

If `options` is `[]`, the default `delaunay` options are used. If `options` is `{''}`, no options are used, not even the default.

`voronoi(AX,...)` plots into `AX` instead of `gca`.

`voronoi(...,'LineSpec')` plots the diagram with color and line style specified.

`h = voronoi(...)` returns, in `h`, handles to the line objects created.

`[vx,vy] = voronoi(...)` returns the finite vertices of the Voronoi edges in `vx` and `vy` so that `plot(vx,vy,'-',x,y,'.')` creates the Voronoi diagram.

Note For the topology of the Voronoi diagram, i.e., the vertices for each Voronoi cell, use `voronoin`.

```
[v,c] = voronoin([x(:) y(:)])
```

Visualization

Use one of these methods to plot a Voronoi diagram:

- If you provide no output argument, `voronoi` plots the diagram. See Example 1.
- To gain more control over color, line style, and other figure properties, use the syntax `[vx,vy] = voronoi(...)`. This syntax returns the vertices of the finite Voronoi edges, which you can then plot with the `plot` function. See Example 2.
- To fill the cells with color, use `voronoin` with `n = 2` to get the indices of each cell, and then use `patch` and other plot functions to generate the figure. Note that `patch` does not fill unbounded cells with color. See Example 3.

Examples

Example 1. This code uses the `voronoi` function to plot the Voronoi diagram for 10 randomly generated points.

```
rand('state',5);
x = rand(1,10); y = rand(1,10);
voronoi(x,y)
```

Example 2. This code uses the vertices of the finite Voronoi edges to plot the Voronoi diagram for the same 10 points.

```
rand('state',5);
x = rand(1,10); y = rand(1,10);
[vx, vy] = voronoi(x,y);
plot(x,y,'r+',vx,vy,'b-'); axis equal
```

Note that you can add this code to get the figure shown in Example 1.

```
xlim([min(x) max(x)])
ylim([min(y) max(y)])
```

Example 3. This code uses `voronoin` and `patch` to fill the bounded cells of the same Voronoi diagram with color.

```
rand('state',5);
x=rand(10,2);
[v,c]=voronoin(x);
for i = 1:length(c)
if all(c{i}~=1)   % If at least one of the indices is 1,
                  % then it is an open region and we can't
                  % patch that.
patch(v(c{i},1),v(c{i},2),i); % use color i.
end
end
axis equal
```

Algorithm

If you supply no triangulation `TRI`, the `voronoi` function performs a Delaunay triangulation of the data that uses Qhull [2]. For information about Qhull, see `http://www.qhull.org/`. For copyright information, see `http://www.qhull.org/COPYING.txtCOPYING.txt`.

See Also

`convhull`, `delaunay`, `LineSpec`, `plot`, `voronoin`

Reference

[1] Barber, C. B., D.P. Dobkin, and H.T. Huhdanpaa, "The Quickhull Algorithm for Convex Hulls," *ACM Transactions on Mathematical Software*, Vol. 22, No. 4, Dec. 1996, p. 469-483. Available in HTML format at `http://www.acm.org/pubs/citations/journals/toms/1996-22-4/p469-barber/` and in PostScript format at `ftp://geom.umn.edu/pub/software/qhull-96.ps`.

[2] National Science and Technology Research Center for Computation and Visualization of Geometric Structures (The Geometry Center), University of Minnesota. 1993.

Purpose

N-dimensional Voronoi diagram

Syntax

```
[V,C] = voronoin(X)
[V,C] = voronoin(X,options)
```

Description

`[V,C] = voronoin(X)` returns Voronoi vertices `V` and the Voronoi cells `C` of the Voronoi diagram of `X`. `V` is a `numv`-by-`n` array of the `numv` Voronoi vertices in n-dimensional space, each row corresponds to a Voronoi vertex. `C` is a vector cell array where each element contains the indices into `V` of the vertices of the corresponding Voronoi cell. `X` is an `m`-by-`n` array, representing `m` n-dimensional points, where `n > 1` and `m >= n+1`.

The first row of `V` is a point at infinity. If any index in a cell of the cell array is `1`, then the corresponding Voronoi cell contains the first point in `V`, a point at infinity. This means the Voronoi cell is unbounded.

`voronoin` uses Qhull.

`[V,C] = voronoin(X,options)` specifies a cell array of strings `options` to be used in Qhull. The default options are

- `{'Qbb'}` for 2- and 3-dimentional input
- `{'Qbb','Qx'}` for 4 and higher-dimensional input

If `options` is `[]`, the default options are used. If `code` is `{''}`, no options are used, not even the default. For more information on Qhull and its options, see `http://www.qhull.org`.

Visualization

You can plot individual bounded cells of an n-dimensional Voronoi diagram. To do this, use `convhulln` to compute the vertices of the facets that make up the Voronoi cell. Then use `patch` and other plot functions to generate the figure. For an example, see "Tessellation and Interpolation of Scattered Data in Higher Dimensions" in the MATLAB documentation.

Examples

Let

```
x = [ 0.5    0
      0      0.5
     -0.5   -0.5
     -0.2   -0.1
     -0.1    0.1
```

```
       0.1   -0.1
       0.1    0.1 ]
```

then

```
[V,C] = voronoin(x)

V =
       Inf       Inf
       0.3833    0.3833
       0.7000   -1.6500
       0.2875    0.0000
      -0.0000    0.2875
      -0.0000   -0.0000
      -0.0500   -0.5250
      -0.0500   -0.0500
      -1.7500    0.7500
      -1.4500    0.6500

C =

    [1x4 double]
    [1x5 double]
    [1x4 double]
    [1x4 double]
    [1x4 double]
    [1x5 double]
    [1x4 double]
```

Use a `for` loop to see the contents of the cell array `C`.

```
for i=1:length(C), disp(C{i}), end

     4     2     1     3
    10     5     2     1     9
     9     1     3     7
    10     8     7     9
    10     5     6     8
     8     6     4     3     7
     6     4     2     5
```

2wait

Purpose

Wait until a timer stops running

Syntax

```
wait(obj)
```

Description

`wait(obj)` blocks the MATLAB command line and waits until the timer, represented by the timer object `obj`, stops running. When a timer stops running, the value of the timer object's `Running` property changes from `'on'` to `'off'`.

If `obj` is an array of timer objects, `wait` blocks the MATLAB command line until all the timers have stopped running.

If the timer is not running, `wait` returns immediately.

See Also

`timer`, `start`, `stop`

waitbar

Purpose

Display waitbar

Syntax

```
h = waitbar(x,'title')
waitbar(x,'title','CreateCancelBtn','button_callback')
waitbar(...,property_name,property_value,...)
waitbar(x)
waitbar(x,h)
waitbar(x,h,'updated title')
```

Description

A waitbar shows what percentage of a calculation is complete, as the calculation proceeds.

`h = waitbar(x,'title')` displays a waitbar of fractional length `x`. The handle to the waitbar figure is returned in `h`. `x` must be between 0 and 1.

`waitbar(x,'title','CreateCancelBtn','button_callback')` specifying **`CreateCancelBtn`** adds a cancel button to the figure that executes the MATLAB commands specified in `button_callback` when the user clicks the cancel button or the close figure button. `waitbar` sets both the cancel button callback and the figure `CloseRequestFcn` to the string specified in `button_callback`.

`waitbar(...,property_name,property_value,...)` optional arguments `property_name` and `property_value` enable you to set corresponding `waitbar` figure properties.

`waitbar(x)` subsequent calls to `waitbar(x)` extend the length of the bar to the new position `x`.

`waitbar(x,h)` extends the length of the bar in the waitbar `h` to the new position `x`.

Example

`waitbar` is typically used inside a `for` loop that performs a lengthy computation. For example,

```
h = waitbar(0,'Please wait...');

for i=1:100, % computation here %
waitbar(i/100)
end

close(h)
```



See Also

"Predefined Dialog Boxes" for related functions

waitfor

Purpose

Wait for condition before resuming execution

Syntax

```
waitfor(h)
waitfor(h,'PropertyName')
waitfor(h,'PropertyName',PropertyValue)
```

Description

The `waitfor` function blocks the caller's execution stream so that command-line expressions, callbacks, and statements in the blocked M-file do not execute until a specified condition is satisfied.

`waitfor(h)` returns when the graphics object identified by `h` is deleted or when a **Ctrl-C** is typed in the Command Window. If `h` does not exist, `waitfor` returns immediately without processing any events.

`waitfor(h,'PropertyName')`, in addition to the conditions in the previous syntax, returns when the value of `'PropertyName'` for the graphics object `h` changes. If `'PropertyName'` is not a valid property for the object, `waitfor` returns immediately without processing any events.

`waitfor(h,'PropertyName',PropertyValue)`, in addition to the conditions in the previous syntax, `waitfor` returns when the value of `'PropertyName'` for the graphics object `h` changes to `PropertyValue`. `waitfor` returns immediately without processing any events if `'PropertyName'` is set to `PropertyValue`.

Remarks

While `waitfor` blocks an execution stream, other execution streams in the form of callbacks may execute as a result of various events (e.g., pressing a mouse button).

`waitfor` can block nested execution streams. For example, a callback invoked during a `waitfor` statement can itself invoke `waitfor`.

See Also

`uiresume`, `uiwait`

"Interactive User Input" for related functions

Purpose

Wait for key or mouse button press

Syntax

```
k = waitforbuttonpress
```

Description

`k = waitforbuttonpress` blocks the caller's execution stream until the function detects that the user has pressed a mouse button or a key while the figure window is active. The function returns

- `0` if it detects a mouse button press
- `1` if it detects a key press

Additional information about the event that causes execution to resume is available through the figure's `CurrentCharacter`, `SelectionType`, and `CurrentPoint` properties.

If a `WindowButtonDownFcn` is defined for the figure, its callback is executed before `waitforbuttonpress` returns a value.

Example

These statements display text in the Command Window when the user either clicks a mouse button or types a key in the figure window:

```
w = waitforbuttonpress;
if w == 0
    disp('Button press')
else
    disp('Key press')
end
```

See Also

`dragrect`, `ginput`, `rbbox`, `waitfor`

"Developing User Interfaces" for related functions

warndlg

Purpose

Display warning dialog box

Syntax

```
h = warndlg('warningstring','dlgname')
```

Description

`warndlg` displays a dialog box named `'Warning Dialog'` containing the string `'This is the default warning string.'` The warning dialog box disappears after you press the **OK** button.

`warndlg('warningstring')` displays a dialog box with the title `'Warning Dialog'` containing the string specified by `warningstring`.

`warndlg('warningstring','dlgname')` displays a dialog box with the title `dlgname` that contains the string `warningstring`.

`h = warndlg(...)` returns the handle of the dialog box.

Examples

The statement

```
warndlg('Pressing OK will clear memory','!! Warning !!')
```

displays this dialog box:

See Also

`warning`, `dialog`, `errordlg`, `helpdlg`, `msgbox`

"Predefined Dialog Boxes" for related functions

Purpose

Display warning message

Syntax

```
warning('message')
warning('message', a1, a2, ...)
warning('message_id', 'message')
warning('message_id', 'message', a1, a2, ..., an)
s = warning('state', 'message_id')
s = warning('state', 'mode')
```

Description

`warning('message')` displays the text `'message'` like the `disp` function, except that with `warning`, message display can be suppressed.

`warning('message', a1, a2,...)` displays a message string that contains formatting conversion characters, such as those used with the MATLAB `sprintf` function. Each conversion character in `message` is converted to one of the values `a1`, `a2`, `...` in the argument list.

Note MATLAB converts special characters (like `\n` and `%d`) in the warning message string only when you specify more than one input argument with `warning`. See Example 4 below.

`warning('message_id', 'message')` attaches a unique identifier, or `message_id`, to the warning message. The identifier enables you to single out certain warnings during the execution of your program, controlling what happens when the warnings are encountered. See “Message Identifiers” and “Warning Control” in the MATLAB documentation for more information on the `message_id` argument and how to use it.

`warning('message_id', 'message', a1, a2, ..., an)` includes formatting conversion characters in `message`, and the character translations in arguments `a1, a2, ..., an`.

`s = warning(state, 'message_id')` is a warning control statement that enables you to indicate how you want MATLAB to act on certain warnings. The `state` argument can be `'on'`, `'off'`, or `'query'`. The `message_id` argument can

be a message identifier string, `'all'`, or `'last'`. See “Control Statements” in the MATLAB documentation for more information.

Output `s` is a structure array that indicates the current state of the selected warnings. The structure has the fields `identifier` and `state`. See “Output from Control Statements” in the MATLAB documentation for more.

`s = warning(state, mode)` is a warning control statement that enables you to enter debug mode, display an M-stack trace, or display more information with each warning. The `state` argument can be `'on'`, `'off'`, or `'query'`. The `mode` argument can be `'debug'`, `'backtrace'`, or `'verbose'`. See “Debug, Backtrace, and Verbose” in the MATLAB documentation for more information.

Examples

Example 1

Generate a warning that displays a simple string:

```
if ~ischar(p1)
   warning('Input must be a string')
end
```

Example 2

Generate a warning string that is defined at run-time. The first argument defines a message identifier for this warning:

```
warning('MATLAB:paramAmbiguous', ...
        'Ambiguous parameter name, "%s".', param)
```

Example 3

Using a message identifier, enable just the `actionNotTaken` warning from Simulink by first turning off all warnings and then setting just that warning to on:

```
warning off all
warning on Simulink:actionNotTaken
```

Use `query` to determine the current state of all warnings. It reports that you have set all warnings to `off` with the exception of `Simulink:actionNotTaken`:

```
warning query all
The default warning state is 'off'. Warnings not set to the
default are
```

```
  State  Warning Identifier

     on  Simulink:actionNotTaken
```

Example 4

MATLAB converts special characters (like `\n` and `%d`) in the warning message string only when you specify more than one input argument with `warning`. In the single argument case shown below, `\n` is taken to mean `backslash-n`. It is not converted to a newline character:

```
warning('In this case, the newline \n is not converted.')
Warning: In this case, the newline \n is not converted.
```

But, when more than one argument is specified, MATLAB does convert special characters. This is true regardless of whether the additional argument supplies conversion values or is a message identifier:

```
warning('WarnTests:convertTest', ...
      'In this case, the newline \n is converted.')
Warning: In this case, the newline
 is converted.
```

Example 5

To enter debug mode whenever a `parameterNotSymmetric` warning is invoked in a component called `Control`, first turn off all warnings and enable only this one type of warning using its message identifier. Then turn on debug mode for all enabled warnings. When you run your program, MATLAB will stop in debug mode just before this warning is executed. You will see the debug prompt (`K>>`) displayed:

```
warning off all
warning on Control:parameterNotSymmetric
warning on debug
```

Example 6

Turn on one particular warning, saving the previous state of this one warning in `s`. Remember that this nonquery syntax performs an implicit query prior to setting the new state:

```
s = warning('on', 'Control:parameterNotSymmetric');
```

After doing some work that includes making changes to the state of some warnings, restore the original state of all warnings:

```
warning(s)
```

See Also

`lastwarn`, `warndlg`, `error`, `lasterr`, `errordlg`, `dbstop`, `disp`, `sprintf`

Purpose

Waterfall plot

Syntax

```
waterfall(Z)
waterfall(X,Y,Z)
waterfall(...,C)
waterfall(axes_handle,...)
h = waterfall(...)
```

Description

The `waterfall` function draws a mesh similar to the `meshz` function, but it does not generate lines from the columns of the matrices. This produces a "waterfall" effect.

`waterfall(Z)` creates a waterfall plot using `x = 1:size(Z,1)` and `y = 1:size(Z,1)`. `Z` determines the color, so color is proportional to surface height.

`waterfall(X,Y,Z)` creates a waterfall plot using the values specified in `X`, `Y`, and `Z`. `Z` also determines the color, so color is proportional to the surface height. If `X` and `Y` are vectors, `X` corresponds to the columns of `Z`, and `Y` corresponds to the rows, where `length(x) = n`, `length(y) = m`, and `[m,n] = size(Z)`. `X` and `Y` are vectors or matrices that define the *x*- and *y*-coordinates of the plot. `Z` is a matrix that defines the *z*-coordinates of the plot (i.e., height above a plane). If `C` is omitted, color is proportional to `Z`.

`waterfall(...,C)` uses scaled color values to obtain colors from the current colormap. Color scaling is determined by the range of `C`, which must be the same size as `Z`. MATLAB performs a linear transformation on `C` to obtain colors from the current colormap.

`waterfall(axes_handles,...)` plots into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = waterfall(...)` returns the handle of the patch graphics object used to draw the plot.

Remarks

For column-oriented data analysis, use `waterfall(Z')` or `waterfall(X',Y',Z')`.

Examples

Produce a waterfall plot of the `peaks` function.

```
[X,Y,Z] = peaks(30);
waterfall(X,Y,Z)
```



Algorithm

The range of `X`, `Y`, and `Z`, or the current setting of the axes `Llim`, `YLim`, and `ZLim` properties, determines the range of the axes (also set by `axis`). The range of `C`, or the current setting of the axes `Clim` property, determines the color scaling (also set by `caxis`).

The `CData` property for the patch graphics objects specifies the color at every point along the edge of the patch, which determines the color of the lines.

The `waterfall` plot looks like a mesh surface; however, it is a patch graphics object. To create a surface plot similar to `waterfall`, use the `meshz` function and set the `MeshStyle` property of the surface to `'Row'`. For a discussion of parametric surfaces and related color properties, see `surf`.

See Also

`axes`, `axis`, `caxis`, `meshz`, `ribbon`, `surf`

Properties for patch graphics objects.

wavfinfo

Purpose

Return information about Microsoft WAVE (`.wav`) sound file

Syntax

```
[m d] = wavfinfo(filename)
```

Description

`[m d] = wavfinfo(filename)` returns information about the contents of the WAVE sound file specified by the string `filename`.

`m` is the string `'Sound (WAV) file'`, if `filename` is a WAVE file. Otherwise, it contains an empty string (`''`).

`d` is a string that reports the number of samples in the file and the number of channels of audio data. If `filename` is not a WAVE file, it contains the string `'Not a WAVE file'`.

See Also

`wavread`

Purpose

Play recorded sound on a PC-based audio output device

Syntax

```
wavplay(y,Fs)
wavplay(...,'mode')
```

Description

`wavplay(y,Fs)` plays the audio signal stored in the vector `y` on a PC-based audio output device. You specify the audio signal sampling rate with the integer `Fs` in samples per second. The default value for `Fs` is 11025 Hz (samples per second). `wavplay` supports only 1- or 2-channel (mono or stereo) audio signals.

`wavplay(...,'mode')` specifies how `wavplay` interacts with the command line, according to the string `'mode'`. The string `'mode'` can be

- `'async'` (default value): You have immediate access to the command line as soon as the sound begins to play on the audio output device (a nonblocking device call).
- `'sync'`: You don't have access to the command line until the sound has finished playing (a blocking device call).

The audio signal `y` can be one of four data types. The number of bits used to quantize and play back each sample depends on the data type.

Data Types for wavplay

Data Type	Quantization
Double-precision (default value)	16 bits/sample
Single-precision	16 bits/sample
16-bit signed integer	16 bits/sample
8-bit unsigned integer	8 bits/sample

Remarks

You can play your signal in stereo if `y` is a two-column matrix.

Examples

The MAT-files `gong.mat` and `chirp.mat` both contain an audio signal `y` and a sampling frequency `Fs`. Load and play the gong and the chirp audio signals.

Change the names of these signals in between `load` commands and play them sequentially using the `'sync'` option for `wavplay`.

```
load chirp;
y1 = y; Fs1 = Fs;
load gong;
wavplay(y1,Fs1,'sync') % The chirp signal finishes before the
wavplay(y,Fs)          % gong signal begins playing.
```

See Also

`wavrecord`

Purpose

Read Microsoft WAVE (.wav) sound file

Graphical Interface

As an alternative to auread, use the Import Wizard. To activate the Import Wizard, select **Import Data** from the **File** menu.

Syntax

```
y = wavread('filename')
[y,Fs,bits] = wavread('filename')
[...] = wavread('filename',N)
[...] = wavread('filename',[N1 N2])
[...] = wavread('filename','size')
```

Description

wavread supports multichannel data, with up to 32 bits per sample, and supports reading 24- and 32-bit .wav files.

`y = wavread('filename')` loads a WAVE file specified by the string `filename`, returning the sampled data in `y`. The `.wav` extension is appended if no extension is given. Amplitude values are in the range `[-1,+1]`.

`[y,Fs,bits] = wavread('filename')` returns the sample rate (`Fs`) in Hertz and the number of bits per sample (`bits`) used to encode the data in the file.

`[...] = wavread('filename',N)` returns only the first `N` samples from each channel in the file.

`[...] = wavread('filename',[N1 N2])` returns only samples `N1` through `N2` from each channel in the file.

`siz = wavread('filename','size')` returns the size of the audio data contained in the file in place of the actual audio data, returning the vector `siz = [samples channels]`.

See Also

auread, wavwrite

wavrecord

Purpose

Record sound using a PC-based audio input device.

Syntax

```
y = wavrecord(n,Fs)
y = wavrecord(...,ch)
y = wavrecord(...,'dtype')
```

Description

`y = wavrecord(n,Fs)` records `n` samples of an audio signal, sampled at a rate of `Fs` Hz (samples per second). The default value for `Fs` is 11025 Hz.

`y = wavrecord(...,ch)` uses `ch` number of input channels from the audio device. `ch` can be either 1 or 2, for mono or stereo, respectively. The default value for `ch` is 1.

`y = wavrecord(...,'dtype')` uses the data type specified by the string `'dtype'` to record the sound. The string `'dtype'` can be one of the following:

- `'double'` (default value), 16 bits/sample
- `'single'`, 16 bits/sample
- `'int16'`, 16 bits/sample
- `'uint8'`, 8 bits/sample

Remarks

Standard sampling rates for PC-based audio hardware are 8000, 11025, 2250, and 44100 samples per second. Stereo signals are returned as two-column matrices. The first column of a stereo audio matrix corresponds to the left input channel, while the second column corresponds to the right input channel.

Examples

Record 5 seconds of 16-bit audio sampled at 11025 Hz. Play back the recorded sound using `wavplay`. Speak into your audio device (or produce your audio signal) while the `wavrecord` command runs.

```
Fs = 11025;
y = wavrecord(5*Fs,Fs,'int16');
wavplay(y,Fs);
```

See Also

`wavplay`

Purpose

Write a Microsoft WAVE (`.wav`) sound file

Syntax

```
wavwrite(y,'filename')
wavwrite(y,Fs,'filename')
wavwrite(y,Fs,N,'filename')
```

Description

`wavwrite` writes data to 8-, 16-, 24-, and 32-bit `.wav` files.

`wavwrite(y,'filename')` writes the data stored in the variable `y` to a WAVE file called `filename`. The data has a sample rate of 8000 Hz and is assumed to be 16-bit. Each column of the data represents a separate channel. Therefore, stereo data should be specified as a matrix with two columns. Amplitude values outside the range `[-1,+1]` are clipped prior to writing.

`wavwrite(y,Fs,'filename')` writes the data stored in the variable `y` to a WAVE file called `filename`. The data has a sample rate of `Fs` Hz and is assumed to be 16-bit. Amplitude values outside the range `[-1,+1]` are clipped prior to writing.

`wavwrite(y,Fs,N,'filename')` writes the data stored in the variable `y` to a WAVE file called `filename`. The data has a sample rate of `Fs` Hz and is `N`-bit, where `N` is 8, 16, 24, or 32. For `N` < 32, amplitude values outside the range `[-1,+1]` are clipped.

Note 8-, 16-, and 24-bit files are type 1 integer pulse code modulation (PCM). 32-bit files are written as type 3 normalized floating point.

See Also

`auwrite`, `wavread`

web

Purpose

Open Web site or file in Web browser or Help browser

Syntax

```
web
web url
web url -new
web url -notoolbar
web url -noaddressbox
web url -helpbrowser
web url -browser
web(...)
stat = web('url', '-browser')
[stat, h1] = web
[stat, h1, url] = web
web url -browser
```

Description

`web` opens an empty MATLAB Web browser. The MATLAB Web browser includes an address field where you can enter a URL (Uniform Resource Locator), for example to a Web site or file, a toolbar with common browser buttons, and a MATLAB desktop menu.

`web url` displays the specified `url` in the MATLAB Web browser. If any MATLAB Web browsers are already open, displays the page in the browser that last had focus.

`web url -new` displays the specified `url` in a new MATLAB Web browser.

`web url -notoolbar` displays the specified `url` in a MATLAB Web browser that does not include the toolbar and address field. If any MATLAB Web browsers are already open, also use the `-new` option; otherwise `url` displays in the browser that last had focus, regardless of its toolbar status.

`web url -noaddressbox` displays the specified `url` in a MATLAB Web browser that does not include the address field. If any MATLAB Web browsers are already open, also use the `-new` option; otherwise `url` displays in the browser that last had focus, regardless of its address field status.

`web url -helpbrowser` displays the specified `url` in the MATLAB Help browser.

`web url -browser` displays the default Web browser for your system and loads the file or Web site specified by `url` in it. Generally, `url` specifies a local file or a Web site on the Internet. The `URL` can be in any form that the browser supports. On Windows and Macintosh, the default Web browser is determined by the operating system. On UNIX, the Web browser used is specified via `docopt`, in the `doccmd` string.

`web(...)` is the functional form of `web`.

`stat = web('url', '-browser')` runs `web` and returns the status of `web` to the variable `stat`.

Value of `stat`	Description
0	Browser was found and launched.
1	Browser was not found.
2	Browser was found but could not be launched.

`[stat, h1] = web` returns the status of `web` to the variable `stat`, and returns a handle to the Java class, for the last active browser.

`[stat, h1, url] = web` returns the status of `web` to the variable `stat`, returns a handle to the Java class,for the last active browser, and returns its current URL to `url`.

Example of `web http://www.mathtools.net`



Examples

`web http://www.mathworks.com` loads The MathWorks Web page into the MATLAB Web browser.

`web file:///disk/dir1/dir2/foo.html` opens the file `foo.html` in the MATLAB Web browser.

`web(['file:///' which('foo.html')])` opens `foo.html` if the file is on the MATLAB path or in the current directory.

`web('text://<html><h1>Hello World</h1></html>')` displays the HTML-formatted text `Hello World`.

`web ('http://www.mathworks.com', '-new', '-notoolbar')` loads The MathWorks Web page into a new MATLAB Web browser that does not include a toolbar or address field.

`web file:///disk/dir1/foo.html -helpbrowser` opens the file `foo.html` in the MATLAB Help browser.

`web file:///disk/dir1/foo.html -browser` opens the file `foo.html` in the system Web browser.

`web mailto:email_address` uses your system browser's default e-mail application to send a message to `email_address`.

`web http://www.mathtools.net -browser` opens a browser to `mathtools.net`. Then `[stat,h1,url]=web` returns

```
stat =
     0

h1 =
com.mathworks.mde.webbrowser.WebBrowser[,0,0,591x140,
layout=java.awt.BorderLayout,alignmentX=null,alignmentY=null,
border=,flags=9,maximumSize=,minimumSize=,preferredSize=]

url =
http://www.mathtools.net/
```

Run `methods(h1)` to view allowable methods for the class. As an example, you can use the method `setCurrentLocation` to change the URL displayed in `h1`, as in

```
setCurrentLocation(h1,'http://www.mathworks.com')
```

See Also

`doc`, `docopt`, `helpbrowser`, `matlab:`

weekday

Purpose

Display current day of the week

Syntax

```
[N, S] = weekday(D)
[N, S] = weekday(D, form)
[N, S] = weekday(D, locale)
[N, S] = weekday(D, form, locale)
```

Description

`[N, S] = weekday(D)` returns the day of the week in numeric (`N`) and string (`S`) form for a given serial date number or date string `D`. Input argument `D` can represent more than one date in an array of serial date numbers or a cell array of date strings.

`[N, S] = weekday(D, form)` returns the day of the week in numeric (`N`) and string (`S`) form, where the content of `S` depends on the `form` argument. If `form` is '**`long`**', then `S` contains the full name of the weekday (e.g., `Tuesday`). If `form` is '**`short`**', then `S` contains an abbreviated name (e.g., `Tues`) from this table.

The days of the week are assigned these numbers and abbreviations.

N	S (short)	S (long)
1	Sun	Sunday
2	Mon	Monday
3	Tue	Tuesday
4	Wed	Wednesday
5	Thu	Thursday
6	Fri	Friday
7	Sat	Saturday

`[N, S] = weekday(D, locale)` returns the day of the week in numeric (`N`) and string (`S`) form, where the format of the output depends on the `locale` argument. If `locale` is '**`local`**', then `weekday` uses local format for its output. If `locale` is '**`en_US`**', then `weekday` uses US English.

`[N, S] = weekday(D, form, locale)` returns the day of the week using the formats described above for `form` and `locale`.

Examples

Either

```
[n, s] = weekday(728647)
```

or

```
[n, s] = weekday('19-Dec-1994')
```

returns `n = 2` and `s = Mon`.

See Also

`datenum`, `datevec`, `eomday`

what

Purpose

List MATLAB specific files in current directory

Graphical Interface

As an alternative to the `what` function, use the Current Directory browser. To open it, select **Current Directory** from the **Desktop** menu in the MATLAB desktop.

Syntax

```
what
what dirname
what class
s = what('dirname')
```

Description

`what` lists the `M`, `MAT`, `MEX`, `MDL`, and `P`-files and the class directories that reside in the current working directory.

`what dirname` lists the files in directory `dirname` on the MATLAB search path. It is not necessary to enter the full pathname of the directory. The last component, or last two components, is sufficient.

`what class` lists the files in method directory, `@class`. For example, `what cfit` lists the MATLAB files in `toolbox/curvefit/curvefit/@cfit`.

`s = what('dirname')` returns the results in a structure array with these fields.

Field	Description
`path`	Path to directory
`m`	Cell array of M-file names
`mat`	Cell array of MAT-file names
`mex`	Cell array of MEX-file names
`mdl`	Cell array of MDL-file names
`p`	Cell array of P-file names
`classes`	Cell array of class names

Examples

List the files in `toolbox/matlab/audio`:

```
what audio

M-files in directory matlabroot/toolbox/matlab/audio

Contents            auread              soundsc
audiodevinfo        auwrite             wavplay
audioplayer         lin2mu              wavread
audioplayerreg      mu2lin              wavrecord
audiorecorder       prefspanel          wavwrite
audiorecorderreg    saxis
audiouniquename     sound

MAT-files in directory matlabroot/toolbox/matlab/audio

chirp        handel       splat
gong         laughter     train
```

Obtain a structure array containing the MATLAB filenames in `toolbox/matlab/general`.

```
s = what('general')
s =
       path: 'matlabroot:\toolbox\matlab\general'
          m: {104x1 cell}
        mat: {0x1 cell}
        mex: {5x1 cell}
        mdl: {0x1 cell}
          p: {'helpwin.p'}
    classes: {'char'}
```

See Also

`dir`, `exist`, `lookfor`, `mfilename`, `path`, `which`, `who`

whatsnew

Purpose

Display Release Notes for MathWorks products

Syntax

```
whatsnew
```

Description

`whatsnew` displays the Release Notes in the Help browser, presenting information about new features, problems from previous releases that have been fixed in the current release, and known problems, all organized by product.

See Also

`help`, `lookfor`, `path`, `version`, `which`

Purpose

Locate functions and files

Graphical Interface

As an alternative to the `which` function, use the Current Directory browser.

Syntax

```
which fun
which classname/fun
which private/fun
which classname/private/fun
which fun1 in fun2
which fun(a,b,c,...)
which file.ext
which fun -all
s = which('fun',...)
```

Description

`which fun` displays the full pathname for the argument `fun`. If `fun` is a

- MATLAB function or Simulink model in an M, P, or MDL file on the MATLAB path, then `which` displays the full pathname for the corresponding file
- Workspace variable, then `which` displays a message identifying `fun` as a variable
- Method in a loaded Java class, then `which` displays the package, class, and method name for that method

If `fun` is an overloaded function or method, then `which fun` returns only the pathname of the first function or method found.

`which classname/fun` displays the full pathname for the M-file defining the `fun` method in MATLAB class, `classname`. For example, `which serial/fopen` displays the path for `fopen.m` in the MATLAB class directory, `@serial`.

`which private/fun` limits the search to private functions. For example, `which private/orthog` displays the path for `orthog.m` in the `/private` subdirectory of `toolbox/matlab/elmat`.

`which classname/private/fun` limits the search to private methods defined by the MATLAB class, `classname`. For example, `which dfilt/private/todtf` displays the path for `todtf.m` in the `private` directory of the `dfilt` class.

`which fun1 in fun2` displays the pathname to function `fun1` in the context of the M-file `fun2`. You can use this form to determine whether a subfunction or private version of `fun1` is called from `fun2`, rather than a function on the path. For example, `which get in editpath` tells you which `get` function is called by `editpath.m`.

During debugging of `fun2`, using `which fun1` gives the same result.

`which fun(a,b,c,...)` displays the path to the specified function with the given input arguments. For example, `which feval(g)`, when `g=inline('sin(x)')`, indicates that `inline/feval.m` would be invoked. `which toLowerCase(s)`, when `s=java.lang.String('my Java string')`, indicates that the `toLowerCase` method in `class java.lang.String` would be invoked.

`which file.ext` displays the full pathname of the specified file if that file is in the current working directory or on the MATLAB path. Use `exist` to check for the existence of files anywhere else.

`which fun -all` displays the paths to all items on the MATLAB path with the name `fun`. You may use the **`-all`** qualifier with any of the above formats of the `which` function.

`s = which('fun',...)` returns the results of `which` in the string `s`. For workspace variables, `s` is the string '`variable`'. You may specify an output variable in any of the above formats of the `which` function.

If **`-all`** is used with this form, the output `s` is always a cell array of strings, even if only one string is returned.

Examples

The statement below indicates that `pinv` is in the `matfun` directory of MATLAB.

```
which pinv
matlabroot\toolbox\matlab\matfun\pinv.m
```

To find the `fopen` function used on MATLAB `serial` class objects

```
which serial/fopen
matlabroot\toolbox\matlab\iofun\@serial\fopen.m  % serial method
```

To find the `setTitle` method used on objects of the Java `Frame` class, the class must first be loaded into MATLAB. The class is loaded when you create an instance of the class:

```
frameObj = java.awt.Frame;

which setTitle
java.awt.Frame.setTitle  % Frame method
```

When you specify an output variable, `which` returns a cell array of strings to the variable. You must use the *function* form of `which`, enclosing all arguments in parentheses and single quotes:

```
s = which('private/stradd','-all');
whos s
  Name      Size         Bytes  Class
  s         3x1            562  cell array
Grand total is 146 elements using 562 bytes
```

See Also

`dir`, `doc`, `exist`, `lookfor`, `mfilename`, `path`, `type`, `what`, `who`

while

Purpose

Repeat statements an indefinite number of times

Syntax

```
while expression
    statements
end
```

Description

`while` repeats `statements` an indefinite number of times. The `statements` are executed while the real part of *`expression`* has all nonzero elements. *`expression`* is usually of the form

```
expression rel_op expression
```

where *`rel_op`* is ==, <, >, <=, >=, or ~=.

The scope of a `while` statement is always terminated with a matching `end`.

Arguments

expression

`expression` is a MATLAB expression, usually consisting of variables or smaller expressions joined by relational operators (e.g., `count < limit`) or logical functions (e.g., `isreal(A)`).

Simple expressions can be combined by logical operators (`&`, `|`, `~`) into compound expressions such as the following. MATLAB evaluates compound expressions from left to right, adhering to operator precedence rules.

```
(count < limit) & ((height - offset) >= 0)
```

statements

`statements` is one or more MATLAB statements to be executed only while the *`expression`* is `true` or nonzero.

Remarks

Nonscalar Expressions

If the evaluated `expression` yields a nonscalar value, then every element of this value must be `true` or nonzero for the entire expression to be considered `true`. For example, the statement `while (A < B)` is `true` only if each element of matrix `A` is less than its corresponding element in matrix `B`. See Example 2, below.

Partial Evaluation of the Expression Argument

Within the context of an `if` or `while` expression, MATLAB does not necessarily evaluate all parts of a logical expression. In some cases it is possible, and often advantageous, to determine whether an expression is `true` or `false` through only partial evaluation.

For example, if `A` equals zero in statement 1 below, then the expression evaluates to `false`, regardless of the value of `B`. In this case, there is no need to evaluate `B` and MATLAB does not do so. In statement 2, if `A` is nonzero, then the expression is `true`, regardless of `B`. Again, MATLAB does not evaluate the latter part of the expression.

```
1)   while (A & B)              2)   while (A | B)
```

You can use this property to your advantage to cause MATLAB to evaluate a part of an expression only if a preceding part evaluates to the desired state. Here are some examples.

```
while (b ~= 0) & (a/b > 18.5)

if exist('myfun.m') & (myfun(x) >= y)

if iscell(A) & all(cellfun('isreal', A))
```

Examples

Example 1 - Simple while Statement

The variable `eps` is a tolerance used to determine such things as near singularity and rank. Its initial value is the *machine epsilon*, the distance from 1.0 to the next largest floating-point number on your machine. Its calculation demonstrates `while` loops.

```
eps = 1;
while (1+eps) > 1
    eps = eps/2;
end
eps = eps*2
```

Example 2 - Nonscalar Expression

Given matrices `A` and `B`,

```
A =                   B =
     1     0               1     1
     2     3               3     4
```

Expression	Evaluates As	Because
`A < B`	`false`	`A(1,1)` is not less than `B(1,1)`.
`A < (B + 1)`	`true`	Every element of `A` is less than that same element of `B` with `1` added.
`A & B`	`false`	`A(1,2) & B(1,2)` is false.
`B < 5`	`true`	Every element of `B` is less than `5`.

See Also

`end`, `for`, `break`, `continue`, `return`, `all`, `any`, `if`, `switch`

Purpose

Change axes background color

Syntax

```
whitebg
whitebg(h)
whitebg(ColorSpec)
whitebg(h,ColorSpec)
```

Description

`whitebg` complements the colors in the current figure.

`whitebg(h)` complements colors in all figures specified in the vector `h`.

`whitebg(ColorSpec)` and `whitebg(h,ColorSpec)` change the color of the axes, which are children of the figure, to the color specified by `ColorSpec`.

Remarks

`whitebg` changes the colors of the figure's children, with the exception of shaded surfaces. This ensures that all objects are visible against the new background color. `whitebg` sets the default properties on the root such that all subsequent figures use the new background color.

Examples

Set the background color to blue-gray.

```
whitebg([0 .5 .6])
```

Set the background color to blue.

```
whitebg('blue')
```

See Also

`ColorSpec`

The figure graphics object property `InvertHardCopy`

"Color Operations" for related functions

who, whos

Purpose

List variables in the workspace

Graphical Interface

As an alternative to `whos`, use the Workspace browser.

Syntax

Each of these syntaxes apply to both `who` and `whos`:

```
who
who(variable_list)
who(variable_list, qualifiers)
s = who(variable_list, qualifiers)
who variable_list qualifiers
```

Description

`who` lists the variables currently in the workspace.

`whos` lists the current variables and their sizes and types. It also reports the totals for sizes.

`who(variable_list)` and `whos(variable_list)` list only those variables specified in `variable_list`, where `variable_list` is a comma-delimited list of quoted strings: `'var1', 'var2', ..., 'varN'`. You can use the wildcard character `*` to display variables that match a pattern. For example, `who('A*')` finds all variables in the current workspace that start with `A`.

`who(variable_list, qualifiers)` and `whos(variable_list, qualifiers)` list those variables in `variable_list` that meet all qualifications specified in `qualifiers`. You can specify any or all of the following qualifiers, and in any order.

Qualifier Syntax	Description	Example
`'global'`	List variables in the global workspace.	`whos('global')`

Qualifier Syntax	Description	Example
'**-file**', filename	List variables in the specified MAT-file. Use the full path for filename.	whos('-file', 'mydata')
'**-regexp**', exprlist	List variables that match any of the regular expressions in exprlist.	whos('-regexp', '[AB].', '\w\d')

`s = who(variable_list, qualifiers)` returns cell array `s` containing the names of the variables specified in `variable_list` that meet the conditions specified in `qualifiers`.

`s = whos(variable_list, qualifiers)` returns structure `s` containing the following fields for the variables specified in `variable_list` that meet the conditions specified in `qualifiers`:

```
name     variable name
size     variable size
bytes    number of bytes allocated for the array
class    class of variable
```

`who variable_list qualifiers` and `whos variable_list qualifiers` are the unquoted forms of the syntax. Both `variable_list` and `qualifiers` are space-delimited lists of unquoted strings.

Remarks

Information returned by the command `whos -file` is independent of whether the data in that file is compressed or not. The byte counts returned by this command represent the number of bytes data occupies in the MATLAB workspace, and not in the file the data was saved to. See the function reference for `save` for more information on data compression.

Examples

Show variable names starting with the letter a:

```
who a*
```

Show variables stored in MAT-file `mydata.mat` that start with `java` and end with `Array`. Also show their dimensions and class name:

```
whos -file mydata -regexp \<java.*Array\>
```

```
  Name               Size         Bytes  Class

  javaChrArray        3x1                java.lang.String[][][]
  javaDblArray        4x1                java.lang.Double[][]
  javaIntArray       14x1                java.lang.Integer[][]
```

Get variable names that start with uppercase or lowercase `X`, are followed by zero or more other characters, and end with at least two digits. Assign the output to cell array `xvars`:

```
xvars = who('-regexp', '^[Xx].*\d{2,}$')
xvars =
    'X_JohnDavis_5May03'
    'Xtest_120'
    'xArray5by12'
    'x_times_3pt82'
```

See Also

`assignin`, `clear`, `computer`, `dir`, `evalin`, `exist`, `inmem`, `load`, `save`, `what`, `workspace`

Purpose

Wilkinson's eigenvalue test matrix

Syntax

```
W = wilkinson(n)
```

Description

`W = wilkinson(n)` returns one of J. H. Wilkinson's eigenvalue test matrices. It is a symmetric, tridiagonal matrix with pairs of nearly, but not exactly, equal eigenvalues.

Examples

```
wilkinson(7)

ans =

     3     1     0     0     0     0     0
     1     2     1     0     0     0     0
     0     1     1     1     0     0     0
     0     0     1     0     1     0     0
     0     0     0     1     1     1     0
     0     0     0     0     1     2     1
     0     0     0     0     0     1     3
```

The most frequently used case is `wilkinson(21)`. Its two largest eigenvalues are both about 10.746; they agree to 14, but not to 15, decimal places.

See Also

`eig`, `gallery`, `pascal`

winopen

Purpose

Open file in appropriate application (Windows only)

Syntax

```
winopen('filename')
```

Description

`winopen('filename')` opens `filename` in the appropriate Microsoft Windows application. The `winopen` function uses the appropriate Windows shell command, and performs the same action as if you double-click the file in the Windows Explorer. If `filename` is not in the current directory, specify the absolute path for `filename`.

Examples

Open the file `thesis.doc`, located in the current directory, in Microsoft Word:

```
winopen('thesis.doc')
```

Open `myresults.html` in your system's default Web browser:

```
winopen('D:/myfiles/myresults.html')
```

See Also

`dos`, `open`, `web`

Purpose

Get item from Microsoft Windows registry

Syntax

```
value = winqueryreg('name', 'rootkey', 'subkey')
value = winqueryreg('rootkey', 'subkey', 'valname')
value = winqueryreg('rootkey', 'subkey')
```

Description

`value = winqueryreg('name', 'rootkey', 'subkey')` returns the key names in `rootkey\subkey` in a cell array of strings. The first argument is the literal quoted string, `'name'`.

If the value retrieved from the registry is a string, `winqueryreg` returns a string. If the value is a 32-bit integer, `winqueryreg` returns the value as an integer of MATLAB type `int32`.

`value = winqueryreg('rootkey', 'subkey', 'valname')` returns the value for key `valname` in `rootkey\subkey`.

`value = winqueryreg('rootkey', 'subkey')` returns a value in `rootkey\subkey` that has no value name property.

Note The literal **`name`** argument and the `rootkey` argument are case-sensitive. The `subkey` and `valname` arguments are not.

Remarks

This function works only for the following registry value types:

- strings (REG_SZ)
- expanded strings (REG_EXPAND_SZ)
- 32-bit integer (REG_DWORD)

Examples

Example 1

Get the value of `CLSID` for the MATLAB sample COM control `mwsampctrl.2`:

```
winqueryreg 'HKEY_CLASSES_ROOT' 'mwsamp.mwsampctrl.2\clsid'

ans =
   {5771A80A-2294-4CAC-A75B-157DCDDD3653}
```

Example 2

Get a list in variable `mousechar` for registry subkey `Mouse`, which is under subkey `Control Panel`, which is under root key `HKEY_CURRENT_USER`.

```
mousechar = winqueryreg('name', 'HKEY_CURRENT_USER', ...
   'control panel\mouse');
```

For each name in the `mousechar` list, get its value from the registry and then display the name and its value:

```
for k=1:length(mousechar)
   setting = winqueryreg('HKEY_CURRENT_USER', ...
      'control panel\mouse', mousechar{k});
   str = sprintf('%s = %s', mousechar{k}, num2str(setting));
   disp(str)
   end

ActiveWindowTracking = 0
DoubleClickHeight = 4
DoubleClickSpeed = 830
DoubleClickWidth = 4
MouseSpeed = 1
MouseThreshold1 = 6
MouseThreshold2 = 10
SnapToDefaultButton = 0
SwapMouseButtons = 0
```

See Also

Purpose

Determine if file contains Lotus WK1 worksheet

Syntax

```
[extens, type] = wk1finfo('filename')
```

Description

`[extens, type] = wk1finfo('filename')` returns the string `'WK1'` in `extens`, and `'Lotus 123 Spreadsheet'` in `type` if the file `filename` contains a readable Lotus worksheet.

Examples

This example returns information on spreadsheet file `matA.wk1`:

```
[extens, type] = wk1finfo('matA.wk1')

extens =
   WK1
type =
   Lotus 123 Spreadsheet
```

See Also

`wk1read`, `wk1write`, `csvread`, `csvwrite`

wk1read

Purpose

Read Lotus123 spreadsheet file (`.wk1`)

Syntax

```
M = wk1read(filename)
M = wk1read(filename,r,c)
M = wk1read(filename,r,c,range)
```

Description

`M = wk1read(filename)` reads a Lotus123 WK1 spreadsheet file into the matrix `M`.

`M = wk1read(filename,r,c)` starts reading at the row-column cell offset specified by `(r,c)`. `r` and `c` are zero based so that `r=0`, `c=0` specifies the first value in the file.

`M = wk1read(filename,r,c,range)` reads the range of values specified by the parameter `range`, where `range` can be

- A four-element vector specifying the cell range in the format

  ```
  [upper_left_row upper_left_col lower_right_row lower_right_col]
  ```



- A cell range specified as a string, for example, `'A1...C5'`
- A named range specified as a string, for example, `'Sales'`

Examples

Create a 8-by-8 matrix `A` and export it to Lotus spreadsheet `matA.wk1`:

```
A = [1:8; 11:18; 21:28; 31:38; 41:48; 51:58; 61:68; 71:78]
A =
     1     2     3     4     5     6     7     8
    11    12    13    14    15    16    17    18
    21    22    23    24    25    26    27    28
    31    32    33    34    35    36    37    38
    41    42    43    44    45    46    47    48
```

```
    51    52    53    54    55    56    57    58
    61    62    63    64    65    66    67    68
    71    72    73    74    75    76    77    78

wk1write('matA.wk1', A);
```

To read in a limited block of the spreadsheet data, specify the upper left row and column of the block using zero-based indexing:

```
M = wk1read('matA.wk1', 3, 2)
M =
    33    34    35    36    37    38
    43    44    45    46    47    48
    53    54    55    56    57    58
    63    64    65    66    67    68
    73    74    75    76    77    78
```

To select a more restricted block of data, you can specify both the upper left and lower right corners of the block you want imported. Read in a range of values from row 4, column 3 (defining the upper left corner) to row 6, column 6 (defining the lower right corner). Note that, unlike the second and third arguments, the range argument `[4 3 6 6]` is one-based:

```
M = wk1read('matA.wk1', 3, 2, [4 3 6 6])
M =
    33    34    35    36
    43    44    45    46
    53    54    55    56
```

See Also

`wk1write`

wk1write

Purpose

Write a matrix to a Lotus123 WK1 spreadsheet file

Syntax

```
wk1write(filename,M)
wk1write(filename,M,r,c)
```

Description

`wk1write(filename,M)` writes the matrix `M` into a Lotus123 WK1 spreadsheet file named `filename`.

`wk1write(filename,M,r,c)` writes the matrix starting at the spreadsheet location `(r,c)`. `r` and `c` are zero based so that `r=0`, `c=0` specifies the first cell in the spreadsheet.



Examples

Write a 4-by-5 matrix A to spreadsheet file matA.wk1. Place the matrix with its upper left corner at row 2, column 3 using zero-based indexing:

```
A = [1:5; 11:15; 21:25; 31:35]
A =
     1     2     3     4     5
    11    12    13    14    15
    21    22    23    24    25
    31    32    33    34    35

wk1write('matA.wk1', A, 2, 3)

M = wk1read('matA.wk1')
M =
     0     0     0     0     0     0     0     0
     0     0     0     0     0     0     0     0
     0     0     0     1     2     3     4     5
     0     0     0    11    12    13    14    15
     0     0     0    21    22    23    24    25
```

```
     0     0     0    31    32    33    34    35
```

See Also wk1read, dlmwrite, dlmread, csvwrite, csvread

workspace

Purpose

Display the Workspace browser, a tool for managing the workspace

Graphical Interface

As an alternative to the `workspace` function, select **Workspace** from the **Desktop** menu in the MATLAB desktop.

Syntax

```
workspace
```

Description

`workspace` displays the Workspace browser, a graphical user interface that allows you to view and manage the contents of the MATLAB workspace. It provides a graphical representation of the `whos` display, and allows you to perform the equivalent of the `clear`, `load`, `open`, and `save` functions.



To see and edit a graphical representation of a variable, double-click the variable in the Workspace browser. The variable is displayed in the Array Editor, where you can edit it.

See Also

`who`

2xlabel, ylabel, zlabel

Purpose

Label the *x*-, *y*-, and *z*-axis

Syntax

```
xlabel('string')
xlabel(fname)
xlabel(...,'PropertyName',PropertyValue,...)
xlabel(axes_handle,...)
h = xlabel(...)

ylabel(...)
ylabel(axes_handle,...)
h = ylabel(...)

zlabel(...)
zlabel(axes_handle,...)
h = zlabel(...)
```

Description

Each axes graphics object can have one label for the *x*-, *y*-, and *z*-axis. The label appears beneath its respective axis in a two-dimensional plot and to the side or beneath the axis in a three-dimensional plot.

`xlabel('string')` labels the *x*-axis of the current axes.

`xlabel(fname)` evaluates the function `fname`, which must return a string, then displays the string beside the *x*-axis.

`xlabel(...,'PropertyName',PropertyValue,...)` specifies property name and property value pairs for the text graphics object created by `xlabel`.

`xlabel(axes_handle,...)`, `ylabel(axes_handle,...)`, and `zlabel(axes_handle,...)` plot into the axes with handle `axes_handle` instead of the current axes (`gca`).

`h = xlabel(...)`, `h = ylabel(...)`, and `h = zlabel(...)` return the handle to the text object used as the label.

`ylabel(...)` and `zlabel(...)` label the *y*-axis and *z*-axis, respectively, of the current axes.

Remarks

Reissuing an `xlabel`, `ylabel`, or `zlabel` command causes the new label to replace the old label.

For three-dimensional graphics, MATLAB puts the label in the front or side, so that it is never hidden by the plot.

Examples

Create a multiline label for the *x*-axis using a multiline cell array.

```
xlabel({'first line';'second line'})
```

See Also

`text`, `title`

"Annotating Plots" for related functions

Adding Axis Labels to Graphs for more information about labeling axes

Purpose

Set or query axis limits

Syntax

Note that the syntax for each of these three functions is the same; only the `xlim` function is used for simplicity. Each operates on the respective *x*-, *y*-, or *z*-axis.

```
xlim
xlim([xmin xmax])
xlim('mode')
xlim('auto')
xlim('manual')
xlim(axes_handle,...)
```

Description

`xlim` with no arguments returns the respective limits of the current axes.

`xlim([xmin xmax])` sets the axis limits in the current axes to the specified values.

`xlim('mode')` returns the current value of the axis limits mode, which can be either `auto` (the default) or `manual`.

`xlim('auto')` sets the axis limit mode to `auto`.

`xlim('manual')` sets the respective axis limit mode to `manual`.

`xlim(axes_handle,...)` performs the set or query on the axes identified by the first argument, `axes_handle`. When you do not specify an axes handle, these functions operate on the current axes.

Remarks

`xlim`, `ylim`, and `zlim` set or query values of the axes object `XLim`, `YLim`, `ZLim`, and `XLimMode`, `YLimMode`, `ZLimMode` properties.

When the axis limit modes are `auto` (the default), MATLAB uses limits that span the range of the data being displayed and are round numbers. Setting a value for any of the limits also sets the corresponding mode to `manual`. Note that high-level plotting functions like `plot` and `surf` reset both the modes and the limits. If you set the limits on an existing graph and want to maintain these limits while adding more graphs, use the `hold` command.

Examples

This example illustrates how to set the *x*- and *y*-axis limits to match the actual range of the data, rather than the rounded values of `[-2 3]` for the *x*-axis and `[-2 4]` for the *y*-axis originally selected by MATLAB.

```
[x,y] = meshgrid([-1.75:.2:3.25]);
z = x.*exp(-x.^2-y.^2);
surf(x,y,z)
xlim([-1.75 3.25])
ylim([-1.75 3.25])
```



See Also

`axis`

The axes properties `XLim`, `YLim`, `ZLim`

"Setting the Aspect Ratio and Axis Limits" for related functions

Understanding Axes Aspect Ratio for more information on how axis limits affect the axes

Purpose

Determine if file contains Microsoft Excel (`.xls`) spreadsheet

Syntax

```
type = xlsfinfo('filename')
[type, sheets] = xlsfinfo('filename')
xlsfinfo filename
```

Description

`type = xlsfinfo('filename')` returns the string `'Microsoft Excel Spreadsheet'` in the `type` output if the file specified by `filename` can be read by the MATLAB function `xlsread`. Otherwise, `type` is the empty string.

`[type, sheets] = xlsfinfo('filename')` returns in the `sheets` output a cell array of strings containing the names of each spreadsheet in the file.

`xlsfinfo filename` is the command format for `xlsfinfo`.

Examples

When `filename` is an Excel spreadsheet,

```
[type, sheets] = xlsfinfo('myaccount.xls')

type =
   Microsoft Excel Spreadsheet

sheets =
    'Sheet1'    'Income'    'Expenses'
```

See Also

`xlsread`, `xlswrite`

xlsread

Purpose

Read Microsoft Excel spreadsheet file (`.xls`)

Syntax

```
N = xlsread('filename')
N = xlsread('filename', -1)
N = xlsread('filename', sheet)
N = xlsread('filename', 'range')
N = xlsread('filename', sheet, 'range')
N = xlsread('filename', sheet, 'range', 'basic')
[N, T] = xlsread('filename', ...)
[N, T, rawdata] = xlsread('filename', ...)
xlsread filename sheet range basic
```

Description

`N = xlsread('filename')` returns numeric data in `double` array `N` from the first sheet in the Microsoft Excel spreadsheet file named `filename`. The `xlsread` ignores leading rows or columns of text. However, if a cell not in a leading row or column is empty or contains text, `xlsread` puts a `NaN` in its place in the return array, `N`.

`N = xlsread('filename', -1)` opens the file `filename` in an Excel window, enabling you to interactively select the worksheet to be read and the range of data on that worksheet to import. To import an entire worksheet, first select the sheet in the Excel window and then click the **OK** button in the Data Selection Dialog box. To import a certain range of data from the sheet, select the worksheet in the Excel window, drag and drop the mouse over the desired range, and then click **OK**. (See “COM Server Requirements” below.)

`N = xlsread('filename', sheet)` reads the specified worksheet, where `sheet` is either a positive, double scalar value or a quoted string containing the sheet name. To determine the names of the sheets in a spreadsheet file, use `xlsfinfo`.

`N = xlsread('filename', 'range')` reads data from a specific rectangular region of the default worksheet (`Sheet1`). Specify `range` using the syntax `'C1:C2'`, where `C1` and `C2` are two opposing corners that define the region to be read. For example, `'D2:H4'` represents the 3-by-5 rectangular region between the two corners `D2` and `H4` on the worksheet. The `range` input is not case sensitive and uses Excel A1 notation. (See help in Excel for more information on this notation.) (Also, see “COM Server Requirements” below.)

`N = xlsread('filename', sheet, 'range')` reads data from a specific rectangular region (`range`) of the worksheet specified by `sheet`. See the previous two syntax formats for further explanation of the `sheet` and `range` inputs. (See "COM Server Requirements," below.)

`N = xlsread('filename', sheet, 'range', '`**`basic`**`')` imports data from the spreadsheet in basic import mode. `sheet` must be a quoted string and is case sensitive. `range` is ignored and can be set to the empty string (`''`).

`[N, T]= xlsread('filename', ...)` returns numeric data in array `N` and text data in cell array `T`. All cells in `T` that correspond to numeric data contain the empty string.

If `T` includes data that was previously written to the file using `xlswrite`, and the `range` specified for that `xlswrite` operation caused undefined data (`'#N/A'`) to be written to the worksheet, then cells containing that undefined data are represented in the `T` output as `'ActiveX VT_ERROR: '`.

`[N, T, rawdata] = xlsread('filename', ...)` returns numeric and text data in `N` and `T`, and unprocessed cell content in cell array `rawdata`, which contains both numeric and text data. (See "COM Server Requirements" below.)

`xlsread filename sheet range` **`basic`** is the command format for `xlsread`, showing its usage with all input arguments specified. When using this format, you must specify `sheet` as a string, (for example, `Income` or `Sheet4`) and not a numeric index. If the `sheet` name contains space characters, then quotation marks are required around the string, (for example, `'Income 2002'`).

Remarks

COM Server Requirements

The following four syntax formats are supported only on computer systems capable of starting Excel as a COM server from MATLAB.

```
N = xlsread('filename', -1)
N = xlsread('filename', 'range')
N = xlsread('filename', sheet, 'range')
[N, T, rawdata] = xlsread('filename', ...)
```

Examples

Example 1— Reading Numeric Data

The Microsoft Excel spreadsheet file `testdata1.xls` contains this data:

```
1    6
2    7
3    8
4    9
5   10
```

To read this data into MATLAB, use this command:

```
A = xlsread('testdata1.xls')
A =
    1    6
    2    7
    3    8
    4    9
    5   10
```

Example 2 — Handling Text Data

The Microsoft Excel spreadsheet file `testdata2.xls` contains a mix of numeric and text data:

```
1    6
2    7
3    8
4    9
5   text
```

`xlsread` puts a `NaN` in place of the text data in the result:

```
A = xlsread('testdata2.xls')
A =
    1    6
    2    7
    3    8
    4    9
    5   NaN
```

Example 3 — Selecting a Range of Data

To import only rows `4` and `5` from worksheet `1`, specify the range as `'A4:B5'`:

```
A = xlsread('testdata2.xls', 1, 'A4:B5')

A =
    4    9
    5   NaN
```

Example 4 — Handling Files with Row or Column Headers

A Microsoft Excel spreadsheet labeled `Temperatures` in file `tempdata.xls` contains two columns of numeric data with text headers for each column:

```
Time  Temp
12     98
13     99
14     97
```

If you want to import only the numeric data, use `xlsread` with a single return argument. Specify the filename and sheet name as inputs.

`xlsread` ignores any leading row or column of text in the numeric result.

```
ndata = xlsread('tempdata.xls', 'Temperatures')

ndata =
    12    98
    13    99
    14    97
```

To import both the numeric data and the text data, specify two return values for `xlsread`:

```
[ndata, headertext] = xlsread('tempdata.xls', 'Temperatures')

ndata =
    12    98
    13    99
    14    97

headertext =
    'Time'    'Temp'
```

See Also

`xlswrite`, `xlsfinfo`, `wk1read`, `textread`

xlswrite

Purpose

Write Microsoft Excel spreadsheet file (`.xls`)

Syntax

```
xlswrite('filename', M)
xlswrite('filename', M, sheet)
xlswrite('filename', M, 'range')
xlswrite('filename', M, sheet, 'range')
status = xlswrite('filename', ...)
[status, message] = xlswrite('filename', ...)
xlswrite filename M sheet range
```

Description

`xlswrite('filename', M)` writes matrix `M` to the Excel file `filename`. The input matrix `M` is an `m`-by-`n` numeric, character, or cell array, where `m < 65536` and `n < 256`. The matrix data is written to the first worksheet in the file, starting at cell `A1`.

`xlswrite('filename', M, sheet)` writes matrix `M` to the specified worksheet `sheet` in the file `filename`. The `sheet` argument can be either a positive, double scalar value representing the worksheet index, or a quoted string containing the sheet name.

If `sheet` does not exist, a new sheet is added at the end of the worksheet collection. If `sheet` is an index larger than the number of worksheets, empty sheets are appended until the number of worksheets in the workbook equals `sheet`. In either case, MATLAB generates a warning indicating that it has added a new worksheet.

`xlswrite('filename', M, 'range')` writes matrix `M` to a rectangular region specified by `range` in the first worksheet of the file `filename`. Specify `range` using one of the following quoted string formats:

- A cell designation, such as `'D2'`, to indicate the upper left corner of the region to receive the matrix data.
- Two cell designations separated by a colon, such as `'D2:H4'`, to indicate two opposing corners of the region to receive the matrix data. The range `'D2:H4'` represents the 3-by-5 rectangular region between the two corners `D2` and `H4` on the worksheet.

The `range` input is not case sensitive and uses Excel A1 notation. (See help in Excel for more information on this notation.)

The size defined by `range` should fit the size of `M` or contain only the first cell, (e.g., `'A2'`). If `range` is larger than the size of `M`, Excel fills the remainder of the region with `#N/A`. If `range` is smaller than the size of `M`, only the submatrix that fits into `range` is written to the file specified by `filename`.

`xlswrite('filename', M, sheet, 'range')` writes matrix `M` to a rectangular region specified by `range` in worksheet `sheet` of the file `filename`. See the previous two syntax formats for further explanation of the `sheet` and `range` inputs.

`status = xlswrite('filename', ...)` returns the completion status of the write operation in `status`. If the write completed successfully, `status` is equal to `1` (or `true`). Otherwise, `status` is `0` (or `false`). Unless you specify an output for `xlswrite`, no status is displayed in the Command Window.

`[status, message] = xlswrite('filename', ...)` returns any warning or error message generated by the write operation in the MATLAB structure `message`. The `message` structure has two fields:

- `message` — String containing the text of the warning or error message
- `identifier` — String containing the message identifier for the warning or error

`xlswrite filename M sheet range` is the command format for `xlswrite`, showing its usage with all input arguments specified. When using this format, you must specify `sheet` as a string (for example, `Income` or `Sheet4`). If the `sheet` name contains space characters, then quotation marks are required around the string (for example, `'Income 2002'`).

Examples

Example 1 — Writing Numeric Data to the Default Worksheet

Write a 7-element vector to Microsoft Excel file `testdata.xls`. By default, the data is written to cells `A1` through `G1` in the first worksheet in the file:

```
xlswrite('testdata', [12.7 5.02 -98 63.9 0 -.2 56])
```

Example 2 — Writing Mixed Data to a Specific Worksheet

This example writes the following mixed text and numeric data to the file `tempdata.xls`:

```
d = {'Time', 'Temp'; 12 98; 13 99; 14 97};
```

Call `xlswrite`, specifying the worksheet labeled `Temperatures`, and the region within the worksheet to write the data to. The 4-by-2 matrix will be written to the rectangular region that starts at cell `E1` in its upper left corner:

```
s = xlswrite('tempdata.xls', d, 'Temperatures', 'E1')
s =
    1
```

The output status `s` shows that the write operation succeeded. The data appears as shown here in the output file:

```
Time   Temp
  12     98
  13     99
  14     97
```

Example 3 — Appending a New Worksheet to the File

Now write the same data to a worksheet that doesn't yet exist in `tempdata.xls`. In this case, MATLAB appends a new sheet to the workbook, calling it by the name you supplied in the `sheets` input argument, `'NewTemp'`. MATLAB displays a warning indicating that it has added a new worksheet to the file:

```
xlswrite('tempdata.xls', d, 'NewTemp', 'E1')
Warning: Added specified worksheet.
```

If you don't want to see these warnings, you can turn them off using the command indicated in the message above:

```
warning off MATLAB:xlswrite:AddSheet
```

Now try the command again, this time creating another new worksheet, `NewTemp2`. Although the message is not displayed this time, you can still retrieve it and its identifier from the second output argument, `m`:

```
[stat mmsg] = xlswrite('tempdata.xls', d, 'NewTemp2', 'E1');

msg
msg =
       message: 'Added specified worksheet.'
    identifier: 'MATLAB:xlswrite:AddSheet'
```

See Also

`xlsread`, `xlsfinfo`, `wk1read`, `textread`

Purpose

Parse XML document and return Document Object Model node

Syntax

```
DOMnode = xmlread(filename)
```

Description

`DOMnode = xmlread(filename)` reads a URL or `filename` and returns a Document Object Model node representing the parsed document.

Remarks

Find out more about the Document Object Model at the World Wide Web Consortium (W3C) Web site, `http://www.w3.org/DOM/`. For specific information on using Java DOM objects, visit the Sun Web site, `http://www.java.sun.com/xml/docs/api`.

See Also

`xmlwrite`, `xslt`

xmlwrite

Purpose

Serialize XML Document Object Model node

Syntax

```
xmlwrite(filename, DOMnode)
str = xmlwrite(DOMnode)
```

Description

`xmlwrite(filename, DOMnode)` serializes the Document Object Model node `DOMnode` to the file specified by `filename`.

`str = xmlwrite(DOMnode)` serializes the Document Object Model node `DOMnode` and returns the node tree as a string, `s`.

Remarks

Find out more about the Document Object Model at the World Wide Web Consortium (W3C) Web site, `http://www.w3.org/DOM/`. For specific information on using Java DOM objects, visit the Sun Web site, `http://www.java.sun.com/xml/docs/api`.

Example

```
% Create a sample XML document.
docNode = com.mathworks.xml.XMLUtils.createDocument...
    ('root_element')
docRootNode = docNode.getDocumentElement;
for i=1:20
    thisElement = docNode.createElement('child_node');
    thisElement.appendChild...
        (docNode.createTextNode(sprintf('%i',i)));
    docRootNode.appendChild(thisElement);
end
docNode.appendChild(docNode.createComment('this is a comment'));

% Save the sample XML document.
xmlFileName = [tempname,'.xml'];
xmlwrite(xmlFileName,docNode);
edit(xmlFileName);
```

See Also

`xmlread`, `xslt`

Purpose

Exclusive or

Syntax

```
C = xor(A, B)
```

Description

`C = xor(A, B)` performs an exclusive OR operation on the corresponding elements of arrays `A` and `B`. The resulting element `C(i,j,...)` is logical true (`1`) if `A(i,j,...)` or `B(i,j,...)`, but not both, is nonzero.

A	B	C
Zero	Zero	0
Zero	Nonzero	1
Nonzero	Zero	1
Nonzero	Nonzero	0

Examples

Given `A = [0 0 pi eps]` and `B = [0 -2.4 0 1]`, then

```
C = xor(A,B)
C =
   0   1   1   0
```

To see where either `A` or `B` has a nonzero element and the other matrix does not,

```
spy(xor(A,B))
```

See Also

`all`, `any`, `find`, Elementwise Logical Operators, Short-Circuit Logical Operators

xslt

Purpose

Transform XML document using XSLT engine

Syntax

```
result = xslt(source, style, dest)
[result,style] = xslt(...)
xslt(...,'-web')
```

Description

`result = xslt(source, style, dest)` transforms an XML document using a stylesheet and returns the resulting document's URL. The function uses these inputs, the first of which is required:

- `source` is the filename or URL of the source XML file. `source` can also specify a DOM node.
- `style` is the filename or URL of an XSL stylesheet.
- `dest` is the filename or URL of the desired output document. If `dest` is absent or empty, the function uses a temporary filename. If `dest` is `'-tostring'`, the function returns the output document as a MATLAB string.

`[result,style] = xslt(...)` returns a processed stylesheet appropriate for passing to subsequent XSLT calls as `style`. This prevents costly repeated processing of the stylesheet.

`xslt(...,'-web')` displays the resulting document in the Help Browser.

Remarks

Find out more about XSL stylesheets and how to write them at the World Wide Web Consortium (W3C) web site, `http://www.w3.org/Style/XSL/`.

Example

This example converts the file `info.xml` using the stylesheet `info.xsl`, writing the output to the file `info.html`. It launches the resulting HTML file in the Help Browser. MATLAB has several `info.xml` files that are used by the **Start** menu.

```
xslt info.xml info.xsl info.html -web
```

See Also

`xmlread`, `xmlwrite`

2zeros

Purpose

Create an array of all zeros

Syntax

```
B = zeros(n)
B = zeros(m,n)
B = zeros([m n])
B = zeros(d1,d2,d3...)
B = zeros([d1 d2 d3...])
B = zeros(size(A))
zeros(m, n,...,classname)
zeros([m,n,...],classname)
```

Description

`B = zeros(n)` returns an `n`-by-`n` matrix of zeros. An error message appears if `n` is not a scalar.

`B = zeros(m,n)` or `B = zeros([m n])` returns an `m`-by-`n` matrix of zeros.

`B = zeros(d1,d2,d3...)` or `B = zeros([d1 d2 d3...])` returns an array of zeros with dimensions `d1`-by-`d2`-by-`d3`-by-`... .`

`B = zeros(size(A))` returns an array the same size as `A` consisting of all zeros.

`zeros(m, n,...,classname)` or `zeros([m,n,...],classname)` is an `m`-by-`n`-by-... array of zeros of data type `classname`. `classname` is a string specifying the data type of the output. `classname` can have the following values: `'double'`, `'single'`, `'int8'`, `'uint8'`, `'int16'`, `'uint16'`, `'int32'`, or `'uint32'`.

Example

```
x = zeros(2,3,'int8');
```

Remarks

The MATLAB language does not have a dimension statement; MATLAB automatically allocates storage for matrices. Nevertheless, for large matrices, MATLAB programs may execute faster if the `zeros` function is used to set aside storage for a matrix whose elements are to be generated one at a time, or a row or column at a time. For example

```
x = zeros(1,n);
for i = 1:n, x(i) = i; end
```

See Also eye, ones, rand, randn

Purpose

Create compressed version of files in zip format

Syntax

```
zip('zipfilename','files')
zip('zipfilename','directory')
zip(...,'rootdirectory')
```

Description

`zip('zipfilename','files')` creates a zip file named `zipfilename` from the file named `files`. For multiple files, make `files` a cell array of strings. Paths for `zipfilename` and `files` are relative to the current directory. Zip files are often used for archiving or for minimizing file transmission time.

`zip('zipfilename','directory')` creates a zip file named `zipfilename` consisting of the specified directory and all the files in it. The paths for `zipfilename` and `directory` are relative to the current directory.

`zip('zipfilename','source','rootdirectory')` allows the path specified for `source` to be relative to `'rootdirectory'` rather than to the current directory. Note that `source` cannot be an absolute path.

Examples

Zipping a File

Create a zip file of the file `guide.viewlet`, which is in the `demos` directory of MATLAB. It saves the zip file in `d:/mymfiles/viewlet.zip`.

```
zip('d:/mymfiles/viewlet.zip','$matlabroot/demos/guide.viewlet')
```

Zip the files `guide.viewlet` and `import.viewlet` and save the zip file in `viewlets.zip`. The source files and zipped file are in the current directory.

```
zip('viewlets.zip',{'guide.viewlet','import.viewlet'})
```

Zipping a Directory

Zip the directory `D:/mymfiles` and its contents to the zip file `mymfiles` in the directory one level up from the current directory.

```
zip('../mymfiles','D:/mymfiles')
```

Zip the files `thesis.doc` and `defense.ppt`, which are located in `d:/PhD`, to the zip file `thesis.zip` in the current directory.

```
zip('thesis.zip',{'thesis.doc','defense.ppt'},'d:/PhD')
```

See Also unzip

Purpose

Zoom in and out on a 2-D plot

Syntax

```
zoom on
zoom off
zoom out
zoom reset
zoom
zoom xon
zoom yon
zoom(factor)
zoom(fig, option)
```

Description

`zoom on` turns on interactive zooming. When interactive zooming is enabled in a figure, pressing a mouse button while your cursor is within an axes zooms into the point or out from the point beneath the mouse. Zooming changes the axes limits.

- For a single-button mouse, zoom in by pressing the mouse button and zoom out by simultaneously pressing **Shift** and the mouse button.
- For a two- or three-button mouse, zoom in by pressing the left mouse button and zoom out by pressing the right mouse button.

Clicking and dragging over an axes when interactive zooming is enabled draws a rubberband box. When the mouse button is released, the axes zoom in to the region enclosed by the rubberband box.

Double-clicking over an axes returns the axes to its initial zoom setting.

`zoom off` turns interactive zooming off.

`zoom out` returns the plot to its initial zoom setting.

`zoom reset` remembers the current zoom setting as the initial zoom setting. Later calls to `zoom out`, or double-clicks when interactive `zoom` mode is enabled, will return to this zoom level.

`zoom` toggles the interactive zoom status.

`zoom xon` and `zoom yon` set `zoom on` for the *x*- and *y*-axis, respectively.

`zoom(factor)` zooms in or out by the specified zoom factor, without affecting the interactive zoom mode. Values greater than 1 zoom in by that amount, while numbers greater than 0 and less than 1 zoom out by `1/factor`.

`zoom(fig, option)` Any of the above options can be specified on a figure other than the current figure using this syntax.

Remarks

`zoom` changes the axes limits by a factor of two (in or out) each time you press the mouse button while the cursor is within an axes. You can also click and drag the mouse to define a zoom area, or double-click to return to the initial zoom level.

See Also

`linkaxes`, `pan`

"Object Manipulation" for related functions

Index

Numerics

1-norm 2-1810

A

Accelerator
  Uimenu property 2-2370
activelegend 2-1692
allocation of storage (automatic) 2-2545
AlphaData
  surface property 2-2156
  surfaceplot property 2-2171
AlphaDataMapping
  patch property 2-1615
  surface property 2-2156
  surfaceplot property 2-2171
AmbientStrength
  Patch property 2-1615
  Surface property 2-2157
  surfaceplot property 2-2172
annotating plots 2-1693
archiving files 2-2547
arguments, M-file
  passing variable numbers of 2-2455
array
  product of elements 2-1741
  of random numbers 2-1799, 2-1801
  removing first n singleton dimensions of 2-1953
  removing singleton dimensions of 2-2022
  reshaping 2-1858
  shifting dimensions of 2-1953
  size of 2-1964
  sorting elements of 2-1974
  structure 2-1875, 2-1946
  sum of elements 2-2138
  swapping dimensions of 2-1672
  of all zeros 2-2545
arrays
  editing 2-2528
ASCII data
  converting sparse matrix after loading from 2-1984
  saving to disk 2-1899
aspect ratio of axes 2-1642
AutoScale
  quivergroup property 2-1783
AutoScaleFactor
  quivergroup property 2-1783
axes
  setting and querying limits 2-2531
  setting and querying plot box aspect ratio 2-1642
axes
  editing 2-1693
azimuth (spherical coordinates) 2-1992
azimuth of viewpoint 2-2468

B

BackFaceLighting
  Surface property 2-2157
  surfaceplot property 2-2172
BackFaceLightingpatch property 2-1616
BackGroundColor
  Uicontrol property 2-2339
BackgroundColor
  Text property 2-2230
badly conditioned 2-1810
BaseLine
  stem property 2-2053
BaseValue
  stem property 2-2053

BeingDeleted
group property 2-2231
quivergroup property 2-1783
rectangle property 2-1824
scatter property 2-1913
stairseries property 2-2029
stem property 2-2053
surface property 2-2157
surfaceplot property 2-2172
transform property 2-1616
Uipushtool property 2-2402
Uitoggletool property 2-2424
Uitoolbar property 2-2435
binary data
saving to disk 2-1899
bold font
TeX characters 2-2246
bubble plot (scatter function) 2-1909
Buckminster Fuller 2-2209
BusyAction
patch property 2-1616
quivergroup property 2-1783
rectangle property 2-1824
Root property 2-1878
scatter property 2-1913
stairseries property 2-2029
stem property 2-2053
Surface property 2-2158
surfaceplot property 2-2173
Text property 2-2231
Uicontextmenu property 2-2324
Uicontrol property 2-2339
Uimenu property 2-2371
Uipushtool property 2-2402
Uitoggletool property 2-2424
Uitoolbar property 2-2435
ButtonDownFcn
patch property 2-1617
quivergroup property 2-1784
rectangle property 2-1825
Root property 2-1878
scatter property 2-1914
stairseries property 2-2030
stem property 2-2054
Surface property 2-2158
surfaceplot property 2-2173
Text property 2-2232
Uicontextmenu property 2-2324
Uicontrol property 2-2340

C

caching
MATLAB directory 2-1634
CallBack
Uicontextmenu property 2-2324
Uicontrol property 2-2340
Uimenu property 2-2371
CallbackObject, Root property 2-1878
CaptureMatrix, Root property 2-1878
CaptureRect, Root property 2-1878
Cartesian coordinates 2-1702, 2-1992
case
in switch statement (defined) 2-2198
lower to upper 2-2450
Cayley-Hamilton theorem 2-1718
CData
scatter property 2-1914
Surface property 2-2158
surfaceplot property 2-2173
Uicontrol property 2-2341
Uipushtool property 2-2403
Uitoggletool property 2-2425
CDataMapping

patch property 2-1619
Surface property 2-2159
surfaceplot property 2-2174
CDataMode
surfaceplot property 2-2174
CDatapatch property 2-1617
CDataSource
scatter property 2-1914
surfaceplot property 2-2174
characters
conversion, in format specification string 2-2011
escape, in format specification string 2-2012
check boxes 2-2330
Checked, Uimenu property 2-2371
checkerboard pattern (example) 2-1856
child functions 2-1742
Children
patch property 2-1620
quivergroup property 2-1784
rectangle property 2-1825
Root property 2-1878
scatter property 2-1915
stairseries property 2-2030
stem property 2-2054
Surface property 2-2159
surfaceplot property 2-2175
Text property 2-2232
Uicontextmenu property 2-2324
Uicontrol property 2-2341
Uimenu property 2-2372
Uitoolbar property 2-2436
Cholesky factorization
lower triangular factor 2-1602
minimum degree ordering and (sparse) 2-2207
ClickedCallback
Uipushtool property 2-2403
Uitoggletool property 2-2425
Clipping
quivergroup property 2-1784
rectangle property 2-1825
Root property 2-1878, 2-1879
scatter property 2-1915
stairseries property 2-2030
stem property 2-2055
Surface property 2-2159
surfaceplot property 2-2175
Text property 2-2232
Uicontextmenu property 2-2324
Uicontrol property 2-2341
Clippingpatch property 2-1620
closest triangle search 2-2300
closing
MATLAB 2-1777
Color
quivergroup property 2-1784
stairseries property 2-2030
stem property 2-2055
Text property 2-2232
colormaps
converting from RGB to HSV 2-1866
plotting RGB components 2-1867
commands
system 2-2212
UNIX 2-2444
complex
numbers, sorting 2-1974, 2-1977
sine 2-1959
unitary matrix 2-1759
complex Schur form 2-1925
compress files 2-2547
condition number of matrix 2-1810
context menu 2-2320
continued fraction expansion 2-1805

conversion
cylindrical to Cartesian 2-1702
full to sparse 2-1981
lowercase to uppercase 2-2450
partial fraction expansion to pole-residue 2-1860
polar to Cartesian 2-1702
pole-residue to partial fraction expansion 2-1860
real to complex Schur form 2-1897
spherical to Cartesian 2-1992
string to numeric array 2-2070
conversion characters in format specification string 2-2011
coordinate system and viewpoint 2-2468
coordinates
Cartesian 2-1702, 2-1992
cylindrical 2-1702
polar 2-1702
spherical 2-1992
CreateFcn
patch property 2-1620
quivergroup property 2-1785
rectangle property 2-1825
Root property 2-1879
scatter property 2-1915
stairseries property 2-2030
stemseries property 2-2055
Surface property 2-2159
surfaceplot property 2-2175
Text property 2-2232
Uicontextmenu property 2-2324
Uicontrol property 2-2341
Uimenu property 2-2372
Uipushtool property 2-2403
Uitoggletool property 2-2425
Uitoolbar property 2-2436
cubic interpolation 2-1651
current directory 2-1754
CurrentFigure, Root property 2-1879
Curvature, rectangle property 2-1826
curve fitting (polynomial) 2-1711
Cuthill-McKee ordering, reverse 2-2207, 2-2209
cylindrical coordinates 2-1702

D

data
ASCII, saving to disk 2-1899
binary, saving to disk 2-1899
computing 2-D stream lines 2-2076
computing 3-D stream lines 2-2078
formatting 2-2010
reading from files 2-2249
reducing number of elements in 2-1838
smoothing 3-D 2-1972
writing to strings 2-2010
data, ASCII
converting sparse matrix after loading from 2-1984
debugging
M-files 2-1742
decomposition
“economy-size” 2-1759, 2-2193
orthogonal-triangular (QR) 2-1759
Schur 2-1925
singular value 2-1804, 2-2193
definite integral 2-1770
DeleteFcn
quivergroup property 2-1785
Root property 2-1879
scatter property 2-1915
stairseries property 2-2031
stem property 2-2055

Surface property 2-2160
surfaceplot property 2-2175
Text property 2-2233, 2-2234
Uicontextmenu property 2-2325, 2-2342
Uimenu property 2-2373
Uipushtool property 2-2404
Uitoggletool property 2-2426
Uitoolbar property 2-2437
DeleteFcn, rectangle property 2-1826
DeleteFcnpatch property 2-1620
dependence, linear 2-2135
dependent functions 2-1742
derivative
polynomial 2-1708
detecting
positive, negative, and zero array elements 2-1958
diagonal
k-th (illustration) 2-2290
sparse 2-1986
dialog box
print 2-1739
question 2-1776
warning 2-2486
Diary, Root property 2-1879
DiaryFile, Root property 2-1879
differences
between sets 2-1944, 2-1945
differential equation solvers
ODE boundary value problems
extracting properties of 2-2288, 2-2289
parabolic-elliptic PDE problems 2-1657
DiffuseStrength
Surface property 2-2160
surfaceplot property 2-2176
DiffuseStrengthpatch property 2-1621
digamma function 2-1750
dimension statement (lack of in MATLAB) 2-2545
dimensions
size of 2-1964
direct term of a partial fraction expansion 2-1860
directories
listing MATLAB files in 2-2506
MATLAB
caching 2-1634
removing 2-1871
removing from search path 2-1876
directory
temporary system 2-2216
directory, current 2-1754
discontinuities, eliminating (in arrays of phase angles) 2-2447
DisplayName
quivergroup property 2-1785
scatter property 2-1916
stairseries property 2-2031
stem property 2-2056
division
remainder after 2-1854

E

Echo, Root property 2-1879
EdgeAlpha
patch property 2-1621
surface property 2-2160
surfaceplot property 2-2176
EdgeColor
patch property 2-1621
Surface property 2-2161
surfaceplot property 2-2176
Text property 2-2233
EdgeColor, rectangle property 2-1826
EdgeLighting

patch property 2-1622
Surface property 2-2161
surfaceplot property 2-2177
editable text 2-2330
eigenvalue
modern approach to computation of 2-1706
problem 2-1709
problem, generalized 2-1709
problem, polynomial 2-1709
Wilkinson test matrix and 2-2519
eigenvector
matrix, generalized 2-1798
elevation (spherical coordinates) 2-1992
elevation of viewpoint 2-2468
`Enable`
Uicontrol property 2-2342
Uimenu property 2-2374
Uipushtool property 2-2404
Uitogglehtool property 2-2426
`EraseMode`
quivergroup property 2-1786
rectangle property 2-1826
scatter property 2-1916
stairseries property 2-2031
stem property 2-2056
Surface property 2-2162
surfaceplot property 2-2177
Text property 2-2234
`EraseMode`patch property 2-1622
error messages
`Out of memory` 2-1596
`ErrorMessage`, Root property 2-1880
`ErrorType`, Root property 2-1880
escape characters in format specification string 2-2012
examples
reducing number of patch faces 2-1835
reducing volume data 2-1838
subsampling volume data 2-2141
Excel spreadsheets
loading 2-2534
executing statements repeatedly 2-2512
execution
improving speed of by setting aside storage 2-2545
pausing M-file 2-1641
time for M-files 2-1742
extension, filename
`.mat` 2-1899
`Extent`
Text property 2-2235
Uicontrol property 2-2343

F

`FaceAlpha`patch property 2-1623
`FaceAlpha`surface property 2-2163
`FaceAlpha`surfaceplot property 2-2178
`FaceColor`
Surface property 2-2163
surfaceplot property 2-2179
`FaceColor`, rectangle property 2-1827
`FaceColor`patch property 2-1624
`FaceLighting`
Surface property 2-2163
surfaceplot property 2-2179
`FaceLighting`patch property 2-1624
faces, reducing number in patches 2-1834
`Faces`,patch property 2-1624
`FaceVertexAlphaData`, patch property 2-1625
`FaceVertexCData`,patch property 2-1626
factorization
QZ 2-1710, 2-1798
See also decomposition

factorization, Cholesky
  minimum degree ordering and (sparse) 2-2207
Figure
  redrawing 2-1840
figures
  annotating 2-1693
  saving 2-1904
filename
  temporary 2-2217
filename extension
  .mat 2-1899
files
  compressing 2-2547
  Excel spreadsheets
    loading 2-2534
  fig 2-1904
  figure, saving 2-1904
  listing
    in directory 2-2506
  locating 2-2509
  mdl 2-1904
  model, saving 2-1904
  opening
    in Web browser 2-2500
  opening in Windows applications 2-2520
  pathname for 2-2509
  reading
    data from 2-2249
  sound
    reading 2-2497
    writing 2-2499
  .wav
    reading 2-2497
    writing 2-2499
  WK1
    loading 2-2524
    writing to 2-2526
finding
  sign of array elements 2-1958
finish.m 2-1777
fixed-width font
  text 2-2236
  uicontrols 2-2344
FixedWidthFontName, Root property 2-1880
floating-point arithmetic, IEEE
  smallest postive number 2-1814
flow control
  return 2-1865
  switch 2-2198
  while 2-2512
font
  fixed-width, text 2-2236
  fixed-width, uicontrols 2-2344
FontAngle
  Text property 2-2235
  Uicontrol property 2-2344
FontName
  Text property 2-2235
  Uicontrol property 2-2344
fonts
  bold 2-2236
  italic 2-2235
  specifying size 2-2236
  TeX characters
    bold 2-2246
    italics 2-2246
    specifying family 2-2246
    specifying size 2-2246
  units 2-2236
FontSize
  Text property 2-2236
  Uicontrol property 2-2344
FontUnits
  Text property 2-2236

Uicontrol property 2-2344
FontWeight
Text property 2-2236
Uicontrol property 2-2345
ForegroundColor
Uicontrol property 2-2345
Uimenu property 2-2374
Format 2-1880
format
specification string, matching file data to 2-2024
FormatSpacing, Root property 2-1881
formatting data 2-2010
fraction, continued 2-1805
fragmented memory 2-1596
functions
locating 2-2509
pathname for 2-2509
that work down the first non-singleton dimension 2-1953

G

gamma function
logarithmic derivative 2-1750
Gaussian elimination
Gauss Jordan elimination with partial pivoting 2-1895
generalized eigenvalue problem 2-1709
geodesic dome 2-2209
graphics objects
Patch 2-1603
resetting properties 2-1857
Root 2-1877
setting properties 2-1938
Surface 2-2152
Text 2-2222
uicontextmenu 2-2320
Uicontrol 2-2329
Uimenu 2-2366
graphs
editing 2-1693
Greek letters and mathematical symbols 2-2244
GUIs, printing 2-1734

H

Hadamard matrix
subspaces of 2-2135
HandleVisibility
patch property 2-1627
quivergroup property 2-1787
rectangle property 2-1827
Root property 2-1881
scatter property 2-1917
stairseries property 2-2032
stem property 2-2057
Surface property 2-2164
surfaceplot property 2-2179
Text property 2-2236
Uicontextmenu property 2-2326
Uicontrol property 2-2345
Uimenu property 2-2374
Uipushtool property 2-2405
Uitoggletool property 2-2427
Uitoolbar property 2-2437
HitTest
Patch property 2-1628
quivergroup property 2-1788
rectangle property 2-1828
Root property 2-1881
scatter property 2-1918
stairseries property 2-2033
stem property 2-2058

Surface property 2-2165
surfaceplot property 2-2180
Text property 2-2237
Uicontextmenu property 2-2326
Uicontrol property 2-2346
HitTestArea
quivergroup property 2-1788
scatter property 2-1918
stairseries property 2-2034
stem property 2-2058
HorizontalAlignment
Text property 2-2238
Uicontrol property 2-2346
HTML files
opening 2-2500
hyperbolic
secant 2-1931
sine 2-1963
tangent 2-2215
hyperplanes, angle between 2-2135

I

identity matrix
sparse 2-1989
IEEE floating-point arithmetic
smallest positive number 2-1814
indices, array
of sorted elements 2-1975
integration
polynomial 2-1714
quadrature 2-1770
interpolated shading and printing 2-1735
Interpreter
Text property 2-2239
Interruptible
patch property 2-1628
quivergroup property 2-1788
rectangle property 2-1828
Root property 2-1881
scatter property 2-1918
stairseries property 2-2034
stem property 2-2058, 2-2061
Surface property 2-2165, 2-2181
Text property 2-2240
Uicontextmenu property 2-2326
Uicontrol property 2-2346
Uimenu property 2-2374
Uipushtool property 2-2406
Uitoggletool property 2-2428
Uitoolbar property 2-2437
involutary matrix 2-1602
italics font
TeX characters 2-2246

J

Jacobi rotations 2-2008
Java version used by MATLAB 2-2464
jvm
version used by MATLAB 2-2464

K

keyboard mode
terminating 2-1865
KeyPressFcn
Uicontrol property 2-2347

L

Label, Uimenu property 2-2375
labeling
axes 2-2529

LaTeX, see TeX 2-2244
least squares
  polynomial curve fitting 2-1711
  problem, overdetermined 2-1679
limits of axes, setting and querying 2-2531
Line
  properties 2-1824
line
  editing 2-1693
linear dependence (of data) 2-2135
linear equation systems
  solving overdetermined 2-1761–2-1762
linear regression 2-1711
lines
  computing 2-D stream 2-2076
  computing 3-D stream 2-2078
  drawing stream lines 2-2080
LineStyle
  patch property 2-1629
  quivergroup property 2-1789
  rectangle property 2-1829
  stairseries property 2-2034
  stem property 2-2059
  surface object 2-2165
  surfaceplot object 2-2181
  text object 2-2240
LineWidth
  Patch property 2-1629
  quivergroup property 2-1789
  rectangle property 2-1829
  scatter property 2-1919
  stairseries property 2-2035
  stem property 2-2059
  Surface property 2-2166
  surfaceplot property 2-2181
  text object 2-2241
list boxes 2-2330
  defining items 2-2351
ListboxTop, Uicontrol property 2-2348
logarithm
  of real numbers 2-1812
logarithmic derivative
  gamma function 2-1750
logical operations
  XOR 2-2543
Lotus WK1 files
  loading 2-2524
  writing 2-2526
lower triangular matrix 2-2290
lowercase to uppercase 2-2450

M

machine epsilon 2-2513
Marker
  Patch property 2-1629
  quivergroup property 2-1789
  scatter property 2-1919
  stairseries property 2-2035
  stem property 2-2059
  Surface property 2-2166
  surfaceplot property 2-2181
MarkerEdgeColor
  Patch property 2-1630
  quivergroup property 2-1790
  scatter property 2-1920
  stairseries property 2-2036
  stem property 2-2060
  Surface property 2-2167
  surfaceplot property 2-2182
MarkerFaceColor
  Patch property 2-1630
  quivergroup property 2-1790
  scatter property 2-1920

stairseries property 2-2036
stem property 2-2060
Surface property 2-2167
surfaceplot property 2-2183
MarkerSize
Patch property 2-1630
quivergroup property 2-1790
stairseries property 2-2036
stem property 2-2061
Surface property 2-2167
surfaceplot property 2-2183
MAT-file 2-1899
converting sparse matrix after loading from 2-1984
MAT-files
listing for directory 2-2506
MATLAB
quitting 2-1777
version number, displaying 2-2458
MATLAB startup file 2-2043
matlab.mat 2-1899
matrices
preallocation 2-2545
matrix
complex unitary 2-1759
condition number of 2-1810
converting to from string 2-2023
decomposition 2-1759
Hadamard 2-2135
Hermitian Toeplitz 2-2284
involutary 2-1602
lower triangular 2-2290
magic squares 2-2138
orthonormal 2-1759
Pascal 2-1602, 2-1717
permutation 2-1759
pseudoinverse 2-1679
reduced row echelon form of 2-1895
replicating 2-1856
rotating 90° 2-1890
Schur form of 2-1897, 2-1925
sorting rows of 2-1977
sparse *See* sparse matrix
square root of 2-2019
subspaces of 2-2135
Toeplitz 2-2284
trace of 2-2285
unitary 2-2193
upper triangular 2-2296
Vandermonde 2-1713
Wilkinson 2-1987, 2-2519
writing to spreadsheet 2-2526
Max, Uicontrol property 2-2348
MaxHeadSize
quivergroup property 2-1791
memory
minimizing use of 2-1596
variables in 2-2516
mesh plot
tetrahedron 2-2218
MeshStyle, Surface property 2-2167
MeshStyle, surfaceplot property 2-2183
message
error See error message
warning See warning message
methods
locating 2-2509
MEX-files
listing for directory 2-2506
M-file
pausing execution of 2-1641
M-files
creating
in MATLAB directory 2-1634

debugging with profile 2-1742
listing names of in a directory 2-2506
optimizing 2-1742
Microsoft Excel files
loading 2-2534
Min, Uicontrol property 2-2349
minimum degree ordering 2-2207
models
saving 2-1904
MonitorPosition
Root property 2-1881
Moore-Penrose pseudoinverse 2-1679
multidimensional arrays
rearranging dimensions of 2-1672
removing singleton dimensions of 2-2022
reshaping 2-1858
size of 2-1964
sorting elements of 2-1974

N

NaN (Not-a-Number)
returned by rem 2-1854
nonzero entries
specifying maximum number of in sparse matrix 2-1981
nonzero entries (in sparse matrix)
replacing with ones 2-2001
norm
1-norm 2-1810
pseudoinverse and 2-1679–2-1681
NormalMode
Patch property 2-1631
Surface property 2-2167
surfaceplot property 2-2183
numbers
prime 2-1724
random 2-1799, 2-1801
real 2-1811
smallest positive 2-1814
numerical evaluation
triple integral 2-2292

O

OffCallback
Uitoggletool property 2-2429
OnCallback
Uitoggletool property 2-2429
opening
files in Windows applications 2-2520
operating system command 2-2212
optimizing M-file execution 2-1742
ordering
minimum degree 2-2207
reverse Cuthill-McKee 2-2207, 2-2209
orthogonal-triangular decomposition 2-1759
orthonormal matrix 2-1759
Out of memory (error message) 2-1596
overdetermined equation systems, solving 2-1761–2-1762

P

pack 2-1596
pagesetupdlg **2-1598**
Parent
Patch property 2-1631
quivergroup property 2-1791
rectangle property 2-1829
Root property 2-1882
scatter property 2-1920
stairseries property 2-2036
stem property 2-2061

Surface property 2-2168
surfaceplot property 2-2183
Text property 2-2243
Uicontextmenu property 2-2327
Uicontrol property 2-2349
Uimenu property 2-2376
Uipushtool property 2-2407
Uitoggletool property 2-2429
Uitoolbar property 2-2438
pareto 2-1600
partial fraction expansion 2-1860
partialpath 2-1601
pascal **2-1602**
Pascal matrix 2-1602, 2-1717
Patch
converting a surface to 2-2150
creating 2-1603
defining default properties 2-1609
properties 2-1615
reducing number of faces 2-1834
reducing size of face 2-1955
patch 2-1603
path
current 2-1634
removing directories from 2-1876
viewing 2-1639
path 2-1634
path2rc 2-1636
pathdef 2-1637
pathname
partial 2-1601
pathnames
of functions or files 2-2509
relative 2-1601
pathsep 2-1638
pathtool 2-1639
pause **2-1641**
pausing M-file execution 2-1641
pbaspect 2-1642
pcg **2-1647**
pcg **2-1647**
pchip **2-1651**
pcode **2-1653**
pcolor 2-1654
PDE *See* Partial Differential Equations
pdepe **2-1657**
pdeval **2-1668**
perl 2-1670
Perl scripts in MATLAB 2-1670
perms **2-1671**
permutation
of array dimensions 2-1672
matrix 2-1759
random 2-1803
permutations of n elements 2-1671
permute **2-1672**
persistent **2-1673**
persistent variable 2-1673
phase, complex
correcting angles 2-2446
pi **2-1674**
pie 2-1675
pie3 2-1677
pinv **2-1679**
planerot **2-1682**
playshow function 2-1683
plot 2-1684
editing 2-1693
plot box aspect ratio of axes 2-1642
plot editing mode
overview 2-1694
Plot Editor
interface 2-1694, 2-1748
plot, volumetric

slice plot 2-1967
plot3 2-1690
plotedit **2-1692**
plotmatrix 2-1696
plotting
2-D plot 2-1684
3-D plot 2-1690
plot with two y-axes 2-1699
ribbon plot 2-1868
rose plot 2-1887
scatter plot 2-1696
scatter plot, 3-D 2-1911
semilogarithmic plot 2-1934
stem plot, 3-D 2-2051
surface plot 2-2145
volumetric slice plot 2-1967
plotting *See* visualizing
plotyy 2-1699
PointerLocation, Root property 2-1882
PointerWindow, Root property 2-1882
pol2cart **2-1702**
polar 2-1703
polar coordinates 2-1702
converting to cylindrical or Cartesian 2-1702
poles of transfer function 2-1860
poly **2-1705**
polyarea **2-1707**
polyder **2-1708**
polyeig **2-1709**
polyfit **2-1711**
polygamma function 2-1750
polygon
area of 2-1707
creating with patch 2-1603
polyint **2-1714**
polynomial
analytic integration 2-1714
characteristic 2-1705–2-1706, 2-1885
coefficients (transfer function) 2-1860
curve fitting with 2-1711
derivative of 2-1708
eigenvalue problem 2-1709
evaluation 2-1715
evaluation (matrix sense) 2-1717
polyval **2-1715**
polyvalm **2-1717**
pop-up menus 2-2330
defining choices 2-2351
Position
Text property 2-2243
Uicontextmenu property 2-2327
Uicontrol property 2-2350
Uimenu property 2-2376
Position, rectangle property 2-1829
PostScript
printing interpolated shading 2-1735
pow2 **2-1719**
power
of real numbers 2-1815
ppval **2-1720**
preallocation
matrix 2-2545
prefdir 2-1721
preferences
opening the dialog box 2-1723
prime numbers 2-1724
primes **2-1724**
print 2-1721
printdlg 2-1739
printer drivers
GhostScript drivers 2-1726
interploated shading 2-1735
MATLAB printer drivers 2-1726
printing

GUIs 2-1734
interpolated shading 2-1735
on MS-Windows 2-1733
with a variable filename 2-1736
with non-normal EraseMode 2-1623, 2-1827, 2-2162, 2-2178, 2-2235
printing tips 2-1733
printopt 2-1725
printpreview 2-1740
prod **2-1741**
product
of array elements 2-1741
profile 2-1742
profsave 2-1747
propedit **2-1742**
proppanel 2-1749
pseudoinverse 2-1679
psi **2-1750**
publish function 2-1752
push buttons 2-2331
pwd 2-1754

Q

qmr **2-1755**
qr **2-1759**
QR decomposition 2-1759
deleting column from 2-1763
qrdelete **2-1763**
qrinsert **2-1765**
qrupdate **2-1767**
quad **2-1770**
quad8 **2-1770**
quadl **2-1772**
quadrature 2-1770
quadv 2-1774
questdlg 2-1776
quit 2-1777
quitting MATLAB 2-1777
quiver 2-1778
quiver3 2-1781
qz **2-1798**
QZ factorization 2-1710, 2-1798

R

radio buttons 2-2331
rand **2-1799**
randn **2-1801**
random
numbers 2-1799, 2-1801
permutation 2-1803
sparse matrix 2-2006, 2-2007
symmetric sparse matrix 2-2008
randperm **2-1803**
rank **2-1804**
rank of a matrix 2-1804
rat **2-1805**
rational fraction approximation 2-1805
rats **2-1805**
rbbox 2-1808, 2-1840
rcond **2-1810**
reading
data from files 2-2249
formatted data from strings 2-2023
readme files, displaying 2-2508
real **2-1811**
real numbers 2-1811
reallog **2-1812**
realmax **2-1813**
realmin **2-1814**
realpow **2-1815**
realsqrt **2-1816**
rearranging arrays

removing first n singleton dimensions 2-1953
removing singleton dimensions 2-2022
reshaping 2-1858
shifting dimensions 2-1953
swapping dimensions 2-1672
rearranging matrices
rotating 90° 2-1890
rectint **2-1831**
RecursionLimit
Root property 2-1882
recycle **2-1832**
reduced row echelon form 2-1895
reducepatch 2-1834
reducevolume 2-1838
refresh 2-1840
regexp **2-1843**
regexpi **2-1843**
regexprep **2-1849**
regression
linear 2-1711
rehash 2-1852
rem **2-1854**
remainder after division 2-1854
repeatedly executing statements 2-2512
replicating a matrix 2-1856
repmat **2-1856**
reshape **2-1858**
residue **2-1860**
residues of transfer function 2-1860
restoredefaultpath 2-1863
rethrow **2-1864**
return **2-1865**
reverse Cuthill-McKee ordering 2-2207, 2-2209
RGB, converting to HSV 2-1866
rgb2hsv 2-1866
rgbplot 2-1867
ribbon 2-1868
right-click and context menus 2-2320
rmdir 2-1871
rmdir (ftp) 2-1874
rmfield **2-1875**
rmpath 2-1876
root 2-1877
Root graphics object 2-1877
root object 2-1877
root, see rootobject 2-1877
roots **2-1885**
roots of a polynomial 2-1705–2-1706, 2-1885
rose 2-1887
rosser **2-1889**
rot90 **2-1890**
rotate 2-1891
rotate3d 2-1893
Rotation, Text property 2-2243
rotations
Jacobi 2-2008
round
to nearest integer 2-1894
round **2-1894**
roundoff error
characteristic polynomial and 2-1706
partial fraction expansion and 2-1861
polynomial roots and 2-1885
sparse matrix conversion and 2-1985
rref **2-1895**
rrefmovie **2-1895**
rsf2csf **2-1897**
rubberband box 2-1808

S

save **2-1899**
saveas 2-1904
saveobj **2-1907**

savepath 2-1908
saving
  ASCII data 2-1899
  workspace variables 2-1899
schur **2-1925**
Schur decomposition 2-1925
Schur form of matrix 2-1897, 2-1925
ScreenDepth, Root property 2-1882
ScreenSize, Root property 2-1883
script **2-1927**
search path 2-1876
  MATLAB's 2-1634
  modifying 2-1639
  viewing 2-1639
sec **2-1928**
secant 2-1928
  hyperbolic 2-1931
secd 2-1930
sech **2-1931**
Selected
  Patch property 2-1631
  quivergroup property 2-1791
  rectangle property 2-1830
  Root property 2-1883
  scatter property 2-1920
  stairseries property 2-2036
  stem property 2-2061
  Surface property 2-2168
  surfaceplot property 2-2184
  Text property 2-2244
  Uicontextmenu property 2-2328
  Uicontrol property 2-2350
selecting areas 2-1808
SelectionHighlight
  Patch property 2-1631
  quivergroup property 2-1791
  rectangle property 2-1830
  scatter property 2-1921
  stairseries property 2-2037
  stem property 2-2061
  Surface property 2-2168
  surfaceplot property 2-2184
  Text property 2-2244
  Uicontextmenu property 2-2328
  Uicontrol property 2-2350
selectmoveresize 2-1933
semilogx 2-1934
semilogy 2-1934
sendmail 2-1936
Separator
  Uipushtool property 2-2407
  Uitoggletool property 2-2429
Separator, Uimenu property 2-2376
set 2-1938
set
  timer object 2-1941
set operations
  difference 2-1944, 2-1945
  exclusive or 2-1949
  union 2-2441
  unique 2-2442
setdiff **2-1945**
setfield **2-1946**
setstr **2-1948**
setxor **2-1949**
shading 2-1944
shading colors in surface plots 2-1950
shell script 2-2212, 2-2444
shiftdim **2-1953**
ShowArrowHead
  quivergroup property 2-1791
ShowHiddenHandles, Root property 2-1883
shrinkfaces 2-1955
shutdown 2-1777

sign **2-1958**
signum function 2-1958
Simpson's rule, adaptive recursive 2-1771
Simulink
  version number, displaying 2-2458
sin **2-1959**
sind 2-1961
sine 2-1959
  hyperbolic 2-1963
single **2-1962**
singular value
  decomposition 2-1804, 2-2193
  rank and 2-1804
sinh **2-1963**
size
  array dimesions **2-1964**
size of array dimensions 2-1964
size of fonts, see also FontSize property 2-2246
size vector 2-1858
SizeData
  scatter property 2-1921
slice 2-1967
sliders 2-2331
SliderStep, Uicontrol property 2-2350
smooth3 2-1972
smoothing 3-D data 2-1972
soccer ball (example) 2-2209
sort **2-1974**
sorting
  array elements 2-1974
  matrix rows 2-1977
sortrows **2-1977**
sound
  converting vector into 2-1978, 2-1979
  files
    reading 2-2497
    writing 2-2499
  playing 2-2495
  recording 2-2498
  resampling 2-2495
  sampling 2-2498
sound **2-1978**, **2-1979**
source control systems
  undo checkout 2-2440
spalloc **2-1980**
sparse **2-1981**
sparse matrix
  allocating space for 2-1980
  applying function only to nonzero elements of 2-1990
  diagonal 2-1986
  identity 2-1989
  random 2-2006, 2-2007
  random symmetric 2-2008
  replacing nonzero elements of with ones 2-2001
  results of mixed operations on 2-1982
  solving least squares linear system 2-1760
  specifying maximum number of nonzero elements 2-1981
  visualizing sparsity pattern of 2-2016
spaugment **2-1983**
spconvert **2-1984**
spdiags **2-1986**
SpecularColorReflectance
  Patch property 2-1631
  Surface property 2-2168
  surfaceplot property 2-2184
SpecularExponent
  Patch property 2-1632
  Surface property 2-2168
  surfaceplot property 2-2184
SpecularStrength
  Patch property 2-1632
  Surface property 2-2168

surfaceplot property 2-2184
speye **2-1989**
spfun **2-1990**
sph2cart **2-1992**
sphere 2-1993
spherical coordinates 2-1992
spinmap 2-1995
spline **2-1996**
spones **2-2001**
spparms **2-2002**
sprand **2-2006**
sprandn **2-2007**
sprandsym **2-2008**
sprank **2-2009**
spreadsheets
loading WK1 files 2-2524
loading XLS files 2-2534
writing from matrix 2-2526
sprintf **2-2010**
sqrt **2-2018**
sqrtm **2-2019**
square root
of a matrix 2-2019
of array elements 2-2018
of real numbers 2-1816
squeeze **2-2022**
sscanf **2-2023**
standard deviation 2-2044
start
timer object 2-2040
startat
timer object 2-2041
startup 2-2043
startup file 2-2043
State
Uitoggletool property 2-2429
static text 2-2331
std **2-2044**
stem3 2-2051
stop
timer object 2-2065
stopwatch timer 2-2271
storage
sparse 2-1981
storage allocation 2-2545
str2double **2-2066**
str2func **2-2067**
str2mat **2-2069**
str2num **2-2070**
strcat **2-2071**
strcmp **2-2073**
strcmpi **2-2075**
stream lines
computing 2-D 2-2076
computing 3-D 2-2078
drawing 2-2080
stream2 2-2076
stream3 2-2078
strfind **2-2101**
String
Text property 2-2244
Uicontrol property 2-2351
string
comparing one to another 2-2073
comparing the first n characters of two 2-2107
converting to numeric array 2-2070
converting to uppercase 2-2450
dictionary sort of 2-1977
finding first token in 2-2117
searching and replacing 2-2116
strings
converting to matrix (formatted) 2-2023
writing data to 2-2010
strings **2-2103**

strjust **2-2105**
strmatch **2-2106**
strncmp **2-2107**
strncmpi **2-2108**
strread **2-2109**
strrep **2-2116**
strtok **2-2117**
strtrim **2-2120**
struct **2-2121**
struct2cell **2-2123**
structure array
  remove field from 2-1875
  setting contents of a field of 2-1946
strvcat **2-2124**
Style
  Uicontrol property 2-2352
sub2ind **2-2125**
subplot 2-2127
subsasgn **2-2133**
subscripts
  in axis title 2-2281
  in text strings 2-2246
subsindex **2-2134**
subspace **2-2135**
subsref **2-2136**
substruct **2-2137**
subvolume 2-2141
sum
  of array elements 2-2138
sum **2-2138**
superiorto **2-2143**
superscripts
  in axis title 2-2282
  in text strings 2-2246
support **2-2143**
surf 2-2145
surf2patch 2-2150
Surface
  converting to a patch 2-2150
  creating 2-2152
  defining default properties 2-1821, 2-2155
  properties 2-2156, 2-2171
surface 2-2152
surfc 2-2145
surfl 2-2188
surfnorm 2-2191
svd **2-2193**
svds **2-2196**
switch **2-2198**
symamd **2-2200**
symbfact **2-2202**
symbols in text 2-2244
symmlq **2-2203**
symmmd **2-2207**
symrcm **2-2209**
system 2-2212
system directory, temporary 2-2216

T

Tag
  Patch property 2-1632
  quivergroup property 2-1791
  rectangle property 2-1830
  Root property 2-1883
  scatter property 2-1921
  stairseries property 2-2037
  stem property 2-2061
  Surface property 2-2169
  surfaceplot property 2-2184
  Text property 2-2247
  Uicontextmenu property 2-2328
  Uicontrol property 2-2352
  Uimenu property 2-2376

Uipushtool property 2-2407
Uitoggletool property 2-2429
Uitoolbar property 2-2438
tan **2-2213**
tand 2-2214
tangent 2-2213
hyperbolic 2-2215
tanh **2-2215**
tempdir 2-2216
tempname 2-2217
temporary
files 2-2217
system directory 2-2216
terminating MATLAB 2-1777
tetrahedron
mesh plot 2-2218
tetramesh **2-2218**
TeX commands in text 2-2244
Text
creating 2-2222
defining default properties 2-2225
fixed-width font 2-2236
properties 2-2230
text
subscripts 2-2246
superscripts 2-2246
text 2-2222
editing 2-1693
textread **2-2249**
textscan 2-2255
textwrap 2-2270
tic **2-2271**
tiling (copies of a matrix) 2-1856
time
elapsed (stopwatch timer) 2-2271
timer
properties 2-2272
timer
timer object 2-2272
timerfind
timer object 2-2277
timerfindall
timer object 2-2279
title
with superscript 2-2281, 2-2282
title 2-2271
toc **2-2271**
todatenum **2-2283**
toeplitz **2-2284**
Toeplitz matrix 2-2284
toggle buttons 2-2331
token *See also* string 2-2117
TooltipString
Uicontrol property 2-2352
Uipushtool property 2-2407
Uitoggletool property 2-2430
trace **2-2285**
trace of a matrix 2-2285
trapz **2-2286**
treelayout **2-2288**
treeplot **2-2289**
triangulation
2-D plot 2-2294
tril **2-2290**
trimesh 2-2283
triple integral
numerical evaluation 2-2292
triplequad **2-2292**
triplot **2-2294**
trisurf 2-2295
triu **2-2296**
true **2-2297**
try **2-2298**
tsearch **2-2299**

tsearchn **2-2300**
Type
  Patch property 2-1632
  quivergroup property 2-1792
  rectangle property 2-1830
  Root property 2-1883
  scatter property 2-1921
  stairseries property 2-2037
  stem property 2-2062
  Surface property 2-2169
  surfaceplot property 2-2185
  Text property 2-2247
  Uicontextmenu property 2-2328
  Uicontrol property 2-2352
  Uimenu property 2-2376
  Uipushtool property 2-2407
  Uitoggletool property 2-2430
  Uitoolbar property 2-2439

U

UData
  quivergroup property 2-1792
UDataSource
  quivergroup property 2-1793
Uibuttongroup
  defining default properties 2-2308
uibuttongroup function 2-2301
Uibuttongroup Properties 2-2308
UIContextMenu
  Patch property 2-1632
  quivergroup property 2-1792
  rectangle property 2-1830
  scatter property 2-1921
  stairseries property 2-2037
  stem property 2-2062
  Surface property 2-2169
  surfaceplot property 2-2185
  Text property 2-2247
UiContextMenu
  Uicontrol property 2-2352
Uicontextmenu
  Uicontextmenu property 2-2328
uicontextmenu 2-2320
Uicontextmenu Properties 2-2323
Uicontrol
  defining default properties 2-2337
  fixed-width font 2-2344
  types of 2-2329
uicontrol 2-2329
Uicontrol Properties 2-2337
uigetdir 2-2355
uigetfile 2-2359
uiimport **2-2365**
Uimenu
  creating 2-2366
  defining default properties 2-2369
  Properties 2-2369
uimenu 2-2366
Uimenu Properties 2-2369
uint8 **2-2377**
uint8, uint16, uint32, uint64 **2-2377**
uiopen 2-2379
Uipanel
  defining default properties 2-2385
uipanel function 2-2380
Uipanel Properties 2-2385
Uipushtool
  defining default properties 2-2401
uipushtool 2-2397
Uipushtool Properties 2-2401
uiputfile 2-2408
uiresume 2-2413
uisave 2-2414

uisetcolor 2-2415
uisetfont 2-2416
uistack 2-2418
Uitoggletool
  defining default properties 2-2423
uitoggletool 2-2419
Uitoggletool Properties 2-2423
Uitoolbar
  defining default properties 2-2434
uitoolbar 2-2431
Uitoolbar Properties 2-2434
uiwait 2-2413
uncompress files 2-2449
undocheckout 2-2440
union **2-2441**
unique **2-2442**
unitary matrix (complex) 2-1759
Units
  Root property 2-1883
  Text property 2-2247
  Uicontrol property 2-2353
unix 2-2444
unmkpp **2-2445**
unwrap **2-2446**
unzip 2-2449
upper **2-2450**
upper triangular matrix 2-2296
url
  opening in Web browser 2-2500
urlread 2-2451
UserData
  Patch property 2-1633
  quivergroup property 2-1792
  rectangle property 2-1830
  Root property 2-1884
  scatter property 2-1922
  stairseries property 2-2038
  stem property 2-2062
  Surface property 2-2169
  surfaceplot property 2-2185
  Text property 2-2247
  Uicontextmenu property 2-2328
  Uicontrol property 2-2353
  Uimenu property 2-2376
  Uipushtool property 2-2407
  Uitoggletool property 2-2430
  Uitoolbar property 2-2439

V

Value, Uicontrol property 2-2353
vander **2-2453**
Vandermonde matrix 2-1713
var **2-2454**
varargout **2-2455**
variable numbers of M-file arguments 2-2455
variables
  graphical representation of 2-2528
  in workspace 2-2528
  listing 2-2516
  persistent 2-1673
  saving 2-1899
  sizes of 2-2516
VData
  quivergroup property 2-1793
VDataSource
  quivergroup property 2-1793
vectorize **2-2457**
vectorize **2-2457**
ver 2-2458
verctrl 2-2460
version 2-2464
version numbers
  displaying 2-2458

returned as strings 2-2464
vertcat **2-2465**
VertexNormals
Patch property 2-1633
Surface property 2-2169
surfaceplot property 2-2185
VerticalAlignment, Text property 2-2248
Vertices, Patch property 2-1633
view
azimuth of viewpoint 2-2468
coordinate system defining 2-2468
elevation of viewpoint 2-2468
view 2-2467
viewmtx 2-2470
Visible
Patch property 2-1633
quivergroup property 2-1792
rectangle property 2-1830
Root property 2-1884
scatter property 2-1922
stairseries property 2-2038
stem property 2-2062
Surface property 2-2169
surfaceplot property 2-2185
Text property 2-2248
Uicontextmenu property 2-2328
Uicontrol property 2-2354
Uimenu property 2-2376
Uipushtool property 2-2407
Uitoggletool property 2-2430
Uitoolbar property 2-2439
visualizing
sparse matrices 2-2016
volumes
computing 2-D stream lines 2-2076
computing 3-D stream lines 2-2078
drawing stream lines 2-2080
reducing face size in isosurfaces 2-1955
reducing number of elements in 2-1838
voronoi **2-2476**
Voronoi diagrams
multidimensional vizualization 2-2479
two-dimensional vizualization 2-2476
voronoin **2-2479**

W

wait
timer object 2-2481
waitbar 2-2482
waitfor 2-2482
waitforbuttonpress 2-2485
warndlg 2-2486
warning **2-2487**
warning message (enabling, suppressing, and displaying) 2-2487
waterfall 2-2486
.wav files
reading 2-2497
writing 2-2499
waverecord 2-2498
wavfinfo 2-2494
wavplay 2-2495
wavplay 2-2495
wavread **2-2494**, **2-2497**
wavrecord 2-2498
wavwrite **2-2499**
WData
quivergroup property 2-1794
WDataSource
quivergroup property 2-1794
web 2-2500
Web browser
pointing to file or url 2-2500

weekday **2-2504**
well conditioned 2-1810
what 2-2506
whatsnew 2-2508
which 2-2509
while **2-2512**
white space characters, ASCII 2-2117
whitebg 2-2515
wilkinson **2-2519**
Wilkinson matrix 2-1987, 2-2519
winopen **2-2520**
winqueryreg 2-2521
WK1 files
  loading 2-2524
  writing from matrix 2-2526
wk1finfo **2-2523**
wk1read **2-2524**
wk1write 2-2526
workspace
  consolidating memory 2-1596
  predefining variables 2-2043
  saving 2-1899
  variables in 2-2516
  viewing contents of 2-2528
workspace 2-2528

X

x-axis limits, setting and querying 2-2531
XData
  Patch property 2-1633
  quivergroup property 2-1794
  scatter property 2-1922
  stairseries property 2-2038
  stem property 2-2062
  Surface property 2-2170
  surfaceplot property 2-2185
XDataMode
  quivergroup property 2-1795
  stairseries property 2-2038
  stem property 2-2063
  surfaceplot property 2-2185
XDataSource
  area property 2-1922
  quivergroup property 2-1795
  stairseries property 2-2038
  stem property 2-2063
  surfaceplot property 2-2186
xlabel 2-2529
xlim 2-2531
XLS files
  loading 2-2534
xlsfinfo **2-2533**
xlsread **2-2534**
xlswrite **2-2538**
xmlread **2-2541**
xmlwrite **2-2542**
logical XOR 2-2543
xor **2-2543**
XOR, printing 2-1623, 2-1786, 2-1827, 2-1917, 2-2032, 2-2056, 2-2162, 2-2178, 2-2235
xslt **2-2544**
xyz coordinates *See* Cartesian coordinates

Y

y-axis limits, setting and querying 2-2531
YData
  Patch property 2-1633
  quivergroup property 2-1795
  scatter property 2-1923
  stairseries property 2-2039
  stem property 2-2063
  Surface property 2-2170

surfaceplot property 2-2186
YDataMode
quivergroup property 2-1796
surfaceplot property 2-2186
YDataSource
quivergroup property 2-1796
scatter property 2-1923
stairseries property 2-2039
stem property 2-2063
surfaceplot property 2-2186
ylabel 2-2529
ylim 2-2531

Z

z-axis limits, setting and querying 2-2531
ZData
lineseries property 2-1923
Patch property 2-1633
quivergroup property 2-1796
stemseries property 2-2064
Surface property 2-2170
surfaceplot property 2-2187
ZDataSource
lineseries property 2-1923, 2-2064
surfaceplot property 2-2187
zeros **2-2545**
zip 2-2547
zlabel 2-2529
zlim 2-2531
zoom 2-2549